00-I-675F
AMENDMENT-3
September 12, 1977
SUPERSEDING
Int. Amendment-2 (Army-GL)
November 13, 1975 and
Amendment-1
April 22, 1975

FEDERAL SPECIFICATION

IRONERS, FLATWORK, COMMERCIAL (AND ACCESSORIES)

* This amendment which forms a part of Federal Specification 00-I-675F, dated November 20, 1973, was approved by the Commissioner, Federal Supply Service, General Services Administration, for the use of all Federal agencies.

PAGE 2

1.2.2, Item 4A, at the end of the first line: Delete "crossfolder (Multi-lane) and substitute "crossfolder (single-lane)".

PAGE 3

2.1, under "Military Standards": Add "MIL-STD-1474 - Noise Limits for Army Materiel".

PAGE 4

3.1: Delete in its entirety.

PAGE 5

3.3.1: Delete lines 1 and 2 and substitute "Prior to commencing production, the supplier shall submit to".

PAGE 8

Add in proper sequence: "3.5.11 Noise limits. The ironer shall meet the noise limits specified in MIL-STD-1474 and, where practicable, shall not exceed 85 decibels A-weighted at the normal operator position.

FSC 3510

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:00Z
Check the source to verify that this is the current version before use.

PAGE 12

3.7: Add "The following items shall be compatible with the ironers specified in 3.6".

PAGE 13

3.7.2.3, last sentence: Delete and substitute "The table (when adjustable or non-adjustable, solidly attached to the frame of the folder) top height shall be 27-3/4 inches minimum to 33-3/4 inches maximum from the floor."

PAGE 14

3.7.3.1.5, line 3: Add "The delivery table (when adjustable or non-adjustable, solidly attached to the frame of the folder) top height shall be 27-3/4 inches minimum to 33-3/4 inches maximum from the floor."

PAGE 20

4.2: Delete "1. First article inspection (see 4.3)."

4.3: Delete in its entirety.

PAGE 24

4.4.2.3: Delete in its entirety and substitute:

4.4.2.3 End item testing. Sample ironers and accessory items, as applicable, shall be tested as specified in 4.7.1 and 4.7.2 using inspection level S-2. The applicable tests specified in 4.7.3.1 through 4.7.5 shall be performed on one production unit. Failure of any test shall be cause to reject the lot.

PAGE 26

4.7.3.2: Delete in its entirety and substitute:

"4.7.3.2 Crossfolder. Connect the crossfolder to electric power and air supply and feed full size folded bed sheets through the machine for one hour at a minimum rate of 70 linear feet per minute, and in conjunction with accessories of normal use. Inability of the folding machine to meet the requirements specified in 3.7.2 shall constitute failure of the test."

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:00Z
Check the source to verify that this is the current version before use.

PAGE 27

4.7.3.4: Delete in its entirety and substitute

"4.7.3.4 Folding machine with built-in crossfolder. Connect the machine to the specified electric power source and air supply and feed full size bed sheets at a minimum rate of 70 linear feet per minute through the machine for one hour. This test shall be performed in conjunction with accessories of normal use. Inability of the folding machine to meet the requirements specified in 3.7.4 shall constitute failure of the test."

PAGE 28

Add in proper sequence: "4.7.5 Noise test. The ironer shall be tested for conformance with the noise limits of 3.5.11 in accordance with MIL-STD-1474."

PAGE 29

6.2(d): Delete in its entirety.

PAGE 30

6.5: Delete in its entirety.

Custodians:

Army - GL
Navy - YD
Air Force - 99

Review activity:

Army - MD
DSA - GS

User activities:

Army - CE
Navy - MC, MS

Preparing activity:

Army - GL

Civil Agency Coordinating Activities:

GSA - FSS
VA - DMS

Project No. 3510-0266

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T12:00Z
Check the source to verify that this is the current version before use.