MILITARY SPECIFICATION

TELESCOPE, ELBOW: M114E1

This Amendment forms a part of Military Specification MIL-T-50384(MU), dated 16 June 1970, and is approved for use by the US Army Armament Munitions and Chemical Command and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 1

Title: Change "M114E1" to "M114A1", and whereever it appears in the specification.

2.1 Specifications: Add "MIL-L-50778 Liquid Scintillation System for Radioactive Fire Control".

Drawings: Change "Frankford Arsenal" to "Armament Research and Development Center".

PAGE 2

Add "MIL-HDBK-204 Military Standardization Handbook Inspection Equipment Design".

Delete "of DSAM 4145.8".

PAGE 4

3.10: Delete and substitute 3.10 and add 3.10.1 and 3.10.2:

"3.10 Illumination.

3.10.1 Reticle. The reticle markings shall be visible in ambient light conditions ranging from dusk into night. When required, the use of a mask with a 3/4" aperture, located on the entrance window, will be permitted to meet the requirements.

3.10.2 External tritium contamination. There shall be no trace of tritium in excess of 1000 disintegrations per minute (dpm)/100 sq. cm. on the external surface of the telescope."

FSC 1240

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:23Z
Check the source to verify that this is the current version before use.

PAGE 6

4.3.2.2, Table II: After CRITICAL: Change to "None".

Add "MAJOR: 100% inspection".

Add "3. External Tritium Contamination, 3.10.2, 4.2.16".

113.: Change "3.10" to 3.10.1".

112: After operability: Add "(60°F(16°C) to 90°F(32°C))".

Add: "115 Fabrication, 3.2, MIL-F-13926".

4.4.1, line 2: Delete the second sentence and add "or from each months production, whichever occurs first, and be subjected to the requirements and tests of Table III."

Table III: Delete 301, 302, and 303.

304: After storage: Add (-80°F(-62°C)) and +160°F(+71°C))", and after 4.6.1.1, add: "Visual/Tactile".

305: After operating: Add "(-40°F(-40°C) and +150°F(+65°C))".

PAGE 11

4.6.2.15, Line 8 and 13: Change "3.10" to "3.10.1".

Add new paragraph 4.2.16:

"4.2.16 External tritium contamination. Contamination test shall be performed by wiping the telescope with filter paper moistened in distilled water. The wiping shall be performed with moderate finger pressure. The damp filter paper shall be placed in a container with the proper portion of scintillation liquid. The scintillating system used to measure contamination must be calibrated and meet the minimum requirement of MIL-L-50778. The readout shall be within 10% of the known standard value when counted to a total of 1000 disintergrations. The actual test for determining contamination is performed by placing the container into the scintillation system. The measured contamination shall be within the limits specified in 3.10.2".

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:23Z
Check the source to verify that this is the currentversion before use.

6.2: Add new subparagraph d:

"d. Contract data requirements for submission of inspection equipment designs conforming to Data Item Description DI-R-1714, Tailored. See 6.4.1."

Add new paragraphs 6.4 and 6.4.1:

"6.4 Inspection equipment design.

6.4.1 Submission of designs for approval. Contractor designs for final acceptance inspection shall be approved by the Government prior to fabrication or procuring the equipment. The contractor is referred to MIL-HDBK-204 for guidance. Submission of design concept on inspection equipment is permissible for tentative approval. The completion date for design review will be based on the date of the final submission of designs and the required delivery schedule as stipulated in the contract. Submit designs as required to: Commander, US Army Armament Research and Development Center, ATTN: DRSMC-QAF-I(D), Dover, NJ 07801-5001. When the contractor submits inspection equipment designs to the government for approval he shall give the following information in his letter of transmittal:

a. The contract number.

b. The contract item (name, model number, etc.).

c. The designs remaining to be submitted and the expected date of submittal."

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1240-A829)

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:23Z
Check the source to verify that this is the current version before use.