MIL-C-48294 (PA)
12 February 1974

MILITARY SPECIFICATION

CONTAINER, SHIPPING AND STORAGE, MINE CANISTER: M602

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers the inspection and test of the canister used in the reload kit assembly of the M56 anti-tank mine canisters.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition, General Specification for
MIL-T-5021 - Test, Aircraft and Missile, Welding Operators Qualification

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168- Lot Numbering and Ammunition

DRAWINGS

U.S. ARMY PICATINNY ARSENAL

PRODUCT DRAWINGS

9268991 - Shipping and Storage Container, Mine Canister: M602

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

(Copies of specifications, standards, drawings and publications listed above or in the item detail specification required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer).

3. REQUIREMENTS

3.1 Material. - Materials shall be in accordance with applicable specifications and drawings.

3.2 Assembly. - The assembly shall comply with all requirements specified on drawing (dwg.) 9268991 and with all requirements specified in applicable specifications.

3.3 Base Assembly Tensile Weld Strength. - The base assembly welds shall have a minimum tensile strength of forty five thousand pounds per square inch (45,000 p.s.i.).

3.4 Welding. - Welds shall be reasonably smooth and free from craters. They shall exhibit characteristics of fusion, penetration and soundness of weld deposits representative of good welding practice. All welding fluxes, scale, and excessive weld spatter, acids or basic solutions shall be completely removed prior to application of any finish. All welding shall be in accordance with applicable specifications. All welding shall be performed by operators who are currently certified as Class B Operators in accordance with MIL-T-5021.

3.5 Performance Characteristics. - The container shall comply with all of the requirements specified on applicable drawings and with all requirements specified in this specification when loaded with inert M56 canister assemblies without evidence of loose parts broken or permanently set structual members which render the container unusable. Minor dents or creases in non-structual members shall not be considered objectionable. The container shall be operable after completion of the below listed tests. All tests shall be conducted at a temperature of eighty degrees Fahrenheit, plus or minus twenty degrees Fahrenheit. (80°F $\pm$ 20°F).

3.5.1 Fork Lifting. - The loaded container shall be capable of being lifted by a suitable fork type lift truck without evidence of puncture, and broken or bent frame structure when tested as specified in 4.4.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

3.5.2 Stacking. - The loaded container shall be capable of supporting a simulated stacking load equal to nine (9) times the weight of a loaded container without evidence of permanent set or breakage in any of its structural members. The test shall be conducted as specified in 4.4.5.

3.5.3 Edgewise Drop. - The loaded container shall meet the requirements of 3.5 when tested as specified in 4.4.6.

3.5.4 Cornerwise Drop. - The loaded container shall meet the requirements of 3.5 when tested as specified in 4.4.7.

3.5.5 Vibration. - The loaded container, shall withstand vibrations as specified in Table I without evidence of loose parts or fasteners and breakage or cracks in the case structure. The vibration shall be applied in the vertical axis and as specified in 4.4.8.

TABLE I

Frequency	Acceleration
(Hertz)	(G's)
5.5 to 10.0	1.0
10.0 to 50.0	1.5

Sweep rate: 0.8 octaves per minute for a total of 48 minutes.

3.6 Workmanship. - All parts shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products, and other foreign matter. The cleaning method used shall not be injurious to any parts, nor shall the parts be contaminated by the cleaning agents. All markings and stampings shall be neat and sharply defined.

3.7 Submission of results of contractor-conducted examinations and tests. - The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract (see 6.4).

3.8 First Article Inspection This specification makes technical provisions for first article inspection. Requirements

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of Product.-At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted.

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agents authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

4.2 First Article Inspection

4.2.1 Submission.-Prior to the start of regular production the contractor shall submit a first article sample (see 6.1c) to a Government approved facility as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2 and 4.2.3. The first article sample shall consist of ten (10) sets of component parts and ten (10) of each sub-assembly and assembly. All parts and materials including packaging and packing shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including a certificate of conformance for materials. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer. A first article sample, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.

4.2.2 Inspections to be performed.- The ten (10) sets of components, subassemblies and assemblies will be subjected by the Government to any or all of the examinations and tests specified in this specification and any or all requirements of the applicable drawings except 4.3.3.2 and 4.3.3.3.

4.2.2.1 In addition, the following tests shall be performed of five (5) containers after they have undergone the requirements of 4.3.2 and 4.3.3 as noted above.

a. Fork lifting (see 3.5.1)
b. Stacking (see 3.5.2)
c. Edgewise Drops (see 3.5.3)
d. Cornerwise drops (see 3.5.4)
e. Vibration (see 3.5.5)

After completion of these tests, the above five (5) containers shall be tested for the air pressure test of 4.4.2.

4.2.2.2 The five (5) assemblies not subjected to the tests in 4.2.2.1 shall be tested for the air pressure tests of 4.4.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

4.2.2.3 One (1) of the containers from 4.2.2.2 shall then be destructively tested for the tensile weld strength in accordance with 4.4.3.

4.2.3 Rejection. - If any container or component fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon encountering any failure of an item to comply with any of the stated requirements.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchanged process using the same materials and methods in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specifications, or drawings not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

major and minor defects listed, the contractor may elect to apply an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable sub-paragraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Base Assembly (see dwg. 9268993, covering a detail of dwg. 9268991).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	AQL 1.0 percent		
101.	Partitions not properly positioned	Gage	01001
102.	Partition welds missing or improper (see 3.4)	Visual	01002
103.	Corner welds missing or improper (see 3.4)	Visual	01003
104.	Any component missing	Visual	01004
105.	Bracket hole location	Gage	01005
106.	Inside height	Gage	01006
107.	Inside length	Gage	01007
108.	Inside width	Gage	01008
109.	Location of relief valve mounting hole	Gage	01009
110.	Location of humidity indicator mounting hole	Gage	01010
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.6)	Visual	01011

4.3.2.2 Cover Assembly (see dwg. 9268992 covering a detail of dwg. 9268991).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.40 percent		
101.	Inside length	Gage	02001
102.	Inside width	Gage	02002
Minor:	AQL 1.0 percent		
201.	Missing part	Visual	02003
202.	Evidence of poor workmanship (see 3.6)	Visual	02004

4.3.2.3 Gasket, Container, (see dwg. 9269046, covering a detail of dwg. 9268991).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Developed length	Gage	03001
102.	Diameter of rubber	Gage	03002
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.6)	Visual	03003

4.3.2.4 Shipping and Storage Container, Mine Canister: M602 (see dwg. 9268991).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Cover and base assemblies do not line-up	Visual	04001
102.	Channels do not line up on base assembly	Visual	04002
103.	Any part missing	Visual	04003
104.	Finish coat damaged	Visual	04004
105.	Welded joints improper (see 3.4)	Visual	04005
106.	Channel gaskets not secured ...	Manual	04006

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.6)	Visual	04007

4.3.3 TESTING

4.3.3.1 Gasket Vulcanized Joint Strength (see dwg. 9269046) - Major Defect - Code No. 03004. - Ten (10) gaskets shall be randomly selected from each vulcanized lot and tested in accordance with 4.4.1. The lot shall be rejected if one (1) or more gaskets is classed defective (Non-Destructive test).

4.3.3.2 Air Pressure Test (see dwg. 9268991). - Major Defect - Code No. 04007. - Twenty five (25) containers from each lot shall be assembled from randomly selected parts and subassemblies and tested in accordance with 4.4.2. The lot shall be rejected if one (1) or more samples are classed defective (Non-Destructive test).

4.3.3.3 Base Assembly Weld Strength (see 3.3). - Major Defect- Code No. 01012. - One base assembly shall be randomly selected from each lot and tested for the specified requirements in accordance with 4.4.3. The lot shall be rejected if one (1) or more of the test specimen are classed defective. (Destructive test).

4.3.4 Inspection Equipment.-Inspection equipment required to perform the inspections prescribed in this specification is identified in the Examination (4.3.2) and Test Method (4.4) paragraphs herein. See 6.3 for details concerning responsibilities for inspection design and approval.

4.4 TEST METHODS AND PROCEDURES

4.4.1 Gasket Vulcanized Joint Strength. - The gasket shall be held in an approved test fixture on either side of the vulcanized joint and the specified pull force shall be applied. Observation shall be made for conformance with the applicable drawing requirements. Any gasket that fails to comply with the specified requirements shall be classed defective.

4.4.2 Air Pressure Test. - With the pressure equalizing valve blocked off, the container shall be pressurized to the specified internal pressure. Observation shall be made for conformance with the applicable drawing requirement. Any container failing to conform with the requirements shall be classed defective.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

4.4.3 Base Assembly Tensile Strength Test. - Sections shall be cut from each corner weld and each lifting support bracket to be used as a tensile strength speciman. Testing shall be in accordance with test method 211.1 of FED-STD-151.

4.4.4 Fork Lifting. - The container shall be lifted clear of another container (or equipment) when stacked, lowered to the floor by a fork-lift truck having forks forty (40) inches minimum in length . The truck shall be cleared of the container, reassume lifting position and restack. This procedure shall be followed in lifting once from each side. The container shall be examined for punctures or broken or bent frame structures.

4.4.5 Stacking. - The required load shall be placed on top of the container in such a manner as to simulate stacking of nine (9) additional loaded containers thereon. The containers shall be examined for permanent set and breakage of sturctural members.

4.4.6 Edgewise Drops. - The container with load assembled, shall be supported at one corner of its base on a block approximately five (5) inches in height and with a block approximately twelve inch high placed under the other corner of the same end of the container. The opposite end of the container shall be raised and allowed to fall freely from a eighteen inch height, measured from the lower of the two (2) corners, to a concrete or similarly hard surface. This test shall be applied to one corner of each end of the container. The container shall be observed for compliance with the applicable requirements.

4.4.7 Cornerwise Drops. - The container, with load assembled, shall be supported at one end of its base on a sill approximately five (5) inches in height and placed at right angles to the skids. The other end of the container shall be raised and allowed to fall freely from an eighteen inch height to a concrete or similarly hard surface. This test shall be applied to both ends of the container. Observation shall be made for compliance with the applicable requirements.

4.4.8 Vibration. - The loaded container shall withstand the vibrations specified in Table I. The container shall be assembled to an approved fixture with the cover closed and all latches fastened in a normal manner. Adequate safety precautions shall be observed to preclude endangering personnel and equipment. Any container failing to conform with the applicable requirements shall be classed defective.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level C. - The containers shall be preserved and packaged in accordance with MIL-STD-1169.

5.2 Packing

5.2.1 Level C. - The containers preserved and packaged as specified in 5.1.1, shall be packed for shipment in accordance with MIL-STD-1169.

5.3 Marking. - Marking of the carton shall comply with MIL-STD-1169.

5.4 Shipping. - When containers from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards. - Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. They should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.3).

6.3 Inspection Equipment Designs.-Inspection equipment designs are of two types - Government Special Inspection Equipment (SIE) designs and contractor designs. SIE designs are designated by drawing numbers under the "Method of Inspection" headings in Section 4. Design responsibility for all other

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

inspection equipment is assigned to the contractor. The contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.3.2 and 6.3.3 should he elect to do so.

6.3.1 SIE designs.-SIE designs may consist of any of the following:

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.

b. A source control drawing or a specification control drawing as defined in MIL-STD-100.

c. An envelope drawing, as defined in MIL-STD-100, which establishes the criteria which a detailed design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein.

6.3.2 Contractor designs.-Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the contractor proposes to use. (Commercial equipment is defined as unmodified equipment which is cataloged and available for purchase by the general public). Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures. Commercial equipment shall be fully described by catalog listings or other means which provide sufficient information to permit identification and evaluation by the Government and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered thereby (see 6.3.1c). Designs shall be of the category and form (per MIL-D-1000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204, "Inspection Equipment Design" for guidance. The specification number and the applicable five digit defect code number (or other specific identifying information) from Section 4 of this specification shall be referenced on each contractor design together with the component or assembly drawing number and revision letter to which the specific design applies.

6.3.3 Submission of Designs for Approval.-Contractor designs shall be approved by the Government prior to fabricating or procuring the equipment. Designs shall be submitted for approval to

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

Picatinny Arsenal, ATTN: SARPA-QA-A-M, Dover, New Jersey 07801 in accordance with the stipulations, time frame and distribution specified in the Contract Data Requirements List (DD Form 1423) or in the contract. The contractor must include in his submission of designs a listing of any and all Government SIE designs which will be utilized. Partial submission of inspection designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will normally be accomplished within one month after receipt.

6.4 Submission of results of contractor conducted examinations and tests (see 3.7). - The contractor shall send his results to:

Commander
Picatinny Arsenal
ATTN: SARPA-QA-A-M
Dover, New Jersey 07801

Custodian:
Army-PA

Preparing Activity:
Army-PA

Project Number: 1345-A-045

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T03:55Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426

REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 202610-26T03:55Z
Check the source to verify that this is the current version before use.