MIL-B-467D
1 July 1976
SUPERSEDING
MIL-B-467C
16 September 1965

MILITARY SPECIFICATION

BREAKERS, PAVING:

PNEUMATIC

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers manually controlled, pneumatic, paving breakers.

1.2 Classification. The pneumatic paving breakers shall be of the following sizes, as specified (see 6.2):

60-pound.
80-pound.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS
FEDERAL

QQ-T-580	- Tool Steel, Carbon and Carbon-Vanadium.
WW-C-633	- Couplings, Hose: (Half), Pneumatic, Universal Type.
PPP-P-40	- Packaging and Packing of Hand Tools.

FSC 3820

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-O-13417	- Oilers, Air Line, For Pneumatic Tools.
MIL-T-704	- Treatment and Painting of Materiel.

STANDARDS
FEDERAL

FED. STD. No. 356	- Commercial Packaging of Supplies and Equipment.

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-1474	- Noise Limits for Army Materiel.
MS35793	- Handle, Bail-Chest, Surface Mounting, Plain Holes.

(Copies of specifications and standards required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

COMPRESSED AIR AND GAS INSTITUTE

Compressed Air and Gas Handbook.

(Application for copies should be addressed to the Compressed Air and Gas Institute, 122 East 42nd Street, New York, NY 10017.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Description. Each pneumatic paving breaker shall consist of a backhead equipped with a T-handle, cylinder, and throttle, and a front-head equipped with a chuck for collared-shank tools. The pneumatic paving breaker (hereinafter referred to as "breaker") shall conform to Table I.

Table I. Physical and Performance Characteristics

Size	Weight without Accessories		Air consumption total (90 psig at the tool) max.	Piston diameter, min.	Piston stroke, min.	Piston speed, no load, min.	Force of blow (90 psig at the tool) min.
	min.	max.					
	lb	lb	cfm	inch	inch	blows/minute	ft-lb/blow
60	53	65	65	2.000	4-1/2	1,290	40
80	75	94	78	2.250	5-1/2	1,250	60

3.1.1 Performance. The breaker shall operate on compressed air at pressures between 70 and 100 pounds per square inch gage (psig). The breaker shall break a 5-inch or thicker slab of Portland cement concrete, having a compressive strength of not less than 3,200 pounds per square inch (psi), into sections having an approximate top surface area not greater than 35 square inches without malfunction, damage, scored parts, wear of piston diameter, or cylinder diameter of more than 0.001 inch, or absence of oil vapor in the exhaust air when tested as specified in 4.6.2.2.

3.2 First article (preproduction model). The contractor shall furnish one or more breakers for examination and testing within the time frame specified (see 6.2), to prove prior to starting production, that his production methods and choice of design detail will produce breakers that comply with the requirements of this specification. Examination and tests shall be as specified in Section 4; and, unless otherwise

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

specified herein, all examinations and tests shall be conducted by the contractor subject to surveillance and approval by the Government (see 6.4). When specified (see 6.2), the Government will conduct any or all of the preproduction examination and tests, as specified.

3.3 Initial production. When specified (see 6.2), the contractor shall furnish to the Government a breaker for testing as specified in 4.4.

3.4 Materials. Material shall be as specified herein. Material not specified herein shall be selected by the contractor and shall be subject to all provisions of this specification.

3.5 Safety. Each breaker shall be provided with a retainer which will prevent the accessory tool from becoming accidentally disengaged from the breaker.

3.6 Interchangeability. All parts having the same manufacturer's part number shall be interchangeable with each other with respect to installation and performance.

3.7 Backhead assembly. The backhead assembly shall include a housing, T-handle, and throttle lever.

3.7.1 Housing. The housing shall be forged steel.

3.7.2 Throttle lever. The throttle lever shall be located on the T-handle, and shall be operable from either side of the breaker.

3.7.3 Throttle valve. The throttle valve shall be self-closing when the throttle lever is released.

3.8 Cylinder assembly. The cylinder assembly shall include a cylinder, piston, and hose connection tube with coupling.

3.8.1 Cylinder. The cylinder shall be forged steel or have a surface hardened cylinder liner.

3.8.2 Piston. The piston shall be reversible.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

3.8.3 Hose connection tube. The hose connection tube shall be shaped in a gooseneck and shall be of the swivel type. The tube end thread shall be 3/4-inch, external, American National Pipe Thread.

3.8.3.1 Coupling. A 3/4-inch size universal hose coupling conforming to WW-C-633, Type II, shall be furnished.

3.9 Fronthead assembly. The fronthead shall include a retainer, chuck, and housing for the chuck.

3.9.1 Housing. When a separate fronthead assembly is provided, the housing shall be forged steel.

3.9.1.1 Liner. The chuck housing shall contain a replaceable liner.

3.9.2 Chuck. The chuck shall be 1-1/4 inch hexagonal (nominal size), in accordance with Compressed Air and Gas Handbook, standard chuck gage size.

3.9.3 Retainer. The retainer shall be of the latch type (see 3.5).

3.10 Air strainer. When an air strainer is furnished (see 6.2), the air strainer or screen with a minimum mesh of 24 per inch shall be replaceable and shall not be damaged when the supply hose is connected or disconnected from the air inlet connection.

3.11 Exhaust port. The exhaust port shall be located to direct exhaust air downward and away from the operator.

3.12 Sound level requirement. The sound level of the breaker shall be in accordance with MIL-STD-1474, Category A for steady-state noise when tested in accordance with 4.6.2.6. Hearing protectors need not be supplied with the breaker. If the breaker operates at a noise level exceeding 85dB(A) per MIL-STD-1474, the manual shall include the requirement for hearing protection, the noise level of the item, the distance from the item at which 85dB(A) will always be met, and what operational or system configuration situations will reduce the level to 85dB(A). Hazard warning statement, if required, shall say "CAUTION, HEARING PROTECTION REQUIRED" and shall be included in the operator's manual and on a plate permanently attached to the breaker.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

3.13 Accessories. Such accessories as are specified (see 6.2), shall be furnished.

Table II. Accessories

Accessory	Nominal length under collar	Tool end
	inches	
(a) Chisel	13.5 to 14.5	2.75 to 3.25-inch wide point
(b) Moil point	13.5 to 14.5	
(c) Tamping rod	8 to 9	1.640-inch diameter
(d) Tamping pad	not applicable	5- to 6-inch diameter

3.13.1 Chisel and moil point. The chisel and moil point shall be of forged steel conforming to QQ-T-580, Grade A, (regular), Class W1-08 or W1-09.

3.13.1.1 Heat treatment. After forging, the chisel and moil point shall be normalized, hardened, and tempered to a hardness of 54 to 60 Rockwell C.

3.13.2 Tamping rod. The tamping rod shall be of forged steel conforming to QQ-T-580, Grade A, (regular), Class W1-08 or W1-09.

3.13.3 Tamping pad. The tamping pad shall be of malleable iron. The tamping pad shall attach to the tamping rod by means of a tampered fit.

3.14 Attachments. Such attachments as are specified (see 6.2), shall be furnished:

(a) Spike driver.
(b) Sheeting driver (for 80-pound-size breaker).

3.14.1 Spike driver. The breaker shall be convertible to use as a spike driver by replacement of the standard fronthead or cylinder with a fronthead or cylinder constructed specifically for driving railroad spikes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

3.14.2 Sheeting driver. The 80-pound-size breaker shall be convertible to use as a sheeting driver by replacement of the standard fronthead or cylinder with a fronthead or cylinder constructed specifically for driving sheeting and planks. The sheeting driver shall be adjustable for driving 2 to 3 inch planks.

3.15 Driving tools. Such driving tools as specified (see 6.2), shall be furnished:

(a) Spike driving tool.
(b) Sheeting driver.

3.15.1 Spike driving tool. The spike driving tool shall have a 1-1/4 inch hexagonal shank and shall have a lower end designed specifically for driving railroad spikes.

3.15.2 Sheeting driver. The sheeting driver tool shall have a 1-1/4 hexagonal shank and shall be designed specifically for driving 2 to 3 inch thick plank.

3.16 Oil reservoir. When specified (see 6.2), an oil reservoir shall be furnished. The oil reservoir shall have capacity for not less than 25 minutes of continuous operation while operating at 90 psig at the tool. The oil reservoir shall be built in the backhead or cylinder.

3.17 Leader hose. When an oil reservoir is not furnished, a 10-foot-long, 3/4-inch-inside-diameter hose shall be furnished with an external NPT connector on one end and a universal hose coupling conforming to WW-C-633 on the other end.

3.18 Lubrication. All surfaces requiring lubrication shall be provided with a means for lubricating by the use of either an internal oil reservoir (see 3.16), or an air-line oiler conforming to MIL-O-13417. The air-line oiler shall not be furnished under this specification.

3.18.1 Lubricants. The breakers shall operate as specified herein when lubricated with military lubricants (see 6.3).

3.19 Identification marking. The breaker shall be identified in accordance with MIL-STD-130.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

3.20 Treatment and painting. The portions of the breaker and its components normally painted shall be cleaned, treated, and painted in accordance with MIL-T-704, Type A, color as specified (see 6.2).

3.21 Chest. When specified (see 6.2), a chest made of steel not less than 0.071 inch in thickness shall be provided. The steel shall conform to ASTM A366 or A569. The chest shall be of a size to hold the maintenance tools, leader hose, breaker, repair parts, and accessories furnished with each breaker. The chest shall have an overlapping hinge lid which prevents the entry of rain and dirt with not less than two tension-type hook latches. The chest lid shall open at least 90 degrees from the closed position and shall remain in the open position either by its own weight or by a holding device. A hasp that will accommodate a padlock with a 3/8-inch shackle shall be provided to secure the lid to the chest. Two lifting handles conforming to MS35793 shall be provided, one located at each end of the chest.

3.22 Workmanship. The breaker shall be free of defects such as galvanic action resulting from contact of dissimilar metals, rust, cracks, and other defects that could impair its operation or serviceability.

3.22.1 Surfaces. All parts, components, and assemblies of the breaker including castings, forgings, molded parts, stampings, bearings, seals, and machined surfaces shall be clean and free from sand, dirt, fins, pits, sprues, scale, and other harmful or extraneous materials. All edges shall be rounded or beveled.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Initial production inspection (see 4.4).
(c) Quality conformance inspection (see 4.5).
(d) Inspection comparison (see 4.7).
(e) Inspection of packaging (see 4.8).

4.3 Preproduction inspection.

4.3.1 Examination. The breaker shall be examined as specified in 4.6.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. The breaker shall be tested as specified in 4.6.2 through 4.6.2.6. Failure of any test shall be cause for rejection.

4.4 Initial production inspection. When specified (see 3.3), one or more initial production breakers will be selected at random by the Government from the breakers being produced by production tooling and will be examined as specified in 4.6.1 and tested as specified in 4.6.2 through 4.6.2.6 to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Acceptance of an initial production breaker shall not exclude the remaining breakers from the quality conformance inspection and acceptance provisions specified in Section 4. In addition to any test specified as part of the initial production test, the Government reserves the right to conduct any and all other tests contained in this specification as part of the initial production test and failure of such additional tests shall have the same effect as failure of those tests specified as initial production tests.

4.4.1 Inspection failure. Failure of an initial production breaker to meet any requirement specified herein during and as a result of the examination and tests specified in 4.4 shall be cause for rejection of the initial production breaker(s) and shall be cause for refusal by the Government to continue acceptance of production breakers until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

shall be accomplished by the contractor at no cost to the Government on breakers previously accepted and produced under the contract. Any deficiencies found as a result of the initial production inspection will be considered prima facie evidence that all breakers accepted prior to the completion of initial production inspection are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.5 Quality conformance inspection.

4.5.1 Sampling. Sampling shall be in accordance with MIL-STD-105, Inspection Level II. The sample unit shall be one completely finished breaker.

4.5.2 Examination. Samples selected in accordance with 4.5.1 shall be examined as specified in 4.6.1. AQL shall be 1.5 percent defective for major defects and 2.5 percent defective for minor defects.

4.5.3 Tests. Samples selected in accordance with 4.5.1 shall be tested as specified in 4.6.2.3, 4.6.2.5, and 4.6.2.7. AQL shall be 2.5 percent defective.

4.6 Inspection procedure.

4.6.1 Examination. The breaker shall be examined as specified in 4.5.2 for the following characteristics:

MAJOR

101. Weight not as specified (see Table I).
102. Dimensions not as specified (see Table I).
103. Material not as specified (see 3.4).
104. Accessory tool lock not furnished or not of the latch type (see 3.5 and 3.9.3).
105. Interchangeability of parts not as specified (see 3.6).
106. Location of throttle lever not as specified (see 3.7.2).
107. Throttle valve not of the self-closing, lever-operated type (see 3.7.3).
108. Hose connection tube not as specified (see 3.8.3).
109. Coupling not furnished or not as specified (see 3.8.3.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

110. Renewable liner not furnished with 80-pound breaker (see 3.9.1.1).
111. Chuck not suitable for accessories (see 3.9.2).
112. Air strainer not as specified (see 3.10).
113. Accessories not as specified (see 3.13).
114. Tamping pad taper not compatible with tamping rod taper (see 3.13.3).
115. Attachments not as specified (see 3.14).
116. Special tools not as specified (see 3.15).
117. Oil reservoir not as speciifed (see 3.16).
118. Leader hose not furnished or not as specified (see 3.17).

MINOR

201. Identification markings not as specified (see 3.19).
202. Treatment and painting not as specified (see 3.20).
203. Chest not as specified (see 3.21).
204. Workmanship not as specified (see 3.22 and 3.22.1).

4.6.2 Tests.

4.6.2.1 Test conditions. Unless otherwise specified, tests shall be performed without shelter and at the climatic conditions existing at the place of test. The breaker shall operate as specified herein without main enance other than the contractor's recommended normal scheduled maintenance as established by a maintenance schedule prepared and submitted by the contractor prior to test. Prior to test, the breaker shall be lubricated with military oils. Oils shall be those designated for use in the ambient temperatures at which the test is being performed. A slab of Portland cement concrete having a compressive strength of 3,200 psi, 5 inches thick or thicker with a top surface area of 100 square feet shall be made available for testing.

4.6.2.2 Performance. Using the chisel or moil point accessories, operate the breaker for 25 hours each at compressed air pressures at the tool of 70 and 100 psig, breaking the concrete slab into sections with top areas not greater than 35 square inches. At 5-hour intervals during the test, examine the exhaust for oil in the exhausted air. At the completion of 50 hours of operation, take the following action:

(a) Examine all external parts of the breaker.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

(b) Disassemble the breaker and examine the parts for damage, wearing, or scoring.

Evidence of mechanical failure, permanent deformation, or damaged or scored parts; evidence of wearing of the piston diameter or cylinder diameter of more than 0.001 inch; or absence of oil vapor in the exhaust air shall constitute failure of this test.

4.6.2.3 Force of blow. Attach a steel ball with a brinell hardness of not less than 200 and a 0.499 to 0.500-inch spherical diameter to the end of an accessory bar. Make 20 impressions with the steel ball in a 1/4-inch-thick strip of 1020 steel which has a brinell hardness between 163 and 179. Measure in millimeters the mean diameter of the impressions. Convert to foot-pounds using Table III. Force of blow less than that specified in Table I shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

Table III. Force of Blow Conversion Table

Impression diameter	Force of blow-ft/lb									
mm	.00	.01	.02	.03	.04	.05	.06	.07	.08	.09
6.0	23.9	24.07	24.24	24.41	24.58	24.75	25.92	25.09	25.26	25.43
6.1	25.6	25.77	25.94	26.11	26.28	26,45	26.62	26.79	29.96	27.13
6.2	27.3	27.49	27.69	27.88	28.08	28.27	28.47	28.66	28.86	29.05
6.3	29.25	29.46	29.67	29.88	30,09	30,30	30.51	30.72	30.93	31.14
6.4	31.35	31.59	31.85	32.09	32,34	32,58	32.83	33.07	33.32	33.56
6.5	33.80	34.05	34.30	34.55	34.80	35,05	35.30	35.55	35.80	36.05
6.6	36.3	36.57	36.83	37.11	37.38	37.65	37.92	38.19	38.46	38.73
6.7	39.0	39.3	39.6	39.9	40.2	40,5	40.8	41.1	41.4	41.70
6.8	42.0	42.33	42.66	42.99	43,32	43.65	43.98	44.31	44.64	44.97
6.9	45.3	45.64	45.99	46.33	46.68	47,02	47.37	47.71	48.06	48.40
7.0	48.75	49.10	49.46	49.81	50.17	50,52	50.88	51.23	51.59	52.94
7.1	52.3	52.70	53.10	53.50	53.90	54,30	54.70	55.10	55.50	55.90
7.2	56.3	56.67	57.04	57.41	57.78	58.15	58.52	58.89	59.26	59.63
7.3	60.0	60.37	60.74	61.11	61.48	61,85	62.22	62.59	62.96	63.33
7.4	63.7	64.08	64.46	64.84	65.22	65,60	65.98	66.36	66.74	67.12
7.5	67.5	67.87	68.24	68.61	68.98	69,35	69.72	70.09	70.46	70.83
7.6	71.2									

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

4.6.2.4 Air-consumption test. Measure the total air consumption (cubic feet per minute of free air) at 90 psig with the throttle valve fully open during the operational test. A water displacement meter or airflow meter shall be used in accordance with procedures outlined in the Compressed Air and Gas Handbook to determine air consumption. Air consumption exceeding that specified in Table I shall constitute failure of this test.

4.6.2.5 Piston speed test. Determine the piston speed (blows per minute at no load). Piston speed less than that specified in Table I at no load shall constitute failure of this test.

4.6.2.6 Sound level measurement.

4.6.2.6.1 Operator's station. Measure the sound level at the operator's station in accordance with MIL-STD-1474 for steady-state noise at the operating conditions of breaking concrete on a surface of concrete.

4.6.2.6.2 Exterior spectator. Measure the exterior sound level in accordance with MIL-STD-1474 for exterior noise.

4.6.2.7 Individual operation. Operate each breaker for 10 minutes at 100 psi. Any operational difficulties, breakage, or permanent deformation shall constitute failure of this test.

4.7 Inspection comparison. The Government may select breakers at any time during the contract production period and subject these breakers to the examination specified in 4.6.1 and the tests specified in 4.6.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government, at a site selected by the Government, on units selected at random from those which have been accepted by the Government and will not include the previously inspected preproduction model and initial production breakers. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

4.7.1 Inspection failure. Failure of an inspection comparison breaker to meet any requirement specified herein during and as a result of the examination and tests specified in 4.7 shall be cause for rejection of the inspection comparison breaker(s) and shall be cause for refusal by the Government to continue acceptance of production breakers until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on breakers previously accepted and produced under the contract. Any deficiencies found as a result of the inspection comparison will be considered prima facie evidence that all breakers accepted prior to the completion of inspection comparison are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.8 Inspection of packaging. The preservation and packing shall be examined for compliance with documents referenced in Section 5.

5. PACKAGING

5.1 Preservation and packing. Preservation and packing shall be military or commercial as specified (see 6.2).

5.1.1 Military. The breakers, accessories, repair parts, tools, and publications shall be preserved and packed in accordance with PPP-P-40. The level of preservation and packaging shall be A, and the level of packing shall be Level A or B as specified (see 6.2).

5.1.2 Commercial. The breakers shall be preserved and packed in accordance with FED. STD. No. 356 (see 6.2).

5.2 Marking. Military marking shall be in accordance with MIL-STD-129. Commercial marking shall be in accordance with FED. STD. No. 356.

6. NOTES

6.1 Intended use. The breakers covered by this specification are intended for use in breaking up concrete, brick, and macadam pavement, and for performing similar demolition work.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Size required (see 1.2).
(c) Time frame required for submission of the preproduction model (see 3.2).
(d) When the Government will conduct any or all of the preproduction model examination and tests. When the Government will conduct some but not all of the preproduction examination and tests, the contracting officer should specify which examination and tests will be conducted by the Government and which examination and tests shall be conducted by the contractor (see 3.2).
(e) When an initial production breaker is required (see 3.3).
(f) When an air strainer is to be furnished (see 3.10).
(g) Accessories required (see 3.13).
(h) Attachments required (see 3.14).
(i) Driving tools required (see 3.15).
(j) When an oil reservoir is to be furnished (see 3.16).
(k) Color required (see 3.20).
(l) When chest is required (see 3.21).
(m) Whether Level A (military) or commercial preservation and Level A (military), Level B (military), or commercial packing is required (see 5.1, 5.1.1, and 5.1.2).

6.3 Lubricants. The contracting officer should furnish a list of military lubricants applicable to the breakers covered by this specification as contained in the Federal Supply Catalog, Department of Defense Section, Identification List C9100-1L, for FSC Group 91.

6.4 Preproduction model. Any changes or deviations of production breakers from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the contractor of his obligation to furnish breakers conforming to this specification.

6.5 Data requirement. The contracting officer should include requirements for such data as technical publications, instructional materials, illustrated parts lists, and contractor's maintenance and operation manual to be furnished with each breaker.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

6.6 Provisioning. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including any special tools), and instructions regarding shipment of breakers.

Custodians:
Army - ME
Navy - YD
Air Force - 99

Preparing activity:
Army - ME

Project 3820-0153

Review activities:
Army - AT
DSA - CS

User activities:
Navy - MC
Air Force - 85

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/ vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE MIL-B-467D BREAKERS, PAVING: PNEUMATIC

NAME OF ORGANIZATION AND ADDRESS	CONTRACT NUMBER
	MATERIAL PROCURED UNDER A ☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?
   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*	TELEPHONE NO.
	DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T07:31Z
Check the source to verify that this is the current version before use.