MILITARY SPECIFICATION

(CABINET, EQUIPMENT STOWAGE - BATTERY CHARGING BCU-13/E)

This specification has been approved by the Naval Air Systems Command, Department of the Navy.

1. SCOPE

1.1 Scope - The equipment covered by this specification shall provide storage and charge facilities for Beacon Radio, T-1129A/URT-26(V) and Battery Assembly, Control, Dispenser BB-620/URT-26(V) at Organizational Level.

1.2 Classification - This equipment shall be Class 2 Organizational per MIL-T-21200.

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:32Z
Check the source to verify that this is the current version before use.

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

MIL-T-21200	Test Equipment for use with Electronic and Electrical Equipment, General Specification for.
MIL-F-15733	Filter, R.F. General Specification for.
MIL-R-900	Rubber Gasket Material.
MIL-S-3786	Switch, Rotary, General Specification for.
MIL-S-3950	Switch, Toggle General Specification for.
MIL-S-8834	Switch, Toggle, Positive Break, Aircraft, General Specification for.
MIL-N-25027	Nut, Self-Locking.
MIL-T-27	Transformer and Inductor, General Specification for.
MIL-C-39019	Circuit Breakers, Magnetic, Low-Power, Sealed, Trip-Free, General Specification for.
MIL-T-713	Twine, Impregnated, Lacing and Tying.
MIL-N-18307	Nomenclature and Nameplates for Aeronautical Electronic and Associated Equipment.
MIL-M-7793	Meter, Time Totalizing.
MIL-T-18303	Test Procedures, Preproduction and Inspection, for Aircraft Electronic Equipment, format for.
MIL-STD-143	Standards and Specifications Order of Precedence for the Selection of.
MIL-STD-454	Standard General Requirements for Electronic Equipment.
MIL-STD-415	Test Provisions for Electronic Systems and Associated Equipment.
MIL-STD-108	Definition of and Basic Requirements for, Enclosure for Electric and Electronic Equipment.
MIL-BUL-400	Airborne Electronic and Associated Equipment, Applicable Documents.
MS-25083	Jumper Assembly, Electric, Bonding and Current Return.
Specification Control Drawing 10114 (Leigh Instruments Limited)	Battery, Stowage, Nickel-Cadmium 2 Ampere-hour.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

2.1.1 Availability of Documents

(1) When requesting specifications, standards, drawings, and publications, refer to both title and number. Copies of this specification and applicable specifications required by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Naval Publications and Forms Center, 5801 Tabor Avenue, Philadelphia, Pennsylvania 19120

3. REQUIREMENTS

3.1 Testing - This specification makes provision for testing (see 4).

3.2 Materials, Parts, and Processes - Materials, Parts and Processes shall be in accordance with MIL-T-21200 as stated herein.

3.2.1 Selection of Parts - All parts used in the construction of the equipment shall be in accordance with the requirements stated herein. The selection of parts shall be in accordance with the following order of preference:

(a) MIL-BUL-400

(b) Other Standards, Specifications and requirements listed herein but not included in MIL-BUL-400

(c) MIL-STD-143

All parts used except as covered in (a) and (b) will require written approval in accordance with 3.2.1.1.

3.2.1.1 Approval of Non-Standard Parts - Action for approval of non-standard parts shall be in accordance with MIL-T-21200 Category III.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

3.2.2 Interchangeability - Interchangeability shall be in accordance with MIL-STD-454 requirement 7.

3.2.3 Batteries - Batteries shall be Nickel-Cadmium rechargeable sealed cells in accordance with Leigh Instruments Specification Control Drawing 10114. Batteries shall be rigidly mounted and shall be removable and replaceable without damage to the equipment. The battery compartment shall be marked as specified herein to indicate connections, polarity, voltage, and manufacturers part number.

3.2.4 Cable and Wiring

3.2.4.1 Wire, Hook-up - Hook-up wire shall conform to MIL-STD-454 Requirement 20.

3.2.4.1.1 Color Coding of Hook-up Wiring - Color coding identification shall be used for all chassis wiring in accordance with MIL-STD-454, Requirement 20.

3.2.4.2 Interconnection Cable - Power cable shall conform to MIL-STD-454 Requirement 66.

3.2.5 Connectors

3.2.5.1 Electrical Connectors - Electrical connectors shall conform to MIL-STD-454 Requirement 10. Connectors or receptacles which can continue to be energized after unmating shall have socket contacts.

3.2.6 Filters, R.F. - Power line radio interference filters shall conform to MIL-F-15733.

3.2.7 Gaskets - Wherever possible, gasketed surfaces shall have metal-to-metal contact so that the amount of gasket compression can be controlled. The inside radius of gaskets at corners of square or rectangular enclosure openings shall be the maximum value that will not restrict access of inhibit design. The minimum radius shall be consistent with the gasket material.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

3.2.7.1 Gasket Material - Material for non-oil-resistant applications shall conform to MIL-R-900.

3.2.8 Meters - Electrical indicating meters shall be in accordance with MIL-T-21200.

3.2.8.1 External Adjustment - All panel indicating meters shall provide for external zero adjustment.

3.2.8.2 Luminous Markings - Radioactive materials such as self-luminous dial markings, shall not be used.

3.2.9 Rotary Switches - Rotary switches shall conform to MIL-S-3786.

3.2.10 Toggle Switches - Toggle switches shall conform to MIL-S-3950 or MIL-S-8834.

3.2.11 Threaded Devices - Threaded bolts, nuts, screws and studs employed in the construction of the equipment shall conform to MIL-STD-454 Requirement 12.

3.2.12 Nuts - All nuts shall be metal self-locking and shall conform to MIL-N-25027.

3.2.13 Transformers - Transformers shall conform to MIL-T-27 Grade 5 temperature Class S, life expectance X. Power transformers shall incorporate electrostatic shields.

3.2.14 Circuit Breakers - Circuit breakers shall conform to MIL-C-39019.

3.3 Design and Construction

3.3.1 Pigtailed Parts Mounting - Parts provided with pigtail leads such as small resistors and capacitors, other than those mounted on printed wiring boards shall be secured between solder-type terminals on part mounting boards whose general design and material are as specified herein. The arrangement of these parts shall be such as to limit the number of leads terminating at any one terminal to three.

Source: https://assist.dla.mil - Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

Parts with axial leads shall not be supported by means of the wire leads alone except that parts whose weight does not exceed 1/2 ounce may be secured only by their leads if the total length of leads does not exceed 1 inch.

3.3.1.1 Soldering - Soldering shall be in accordance with Requirement 5 of MIL-STD-454.

3.3.2 Fungus-Nutrient Materials - Only fungus-inert materials shall be used in the construction of the equipment.

3.3.3 Tape, Lacing - Lacing tape for harnesses shall conform to MIL-T-713, Type P, Class 2, waxed.

3.3.4 Aluminum Alloy - Aluminum alloy used in the construction of the equipment shall comply with Para 3.1.6.3 of MIL-T-21200.

3.3.5 Finishes - All finishes used in the construction of the equipment shall comply with MIL-T-21200 Para 3.1.8.

3.3.6 Safety - Equipment design shall comply with Requirement 1 of MIL-STD-454. A battle short will not be required.

3.3.6.1 Primary Power Circuits - Primary power circuits shall be isolated from the equipment enclosure or chassis.

3.3.6.2 Overload Protection - Overload protection shall conform to Requirement 8 of MIL-STD-454, Class 1. Protection shall be furnished by trip free circuit breakers in accordance with Para 3.2.14 of this specification.

3.3.6.3 Bonding - The equipment enclosure shall be furnished with a stud for grounding purposes. This stud shall be 3/8 inch dia (USS thread), spot welded to the cabinet.

3.3.6.3.1 Electrical bonding of access doors etc, shall be by means of bonding jumpers conforming to MS25083.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

3.3.7 Cabling - Internal conductors shall be combined into a harness wherever possible and securely held by lacing tape (see Para 3.3.3) or cable ducts. When cabling is carried across a hinge sufficient support, slack and protection shall be provided to prevent chafing or breakage with repeated flexing. Selection of cables shall be in accordance with Requirement 66 of MIL-STD-454.

3.3.8 Test Points - Test points shall be provided conforming to MIL-STD-415.

3.3.9 Enclosure - The basic enclosure shall conform to Class 2 of MIL-T-21200 and shall be watertight in accordance with MIL-STD-108. With the cover removed and the access door closed, the enclosure shall be drip-proof in accordance with MIL-STD-108.

3.3.9.1 Access Door - The internal access door shall be capable of being retained in its open position to prevent accidental closing due to ship movement. When open, covers, doors etc, shall not cause the equipment to overbalance.

3.3.9.2 Access Door Fastening - The internal access door shall be hinged on one of the longer sides and shall be fastened by a lever and three-point latch on the opposite side.

3.3.10 Panels - Panel layouts and arrangement of operating controls shall conform to MIL-T-21200. Lighting of control panels shall not be required.

3.3.11 Nomenclature and Nameplates - Nomenclature shall be requested and assigned in accordance with MIL-N-18307. Nameplates shall conform to MIL-N-18307.

3.3.12 Workmanship - General workmanship shall conform to Requirement 9 of MIL-STD-454.

3.4 Performance

3.4.1 Electrical - The equipment shall operate from a nominal 115V 60 Hz single phase supply. All performance requirements shall be met within the steady state tolerances of plus or minus 10 percent nominal voltage and plus or minus 5 percent of nominal frequency.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

3.4.1.1 Transient Voltage - The equipment shall withstand a voltage transient of up to plus or minus 20 percent of nominal from any point within the steady state limits, recoverable to the steady state limits within 2 seconds. Stated performance is not required during transients, but shall be recovered on recovery inside the steady state limits.

3.4.1.2 Transient Frequency - The equipment shall withstand a frequency transient of up to plus or minus 3 percent of nominal, from any point within the steady state limits such that total departure from nominal does not exceed plus or minus 6 percent of nominal, recoverable to the steady state limits within 2 seconds. Stated performance shall be maintained during frequency transients.

3.4.1.3 Power Interruption - The equipment shall withstand the following power interruptions:

(a) Power loss for up to 30 seconds.

(b) High voltage transients of up to 3.5 times nominal supply voltage of less than one cycle duration, ie: 16.7 milliseconds.

3.4.2 Vibration - Stated performance shall be maintained when subjected to MIL-T-21200, Class 2 vibration.

3.4.3 Shock - The equipment shall meet the requirements of Para 3.2.19.5 of MIL-T-21200.

Stated performance shall be maintained during and after all shock tests. Additionally, units stored internally (see 3.5.1) shall be protected from all damage associated with applied shocks as specified herein.

3.4.4 Environmental - Stated performance shall be maintained under any or all of the following environmental conditions:

3.4.4.1 Temperature

Operating	$-40^{\circ}C$ to $+55^{\circ}C$
Non-Operating	$-62^{\circ}C$ to $+85^{\circ}C$

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

3.4.4.2 Humidity

Up to 95% continuous, including conditions where condensation takes place in and on the equipment in the form of water and/or frost.

3.4.4.3 Salt Atmosphere - The equipment shall withstand, in an operating and non-operating condition, exposure to salt-sea atmosphere.

3.4.5 Operating Life - The equipment shall have a minimum total operating life of 5 years.

3.4.6 Reliability - The equipment, including any built-in test provisions, shall have a minimum Specified Mean Time Between Failures of 5000 hours.

3.4.7 Maintainability

3.4.7.1 Test Points - Test point provisions shall be in accordance with MIL-STD-454, Requirement 32.

3.4.7.2 Maintenance Times - The equipment, including any built-in-test provisions, shall be designed to meet the following quantitative maintainability requirements for corrective maintenance.

(a) Mean time to repair $\overline{M}_{ct}$ 0.1 hours.

(b) Maximum time to repair $M_{max\ ct}$ 1.0 hours (90th percentile)

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:32Z
Check the source to verify that this is the current version before use.

3.5 Detail Requirements

3.5.1 Function - The equipment shall provide for protective storage and charge of:

(a) Not exceeding quantity three (3) T-1129/URT-26(V) or T-1129A/URT-26(V). (or any combination not exceeding three).

(b) Not exceeding quantity three (3) BB-620/URT-26(V)

3.5.2 Charge Current - The equipment shall provide for selection of either of two charge rates for each stored unit. The two charge rates shall provide for 24 hour charge and continuous standby (trickle) charging respectively. The alternative charge rates shall be as follows:

	CHARGE (0.08C approx)		STANDBY (0.01C approx)	
T-1129	0.11A	(0.165A RMS)	20 mA	(30 mA RMS)
BB-620	0.11A	(0.2A RMS)	20 mA	(36 mA RMS)

3.5.2.1 Selection of Charge Rate - Charge rate selection shall be by means of six two position switches on the front of the equipment, one switch for each stored unit. There shall be no restriction on the possible combinations of charge rages selected for each stored unit.

3.5.3 Time Meter - The equipment shall contain an elapsed time meter monitoring the total number of hours of operation of the equipment. The time meter shall be visible from the front of the equipment. The meter shall conform to MIL-M-7793.

3.5.4 Emergency Shut-off Voltage Supply - The equipment shall include provision for an integral emergency voltage source to prevent inadvertent Beacon transmission in the event of power loss or failure while under charge or storage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

3.5.5 Battery Voltmeter - The equipment shall include, visible on the front of the equipment a voltmeter to enable monitoring of battery voltage under charge. Normal range of voltage for each type of battery shall be indicated on the scale of the meter. The meter shall monitor the following voltages:

(a) T-1129/URT-26(V) battery voltage Bay 1

(b) T-1129/URT-26(V) battery voltage Bay 2

(c) T-1129/URT-26(V) battery voltage Bay 3

(d) BB-620/URT-26(V) battery voltage Bay 1

(e) BB-620/URT-26(V) battery voltage Bay 2

(f) BB-620/URT-26(V) battery voltage Bay 3

(g) BB-620/URT-26(V) battery voltage under load (at test receptacle)

(h) BA-1109/URT-26(V) battery voltage under load (at test receptacle)

(i) internal emergency beacon shut-off battery voltage.

3.5.6 Beacon Shut-off Battery Stowage - The equipment shall provide for internal stowage of Battery, Dry (Beacon shut-off batteries) BA-1109/URT-26(V) while the associated Beacon is under charge or storage.

3.5.7 Controls - The equipment shall include the following controls accessible on the front face of the equipment:

(a) Main power on-off switch.

(b) 12 position BBM rotary switch enabling selection of voltage monitoring (see Para 3.5.5)

(c) 6 two-position toggle switches enabling selection of charge rates for each unit.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

3.5.8 Indicator - The equipment shall include a power on/off indicator lamp, which shall light when power is applied to the equipment. The lens and bulb color shall be white.

3.5.9 On-Load Battery Voltage Check - The equipment shall include provision for checking on-load voltages of BB-620/URT-26(V) Battery Assemblies and BA-1109/URT-26(V) Battery Dry (Beacon shut-off batteries). This test shall be performed via suitable test receptacles accessible on the front of the equipment.

3.5.10 Input Power - The equipment shall not exceed the following input power requirements:

115V 60 Hz 1 VA

3.5.11 Size - The equipment shall not exceed 48" H x 25" W x 31" D.

3.5.12 Weight: - The weight of the equipment shall be a minimum consistent with the requirements of this specification and shall not exceed 400 lbs.

3.5.13 Lifting Handles - The equipment shall include integral lifting handles, in accordance with Para 3.2.3.1.6 of MIL-T-21200.

3.5.14 Stowage of Internal Connectors - The equipment shall provide for stowage of unused internal cables and connectors when the full complement of stored units is not installed.

3.5.15 Instruction Plate - An instruction plate shall be provided on the front of the equipment providing at least the following information:

(a) Instructions for insertion, connection and removal of stored units;

Source: https://assist.dla.mil -- Downloaded: 202640-23T06:32Z
Check the source to verify that this is the current version before use.

(b) Instructions for charge rate selection and charging cycles information;

(c) Instructions for operation of the voltage monitor and performance of on-load tests, with information on serviceable unit voltages;

(d) A cautionary notice on handling of Beacons;

(e) Emergency procedure in case of inadvertent Beacon transmission.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any inspections deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Classification of tests - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable requirements:

(a) First article (preproduction) tests

(b) Initial production tests

(c) Acceptance tests

4.2 First article (preproduction) tests - First article (preproduction) tests shall be made on an equipment representative of the production equipments to be supplied under the contract. The tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approved test procedure of 4.5. The government inspector and the procuring activity shall be

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:32Z
Check the source to verify that this is the currentversion before use.

advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the services of a commercial testing laboratory acceptable to the Government.

4.2.1 First article (preproduction) test data - The contractor shall submit all data collected in conducting these tests to the procuring agency for review and approval.

4.2.2 Scope of tests - The tests shall include all tests deemed necessary, by the procuring activity, to determine that the equipment meets all the requirements of this specification, other applicable specifications and the contract. First article tests shall include environmental tests in accordance with MIL-T-21200.

4.2.3 First article (preproduction) approval - Approval of the test sample shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the test sample. Prefabrication of production equipment prior to the approval of the test sample is at the contractor's own risk. The approved test sample shall be retained by the contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The test sample shall not be considered as one of the equipments under the contract, however, the test sample may be refurbished and submitted for acceptance tests at the option of the contractor.

4.2.4 Production equipments - Equipments supplied under the contract shall in all respects, including design, construction, workmanship, performance and quality, be equivalent to the approved test sample. Each equipment shall be capable of successfully passing the same tests as imposed on the test sample. Evidence of non-compliance with the above shall constitute cause for rejection and for equipment already accepted by the Government, it shall be the obligation of the contractor to make necessary corrections as approved by the procuring activity.

4.3 Initial production tests - One of the first ten production equipments shall be selected and sent at the contractor's expense to a designated Government laboratory for tests. This equipment shall be selected by the procuring activity after the equipment has successfully passed all individual tests. The test sample shall not be selected for this test.

Source: https://assist.dla.mil -- Downloaded: 202640-23T06:32Z
Check the source to verify that this is the current version before use.

4.3.1 Scope of tests - This equipment may be subjected to any and all tests the procuring activity deems necessary to assure that the production equipment is equivalent to the previously approved test sample in design, construction, workmanship, performance and quality and that it meets all applicable requirements.

4.3.2 Accessory material - In addition to the complete equipment submitted for Initial Production Tests, the contractor shall also submit such accessory material and data necessary to test the equipment.

4.3.3 Initial production sample approval - Approval of the initial production sample shall be by the procuring activity upon satisfactory completion of all tests. Any design, material or performance defect made evident during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Failure of the initial production sample to pass any of the tests shall be cause for deliveries of equipment under the contract to cease until proper corrective action is approved and accomplished. Corrective action shall also be accomplished on equipment previously accepted when requested by the procuring activity.

4.3.4 Reconditioning of initial production test sample - On completion of the initial production test, the equipment shall be reworked by the contractor by replacing all wear or damaged items. After reworking, the contractor shall resubmit the equipment for acceptance.

4.4 Acceptance tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the government inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory, as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

(1) Individual tests (4.4.1)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

(2) Special tests (4.4.2)

4.4.1 Individual tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests:

(1) Examination of product (4.4.1.1)

(2) Operational test (4.4.1.2)

(3) Manufacturing run in test (4.4.1.3)

4.4.1.1 Examination of product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.4.1.2 Operational test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

NOTE: Approval of the operational test procedure must be obtained from the Naval Air Systems Command prior to testing.

4.4.1.3 Manufacturing run in test - Each equipment shall be operated under the conditions specified herein for a period of 6 hours without failure. A failure shall be defined as anything which causes malfunctioning of the equipment. Only those adjustments will be permitted which can be made by using such controls and adjustments that are accessible to the operator during the normal use of the equipment.

Temperature	Ambient room
Humidity	Ambient room

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:32Z
Check the source to verify that this is the current version before use.

During the 6-hour period of operation, the equipment shall be mechanically cycled periodically through its various phases of operation. Should a failure occur, it should be repaired and the test started over. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures. The 6-hour period specified above may be composed of two 3-hour periods to conform with standard working hours.

4.4.2 Special tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling tests.

4.4.2.1 Special test schedule - Selection of equipments for special tests shall be made as follows:

(1) On an early equipment after an engineering or material change.

(2) Whenever failure reports or other information indicate additional tests are required. (This will be determined by the procuring activity).

4.4.2.2 Scope of tests - Special tests shall consist of such tests as approved by the procuring activity. Test procedures previously approved for the preproduction tests shall be used where applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

4.4.3 Equipment failure - Should a failure occur during either the sampling or special tests, the following action shall be taken:

(1) Determine the cause of failure.

(2) Determine if the failure is an isolated case or design defect.

(3) Submit to the procuring activity for approval, proposed corrective action intended to reduce the possibility of the same failure(s) occurring in future tests.

(4) Where practical, include a test in the individual test to check all equipment for this requirement until reasonable assurance is obtained that the defect has been satisfactorily corrected.

4.4.4 Reconditioning of tested equipment - Equipment which has been subjected to acceptance tests shall be reconditioned by the contractor by replacing all wear or damaged items. After reworking, the contractor shall resubmit the equipment for acceptance.

4.5 Test procedures - The procedures used for conducting preproduction tests and acceptance tests shall be prepared by the contractor and submitted to the procuring activity for review and approval. The right is reserved by the procuring activity or the government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification and the contract. MIL-T-18303 shall be used as a guide for preparation of test procedures. When approved test procedures are available from previous contracts such procedures will be provided and may be used when their use is approved by the procuring activity. However, the right is reserved by the procuring activity to require modification of such procedures, including additonal tests, when deemed necessary.

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:32Z
Check the source to verify that this is the current version before use.

4.6 Presubmission testing - No item, part or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.7 Rejection and retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished to the government inspector.

5. PREPARATION FOR DELIVERY

5.1 Preservation and Packaging - Preservation and packaging for delivery shall be as specified in the individual contract.

6. NOTES

6.1 Intended Use - The equipment covered by this specification is intended for Naval service where it is expected to withstand continuous use for long periods under military service conditions with a minimum of attention. This equipment is particularly intended for use on aircraft carriers to support aircraft carrying an AN/ASH-20(V)_ _ Flight Recorder-Locator System. It provides a facility for local storage of spare Beacons and Battery Assemblies ready for instant use, and additionally a means for temporarily securing these units and maintaining them fully operational should their associated airplane be down without external power for extended periods.

It is intended that the Cabinet, Equipment Stowage-Battery Charging be installed as close as possible to the aircraft maintenance area to minimize the possibility of accidental damage to the Beacons while being transferred from the airplane to the Cabinet or vice versa.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

6.2 Precedence of Documents - When the requirements of the contract, this specification or subsidiary specifications are in conflict, the following precedence shall apply:

(1) The contract

(2) This specification

(3) Referenced specifications.

6.3 Ordering Data - Procurement documents should specify title, number and date of this specification.

Custodians:

Naval Air Systems Command
NAVY-AS

Preparing Activity:

NAVY-AS

Project No. 5825-N007

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:32Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

MIL-C-81972(AS) CABINET, EQUIPMENT STOWAGE - BATTERY CHARGING BCU-13/E

NAME OF ORGANIZATION AND ADDRESS	CONTRACT NUMBER
	MATERIAL PROCURED UNDER A ☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*	TELEPHONE NO.
	DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED S/N 0102-014-1802

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:32Z
Check the source to verify that this is the current version before use.