MILITARY SPECIFICATION

CONNECTOR, PLUG, ELECTRICAL UG-1870( )/U
CONNECTOR, RECEPTACLE, ELECTRICAL UG-1837( )/U

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope.- This specification covers Connector, Receptacle, Electrical UG-1837( )/U used on Test Set AN/PTM-7, Restorers TD-206 and on Shelters of Low, Medium and High Capacity, Tropo Subsystems of Army Area Communications Systems. The receptacle mates with Connector, Plug, Electrical UG-1870( )/U which terminates Cable Assemblies, Special Purpose, Electrical CX-11230( )/G and CX-10734( )/G. The connectors are hermaphroditic, twin coaxial and watertight. (See 6.3).

2. APPLICABLE DOCUMENTS

2.1 Documents.- The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

PPP-B-566	Boxes, Folding Paperboard.
PPP-B-636	Boxes, Fiberboard.
PPP-B-676	Boxes, Set-up, Paperboard.
PPP-P-291	Paperboard, Wrapping, Cushioning.
PPP-T-45	Tape, Gummed, Paper Reinforced.

MILITARY

MIL-P-116	Preservation, Methods of.
MIL-M-13231	Marking of Electronic Items.
MIL-F-14072	Finish for Ground Signal Equipment.

FSC 5935

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	Marking for Shipment and Storage.
MIL-STD-202	Test Methods for Electronic and Electrical Component Parts.
MIL-STD-454	Standard General Requirements for Electronic Equipment.

DRAWINGS

ELECTRONICS COMMAND

GL-SM-B-323070	Gages for Connector UG-1837( )/U.
SC-GL-323378	Gages for Connector UG-1870( )/U.
DL-SC-A-339550	Connector, Plug, Electrical UG-1870( )/U.
DL-SC-B-598923	Connector, Receptacle, Electrical UG-1837( )/U.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies.)

3. REQUIREMENTS

3.1 First article.- When specified in the contract, the contractor shall furnish first article units in accordance with 4.3.

3.2 Construction.- Connector, Receptacle, Electrical UG-1837( )/U shall be constructed in accordance with the requirements of this specification, and of DL-SC-B-598923 and Connector, Plug, Electrical UG-1870( )/U shall be constructed in accordance with the requirements of this specification, and of DL-SC-A-339550.

3.3 Cast and molded parts.-

3.3.1 Casting.- Castings shall be of uniform quality and condition, and free from cracks, harmful shrinkage, porosity, gas holes, foreign matter, and other injurious defects. The surface of the castings shall be free from pits, parting lines, porous areas, fins, ridges, modules, raised metal, and scale. All castings shall be completely cleaned prior to presentation for inspection. Castings shall not be plugged or welded, nor shall imperfections be filled in.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

3.3.2 Molded parts.- Molded parts shall be uniform in quality, condition, and color. The molded parts shall be clean, smooth, free from porous areas, foreign materials, weak sections, bubbles, flash and any other injurious defects.

3.4 Soldering.- Soldering used for electrical connections shall conform to Requirement 5 of MIL-STD-454.

3.5 Cleaning.-

3.5.1 Parts.- After fabrication, parts shall be cleaned in accordance with good commercial practice. Cleaning processes shall have no deleterious effect. Corrosive material shall be removed completely before the parts are assembled.

3.5.2 Units.- After assembly, units shall be cleaned thoroughly and shall be free from particles of solder, flux, and other foreign material. In addition, when necessary, such cleaning shall also be performed before final assembly of the units.

3.6 Finish.- Connectors shall be given protective finish in accordance with MIL-F-14072 and connector drawings. (See 4.4).

3.7 Marking.- Marking shall conform to MIL-M-13231 and connector drawings. (See 4.4).

3.8 Interchangeability.- Like units, and assemblies shall be physically and functionally interchangeable, without modification of such items. Individual items shall not be handpicked for fit or performance. Where a listed dimension is not within design limits, it shall be considered a major defect. (See 4.8).

3.9 Electrical requirements.-

3.9.1 Continuity.- Continuity shall exist between each mated pair of contacts. (See 4.6.1).

3.9.2 Dielectric withstanding voltage.-

3.9.2.1 Coaxial contacts.- Each coaxial contact shall withstand a potential of 2,500 volts dc between the center contact and the outer contact for 1 minute when tested in accordance with 4.6.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

3.9.2.2 Outer contacts.- The outer contacts of the coaxial elements shall withstand a potential of 1,500 volts dc for 1 minute when tested in accordance with 4.6.2.

3.9.3 Insulation resistance.- Insulation resistance shall be not less than 50,000 megohms between the center and outer contacts of each coaxial element and between the outer contacts of the coaxial elements when tested in accordance with 4.6.3.

3.10 Environmental requirements.-

3.10.1 Rotation.- The torque required to rotate the coupler shall not exceed 0.75 inch pounds when tested in accordance with paragraph 4.7.1.

3.10.2 Salt spray.- After subjection to the test specified in 4.7.2, the plating shall remain intact and the connectors shall show no evidence of deterioration and in addition Connector UG-1870( )/U shall meet the requirements of 3.10.1.

3.10.3 Thermal shock.- The connectors shall meet the requirements of 3.9.1, 3.9.2 and 3.9.3 after being subjected to the test specified in 4.7.3. There shall be no evidence of deterioration.

3.10.4 Shock.- The connectors shall withstand the shock test specified in 4.7.4 without damage or loosening of parts and shall meet the requirements of 3.9.1, 3.9.2 and 3.9.3.

3.10.5 Shock drop.- After being subjected to the test specified in 4.7.5, there shall be no damage and/or loosening of parts and the connectors shall be mechanically operable. Any physical damage shall be minor and shall meet the requirements of 3.9.1, 3.9.2 and 3.9.3.

3.10.6 Vibration.- The connectors shall withstand the vibration test specified in 4.7.6 without damage or loosening of parts and meet the requirements of 3.9.1, 3.9.2 and 3.9.3.

3.10.7 Pull.- While being subjected to the test specified in 4.7.7, there shall be no loss of continuity of either center conductor or conductor braid. The cable and the connectors shall also meet the requirements of 3.9.1, 3.9.2 and 3.9.3. The locking devices shall not become detached from the connectors.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

3.10.8 Water immersion.- There shall be no deterioration or evidence of water leakage in the connector and the connector shall meet the requirements of 3.9.1, 3.9.2 and 3.9.3. (See 4.7.8).

3.10.9 Moisture resistance.- After being subjected to the test specified in 4.7.9, the assemblies shall meet the requirements of 3.9.1, 3.9.2 and 3.9.3 except that the IR shall be a minimum of 100 megohms during cycling and a minimum of 10,000 megohms after 24 hours drying. The connectors shall show no evidence of deterioration.

3.10.10 Temperature cycling.- During the test specified in 4.7.10, the connectors shall be electrically continuous and meet the requirements of 3.9.1, 3.9.2, 3.9.3 and shall show no evidence of deterioration.

3.11 Workmanship.- The connectors shall meet the applicable portions of the following paragraphs: (See 4.9).

3.3 Cast and molded parts
3.4 Soldering
3.5 Cleaning

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspections.- The inspection requirements specified herein are classified as follows:

(a) First article inspection. (See 4.3). Does not include preparation for delivery.

(b) Inspections covered by subsidiary documents. (See 4.4).

(c) Quality conformance inspections.

(1) Quality conformance inspection of equipment before preparation for delivery. (See 4.5).

(2) Quality conformance inspection of preparation for delivery. (See 4.10).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

4.3 First article.- Unless otherwise specified in the contract, the first article inspection shall be performed by the contractor.

4.3.1 First article units.- The contractor shall furnish twelve (12) first article units of the complete UG-1870( )/U and/or UG-1837( )/U connector(s).

4.3.2 First article inspection.- The first article inspection shall consist of the inspections specified in subsidiary documents covering the items listed in 4.4 and the inspections specified in Table I.

4.3.3 First article data.- The first article test plan and test report(s) shall be as required in the contract.

Table I.- First article inspection

Inspection	Req Para	Test Para	Number of Units to be Tested
Inspection covered by subsidiary documents		4.4	Inspection to be performed on all units
Group A inspection	See Table II		Inspection to be performed on all units
Group B inspection	See Table III		Inspection to be performed on all units
Group C inspection			
Subgroup 1	See Table IV		Inspection to be performed as specified in test paragraphs
Subgroup 2	See Table IV		Inspection to be performed as specified in test paragraphs

4.4 Inspections covered by subsidiary documents.- The following shall be inspected under the applicable subsidiary documents as part of the inspection required by this specification, and the inspection requirement specified in the contract.

Item	Where required
Finish	3.6
Marking	3.7

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

4.5 Quality conformance inspection of equipment before preparation for delivery.- The contractor shall perform the inspections specified in 4.4 and 4.5.1 through 4.5.3. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements.

4.5.1 Group A inspection.- Each unit on contract shall be inspected for conformance to the inspections specified in Table II. Discrete lots shall be formed from units that pass this inspection. Factors of lot composition not defined herein, or in the contract, shall be in accordance with MIL-STD-105. Each lot shall be subject to sampling inspection, utilizing the procedures of MIL-STD-105, using the general inspection levels, the AQLs indicated in Table II.

4.5.1.1 Order of inspection within Group A.- Group A inspection shall be performed in an order satisfactory to the Government.

Table II.- Group A inspection

Inspection	Req Para	Insp Para	AQL Major	AQL Minor
Visual and mechanical	3.11	4.9	1.0%	4.0%
Continuity	3.9.1	4.6.1)		
Dielectric withstanding voltage	3.9.2	4.6.2)	1.0%	*
Insulation resistance	3.9.3	4.6.3)	combined	

* All electrical tests are considered major.

4.5.2 Group B inspection.- Group B inspection shall normally be performed in inspection lots that have passed Group A inspection and on samples selected from units that have been subjected to and met the Group A inspection. This inspection shall conform to Table III and to the special inspection levels of Table I of MIL-STD-105.

4.5.2.1 Group B sampling plans.- The Group B AQLs shall be 1.0 percent defective and the inspection levels shall be S-3.

4.5.2.2 Order of inspection within Group B.- Group B inspection shall be in an order satisfactory to the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

Table III.- Group B inspection

Inspection	Req Para	Insp Para
Interchangeability	3.8	4.8
Rotation (Connector Plug only)	3.10.1	4.7.1
Pull (Connector Plug only)	3.10.7	4.7.7
Water immersion	3.10.8	4.7.8

4.5.3 Group C inspection.- Group C inspection shall be performed on units that have passed Group A and Group B inspection. The inspection shall consist of the inspections specified in Table IV. Samples shall be selected in accordance with 4.5.3.1.

4.5.3.1 Sampling for Group C inspection.-

4.5.3.1.1 Subgroup 1.- For this subgroup, four (4) connectors shall be selected from the first units produced or first production lot. For subsequent Group C inspection, four (4) connectors shall be selected every 3 months or 1,500 units, whichever comes first.

4.5.3.1.2 Subgroup 2.- For this subgroup, two (2) connectors shall be selected from the first production lot. For subsequent Group C inspection two (2) connectors shall be selected every 6 months or every 6,000 units, whichever comes first.

4.5.3.2 Order of inspection within Group C.- Group C inspection shall be performed in an order which is satisfactory to the Government.

Table IV.- Group C inspection

Inspection	Req Para	Insp Para
Subgroup 1		
Salt spray *	3.10.2	4.7.2
Thermal shock	3.10.3	4.7.3
Shock (Connector Plug only)	3.10.4	4.7.4
Shock drop (Connector Plug only)	3.10.5	4.7.5
Vibration	3.10.6	4.7.6
Subgroup 2		
Moisture resistance	3.10.9	4.7.9
Temperature cycling	3.10.10	4.7.10

* The equipment shall be thoroughly washed, cleaned, dried and refurbished after this inspection before proceeding with subsequent inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

4.5.3.3 Group C failures.- Actions required relative to Group C failures shall be as specified in the contract.

4.5.4 Reinspection of conforming Group C sample units.- Unless otherwise specified, sample units which have been subjected to and passed Group C inspection may be accepted on the contract provided all damage is repaired and the sample units are re-subjected to and pass Group A inspection only.

4.5.5 Disposition of Group C sample units.- Unless otherwise specified, sample units which have been subjected to and passed Group C inspection may be delivered on the contract, provided sample units meet requirements of 4.5.4.

4.6 Electrical tests.-

4.6.1 Continuity.- The connector under test shall be mated to a Connector, Plug, Electrical UG-1870( )/U containing a contact assembly from current production, to determine compliance with the requirements specified in 3.9.1.

4.6.2 Dielectric withstanding voltage.- This test shall be conducted in accordance with MIL-STD-202, Method 301 to determine compliance with 3.9.2.

4.6.3 Insulation resistance.- This test shall be conducted in accordance with MIL-STD-202, Method 302, Test Condition B to determine compliance with 3.9.3.

4.7 Environmental tests.-

4.7.1 Rotation.- A torque shall be applied to the coupler of Connector UG-1870( )/U. The torque shall be measured with a torque wrench to determine conformance to 3.10.1.

4.7.2 Salt spray.- Four unmated connectors not assembled to cable shall be subjected to the salt spray (corrosion) test in accordance with MIL-STD-202, Method 101, Condition B, and meet the requirements of 3.10.2.

4.7.3 Thermal shock.- Four connectors each wired to 5 feet of Cable WD-37( )/U shall be tested in accordance with MIL-STD-202, Method 107, Test Condition A. The minimum time exposure to steps 1 and 3 shall be 1 hour after thermal equilibrium has been established. After completion of the fifth cycle, the connectors shall meet the requirements of 3.10.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

4.7.4 Shock.- Four coupled Connectors UG-1870( )/U, each wired to 5 feet of Cable WD-37( )/U shall be tested in accordance with MIL-STD-202, Method 205, Test Condition C, or Method 202 at equivalent acceleration to determine compliance with the requirements of 3.10.4.

4.7.5 Shock drop.- Four unmated Connectors UG-1870( )/U, each wired to 5 feet of Cable WD-37( )/U, shall be dropped at random six (6) times with protective caps coupled to the connectors, and six (6) times with protective caps dangling from a height of 10 feet onto 2 inch fir wood backed by concrete to determine conformance to the requirements of 3.10.5. The connectors shall be visually examined and the caps tightened after each drop.

4.7.6 Vibration.- Four connectors each wired to 5 feet of Cable WD-37( )/U shall be tested in accordance with MIL-STD-202, Method 204, Test Condition A and meet the requirements of 3.10.6. Plugs shall be mated and mounted to the vibration table. Receptacles shall be mounted using connector components.

4.7.7 Pull.- Connectors UG-1870( )/U shall be wired to 5 feet of Cable WD-37( )/U. A static load of 400 pounds shall be applied gradually to the assemblies mated, and approximately 2 feet of cable on each assembly. The load shall be applied for a duration sufficient to complete the tests and meet the requirements specified in 3.10.7.

4.7.8 Water immersion.- The connectors wired to 5 feet of Cable WD-37( )/U shall be immersed to a depth of 3 feet of water for 16 hours to determine compliance with the requirements of 3.10.8. Fifty percent of the connectors shall be mated, twenty-five percent shall be with protective cover in place, and twenty-five percent shall be without protective cover. When the sample size is not a multiple of four (4), the odd connector(s) shall be tested with protective cover(s) in place. The receptacle shall be mounted to a metal waterproof box, not less than 1/8 inch thick, using the mounting nut. The hole where the cable enters the box shall be sealed.

4.7.9 Moisture resistance.- Two connectors wired to 5 feet of Cable WD-37( )/U shall meet the requirements of 3.10.9 after subjection to 10 cycles of moisture resistance in accordance with MIL-STD-202, Method 106, except that the vibration sub-cycle shall be omitted. Measurements shall be made during the periods shown on the standard. The receptacle shall be mounted to a metal waterproof box, not less than 1/8 inch thick, using the mounting nut. The hole where the cable enters the box shall be sealed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

4.7.10 Temperature cycling.- Two connectors wired to 5 feet of Cable WD-37( )/U shall meet the requirements of 3.10.10, during the temperatures listed in Table V.

Table V.- Temperature cycle

Step	Temperature (C)	Time (Hours)
1	85 ± 2	4
2	$25 \begin{smallmatrix}+10\\-5\end{smallmatrix}$	4
3	-55 ± 2	4
4	$25 \begin{smallmatrix}+10\\-5\end{smallmatrix}$	4

4.8 Interchangeability.- The connectors shall be gaged using gages listed on SC-GL-323378 and GL-SM-B-323070 to determine conformance to the physical interchangeability requirements of 3.8.

4.9 Visual and mechanical inspection.- Connector, Receptacle, Electrical UG-1837( )/U and Connector, Plug, Electrical UG-1870( )/U shall be examined for defects listed in Table VI and meet the requirements of 3.11.

Table VI.- Classification of visual and mechanical defects

Classification	Defects
Major	Threads chipped, broken or stripped. Rubber parts cut or ripped. Coupler not operating freely. (plug only). Substandard plating. (flaking, peeling, blisters, etc.). Contacts missing, broken or bent. Scratches, cuts, abrasions, etc., with exposure of bare metal. Any foreign objects or material preventing the mating of connectors. Finish not as specified. Insulators cracked or broken.
Minor	Missing parts. Scratches, cuts, abrasions, etc., without exposure of bare metal. Abrasions on rubber parts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

4.10 Quality conformance inspection of preparation for delivery.- Preparation for delivery shall be in accordance with the requirements of section 5.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.- Preservation and packaging shall be level A or C, as specified. (See 6.2).

5.1.1 Level A.-

5.1.1.1 Cleaning.- Connectors UG-1837( )/U and UG-1870( )/U shall be cleaned in accordance with MIL-P-116, process C-1.

5.1.1.2 Drying.- Connectors UG-1837( )/U and UG-1870( )/U shall be dried in accordance with MIL-P-116.

5.1.1.3 Preservation application.- None required.

5.1.1.4 Unit packaging.- Connectors UG-1837( )/U and UG-1870( )/U shall be individually packaged in accordance with MIL-P-116, Method III. Cushion each connector by wrapping in paperboard conforming to PPP-P-291. Secure cushioning with tape conforming to PPP-T-45. Place each cushioned connector within a close-fitting box conforming to PPP-B-566 or PPP-B-676.

5.1.1.4.1 Intermediate packaging.- Connector packaged as specified in 5.1.1.4, shall be placed in intermediate containers conforming to PPP-B-566 or PPP-B-676. Intermediate containers shall be uniform in size, shape and quantities, shall be of minimum tare and cube and shall contain multiples of 5 unit packages, not to exceed 50 packages. No intermediate packing is required when the total quantity shipped to a single destination is less than 50 unit packages.

5.1.2 Level C.- Cleaned and dried connectors shall be individually packaged in a manner that will afford adequate protection against corrosion, deterioration and physical damage during shipment from supply source to the first receiving activity.

5.2 Packing.- Packing shall be Level A, B or C, as specified. (See 6.2).

5.2.1 Level A.- The packaged Connectors UG-1837( )/U and UG-1870( )/U shall be packed in fiberboard containers conforming to PPP-B-636, class weather resistant, style optional, special requirements. Closure shall be in accordance with the appendix to the box specification. Banding (reinforcement requirements) shall be applied in accordance with the appendix to PPP-B-636 using non-metallic or tape banding only.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

5.2.2 Level B.- Same as 5.2.1.

5.2.3 Level C.- The packaged Connectors UG-1837( )/U and UG-1870( )/U shall be packed in shipping containers in a manner that will afford adequate protection against damage during direct shipment from the supply source to the first receiving activity. These packs shall conform to the applicable carrier rules and regulations.

5.3 Marking.- In addition to any special marking required by the contract, each unit package, intermediate and exterior container shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use.- Connector, Receptacle, Electrical UG-1837( )/U is used on Test Set AN/PTM-7, Restorers TD-206 and on shelters to mate with Connector UG-1870( )/U which terminate Cable Assemblies CX-11230( )/G and CX-10734( )/G.

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number and date of document.

(b) Type required.

(c) Level of packaging and level of packing required for shipment. (Level A, B or C).

(d) Place of final inspection.

6.3 Nomenclature.- The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example, UG-1837W/U. The contractor should apply for nomenclature in accordance with the applicable clause in the contract. (See 1.1).

6.4 Group C inspection.- Approval to ship may be withheld, at the discretion of the Government, pending the decision from the contracting officer on the adequacy of corrective action. (See 4.5.3).

CUSTODIAN

ARMY EL

Preparing Activity

ARMY EL

Project No. 5935-A017

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

To detach this form, cut along this line

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No 22-R255

INSTRUCTIONS This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost Comments and the return of this form will be appreciated Fold on lines on reverse side, staple in corner, and send to preparing activity Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements

SPECIFICATION MIL-C-55661B(EL) CONNECTOR, PLUG, ELECTRICAL UG-1870 ( )/U CONNECTOR, RECEPTACLE, ELECTRICAL UG-1837( )/U

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1 HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A GIVE PARAGRAPH NUMBER AND WORDING

B RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2 COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3 IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4 REMARKS *(Attach any pertinent data which may be of use in improving this specification If there are additional papers attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED

ESC-PM 1068-68

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army
Headquarters
U.S.Army Electronics Command
Fort Monmouth, New Jersey 07703

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding General
U.S.Army Electronics Command
ATTN: AMSEL-RD-TS
Fort Monmouth, New Jersey 07703

FOLD

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:50Z
Check the source to verify that this is the current version before use.