MILITARY SPECIFICATION

GENERATOR SET, GASOLINE ENGINE, TRAILER MOUNTED

3KW, 60 HERTZ, PU-625/G

This amendment forms a part of Military Specification MIL-G-52636B(ME), dated 24 April 1978, and is approved for use by the USA Belvoir Research, Development, and Engineering Center, Department of the Army and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 2

2.1, under SPECIFICATIONS, FEDERAL, delete:

"PPP-P-40 - Packaging and Packing of Hand Tools."

2.1, under SPECIFICATIONS, MILITARY, delete:

"MIL-P-116 - Preservation Packaging, Methods of."

and substitute:

"MIL-P-116 - Preservation, Methods of."

2.1, under STANDARDS, MILITARY, delete:

"MIL-STD-1188 - Commercial Packaging of Supplies and Equipment."

and add:

"MIL-STD-889 - Dissimilar Metals."

AMSC N/A FSC 6115

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:27Z
Check the source to verify that this is the current version before use.

After 2.1, add the following new paragraph:

"2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein. Unless otherwise specified, the issues shall be those in effect on the date of the solicitation."

"US DEPARTMENT OF COMMERCE

Product Standard PS-1 - Softwood Plywood; Construction and Industrial.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)"

2.2, delete in its entirety and add the following:

"2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted shall be those listed in the issue of the DoDISS specified in the solicitation. Unless otherwise specified, the issues of documents not listed in the DoDISS shall be the issue of the nongovernment documents which is current on the date of the solicitation."

ANSI/HPMA-HP 1983 American National Standard for Hardwood and Decorative Plywood.

(Application for copies should be addressed to American National Standards Institute, 1430 Broadway, New York, NY 10018.)

*"(Nongovernment standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)

* "2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, (except for associated detail specifications, specifications sheets or MS standards), the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained."

After 3.1.1.1, add the following paragraph:

"3.1.1.2 Safety. Any changes, deviations, and waivers to TA13205E5150 shall conform with the following requirements. All rotating or reciprocating parts and other parts subject to high operational temperatures that are of such a nature or"

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:27Z
Check the source to verify that this is the current version before use.

"are so located as to be a hazard to operating personnel, shall be guarded or insulated to the extent necessary to eliminate the hazard. Electrical equipment shall be effectively guarded and grounded to protect all persons and objects from electrical shock hazard."

PAGE 4

3.2, delete in its entirety and substitute:

* "3.2 First article. Unless otherwise specified (see 4.3 and 6.3), a sample shall be subjected to first article inspection (see 4.3 and 6.3). Any changes or deviations of generator sets from the approved first article during production will be subject to the approval of the contracting officer. Approval of the first article will not relieve the contractor of his obligation to furnish generator sets conforming to this specification.

3.3, delete in its entirety and substitute:

"3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions in 3.3.1, 3.3.2, and 3.3.3 of this specification."

"3.3.1 Material deterioration and control. The item(s) shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operation and storage environment to which the item may be exposed.

"3.3.2 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

"3.3.3 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with component and subcomponent, and shall make information available upon request to the contracting officer or designated representative.

"3.3.4 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the generator sets may be newly fabricated from recovered materials to the maximum extent practicable, provided the generator sets produced meet all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the generator sets."

* 3.4, under "Item No. 1, Description", after "cargo" delete "M101A1" and substitute "M101A2".

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:27Z
Check the source to verify that this is the current version before use.

* 3.4, under "Item No. 1, Identification", delete "MIL-T-10579" and substitute "NSN 2330-01-102-4697".

3.4, under "Item NO. 2, Identification," delete "FSN" and substitute "NSN".

3.4, after Item No. 2, add:

"3. Cover assembly, cargo body, top NSN 2540-00-513-9794 1"

3.5, after last sentence add: "External surfaces shall be free from burrs, sharp edges and corners except when sharp edges and corners are specified on the applicable drawings."

4.1, line 6, after "perform" add "or repeat".

4.1.1, line 2, delete "Supplementary,".

Line 3, delete "(SQAP)" and substitute "(QAP)".

Line 4, delete "SQAP" and substitute "QAP".

PAGE 5

4.1.2, line 1 and 3, delete "preproduction" and substitute "first article".

4.2, line 3, delete "preproduction" and substitute "first article (see 4.3)".

4.3, line 1, delete "Preproduction inspection" and substitute "First article inspection".

PAGE 6

4.5.1, under defects, delete "101 through 106" in their entirety and substitute:

"101. Material not as specified.
102. Materials are not resistant to corrosion or deterioration or treated to be made resistant to corrosion or deterioration for the applicable storage and operating environment.
103. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other.
104. Contractor does not have documentation available for identification of material, material finishes or treatments.
105. Used, rebuilt, or remanufactured components, pieces or parts incorporated in the generator sets.
106. Treatment and painting not as specified.
107. Dimensions not as shown on drawings.
108. Components missing or not as specified.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:27Z
Check the source to verify that this is the current version before use.

109. Assembly not as shown on the drawings.
110. Workmanship not as specified.
111. Safety not as specified."

4.5.2.1, under (b) after "the" and before "cables" insert "power input" and delete "a commercial power source as follows:", and substitute "the generator sets as follows:"

4.5.2.1, after (4), add the following:

"(c) A 3 phase, 4 wire, 3 KW resistive load shall be connected to the output of the switch box."

4.5.2.3, delete in its entirety and substitute:

"4.5.2.3 Operation. The rotary switch of the switch box shall be placed in the generator No. 1 position. Start and operate generators in accordance with operator's manual at the rated load through the rotary switch for not less than 5 minutes. During this period, phase sequence (rotation) shall be tested in accordance with MIL-STD-705, method 507.1. Phase rotation shall be L1, L2, and L3. This test shall be performed at the load terminals of the switch box. Phase rotation not as specified shall constitute failure of this test. At the conclusion of the generator No. 1 position test, the rotary switch shall be placed in the generator No. 2 position. Repeat the test. Inability of the switch box assembly to maintain or transfer a rated load shall constitute failure of this test. Failure of the GFE generators to operate in accordance with the operator's manual shall not constitute failure of the test. The contracting officer shall be notified immediately of any such failure."

4.6.1, line 1, delete "preproduction" and substitute "first article".

4.6.2.3, under defects delete "107 thru 116" in their entirety and substitute:

"112. Generator sets not preserved as specified.
113. Fire extinguisher not removed and preserved as specified.
114. Power cables and ground wires not disconnected and secured and the cables and terminals not matchmarked as specified.
115. Technical publications not preserved as specified for all levels.
116. Trailer chassis components not preserved as specified.
117. Packing not in accordance with applicable figures for the level required.
118. Marking illegible, incomplete, incorrect, or missing.
119. Depreservation guides not prepared and attached to the power units as specified."

5.1, line 1, 6, 7, 8, delete "preproduction" and substitute "first article".

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:27Z
Check the source to verify that this is the current version before use.

PAGE 8

5.1, line 2, delete "preproduction" and substitute "first article".

5.2, line 1, delete "commercial" and substitute "Level C".

5.2.1.4 and 5.2.1.5, delete in their entirety.

PAGE 9

5.2.2.3, delete in its entirety.

5.2.3, delete in its entirety and substitute:

"5.2.3 Level C. Power units and all surfaces requiring it, shall be preserved to provide protection against deterioration and damage during shipment and handling from the contractor to the initial destination. Cables, fuel, and oil drain lines shall not be disconnected. Technical publications shall be placed in a waterproof bag and secured to the generator set."

5.3, line 1, delete "commercial" and substitute "Level C".

5.3.2, delete in its entirety and substitute:

"5.3.2 Level C. Power units shall be completely mobile. Any components not placed in brackets shall be placed in an out-of-the-way area and secured to prevent movement. The tarpaulin cover shall be in place upon its bows."

5.4, 5.4.1, and 5.4.2, delete in their entirety and substitute:

"5.4 Marking. Marking shall be in accordance with MIL-STD-129."

PAGE 10

6.2, (b) and (c), delete "preproduction" and substitute "first article".

6.2, (d), delete in its entirety and substitute:

"(d) Level of preservation and of packing required (see 5.2 and 5.3)."

6.3, delete in its entirety and substitute the following:

"6.3 First article. When a first article inspection is required, the items should be a preproduction model. The first article should consist of 1 or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, tests, and approval of the first article test results and disposition of the first article."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:27Z
Check the source to verify that this is the current version before use.

6.5, line 1, title, delete "Supplementary Quality Assurance Provisions (SQAP)", and substitute, "Quality Assurance Provisions (QAP)".

Line 2, delete "SQAP" and substitute "QAP".

Line 5, delete "SQAP" and substitute "QAP".

6.6.1, line 1, title, delete "Supplementary Quality Assurance Provisions (SQAP)" and substitute "Quality Assurance Provisions (QAP)".

Lines 1 and 3, delete "SQAP" and substitute "QAP".

PAGE 11

6.7, line 1, 2, and 3, delete "preproduction" and substitute "first article".

6.10, delete in its entirety.

The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

PAGE 12

Table I, under NOTES: first line, change "PS 51" to ANSI/HPMA-HP 1983".

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 6115-A511

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:27Z
Check the source to verify that this is the currentversion before use.

Source: https://assist.dla.mil -- Downloaded: 2026-04-22T21:27Z
Check the source to verify that this is the current version before use.