MIL-P-52284B
21 September 1983
SUPERSEDING
MIL-P-52284A
10 March 1970

MILITARY SPECIFICATION

POST, HANDRAIL, FOOTBRIDGE

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a handrail post to be used with the treadway of the aluminum floating footbridge.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

QQ-S-781	- Strapping, Steel, and Seals.
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 5420

Source: https://assist.dla.mil -- Downloaded: 20261O-22T21:12Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-T-704	- Treatment and Painting of Materiel.
MIL-G-20241	- Gasket Material, Wool Felt, Impregnated, Adhesive, Pressure Sensitive.
MIL-P-23377	- Primer Coatings: Epoxy-Polyamide, Chemical and Solvent Resistant.
MIL-S-81733	- Sealing and Coating Compound, Corrosion Inhibitive.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-889	- Dissimilar Metals.
MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.

2.1.2 Other Government documents. The following other Government documents, form a part of this specification to the extent specified herein.

DRAWINGS

ME

TA13217E9313	- Post Handrail, Footbridge.

(Copies of specifications, standards, and drawings required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI/ASME - Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.
ANSI/AWS A5.10 - Aluminum and Aluminum-Alloy Bare Welding Rods and Electrodes.
ANSI/AWS D1.1 - Structural Welding Code, Section 5, Qualification.

(Application for copies should be addressed to the American National Standards Institute, 1430 Broadway, New York, NY 10018.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 Description. The handrail post shall be as shown on Top Assembly TA13217E9313 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are engineering design drawings. The contractor is responsible for preparing his own shop drawings. Where tolerances prescribed could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the handrail post. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer.

3.2 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 4.3 and 6.3).

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Material shall be new and unused.

3.3.1 Material deterioration and control. The handrail post shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable storage and operating environment to which the item may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals, as defined in MIL-STD-889, shall be electrically insulated from one another to minimize or prevent galvanic corrosion. Insulation may be provided by an insulating barrier such as a coat of epoxy primer conforming to MIL-P-23377, or corrosion inhibiting sealant conforming to MIL-S-81733 or chromate tape conforming to MIL-G-20241. Protection against any galvanic corrosion could also be obtained by exclusion of the electrolyte if feasible.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with components and sub-components, and shall make information available, upon request, to the contracting officer or designated representative.

3.4 Welding electrodes. Welding electrodes shall conform to ANSI/AWS A5.10, classification ER4043, size as required.

3.5 Identification marking. The handrail post shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.6 Treatment and painting. The handrail post shall be cleaned, treated, and painted in accordance with MIL-T-704, type B.

3.7 Workmanship.

3.7.1 Welders and welding.

3.7.1.1 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

ANSI/ASME Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.
ANSI/AWS D1.1, Structural Welding Code, Section 5, Qualification.

Contractors who make only horizontal welds need not qualify welders for "all position welding". Subject to approval by the Government, the contractor's standard welder qualification may be substituted in lieu of the above codes provided that the contractor's procedure is equivalent to the above codes. The contractor shall be responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with ASME or AWS codes.

3.7.1.2 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the provisions of the ANSI/AWS D1.1 - Structural Welding Code. All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wirebrushed clean.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

107. Materials and containers not as specified. Each incorrect material or container shall be considered one defect.
108. Quantities not as specified for level A.
109. Ends of boxes not reinforced as specified for level A.
110. Posts not positioned in the box as specified for level A.
111. Strapping not as specified for level A.
112. Packing not in accordance with the referenced document for commercial.
113. Marking missing, illegible, incorrect, or incomplete for level A or commercial.

5. PACKING

5.1 Preproduction pack. Unless otherwise specified (see 6.2), the contractor shall furnish a preproduction pack for examination within the time frame specified (see 6.2) to prove prior to starting production packaging that the applied packing, and marking comply with the packaging requirements of this specification. Examination shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The preproduction pack may be prepared utilizing either the first article posts or production posts. When the first article posts are utilized, any packing shall be removed by the contractor at no expense to the Government, when requested by the Government, to facilitate comparison between the first article posts and production posts.

5.2 Packing. Packing shall be level A or commercial as specified (see 6.2).

5.2.1 Level A (see 6.5). The posts shall be packed in quantities of 42 in a box conforming to PPP-B-621, class 2, style 2, for type 3 load. The boxes shall be constructed with lumber of any species of groups I or II wood for weight of contents of 250 to 400 pounds. The ends of the box shall be reinforced by the addition of boards covering the entire inner face of each end. The reinforcing boards shall be the same thickness as the end boards, shall be placed with grain direction at right angles to that of the end boards, and shall be nailed to them with the nails clinched. The sides, top, and bottom of the box shall be nailed to the reinforcing boards in addition to the nailing required by the box specification. The box shall be close fitting to prevent movement of the posts and shall be approximately 44-3/4 inches long by 11-1/2 inches wide by 15-1/4 inches high. The posts shall be tightly nested in the box seven posts wide and six layers high, with the ends of each post alternated with respect to adjacent posts. The boxes shall be strapped in accordance with the appendix to the box specification. Straps shall conform to QQ-S-781, class 1, type I or IV, size as applicable, finish B.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

5.2.2 Commercial. The posts shall be packed in accordance with MIL-STD-1188.

5.3 Marking (see 6.5).

5.3.1 Military. Marking for level A packaging shall be in accordance with MIL-STD-129.

5.3.2 Commercial. Marking for commercial packaging shall be in accordance with MIL-STD-1188.

6. NOTES

6.1 Intended use. The handrail posts are to be used with the treadways of the aluminum floating footbridge as support for the handrail rope.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this specification.

b. When a first article is required for inspection and approval and the number of units required (see 3.2).

c. When a preproduction pack is not required (see 5.1).

d. Time frame required for submission of the preproduction pack (see 5.1).

e. Degree of packing required (see 5.2).

6.3 First article. When a first article inspection is required the item shall be examined and should be a first produced handrail post. The contracting officer should include specific instructions in the acquisition documents regarding arrangements for examinations and approval of the documents first article.

6.4 Preproduction pack. Any changes or deviations of production packs from the approved preproduction pack will be subject to the approval of the contracting officer. Approval of the preproduction pack will not relieve the contractor of his obligation to pack and mark the handrail posts in accordance with this specification.

6.5 Packaging. Degrees of preservation have not been included as the posts do not require additional preservation. For purposes of preservation/packing level marking, the preservation shall be designated as level A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

6.6 International standardization agreement. Certain provisions of this specification are the subject of International Standardization Agreement QSTAC 88. When amendment, revision, or cancellation of this specification is proposed which will modify the international agreement concerned, the preparing activity will take appropriate action through international standardization channels, including departmental standardization offices, to change the agreement or make other appropriate accomodations.

Custodian:
Army - ME

Review activity:
Navy - MC

Preparing activity:
Army - ME

Project 5420-0143

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil – Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

MERADCOM
DRDME-DS
Fort Belvoir VA 22060

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.