MIL-M-12760B(MU)
15 NOVEMBER 1963
SUPERSEDING
MIL-M-12760A (Ord)
16 FEBRUARY 1962

MILITARY SPECIFICATION

MINE, ANTI-PERSONNEL NON-METALLIC, M14E1 WITH INTEGRAL FUZE PARTS FOR

1. SCOPE

1.1 This specification covers the parts and parts assemblies for one type of mine designated as Mine, Anti-Personnel, Non-Metallic, M14E1, with Integral Fuze.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

QQ-L-201 — Lead, Sheet

UU-T-111 — Tape; Paper; Gummed (Sealing and Securing)

PPP-B-636 — Boxes, Fiber

MILITARY

MIL-A-2550 — Ammunition and Special Weapons, General Specification for

MIL-P-10025 — Packaging, Packing and Marking for Interplant Shipment of Inert Ammunition Components: General Specification for

MIL-I-45208 — Inspection Requirements, General Specification for

MIL-I-45607 — Inspection Equipment. Supply and Maintenance of

STANDARDS

MILITARY

MIL-STD-105D - Sampling Procedures and Tables for Inspection by Attributes

MIL-STD-109 — Quality Assurance Terms and Definitions

FSC 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.

MIL–STD–1235—Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

ORDNANCE CORPS

82-15-52 — Mine, Apers, NM, M14E1, With Integral Fuze, Parts Assembly and details

8861851 — Carton, Packing, Ammunition, for Mine, Apers, NM, M14 with Integral Fuze.

PUBLICATIONS

ORDNANCE CORPS

IEL–7152622 — Index of Inspection Equipment Lists

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material. Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Mine and fuze assemblies. The mine and fuze assemblies shall comply with all requirements specified on Drawing (dwg.) 82–15–52 and with all requirements specified in applicable specifications.

3.3 Internal air test. The fuze assembly shall evidence no drop in pressure when subjected to an internal air pressure of not less than ten nor more than eleven pounds per square inch gage (p.s.i.g.) for not less than five seconds when tested as specified in 4.4.1.

3.4 Functioning. The fuze assembly shall require an axial load of not less than 20 pounds nor more than 35 pounds to cause sudden reversal of the belleville spring when tested as specified in 4.4.2. (see 6.4).

3.5 Recovery of firing pin of the fuze assembly. The firing pin shall return to the minimum position required by the drawing after a load just prior to functioning (see 6.4) is applied and released when tested as specified in 4.4.3.

3.6 Arming torque. The torque required to arm the fuze assembly shall not exceed 18 inch-pounds when tested as specified in 4.4.6.

3.7 Penetration of firing pin point. The firing pin point shall penetrate into a lead cylinder a minimum of .04 inch. The eccentricity as measured between the center of penetration and the center of the lead cylinder shall not exceed 0.038 inch when tested as specified in 4.4.4.

3.8 Jolt and jumble. The fuze assembly, assembled without cement and taped to the mine body, shall withstand 1750 jolts in each of the three positions of the jolt machine; and after completion of the jolt test, the assemblies used in the jolt test shall withstand 3600 complete revolutions in the jumble machine without having any —

(a) cracking, chipping, or flaking of the visible surfaces.

(b) cemented joints come apart or loosen.

(c) damage to the firing spring assembly or lock key.

(d) inner parts come apart, or any damage which might interfere with satisfactory functioning.

The tests shall be performed as specified in 4.4.5.

3.9 Workmanship. All parts shall be fabricated in a thorough workmanlike manner.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.

They shall be free of cracks, chipped edges, porosity, warpage, sinks, checks, blisters, scratches, excess flash, burrs, chips, sharp, edges, cracks, unblended radii, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agent. All required markings shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions. The supplier is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL–STD–109 in order to define terms used herein. The provisions of Specification MIL–A–2550 shall apply.

4.1.1 *Contractor quality assurance system.* The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL–I–45208.

4.1.2 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

(a) A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.

(b) Number of units of product inspected.

(c) Results obtained for all inspection performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

(e) Certificates of analysis on all material purchased directly by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

(f) Number of items in the lot.

(g) Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.3 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector will verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL–I–45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

Source: https://assist.dla.mil -- Downloaded: 202610-17T23:17Z
Check the source to verify that this is the current version before use.

4.2 Initial production inspection.

4.2.1 *Submission.* Prior to normal production the contractor shall submit an initial production sample consisting of fifty consecutively produced assemblies and complete sets of parts (i.e. 50 each of every individual component and every subassembly including at least enough items from each cavity used to produce plastic parts so that two assemblies can be made up of every possible combination), which have been produced by the production process which the contractor will use in fulfilling the contract, to a Government-approved facility designated by the contracting officer. All parts and materials shall be obtained from the same source of supply as will be used in regular production. The initial production sample shall be accompanied by certificates of analyses for all materials, and a listing of all data pertinent to the process used for production of plastic parts. A sample shall also be submitted whenever a change occurs in manufacturing process, material used, drawing, specification, or source of supply such as to significantly affect product uniformity as determined by the Government.

4.2.2 *Inspections to be performed.* Each assembly and component shall be inspected by the Government for all the inspections specified in 4.3.2 and 4.3.3 of this specification and for all additional requirements of the applicable drawings.

4.2.3 *Rejection.* If any assembly or component fails to comply with the applicable requirements, the initial production sample shall be rejected. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit new or supplemental quantities until such time as a acceptable sample is submitted, or until otherwise directed by the contracting officer.

4.3 Inspection provisions.

4.3.1 *Lot formation.* A lot shall consist of mine parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting safety, performance or fit, as determined by the Government shall not necessitate changing the lot number.

4.3.2 *Examination.* Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL–STD–105D using inspection level I for plastic parts and inspection level II for other parts and assemblies, except that inspection for critical defects, when listed, shall be 100 percent. Plastic parts produced by different cavities shall be considered as separate items for the purposes of sampling and inspection. Continuous sampling plans in accordance with Standard MIL–STD–1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.25 percent for each major defect and an AQL of 0.40 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.

4.3.2.1 Applies to all components and subassemblies not hereinafter specifically listed in 4.3.2.2 through 4.3.2.15. (see 3.9 and applicable drawings).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined.			
Major:	AQL 0.65 percent		
101.	Operation missing or improperly performed	Visual	
102.	Bur or chip on or at intersection of sliding or other functional surfaces	Visual	
103.	Finish of sliding or other functional surface improper	Visual	
104.	Component missing or improperly assembled	Visual	
105.	Protective finish inadequate	Visual	
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship other than that covered under major category above (see 3.9)	Visual	

4.3.2.2 Spider (see dwg. 82–15–54 covering a detail of dwg. 82–15–52).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Total height	Gage	01001
102.	Outside Diameter	Gage	01002
103.	Profile of upper face	Gage	01003
104.	Taper angle of lower face	Gage	01004
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.9)	Visual	01005

4.3.2.3 Key, lock (see dwg. 82–15–53 covering a detail of dwg. 82–15–52).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined.			
Major:	AQL 1.00 percent		
101.	Shaft diameter	Gage	02001
102.	Outside diameter	Gage	02002
103.	Total height	Gage	02003
104.	Location of lugs with respect to flat on shaft	Gage	02004
105.	Height of lugs	Gage	02005
106.	Height of flat on shaft	Gage	02006
107.	Profile of lugs	Gage	02007
108.	Radii on lugs missing	Visual	02008
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.9)	Visual	02009

4.3.2.4 Base, detonator holder (see dwg. 82–15–57).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined.			
Major:	AQL 1.0 percent		
101.	Pitch diameter of thread	Gage	03001
102.	Major diameter of thread	Gage	03002
103.	Total height	Gage	03003
104.	Length of thread	Gage	03004
105.	Height from top of flange to detonator seat	Gage	03005

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of inspection	Code No.
	106. Depth of detonator holder cup groove	Gage	03006
	107. Inside diameter of detonator holder cup groove	Gage	03007
	108. Outside diameter of detonator holder cup groove	Gage	03008
	109. Concentricity of outside diameter of detonator holder cup groove with thread	Gage	03009
	110. Crack or hole through material	Visual	03010
	111. Evidence of poor workmanship (see 3.9)	Visual	03011
Minor:	AQL 1.0 percent		
	201. Distance across flats of flange	Gage	03012
	202. Slot inadequate	Visual	03013

4.3.2.5 Cup, detonator holder (see dwg. 82-15-57).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
	101. Total height	Gage	04001
	102. Inside diameter	Gage	04002
	103. Outside diameter	Gage	04003
	104. Diameter of hole	Gage	04004
	105. Evidence of poor workmanship (see 3.9)	Visual	04005
Minor:	AQL 0.40 percent		
	201. Thickness through bottom, minimum (min.)	Gage	04006

4.3.2.6 Plug, shipping (see dwg. 82-15-57).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major	AQL 0.40 percent		
	101. Pitch diameter of thread	Gage	05001
	102. Major diameter of thread	Gage	05002
	103. Total height	Gage	05003
	104. Diameter above thread, maximum (max.)	Gage	05004
Minor:	AQL 4.0 percent		
	201. Concentricity of firing pin cavity with thread	Gage	05005
	202. Profile of firing pin cavity, min.	Gage	05006
	203. Distance from top of flange to top end	Gage	05007
	204. Distance from top of flange to top shoulder	Gage	05008
	205. Distance from top of flange to bottom shoulder	Gage	05009
	206. Outside diameter at top end, max.	Gage	05010
	207. Diameter of flange	Gage	05011
	208. Screw driver slot inadequate	Visual	05012
	209. Evidence of poor workmanship (see 3.9)	Visual	05013

4.3.2.7 Spring, belleville (see dwg. 82-15-56 covering a detail of dwg. 82-15-52).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
	101. Outside diameter	Gage	06001
	102. Diameter of hole	Gage	06002
	103. Evidence of poor workmanship (see 3.9)	Visual	06003
Minor:	AQL 1.0 percent		
	201. Thickness	Gage	06004
	202. Identification mark or number missing or incorrect	Visual	06005

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.

4.3.2.8 Pin, firing (see dwg. 82–15–51 covering a detail of dwg. 82-15–52).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Length of point	Gage	07001
102.	Diameter of flat on point	Gage	07002
103.	Profile of point	Gage	07003
104.	Slot missing	Visual	07004
Minor:	AQL 1.0 percent		
201.	Major diameter	Gage	07005
202.	Evidence of poor workmanship (see 3.9)	Visual	07006

4.3.2.9 Firing pin assembly (see dwg. 82–15–51 covering a detail of dwg. 82–15–52).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Thickness of firing pin body flange	Gage	08001
102.	Diameter of firing pin body flange	Gage	08002
103.	Distance from face of flange to firing pin point	Gage	08003
104.	Total height	Gage	08004
105.	Body diameter	Gage	08005
Minor:	AQL 0.40 percent		
106.	Evidence of poor workmanship (see 3.9)	Visual	08006

4.3.2.10 Plate, pressure (see dwg. 82–15–53 covering a detail of 82–15–52).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.50 percent		
101.	Outside diameter	Gage	09001
102.	Total height	Gage	09002
103.	Height from O-ring groove to safety clip slots	Gage	09003
104.	Height from O-ring groove to lock ring abuting face	Gage	09004
105.	Width of O-ring groove	Gage	09005
106.	Width of safety clip slots	Gage	09006
107.	Diameter of O-ring groove	Gage	09007
108.	Distance between safety clip slots	Gage	09008
109.	Profile of keyhole	Gage	09009
110.	Location of keyhole flat	Gage	09010
111.	Depth of keyhole	Gage	09011
112.	Profile of safety splines	Gage	09012
113.	Location of safety splines	Gage	09013
114.	Radius of ends of safety splines	Gage	09014
Minor:	AQL 1.50 percent		
201.	Arrow not colored	Visual	09015
202.	Depressions in top face missing	Visual	09016
203.	Keyhole vent missing	Visual	09017
204.	Evidence of poor workmanship (see 3.9)	Visual	09018

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.

4.3.2.11 Body, fuze (see dwg. 82–15–54 covering a detail of dwg. 82–15–52).

Categories	Defects	Method of inspection	Code No.
Critical: None defined.			
Major:	AQL 0.65 percent		
101.	Outside diameter	Gage	10001
102.	Total height	Gage	10002
103.	Height to spring groove	Gage	10003
104.	Width of spring groove	Gage	10004
105.	Profile of interior	Gage	10005
106.	Letter A incorrectly positioned	Gage	10006
107.	Letter S incorrectly positioned	Gage	10007
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.9)	Visual	10008

4.3.2.12 Partition (see dwg. 82–15–51 covering a detail of dwg. 82–15–52).

Categories	Defects	Method of inspection	Code No.
Critical: None defined.			
Major:	AQL 1.00 percent		
101.	Total height	Gage	11001
102.	Height to top of flange	Gage	11002
103.	Height to bottom of flange	Gage	11003
104.	Diameter of flange	Gage	11004
105.	Outside diameter of body	Gage	11005
106.	Inside diameter of body	Gage	11006
107.	Diameter of partition	Gage	11007
108.	Angle of partition taper	Gage	11008
109.	Diameter of center hole	Gage	11009
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.9)	Visual	11010

4.3.2.13 *Ring, lock.*

Categories	Defects	Method of inspection	Code No.
Critical: None defined.			
Major:	AQL 1.00 percent		
101.	Outside diameter	Gage	12001
102.	Total height	Gage	12002
103.	Radius at base	Gage	12003
104.	Profile of slots	Gage	12004
105.	Height of lugs	Gage	12005
106.	Diameter of firing pin body mating surfaces	Gage	12006
107.	Profile of lugs	Gage	12007
108.	Inside radius	Gage	12008
109.	Slots and lugs not in line	Gage	12009
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.9)	Visual	12010

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.

4.3.2.14 Firing pin spring assembly (see dwg. 82–15–51 covering a detail of dwg. 82–15–52).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Firing pin assembly loose	Manual	13001
102.	Firing pin loose	Manual	13002
103.	Spring incorrectly assembled (not in cocked position or inverted)	Visual	13003
104.	Firing pin damaged	Visual	13004
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.9)	Visual	13005

4.3.2.15 Clip, Safety (see dwg. 82–15–53 covering a detail of dwg. 82–15–52).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined.			
Major:	AQL 0.65 percent		
101.	Distance between parrallel flats	Gage	14001
102.	Inside radius	Gage	14002
103.	Outside radius	Gage	14003
104.	Profile of points	Gage	14004
105.	Thickness	Gage	14005
Minor:	AQL 1.50 percent		
201.	Overall length	Gage	14006
202.	Cord hole missing or defective	Visual	14007
203.	Finish improper	Visual	14008
204.	Evidence of poor workmanship (see 3.9)	Visual	14009

4.3.2.16 Gasket, detonator holder (see dwg. 82–15–57 covering a detail of dwg. 82–15–52).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined.			
Major:	AQL 0.25 percent		
101.	Inside diameter	Gage	15001
102.	Thickness	Gage	15002
Minor:	AQL 1.00 percent		
201.	Outside diameter	Gage	15003
202.	Evidence of poor workmanship (see 3.9)	Visual	15004

4.3.2.17 Body, mine (see dwg. 82–15–51 covering a detail of dwg. 82–15–52).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined.			
Major:	AQL 1.00 percent		
101.	Pitch diameter of thread	Gage	16001
102.	Minor diameter of thread	Gage	16002
103.	Diameter of pellet cavity	Gage	16003
104.	Depth of pellet cavity	Gage	16004
105.	Concentricity of outside diameter at top with thread	Gage	16005
106.	Outside diameter at top	Gage	16006
107.	Total height	Gage	16007
108.	Profile of fuze mating surface	Gage	16008
Minor:	AQL 1.00 percent		
201.	Evidence of poor workmanship (see 3.9)	Visual	16009
202.	Cord holes missing or defective	Visual	16010

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.

4.3.2.18 Parts assembly (see dwg. 82–15–52).

Categories	Defects	Method of inspection	Code No.
Critical:			
1.	Safety clip missing or loose (can be removed with light finger pull)	Visual-Manuel	17001
2.	Pressure plate not set in safe ("S") position	Visual	17002
Major:	AQL 0.40 percent		
101.	Arming torque (see 4.4.6)	Test	17003
102.	Clearance between fuze assembly and mine assembly, max.	Gage	17004
103.	Detonator holder washer missing or loose	Visual-Manual	17005
104.	Safety clip cord missing or damaged (frayed, deteriorated, etc.)	Visual	17006
Minor:	AQL 1.5 percent		
201.	Carrying cord missing or damaged (frayed, deteriorated, etc.)	Visual	17007
202.	Evidence of poor workmanship (see 3.9)	Visual	17008
203.	Marking misleading or unidentifiable	Visual	17009

4.3.2.19 Carton, sealed packing (see dwg. 8861851).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.25 percent		
101.	Assembly damaged so that contents are exposed or liable to become exposed	Visual	18001
102.	Sealing strip incomplete, badly wrinkled or separation from carton at any point exceeds one-half inch	Visual	18002
Minor:	AQL 1.0 percent		
201.	Contents move when carton is shaken	Manual	18003
202.	Marking misleading or unidentifiable	Visual	18004

4.3.3 *Testing.*

4.3.3.1 Internal air test (see 3.3) major defect. 17010

4.3.3.1.1 Internal air test (see 3.3) major defect—Initial production. Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified, the sampling plan for this test shall be in accordance with Standard MIL–STD–105D using code letter M and an AQL of 0.25 percent. The test shall be performed as specified in 4.4.1 using equipment in accordance with 4.3.4. Any fuze assembly which fails to comply with the specified requirements shall be classed defective.

4.3.3.1.2 Internal air test (see 3.3) major defect— Normal production. After three consecutive lots have met the criteria of 4.3.3.1.1, the sampling plan for this test shall be in accordance with Standard MIL–STD–105D using code letter K and an AQL of 0.40 percent.

4.3.3.2 Functioning (see 3.4) major defect. 17011

4.3.3.2.1 Functioning (see 3.4) major defect-Initial production. Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified, the sampling plan for this test shall be in accordance with Standard MIL–STD–105D using code letter M and an AQL of 0.10 percent. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4. Any fuze assembly which fails to comply with the

Source: https://assist.dla.mil -- Downloaded: 202610-17T23:17Z
Check the source to verify that this is the current version before use.

specified requirements shall be classed defective.

4.3.3.2.2 Functioning (see 3.4) major defect—Normal production. After three consecutive lots have met the criteria of 4.3.3.2.1, the sampling plan for this test shall be in accordance with Standard MIL–STD–105D using code letter L and an AQL of 0.25 percent.

4.3.3.3 Recovery of firing pin of the fuze assembly (see 3.5) major defect 17012

4.3.3.3.1 Recovery of firing pin of the fuze assembly (see 3.5) major defect—Initial production. Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified, the sampling plan for this test shall be in accordance with Standard MIL–STD–105D using code letter M and an AQL of 0.10 percent.

The test shall be performed as specified in 4.4.3 using equipment in accordance with 4.3.4. Any fuze assembly which fails to comply with the specified requirements shall be classed defective.

4.3.3.3.2 Recovery of firing pin of the fuze assembly (see 3.5) major defect—Normal production. After three consecutive lots have met the criteria of 4.3.3.3.1, the sampling plan for this test shall be in accordance with Standard MIL–STD–105D using code letter L and an AQL of 0.25 percent.

4.3.3.4 Penetration of firing pin point (see 3.7) major defect. 17013

4.3.3.4.1 Penetration of firing pin point (see 3.7) major defect—Initial production. Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified, the sampling plan for this test shall be in accordance with Standard MIL–STD–105D using code letter J and an AQL of 0.65 percent. The test shall be performed as specified in 4.4.4 using equipment in accordance with 4.3.4. Any assembly which fails to comply with the specified requirements shall be classed defective.

4.3.3.4.2 After three consecutive lots have met the criteria of 4.3.3.4.1, the sampling plan for this test shall be in accordance with Standard MIL–STD–105D using code letter I and an AQL of 1.00 percent.

4.3.3.5 Jolt and jumble (see 3.8) major defect. 17014 Jolt 17015 Jumble

4.3.3.5.1 Jolt and jumble (see 3.8) major defect—Initial production. Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified, thirty-six fuze assemblies shall be selected from each lot for these tests. The tests shall be performed as specified in 4.4.5 using equipment in accordance with 4.3.4. If one or more fuze assemblies fail to comply with the requirements specified, the lot shall be rejected.

4.3.3.5.2 Jolt and jumble (see 3.8) major defect—Normal production. After three consecutive lots have met the criteria of 4.3.3.5.1, twelve fuze assemblies shall be elected from each lot for these tests. If one or more fuze assemblies fail to comply with the requirements specified, the lot shall be rejected.

4.3.4 *Inspection equipment.* Index of Inspection Equipment Number IEL–7152622 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production

Source: https://assist.dla.mil -- Downloaded: 202640-17T23:17Z
Check the source to verify that this is the currentversion before use.

and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL–I–45607.

4.3.4.3 *Government use of contractor's inspection equipment.* The contractor shall as required make available to the Government all inspection equipment necessary for determining conformance with contract requirements. Operation of the equipment and verification of its accuracy shall be supplied by the contractor, as required by the Government in performance of its examination or test.

4.4 Test methods and procedures.

4.4.1 *Internal air test.* The fuze assemblies shall be assembled to a specified fixture and subjected to an internal air pressure of not less than 10 pounds nor more than eleven pounds p.s.i.g. for not less than five seconds. Observation shall be made to determine compliance with 3.3.

4.4.2 Functioning. The fuze assemblies selected shall have the safety clips removed. The assemblies shall then be set in the armed position and assembled, without cementing, to the mine. An axial load of not less than 20 pounds nor more than 35 pounds shall then be applied to the fuze at the rate of one-half to one inch per minute. Observation shall be made to determine compliance with 3.4 (see 6.4).

4.4.3 *Recovery of firing pin of the fuze assembly.* The fuze assemblies selected shall have the safety clips removed. The assemblies shall then be set in the armed position and assembled, without cementing, to the mine. A load shall be applied to that point just prior to the point of functioning and then released. The return of the firing pin assembly to the minimum position specified on the applicable drawing shall then be determined using any method satisfactory to the Government inspector.

Note. If a load sufficient to cause sudden reversal of the firing pin assembly is inadvertently applied and the Belleville spring "snaps through," that fuze assembly shall be disregarded and the assembly replaced by another samble.

Observation shall be made to determine compliance with 3.5.

4.4.4 *Penetration of firing pin point.* The fuze assembly shall be cemented to the mine body, or the fuze assembly shall be clamped to the mine body, and held together firmly in a specified fixture that does not distort the assemblies. The detonator holder cup shall be inert-loaded with a lead cylinder, .241–.004 inch in diameter and .370–.005 inch in length, and assembled to the mine body. It is advisable to use a torque of 5 plus 0.5 inch-ounces for tightening the detonator holder assembly in the mine body. (The lead required for the inert cylinders for use in this test shall conform to the requirements of Specification QQ–L–201, Grades A, B, or C, except that bars may be used in lieu of sheet lead.) An axial load of not less than 20 pounds nor more than 35 pounds shall be applied to the pressure plate at a rate of one half to one inch per minute to cause the fuze to function. The depth of penetration of the firing pin point and the eccentricity shall then be measured. Observation shall be made to determine compliance with 3.7. The eccentricity of penetration shall be measured from the center of the lead cylinder to the center of the penetration hole made by the firing pin point.

4.4.5 *Jolt and jumble.* The fuze assembly shall be assembled without cement and taped to a mine body and then attached to a specified jolt testing device. The assembly shall

Source: https://assist.dla.mil -- Downloaded: 202640-17T23:17Z
Check the source to verify that this is the current version before use.

then be subjected to 1750 jolts in each of three positions. After completion of the jolt tests, the same assemblies, without inspection, shall then be subjected to the jumble test. The assemblies shall be placed, singly, in a specified jumble machine and given 3600 complete revolutions at a specified speed. The assemblies shall then be examined to determine compliance with 3.8. This shall be accomplished by cutting open a sidewall section of the assemblies or by disassembling the fuzes by removing the mine body and prying out the component parts starting with the partition in order to inspect the inner parts.

4.4.6 Arming torque (see 3.6). The fuze assemblies selected shall have the safety clips removed and the torque required to arm the fuze assembly measured by a torque wrench or any other suitable means acceptable to the Government inspector. The fuze assembly shall then be returned to the safe position and the safety clip inserted.

5. PREPARATION FOR DELIVERY

5.1 Packaging.

5.1.1 *Level C.* Mine parts assemblies shall be packed in accordance with Drawing 8861-851. The top flaps shall be folded down but not fastened. The top flaps may be fastened temporarily with one strip of tape applied crosswise. The tape shall not interfere with the final closing operation. Unless specifically permitted, cartons with overlapping outer flaps shall not be used.

5.1.1.1 *Marking.* There shall be no marking applied to cartons specified in 5.1.1.

5.2 Packing.

5.2.1 *Level C.* Four filled cartons, as specified in 5.1.1, shall be arranged in a stack and packed in a 200-pound test RSC Style corrugated fiiberboard shipping carton, made in accordance with Specification PPP-B-636. The inside dimensions shall be $13\frac{3}{16}$ inches by $15\frac{3}{4}$ inches by 25 inches.

5.3 Construction. The construction of the fiberboard cartons, and the material requirements of the cartons shall comply with Specification PPP-B-636. When assembled, the corrugations of the cartons shall parallel the carton depth. The manufacturer's joint on the carton shall be secured with reinforced paper tape, or metal-stapled, or stitched. Spacing of staples or stitches shall average not over $1\frac{1}{2}$ inches apart, center to center. A manufacturing tolerance of plus or minus $\frac{1}{32}$ inches is permissible. The parts manufacturer shall be furnished preproduction samples of all packing materials so that proper fit of packing materials and metal parts can be determined. Minor modifications of packing material dimensions to provide a proper fit of all parts, as determined to be necessary by examination of sample packs, are permissible.

5.4 Sealing. The carton flaps shall be secured with gummed Kraft paper not less than 3 inches wide, complying with Specification UU-T-111 for class 2 tape. The tape shall be centered the full length of the outer flap seams and extend over each end of the carton at least 3 inches. The flap edge seams shall be similarily sealed with the tape extending at least 3 inches along the corners of the carton. Tape shall be properly moistened ends sufficiently compressed to insure tight adhesion to the carton.

5.5 Percentage of extra parts packing. Packing for the required percentage of extra parts shall be provided for by furnishing the proper number of prime containers.

5.6 Shipping. When component parts from more than one lot are shipped as a carload, each lot shall be kept separate and the division between lots clearly indicated.

5.7 Marking. The shipping cartons shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.

marked in accordance with Specification MIL–P–10025.

5.8 Data cards. Data card information shall be as specified in Specification MIL–A–2550.

6. NOTES

6.1 Ordering data. Procurement documents shall specify the following:

(a) Title, number and date of this specification.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "contractor design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5, and 6.3.6 will be designated in the Inspection Equipment List by the following codes:

CDOF	— Contractor's design responsibility on Ordnance format; ORDM–608–12.
CDCF	— Contractor's design responsibility on contractor format.
OD	— Ordnance design.
ODMU	— Ordnance design, mandatory for use.
CE	— Commercial equipment.
SCD	— Specification Control Drawing.

6.3.3 *Ordnance designs.* Ordnance designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Ordnance design is listed for an item of inspection equipment. Ordnance designs fall into two basic classifications; mandatory and non-mandatory. When an inspection equipment list references mandatory Ordnance designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawings.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic, or pictorial form only and specify the required performance or other characteristics. Contractors must

Source: https://assist.dla.mil -- Downloaded: 202640-17T23:17Z
Check the source to verify that this is the current version before use.

prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings.

These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial inspection equipment but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDOF shall comply with the format and requirements of ORDM 608–12, and, in addition, contain the detail and information specified above.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Functioning of the fuze is evidenced by the reversal of the Belleville spring and the emergence of the firing pin through the partition.

Custodian:
Army—MU

Preparing activity:
Army—MU

Project No. 1345–A126

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:17Z
Check the source to verify that this is the current version before use.