MILITARY SPECIFICATION

SUPERSTRUCTURE, INTERIOR AND END BAY,

FOR MOBILE FLOATING ASSAULT BRIDGE/FERRY

This amendment forms a part of Military Specification MIL-S-52356D(ME), dated 11 November 1974.

PAGE 1

2.1, under SPECIFICATIONS, FEDERAL, delete

"QQ-S-781 - Strapping, Steel, Flat and Seals."

and substitute

"QQ-S-781 - Strapping, Steel, and Seals."

Add:

"TT-E-522 - Enamel, Phenolic, Outside."

PAGE 2

2.1, under SPECIFICATIONS, MILITARY, add:

"MIL-B-43436 - Band Markers, Blank, General Specification For.

MIL-E-52798 - Enamel, Alkyd, Camouflage."

PAGE 3

2.1, under STANDARDS, MILITARY, delete:

"MS39020 - Band, Marker, Blank."

PAGE 9

3.7.2, line 3, delete and substitute:

"with MIL-T-704, Type B, finish coat shall be forest green conforming to TT-E-522 modified to meet color, reflectance, gloss, sheen, and pigmentation of MIL-E-52798."

3.9, line 3, delete "MS39020" and substitute "MIL-B-43436".

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:15Z
Check the source to verify that this is the current version before use.

PAGE 10

3.14, at end of paragraph, add: "and 4.6.2.17."

PAGE 13

4.1, delete and substitute:

"4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements."

PAGE 18

4.6.2.2, Test schedule, Table III, delete last line and substitute following in appropriate columns:

1	2	3	4	5	6
" -	X	-	-	First-produced endurance.	4.6.2.17
-	-	X	-	Initial production reliability and maintainability.	4.6.2.15"

PAGE 24

4.6.2.15, change title from "Reliability and maintainability" to "Initial production reliability and maintainability".

PAGE 25

4.6.2.15, at end of paragraph, add: "Occurrence of two or fewer reliability failures or attaining a 515 hour MTBF (point estimate) shall constitute conformance to the reliability requirement of 3.14."

PAGE 26

Add new paragraph 4.6.2.17:

"4.6.2.17 First-produced endurance. A first-produced transporter shall be subjected to 1,000 miles of land and 100 hours of water operation. The

Source: https://assist.dla.mil -- Downloaded: 20261-22T21:15Z
Check the source to verify that this is the current version before use.