MILITARY SPECIFICATION

CHARGE, DEMOLITION, M112
PARTS FOR AND LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the parts for and the loading, assembling and packing for one type of demolition charge designated as Charge, Demolition, M112.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-116 - Preservation, Methods of
MIL-A-2550 - Ammunition and Special Weapons, General Specification for
MIL-L-10547 - Liners, Case, and Sheet, Overwrap, Water-Vaporproof or Waterproof, Flexible

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

8876127 - Box, Wirebound, Packing, Ammunition for Charge, Demolition, M112.
9204248 - Charge, Demolition, M112

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

PUBLICATIONS

U.S. ARMY MUNITIONS COMMAND

ET-9204248 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material.-Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Assembly.-The charge assemblies shall comply with all requirements specified on Drawing (dwg.) 9204248, and with all requirements specified in applicable specifications.

3.3 Workmanship.-All parts and assemblies shall be fabricated and loaded in a thorough, workmanlike manner. They shall be free of holes, cracks, tears, surface defects, voids, grease, and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. All required markings shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:27Z
Check the source to verify that this is the current version before use.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 Inspection provisions

4.2.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchanged process using the same materials and methods in accordance with the same drawings, same drawing revisions, same specifications and the same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each lot of demolition charges shall contain:

a. Parts from not more than one lot interfix number from one manufacturer.
b. Composition C-4 from not more than two lots from one manufacturer.

4.2.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.2.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying that AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.2.4.

Source: https://assist.dla.mil - Downloaded: 2026Ø10-22T20:27Z
Check the source to verify that this is the current version before use.

4.2.2.1 Container, Charge, Demolition M112 (see dwg. 9204249 covering a detail of dwg. 9204248)

Categories	Defects	Method of Inspection	Code No. (See 6.2)
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Width of heat seal	Gage	01001
102.	Bag punctured or torn	Visual	01002
103.	Charge container bag or seal fails when assembled with a simulated or actual charge	Visual/Manaul	01003
Minor:	AQL 0.65 Percent		
201.	Evidence of poor workmanship (see 3.3)	Visual	01004

4.2.2.2 Charge, Demolition, M112 (see dwg. 9204248)

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Warning marking missing	Visual	02001
Major:	AQL 0.65 Percent		
101.	Weight of charge	Balance	02002
102.	Pressure sensitive tape missing or improperly applied	Visual	02003
103.	Charge container missing, loose or damaged exposing explosive	Visual/Manual	02004
104.	Marking, other than warning marking, missing, misleading or unidentifiable	Visual	02005
Minor.	AQL 2.50 Percent		
201.	Length of tape	Gage	02006
202.	Charge improperly assebled into container	Visual	02007
203.	Sealing clip missing or insecure	Visual	02008
204.	Wax paper not removed (when applicable)	Visual	02009
205.	Evidence of poor workmanship (see 3.3)	Visual	02010

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

4.2.2.3 Box, Wirebound, Packing, prior to sealing case liner (see dwg. 8876127)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Box improperly assembled	Visual	03001
102.	Incorrect number of demolition charges	Visual	03002
Minor:	AQL 1.50 Percent		
201.	Filler packing material missing	Visual	03003
202.	Case Liner punctured	Visual	03004
203.	Charges incorrectly packed	Visual	03005

4.2.2.4 Box, Wirebound, Packing, prior to sealing (see dwg. 8876127)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Case liner improperly sealed	Visual	04001
Minor:	AQL 0.65 Percent		
201.	Packing material missing	Visual	04002

4.2.2.5 Box, Wirebound, Packing, sealed (see dwg. 8876127)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Loops improperly closed	Visual	05001
102.	Wire broken	Visual	05002
103.	Box damaged	Visual	05003
Minor:	AQL 1.50 Percent		
201.	Contents loose	Manual	05004
202.	Markings misleading or unidentifiable	Visual	05005
203.	Car seal missing, unsealed, or improperly positioned	Visual	05006

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:27Z
Check the source to verify that this is the current version before use.

4.2.3. Testing

4.2.3.1 Specific gravity of charge block (see dwg. 9204248) Major Defect, Code No. 06001.-The specific gravity of the charge block shall be determined for each lot of composition C-4 at the time of loading. A sample of ten charges shall be selected from each lot of composition for this test. If one or more charges fail to meet the requirement specified the lot shall be rejected. The test shall be performed as specified in 4.3.1 using test equipment specified in 4.2.4.

4.2.3.2 Heat seal test of case liner (see dwg. 8876127), Major Defect, Code No. 07001.-A sample of five packed and sealed case liners shall be selected from each lot for this test. If any sealed case liner fails to comply with the requirements specified the lot shall be rejected. The test shall be performed as specified in MIL-P-116 or MIL-L-10547 using test equipment specified in 4.2.4.

4.2.4 Inspection equipment.-Equipment Tabulation Number ET-9204248 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.2.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3 Test methods and procedures

4.3.1 Determination of specific gravity of the explosive charge.-The specific gravity shall be determined as follows: Weigh the block charge to the nearest .01 pound. A suitable container provided with an overflow pipe approximately one-half inch in length shall be filled with water (at a temperature of 25 degrees centigrade (C.) plus or minus 5 degrees C.) level with the overflow pipe. Insert a suitable stopper in the overflow pipe. Carefully place the block charge in the container so that it is completely submerged, taking care to remove all air bubbles remaining on the surfaces of the block charge. Place a tared container under the overflow pipe. Carefully remove the stopper from the pipe, collect the water which overflows and weigh to the nearest .01 pound. Calculate the specific gravity as follows:

$$\text{Specific gravity} = A/B$$

Where:

A = weight of block charge.
B = weight of water displaced

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

4.3.1.1 Determination of specific gravity of the explosive charge, alternate method.-The specific gravity shall be determined as follows:

a. Weigh the block charge to the nearest .01 pound.
b. Weigh charge suspended and immersed in water, taking care to remove all air bubbles remaining on the surfaces of the block charge. (At a water temperature of 25 degrees plus or minus 5 degrees Centigrade (C.))
c. Subtract wet weight from dry weight.

Specific gravity = A/C

Where:
A = weight of charge dry
C = weight in air minus weight in water

5. PREPARATION FOR DELIVERY

5.1 Preservation and Packaging

5.1.1 Level A.-The charge demolition shall be packaged in accordance with dwg. 8876127.

5.2 Packing

5.2.1 Level A.-The charge demolition shall be packed in accordance with dwg. 8876127.

5.3 Marking.-Marking shall be in accordance with dwg. 8876127.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. In addition, they should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the inspection Equipment Lists (EL) referenced on the applicable ET in accordance with the instructions of paragraph 6.3.1 through 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

6.3.1 Inspection equipment lists (EL).-Inspection equipment lists indicated the availability of inspection equipment designs by showing in the the "number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment deisgns, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabriction or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all the information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to MIL-D-1000, Category A, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:27Z
Check the source to verify that this is the currentversion before use.

6.3.5 Submission of contractor designs.-All submitted designs shall contain a reference to the applicable five digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND15. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the Contracting Officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

6.4 Supersession data.-This specification includes the requirements of PA-PD-2663, dated 15 January 1965.

Custodian:
Army - AR

Preparing activity:
Army - AR

Project Number: 1375-A-064

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:27Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-C-50523	CHARGE, DEMOLITION, M112 PARTS FOR AND LOADING, ASSEMBLING & PACKING

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR ☐ USER ☐ MANUFACTURER ☐ OTHER *(Specify)*: _____
b. ADDRESS *(Street, City, State, ZIP Code)*	

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426

PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.