MILITARY SPECIFICATION

PUMP, CENTRIFUGAL, PORTABLE, SUBMERSIBLE

This Interim Amendment is issued for use by the Naval Ship Engineering Center with Military Specification MIL-P-17454B, dated 10 March 1954 and Amendment-1 thereto, dated 3 June 1960.

Page 2, paragraph 2 1, under Military Specifications. Add

"MIL-C-15987 - Cable Assemblies, Power, Electrical (With Grounding for 440-Volt, Portable Equipment, Shipboard Use)
"MIL-I-45208 - Inspection System Requirements."

Page 2, paragraph 2 1, cont'd, under Drawings Delete reference to "9000-S6202-73691" and substitute

"815-1197083 - Motor Starting Switch, Watertight, Rotary Type, 30 Ampere, 450 Volt A.C., Fuse or Fusetron Protected "

Page 2, paragraph 3 2 1: Delete and substitute

"3 2 1 The following minimum characteristics are required when pumping seawater of 1.03 specific gravity

Capacity Gpm	Total head, feet	
	Class 1, 2 or 3	Class 4 or 5
200	50	40
140	70	60
0	90	75

Page 2, paragraph 3.2.3 Delete and substitute

"3.2.3 Operation - Continuous operation shall be as follows:

(a) Each class 1, 2 or 3 pump shall be capable of continuous operation with a total suction lift of 20 feet and a total head of 70 feet, but not necessarily at the delivery specified in 3 2. 1.
(b) Each class 4 or 5 pump shall be capable of continuous operation with a total suction lift of 20 feet and a total head of 55 feet, but not necessarily at the delivery specified in 3.2 1 "

Page 4, paragraph 3.4.5, line 2 Delete "and within 24 hours"

Page 5, paragraph 3 6.4, item (f), line 5 Delete "1/4 hour" and substitute "10 minutes"

Page 6, paragraph 3 6 5 1.2 last two sentences Delete

Page 6, paragraph 3 6.5.1.3, last sentence Delete and substitute "The cable assembly between switches and plugs of class 1 and class 2 pumps shall include the plug connectors and shall be in accordance with MIL-C-15987 Plug connectors shall not be furnished with class 3, 4 and 5 pumps, but the cable ends shall be sealed with rubber and friction tape "

Page 6, paragraph 3 6 6 1 Delete and substitute

3 6 6 1 Each alternating-current unit shall be furnished with a control switch in accordance with Drawing 815-1197083 "

FSC 4320

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T10:11Z
Check the source to verify that this is the current version before use.

MIL-P-17454B
INTERIM AMENDMENT-2(SHIPS)

Page 9, paragraph 4.2.2.1. Delete and substitute:

"4.2.2.1 Lot. - A lot shall consist of a group of pumps of the same class scheduled for production within a three month or 90 day period The selected pumps shall have successfully passed the routine tests."

Page 11, paragraph 4.6.5.1, line 5· Delete "15 minutes" and substitute "10 minutes"

Page 12, Add as paragraph 4.8·

"4 8 Inspection system. - The pump manufacturer shall provide and maintain an inspection system acceptable to the Government. The inspection system shall be in accordance with MIL-I-45208."

Preparing Activity:
Navy-SH
(Project 4320-N124Sh)

Source: https://assist.dla.mil -- Downloaded: 202610-18T10:11Z
Check the source to verify that this is the current version before use.