MIL-B-52055B(ME)
28 August 1978
SUPERSEDING
MIL-B-52055A
13 January 1964

MILITARY SPECIFICATION

BUILDING, PREFABRICATED, READY-CUT, WAREHOUSE TYPE

This specification is approved for use by the Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a prefabricated warehouse building (40 foot wide by 100 foot long) capable of being expanded into a 80-foot-wide by 100-foot-long building utilizing two 40-foot basic buildings and a widening kit.

1.2 Classification. The 40-foot by 100-foot basic building shall be furnished in the following phase(s) of erection, as specified (see 6.2):

Phase I - Framing plus roof and gable covering.
Phase II - Wall covering and sliding door assemblies.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

FSC 5410

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

FF-B-575	- Bolts, Hexagon and Square.
FF-H-106	- Hardware, Builders'; Locks and Door Trim.
FF-H-116	- Hinges, Hardware, Builders'.
FF-N-836	- Nut, Square, Hexagon, Cap Slotted Castellated, Clinch Knurled and Welding.
FF-T-791	- Turnbuckle.
FF-W-92	- Washers, Metal, Flat (Plain).
HH-P-151	- Packing; Rubber-Sheet, Cloth-Insert.
QQ-S-775	- Steel, Sheets, Carbon, Zinc Coated (Galvanized) by the Hot Dip Process.
QQ-S-781	- Strapping, Steel, and Seals.
SS-C-153	- Cement, Bituminous, Plastic.
GGG-P-831	- Punches, Center, Coopers', Drive Pin, Aligning and Prick.
PPP-B-566	- Boxes, Folding, Paperboard.
PPP-B-636	- Boxes, Shipping, Fiberboard.

MILITARY

MIL-P-116	- Preservation-Packaging, Methods of.
MIL-P-514	- Plates Identification, Instruction and Marking Blank.
MIL-T-704	- Treatment and Painting of Materiel.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

DRAWINGS

ME

D11203-1 through -22	- Building, Prefabricated, Ready-Cut, Warehouse Type; Phase I.
D11204-1 through -7	- Building, Prefabricated, Ready-Cut, Warehouse Type, Phase II.
D11340-1 through -11	- Building, Prefabricated, Ready-Cut, Warehouse Type; Packing for Shipment.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A36 - Structural Steel.
A570 - Hot-Rolled Carbon Steel Sheet and Strip, Structural Quality.
A611 - Steel, Cold-Rolled Sheet, Carbon Structural.
D1494 - Diffuse Light Transmission Factor of Reinforced Plastic Panels.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Welding Qualifications, Section IX.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN NATIONAL STANDARDS INSTITUTE, INC. (ANSI)

B18.6.4 - Slotted and Recessed Head Tapping Screws and Metallic Drive Screws.

(Application for copies should be addressed to the American National Standards Institute, Inc., 1430 Broadway, New York, NY 10018.)

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:06Z
Check the source to verify that this is the currentversion before use.

AMERICAN WELDING SOCIETY, INC. (AWS)

D1.1 - Structural Welding Code, Section 5, Qualification.

(Application for copies should be addressed to the American Welding Society, Inc., 2501 N.W. 7th Street, Miami, FL 33125.)

NATIONAL BUREAU OF STANDARDS

PS 53-72 - Glass-Fiber Reinforced Polyester Structural Plastics Panels.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

3. REQUIREMENTS

3.1 Description. The building shall be as shown on Drawings D11203-1 through -22 (Phase I) and D11204-1 through -7 (Phase II). Unless otherwise specified (see 6.2), the phase(s) shall be furnished for a basic 40-foot-wide by 100-foot-long building. A widening kit is used to attach two 40-foot buildings together to make an 80-foot-wide by 100-foot-long building. When 80-foot by 100-foot buildings are required, the number of basic buildings and widening kits shall be as specified (see 6.2).

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the building components. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article (preproduction model). The contractor shall furnish one or more basic buildings or basic building with widening kit for examination and testing within the time frame specified (see 6.2) to prove, prior to starting production, that his production methods will produce buildings and widening kits that comply with the requirements of this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

Examination and tests shall be as specified in Section 4; and, unless otherwise specified herein, all examinations and tests shall be conducted by the contractor subject to surveillance and approval by the Government (see 6.3). When specified (see 6.2), the Government will conduct any or all of the preproduction examination and tests, as specified (see 6.2).

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Copies of analysis and test reports shall be available for all materials specified (see 6.5).

3.3.1 Steel.

3.3.1.1 Plate, shapes, and bar steel. Plate, shapes, and bar steel shall conform to ASTM A36.

3.3.1.2 Sheet and strip steel. Sheet and strip steel, except for outside covering, shall conform to either ASTM A570, Grade C, or ASTM A611, Grade C. Steel for optional girt purlins, except end clips, shall conform to either ASTM A570, Grade D, or ASTM A611, Grade D.

3.4 Components.

3.4.1 Outside covering. Outside covering, except corrugated plastic glazing, shall conform to QQ-S-775, Class C. Corrugated sheets shall be Type II and flashing shall be Type I.

3.4.2 Corrugated plastic glazing. Corrugated plastic glazing shall conform to NBS CS 214-57, Type I, light green color, not less than 0.0625 inch thick, and weight not less than 8 ounces per square foot. Configuration length and width shall be as specified on the drawings. When tested in accordance with ASTM D1494, the panel shall have a light transmission of not less than 27 percent. Endlaps shall be not less than 6 inches and sidelaps shall be not less than one full corrugation.

3.4.3 Sliding doors. Each sliding door panel shall be furnished with a commercial quality, industrial, steel door. The industrial door shall swing freely on zinc-coated hinges conforming to FF-H-116, Type 2127H, and shall lock securely in the sliding door with a latch set conforming to FF-H-106, Series 160, Type A. Weatherstripping for the sliding doors shall conform to HH-P-151, Class 2, 1/8 inch thick.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:06Z
Check the source to verify that this is the current version before use.

3.4.4 Calking compound. Calking compound shall conform to SS-C-153, Type I, and furnished in sealed 0.1-gallon capacity cartridges.

3.4.5 Closure or filler strips. Closure or filler strips shall be of synthetic rubber composition. The strips shall be of the same configuration as cladding on one side and flat on the other with a minimum thickness of 3/16 inch. The strips shall be not less than 1 inch wide and 24 inches long.

3.4.6 Turnbuckles. Turnbuckles shall conform to FF-T-791, Type I, Form 2, Class 2, zinc coated.

3.4.7 Punches. Punches shall conform to GGG-P-831, Type VIII, Class A, Style 1 or 2, Size 3, except the point shall be ground to the configuration shown on Drawing D11203-15.

3.4.8 Fasteners.

3.4.8.1 Nails. Nails shall be made from steel wire and shall be zinc coated.

3.4.8.2 Nuts. Nuts shall conform to FF-N-836, Type II, Style 4, cadmium- or zinc-coated steel.

3.4.8.3 Bolts. Bolts shall conform to FF-B-575, Type 2, cadmium- or zinc-coated steel.

3.4.8.4 Washers.

3.4.8.4.1 Plain. Plain washers shall conform to FF-W-92, Type A, Grade I, Class A, medium weight, cadmium or zinc coated.

3.4.8.4.2 Combination. Combination washers, consisting of synthetic rubber sealing washers back-to-back with cadmium- or zinc-coated steel washers, shall be attached to all duplex-head nails and sheet-metal screws specified on the drawings and shall be of a size and shape to suit application. The sealing washer shall be nearest the point of the fastener and may or may not be laminated to the plain washer.

3.4.8.5 Sheet metal and self-tapping screws. Sheet metal and self-tapping screws shall have slotted hexagon heads and shall conform to ANSI B18.6.4-1966, Type A and Type F, respectively, and shall be cadmium or zinc coated.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

3.5 Marking.

3.5.1 Identification marking. Each building shall be identified in accordance with MIL-STD-130. The marking shall be applied on plates conforming to MIL-P-514, Type 1, Style 3, Composition C, of Type I, Grade A, Class 1 material. The plates shall be riveted to the interior side of each industrial steel door.

3.5.2 Erection marking. Each component of the building, except fasteners and hardware, shall have its erection mark (shown on the drawings) stenciled on the component or on an attached metal tag when the size of the component prevents stenciling directly. Stenciling shall be as specified in 3.7.

3.6 Treatment and painting. The portions of the building components normally painted shall be cleaned, treated, and painted in accordance with MIL-T-704, Type A, color as specified (see 6.2).

3.7 Stenciling. The nomenclature, identification marking as shown on the drawings, and the weight shall be stenciled near the center on both sides of each building component except fasteners and hardware. The letters shall be Gothic capitals, and the numerals shall be 2 inches high where space permits. On small components, the stenciling shall be as large as practicable. Stenciling paint shall conform to MIL-T-704.

3.8 Technical publications. Such technical publications as are specified shall be furnished (see 6.2). The manuals shall consist of isometric or perspective line drawings and pertinent details showing each successive step in field erection. Included in the manuals shall be a complete bill of material, erection diagrams, a packing list and one set of reduced-size prints of applicable drawings showing the following:

(a) Typical foundation details and anchor bolt layout, including anchorage details.
(b) Wall and roof frame layout.
(c) Wall and roof sheet layout.
(d) Details and typical sections of door, ventilators, and windows.
(e) Layout and details for erection, including, but not limited to, special instructions pertaining to flashing, weathertight trim, and details of the installation of electrical and lighting system, if required.
(f) Instructions for dismantling and re-erection of the building, and components required to accomplish the re-erection of the building.
(g) Concrete floor plans, elevations, sections and details, including all reinforcing details.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:06Z
Check the source to verify that this is the currentversion before use.

3.9 Workmanship.

3.9.1 Metal fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the material. Corners shall be square and true. Flame cutting, using tips suitable for the thickness of the steel, may be employed instead of shearing and sawing. All bends shall be made with controlled means to insure uniformity of size and shape. Precaution shall be taken to avoid overheating. Heated steel shall be allowed to cool slowly. External surfaces shall be free of burrs, sharp edges and corners, except when sharp edges or corners are required or where they are not detrimental to safety.

3.9.2 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, mill scale that can be removed by chipping and wire brushing, and other foreign matter. Parent materials, weld filler metals, and fabrication techniques shall be as required to enable the building components to conform to the examination and test requirements specified in Section 4. Parts to be joined by fillet welds shall be brought into as close contact as possible and in no event shall be separated by more than 1/16 inch unless appropriate bridging techniques are used. Unless otherwise specified (see 6.2), the welding process used in fabrication of the building components shall be at the option of the contractor.

3.9.3 Jigs and fixtures. Shop-fabricated components shall be assembled in steel jigs or fixtures and welded while held securely in position. Steel jigs and fixtures shall be designed to minimize the distortion of the parts being welded.

3.9.4 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

AWS D1.1, Structural Welding Code, Section 5, Qualification.
ASME Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

Contractors who make only horizontal welds need not qualify welders for "all position welding". Subject to approval by the Government, the contractor's standard welder qualification may be substituted in lieu of the above codes provided that the contractor's procedure is equivalent to the above codes. The contractor shall be responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with AWS or ASME codes.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:06Z
Check the source to verify that this is the current version before use.

3.9.5 Welding practices.

(a) Preheat of materials being welded and maximum interpass temperature during welding shall be in accordance with the contractor's recommendations.
(b) Tack welds shall be subject to the same quality requirements as final welds.
(c) Work shall be positioned for flat welding whenever practicable.
(d) Procedures and sequences shall be such that distortion and shrinkage will be held to a minimum. When straightening is required, caution shall be exercised to insure that the straightening process does not weaken the part and building component.

3.9.6 Weld quality.

(a) The contractor shall be responsible for determining the inspections needed to insure that, when the welded parts are assembled together to make the building component, the building component shall conform to the inspection requirements specified in Section 4.
(b) All weldments shall be free of slag, flux, weld spatter, and other impurities detrimental to either the appearance or strength of the weldment.
(c) Undercut in weldments shall be held to a minimum and shall not be more than 1/32 inch deep.

3.9.7 Bolted connections. Boltholes shall be accurately formed and shall have the burrs removed. Bolts shall protrude not more than two full threads.

3.9.8 Machine work. Tolerances and gages for metal fits shall conform to the limits specified on the applicable drawings.

3.10 Assembly. The building components shall be fabricated to assure proper assembly and operation of doors.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

4.1.1 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications, standards, and drawings, as applicable.

4.1.2 Disassembly inspection. Failure of any examination or test by the preproduction model shall be cause for disassembly, in the presence of a Government representative, of the preproduction model, to the extent necessary to determine the cause of the failure. Each disassembled part shall be examined in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, tolerances, and workmanship. Parts not complying with such requirements shall be rejected and shall be cause for rejection of the preproduction model. Reassembly with replacement parts and retesting shall be the responsibility of the contractor.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Quality conformance inspection (see 4.4).
(c) Inspection of packaging (see 4.6).

4.3 Preproduction inspection.

4.3.1 Examination. The preproduction building components shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection or for performing the disassembly inspection specified in 4.1.2.

4.3.2 Tests. The preproduction building components shall be tested as specified in 4.5.2. Failure of any test shall be cause for rejection or for performing the disassembly inspection specified in 4.1.2.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination and tests shall be in accordance with MIL-STD-105.

4.4.2 Examination.

4.4.2.1 Samples. Samples selected in accordance with 4.4.1 shall be examined for the defects specified in 4.5.1. AQL shall be 2.5 percent defective.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

4.5 Inspection procedure.

4.5.1 Examination. The building components shall be examined for the following defects:

101. Dimensions shown on the drawings not as specified.
102. Materials not as specified.
103. Building components not as specified.
104. Identification and erection marking not as specified.
105. Treatment and painting not as specified.
106. Stenciling not as specified.
107. Technical publications not as specified.
108. Workmanship not as specified.
109. Certification of welders not as specified.
110. Welding practices and weld quality not as specified.

4.5.2 Tests.

4.5.2.1 Test conditions. Unless otherwise specified in a test, tests shall be performed without shelter and at the climatic conditions existing at the place of test.

4.5.2.2 Assembly test. When the contract or order includes Phase I, a partial structure containing the requires phase(s) for one interior bay and two end bays shall be erected. The contractor shall furnish all labor and materials required for the assembly test. The test building shall be made up of randomly selected structural elements and components necessary to erect a complete, weathertight test building. After the modified test building has been erected and tested, the contractor shall completely disassemble the test building and replace all damaged parts and fasteners, retouch damaged protective coatings, and furnish new high strength steel bolts. When all of the above are replaced and repaired, the building from which the components were selected may be accepted for delivery. The outside covering used on the first-produced item test building shall not be furnished as a part of the contract or order. The test building shall be erected in accordance with procedures and instructions described in the erection manual furnished by the contractor. One or more of the following shall constitute failure of the test:

(a) Components fail to assemble properly.
(b) Deformation of components.
(c) Doors and windows do not operate properly.
(d) Inadequate technical publications, such as erection manuals.

The contractor shall determine the cause of failures, replace failed components, and assure that all like components are of acceptable quality.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

4.6 Inspection of packaging.

4.6.1 Preproduction pack inspection.

4.6.1.1 Examination. Examine the preproduction pack for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

111.	Materials, methods, and containers not as specified for Level A or B. Each incorrect material, method, or container shall be considered one defect.
112.	Unprotected surfaces not coated with preservative as specified for Level A.
113.	Threads of tie rods not preserved as specified for Level A.
114.	Threads of turnbuckles not preserved and turnbuckles secured together as specified for Level A.
115.	Caulking guns not preserved as specified for Level A.
116.	Sliding door trucks not preserved as specified for Level A.
117.	Fasteners and door hardware not preserved as specified for Level A.
118.	Rolls of filter strip not individually preserved as specified for Level A.
119.	Girt clips for each building phase not secured together as specified for Level A.
120.	Technical publications not preserved as specified for Level A.
121.	Boxing and bundling not in accordance with the applicable drawing as specified for Level A.
122.	Components not preserved in accordance with the referenced document for Commercial.
123.	Components not consolidated for shipment in accordance with the applicable drawings as specified for Level A.
124.	Packing not as specified for Level B.
125.	Components not packed in accordance with the referenced document for Commercial.
126.	Marking missing, illegible, incorrect, or incomplete for Level A, Level B, or Commercial.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:06Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 Preproduction pack. The contractor shall furnish a preproduction pack for examination within the time frame specified (see 6.2), to prove prior to starting production packaging that the applied preservation, packing, and marking comply wtih the packaging requirements of this specification. Examination shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The preproduction pack may be accomplished utilizing either the preproduction building or a production building. When the preproduction building is utilized, any preservation and packing shall be removed by the contractor at no expense to the Government, when requested by the Government to facilitate comparison between the preproduction building and the production building.

5.2 Preservation. Preservation shall be Level A or Commercial as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Preservatives. Preservatives specified herein shall conform to the applicable specification listed in and shall be applied in accordance with MIL-P-116.

5.2.1.2 Unprotected surfaces. Unprotected metal components of the warehouse building requiring the application of a contact preservative in accordance with MIL-P-116, and not specifically specified herein, shall be coated with Type P-1 preservative.

5.2.1.3 Tie rods. The threads of the tie rods shall be coated with Type P-1 preservative.

5.2.1.4 Turnbuckles. Turnbuckles for each building phase shall be secured together with soft annealed wire. The threads of the turnbuckles shall be coated with Type P-1 preservative.

5.2.1.5 Calking guns. Each calking gun shall be preserved in accordance with MIL-P-116, Method IC-2, using the contractor's container or a close-fitting box conforming to PPP-B-566, variety, style, and class optional.

5.2.1.6 Sliding door trucks. Sliding door trucks shall be preserved together in accordance with MIL-P-116, Method IC-2, using the contractor's container or a close-fitting box conforming to PPP-B-636, Class Domestic.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:06Z
Check the source to verify that this is the current version before use.

5.2.1.7 Fasteners and door hardware. Fasteners of like description in the quantities required for each building phase shall be preserved together and, the door hardware preserved together, in accordance with MIL-P-116, Method IC-2, applying Type P-7 preservative to threads and surfaces subject to corrosion. The container shall be the contractor's container or a close-fitting box conforming to PPP-B-636, Class Domestic, or PPP-B-566, variety, style, and class optional, as applicable to the weight of contents.

5.2.1.8 Filler strips. Each roll of filler strips shall be preserved in accordance with MIL-P-116, Method IC-1 or IC-3.

5.2.1.9 Girt clips. Girt clips in the quantities required for each building phase shall be secured together with soft annealed wire.

5.2.1.10 Technical publications. Technical publications shall be preserved in accordance with MIL-P-116, Method IC-1 or IC-3.

5.2.1.11 Boxing and bundling. The components shall be boxed and bundled as shown on Drawings D11340-1 through -11. Strapping shall conform to QQ-S-781, Class 1, Type I or IV, Finish B.

5.2.2 Commercial. The components comprising a complete building shall be preserved in accordance with MIL-STD-1188.

5.3 Packing. Packing shall be Level A, Level B, or Commercial as specified (see 6.2).

5.3.1 Level A. The components comprising each complete building phase, boxed, and bundled as specified in 5.2.1.11, shall be consolidated for shipment in crates and secured lifts in accordance with the applicable Drawings D11340-1, D11340-3, DD1340-5, D11340-7, D11340-9, and D11340-11. Crates shall be closed and strapped in accordance with the crate specification. Strapping for secured lifts shall conform to QQ-S-781, Class 1, Type I or IV, Finish B.

5.3.2 Level B. The components comprising each complete building phase, boxed and bundled as specified in 5.2.1.11, and as shown on the applicable Drawings D11340-2, D11340-4, D11340-6, D11340-8, D11340-10, and D11340-11, shall be shipped without overpacking.

5.3.3 Commercial. The components comprising a complete building shall be packed in accordance with MIL-STD-1188.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

5.4 Marking.

5.4.1 Military. Marking for military level of protection shall be in accordance with MIL-STD-129.

5.4.2 Commercial. Marking for commercial packaging shall be in accordance with MIL-STD-1188.

6. NOTES

6.1 Intended use. The warehouse building is intended for phase erection, dismantling, and reassembly in the field by unskilled personnel without benefit of special tools.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Phase(s) or erection required and whether the phase(s) shall be for a width and length of building other than the 40-foot-wide by 100-foot-long basic building (see 1.2 and 3.1).
(c) Number of basic buildings and widening kits if 80-foot by 100-foot buildings are required (see 3.1).
(d) Time frame required for submission of preproduction model, and number of basic buildings with widening kit required (see 3.2).
(e) When the Government will conduct any or all of the preproduction model examination and tests. When the Government will conduct some but not all of the preproduction examination and tests, the contracting officer should specify which examination and tests will be conducted by the Government and which examination and tests shall be conducted by the contractor (see 3.2).
(f) Color required (see 3.6).
(g) Time frame required for submission of the preproduction pack (see 5.1).
(h) Degree of preservation and packing required (see 5.2 and 5.3).

6.3 Preproduction model. Any changes or deviations or production building components from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the contractor of his obligation to furnish building components conforming to this specification.

6.4 Preproduction pack. Any changes or deviations of production packs from the approved preproduction pack will be subject to the approval of the contracting officer. Approval of the preproduction pack will not relieve the contractor of his obligation to preserve, pack, and mark the building or building widening kits in accordance with this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

6.5 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of the specification (see 3.3).

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 5410-A230

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.

NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER *(Number)* AND TITLE

MIL-B-52055B(ME) Building, Prefabricated, Ready-Cut, Warehouse Type

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1426 1 OCT 76

EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID

U.S.MAIL

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Mobility Equipment Research and
Development Command
ATTN: DRDME-DS
Ft. Belvoir, VA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.