INCH-POUND

MIL-B-52075G
29 March 1991
SUPERSEDING
MIL-B-52075F
9 December 1977

MILITARY SPECIFICATION

BATH UNIT, PORTABLE, 8-SHOWER HEAD, M-1958

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a self-contained bath unit for use in the field, using a gasoline operated engine generator and water heater. The unit is designed to pump water from a stream and furnish 16 gallons of normal bath temperature water per minute to the shower heads.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

SPECIFICATIONS

FEDERAL

V-T-276 - Thread, Cotton
W-R-550 - Rods, Ground (with Attachments)

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be used in improving this document should be addressed to: U.S. Army Natick Research, Development, and Engineering Center, Natick, MA 01760-5017 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 4510

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

TT-P-664 - Primer Coating, Alkyd, Corrosion-Inhibiting, Lead and Chromate Free, VOC-Compliant
VV-F-800 - Fuel Oil, Diesel
PPP-T-60 - Tape, Packaging, Waterproof

MILITARY

MIL-C-104 - Crates, Wood, Lumber and Plywood Sheathed, Nailed and Bolted
MIL-P-116 - Preservation, Methods of
MIL-B-121 - Barrier Material, Greaseproofed, Waterproofed, Flexible
MIL-C-496 - Clips, End, Strap
MIL-W-530 - Webbing, Textile, Cotton, General Purpose, Natural or in Colors
MIL-B-543 - Buckles, Tongueless and Web Strap
MIL-T-3530 - Thread and Twine, Mildew Resistant or Water Repellent Treated
MIL-S-7916 - Sealing Compound, Thread and Gasket, Fuel, Oil, and Water Resistant
MIL-C-10578 - Corrosion Removing and Metal Conditioning Compound (Phosphoric Acid Base)
MIL-P-10603 - Pumps and Pumping Units, Centrifugal, Power-Driven, for Water, Packaging of
MIL-W-13518 - Wood Preservative, Tetrachlorophenol and Pentachlorophenol, Surface Sealing Compound
MIL-V-13811 - Varnish, Waterproofing, Electrical, Ignition
MIL-L-21260 - Lubricating Oil, Internal Combustion Engine, Preservative and Break-In
MIL-C-46168 - Coating, Aliphatic Polyurethane, Chemical Agent Resistant

STANDARDS

FEDERAL

FED-STD-751 - Stitches, Seams and Stitchings

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129 - Marking for Shipment and Storage
MIL-STD-130 - Identification Marking of US Military Property
MIL-STD-147 - Palletized Unit Loads
MS 51926 - Clips, End, Strap-Type I, Class 1 and Class 2

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

DRAWINGS

U.S. ARMY NATICK RESEARCH, DEVELOPMENT, AND ENGINEERING CENTER

6-1-733	-	Bath Unit, 8-Shower Head M-1958; Water Heater Assembly
6-1-1984	-	Bath Unit, 8-Shower Head M-1958; Ignition Cable Assembly

(Copies of Drawings are available from the U.S. Army Natick Research, Development, and Engineering Center, ATTN: STRNC-UXT, Natick, MA 01760-5017.)

2.2 Non-Government publications. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN WELDING SOCIETY (AWS)

Standard Qualification Procedure of the American Welding Society

(Copies may be obtained from the American Welding Society, Inc., 550 N.W. Le Jeune Road, P.O. Box 33126, Miami, FL 33135.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Welding Qualifications of the American Society of Mechanical Engineers

(Copies may be obtained from the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA No. 70 - National Electrical Code

(Copies may be obtained from the National Fire Protection Association, 1 Batterymarch Park, Quincy, MA 02269.)

HYDRAULIC INSTITUTE STANDARDS

(Copies may be obtained from the Standard Hydraulic Institute, 122 East 42nd Street, New York, NY 10017.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 3951 - Standard Practice for Commercial Packing

(Applications for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103-1187.)

(Non-Government standards and other publications are normally available from organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3), in accordance with 4.3.

3.2 Alternate components. Components offered as equivalent to components specified herein and on the referenced drawings as a specific manufacturer's part number or equal shall be functionally equal, of equal or better quality with the manufacturer's part number identified. The incorporation and inclusion of such a component in the design of the specified end product shall not require modification or change to any other specified components, unless such modification or change is specifically approved by the contracting officer. Prior to manufacture of the first article, or if none is required, prior to commencing production, the contractor shall submit for the contracting officer's approval, a list identifying each alternate component, together with proof that each listed component complies with requirements specified herein. The contracting officer at his option, may require a physical sample of the proposed substitution. Approval of the submitted listing, together with necessary supporting data does not relieve the contractor of the responsibility that these components perform in accordance with specified requirements when incorporated into the end product.

3.3. Materials and components. The materials and components shall be as specified herein and on the applicable drawings. Materials and components not definitely specified shall be of the quality normally used by the manufacturer provided the completed item complies with all the provisions of this specification. It is encouraged that recycled material be used when practical as long as it meets the requirements of this specification.

3.3.1 Buckle. The 1-inch buckle shall conform to type III, style 3, class 1 of MIL-B-543.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

3.3.2 End clip. The 1-inch end clip shall be brass and conform to type I, class 1 of MIL-C-496, and to MS 51926, Dash No. 3.

3.3.3 Thread, cotton, machine. The thread used for all machine stitching shall be ticket number 12, 4 ply and conform to type IA3 or IB3 of V-T-276. The thread shall match Olive Drab Shade S-1 (CA 66022) and shall be treated for mildew resistance in accordance with type I, class 1 of MIL-T-3530.

3.3.4 Primer. Primer for steel and aluminum surfaces shall conform to TT-P-664.

3.3.5 Enamel. Enamel shall conform to MIL-C-46168. The color shall be lusterless forest green.

3.3.6 Sealer. Sealer for plywood shall conform to type II of MIL-W-13518. Sealer compound for thread joints and gaskets shall conform to MIL-S-7916.

3.4 Design and construction. The design and construction of the bath units shall be as specified herein, and as shown on Drawing 6-1-733 and drawings referenced thereon. The electric power shall be 3 phase, 60 hertz, 4 wire, 120 volts line to neutral on 208 volts line to line 120/208 volts. All wiring shall be in accordance with the provisions of NFPA No. 70. The ground rod with attachments shall conform to type III, class B of W-R-550. The bath unit shall have seven web straps each having a buckle on one end and an end clip on the other. The buckles shall be fastened by a cross stitch 3/4 by 1 inch, double stitched at both ends. Ends of webbing where buckles are attached shall be overedge stitched or turned under before stitching to prevent raveling. The webbing shall be inserted to the full depth of the clip. The clip shall be securely attached without cutting the webbing and shall lie flat at the point of entrance. Two straps, each 3 feet long, shall hold the shower heads in place and be secured to the plywood floor. Three straps, each 3 feet long, shall hold the coiled fire hose. One strap, 18 inches long, shall hold the coiled suction hose and another strap, 3 feet long shall hold all the electric cables together. Machine stitching shall be 5 to 7 stitches per inch. Box stitching shall conform to type 301 of FED-STD-751. Stitching shall conform to type 304 or 503 of FED-STD-751.

3.5 Performance.

3.5.1 Pump, water. The water pump shall operate on 3 phase, 208 volts. The net positive suction head (NPSH) shall not be greater than 4 feet and the performance curve shall not be less than that shown on Drawing 6-1-1984, when tested as specified in 4.4.2.2.1 with the flow rate of the pump not less than 30 gpm at 3.1 motor rated amperage.

3.5.2 Firebox and outside vessel assembly. Each firebox and outside vessel assembly shall have no visible evidence of leakage when individually tested as specified in 4.4.2.2.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

3.5.3 Heater, water. Each water heater shall have no visible evidence of leakage, fractures or breakage of parts when tested as specified in 4.4.2.2.3.

3.5.4 Shower head and riser assembly. Each shower head and riser assembly shall be tested for leaks when tested as specified in 4.4.2.2.4.

3.5.5 Heater, water assembly. All components of the water heater shall be completely assembled and tested as specified in 4.5.1 for the following:

(a) A minimum rate of 16 gallons per minute of water with a minimum temperature rise of 70°F.

(b) The fuel pump shall supply fuel at 100 psi gage with the bypass valve closed.

(c) The combination temperature and pressure control shall stop the supply of fuel when the temperature reaches 120°F and also shall allow the fuel to flow when the water pressure is 15 psi gage or above.

(d) No leakage of the assembly.

3.5.6 Switch, overload and reset. The overload and reset switch of the burner blower shall be capable of stopping the motor when an overload condition occurs, and of being reset to resume motor operation after the overload condition has been eliminated (see 4.5.2).

3.6 Finish.

3.6.1 Surface preparation. After fabrication and completion of tests specified in 4.4.2.2.1 through 4.4.2.2.4 and 4.5.1, each component to be coated shall have all rough and sharp edges and scale removed prior to finishing. All metal surfaces shall be thoroughly cleaned and prepared for painting using compound conforming to type I or II of MIL-C-10578. Surfaces shall be dried prior to application of paint. All plywood surfaces shall be given a coat of sealer specified in 3.3.6. Plywood edges shall be sealed prior to assembly of the shower units using a sealer conforming to type II, class 2 of MIL-W-13518.

3.6.2 Priming. Metal and wood surfaces, except shower head nozzles, shall be coated with primer conforming to TT-P-664.

3.6.3 Enameling. After primer is dry, all metal primed surfaces shall be coated with enamel conforming to MIL-C-46168. Government-furnished painted parts which have become exposed due to alterations shall be touched up.

3.6.4 Handles and plugs. All control handles and drain plugs shall be painted red after cleaning.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

3.7 Marking. Marking for identification shall be in accordance with MIL-STD-130.

3.8 Government-furnished property. Unless otherwise specified (see 6.2), the Government shall furnish 18 feet of cotton, webbing, 1 inch type IIa, class 4, Olive Drab, No. 7 conforming to MIL-W-530.

3.9 Workmanship. The bath unit shall be free from defects such as fractures, splits, punctures, tears, dents, creases, deteriorations, or malformations. There shall be no sharp edges, burrs, or slivers. The finish shall be free of blisters, peel, chipped areas or areas of no film. The finish shall be free from smudges, port touch up, scale, scratches, stain, overspray sag, imprint or embedded foreign matter. All bolts, studs, nuts and screws shall be drawn tight. Rivets shall be driven to completely fill the holes, with full size heads neatly finished and in full contact with the surface of the riveted members.

3.9.1 Welders. Unless otherwise specified (see 6.2), before assigning any welder to work covered by this specification, the contractor shall provide the Government inspection service with the names of the welders to be employed in the work, together with certification that each of the welders has passed a qualification test as prescribed by either of the following listed codes for the type of welding operation to be performed, and that such qualification is effective as defined by that particular code as follows:

(a) Standard Qualification Procedure of the American Welding Society.
(b) Welding Qualification of the American Society of Mechanical Engineers.

3.9.2 Welding. The surface of parts to be welded shall be free from oxide, scale, paint, grease, and other foreign matter. Welds shall be sound, continuous, smooth, and free from porosity, cracks, incomplete fusion, and deformation of material. All scale and flux deposits (when flux is used) shall be removed from the finished welds.

3.9.3 Electrical wiring. Wiring shall not be cut, abraded, or have excessive insulation stripped, and shall be properly and tightly joined at terminals. Wiring shall have adequate slack to provide strain relief.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.1.2 Responsibility for dimensional requirements. Unless otherwise specified in the contract or purchase order, the contractor is responsible for ensuring that all specified dimensions on the drawings have been met. When dimensions cannot be examined on the end item, inspection shall be made at any point, or at all points in the manufacturing process necessary to ensure compliance with all dimensional requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3)
b. Quality conformance inspection (see 4.4)

4.3 First article inspection. When a first article is required (see 3.1 and 6.2), it shall be examined for the defects specified in 4.4.3.1 and 4.4.3.2 and tested for the characteristics specified in 4.5.1 and 4.5.3. Any nonconformance shall be cause for rejection of the first article.

4.4 Quality conformance inspection. Unless otherwise specified, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.4.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents unless otherwise excluded, amended, modified, or qualified in this specification or applicable purchase document.

4.4.2 In-process inspection. Inspection of subassemblies shall be made to ascertain that construction details which cannot be examined in the finished product are in accordance with specified requirements. The Government reserves the right to exclude from consideration for acceptance any material or service for which in-process inspection has indicated nonconformance.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

4.4.2.1 Visual examination of operations. In-process examination shall be made of surface preparation prior to the application of the finished coat to determine compliance with 3.6.1. Also examination of surface preparation prior to welding shall be made to determine compliance with 3.9.2. Whenever nonconformance is noted, correction shall be made to the applicable process and all items processed. Items which cannot be corrected shall be removed from production.

4.4.2.2 In-process testing.

4.4.2.2.1 Pump, water test. One sample water pump shall be tested in accordance with the applicable section of the centrifugal pump test code of the Hydraulic Institute for conformance to the pump operating requirements as specified in 3.5.1. Failure to pass the test shall be cause for rejection of the sample water pump. For certification of the remainder of the pumps, see 4.4.9.

4.4.2.2.2 Firebox and outside vessel assembly test. Prior to painting, each firebox and outside vessel assembly shall be tested separately and under a hydrostatic pressure of 75 psi gage for leaks with the water connections capped for a period of 5 minutes. Any nonconformance with the requirements of 3.5.2 shall constitute failure of this test.

4.4.2.2.3 Heater, water test. Prior to painting, and assembly to the bath unit, each water heater shall be tested under a hydrostatic pressure of 75 psi gage for leakage, fractures or breakage of parts. Any nonconformance with the requirements of 3.5.3 shall constitute failure of this test.

4.4.2.2.4 Shower head and riser assembly test. Prior to painting, each shower head and riser assembly shall be capped and completely submerged in water with an internal pressure of 10 to 15 psi gage. Any nonconformance with the leakage requirements of 3.5.4 shall constitute failure of this test.

4.4.3 End item visual examination. The end items shall be examined for the defects listed in table I. The lot size shall be expressed in units of assembled bath units. The sample unit shall be one complete bath unit. The inspection level shall be II and the acceptable quality level (AQL), expressed in terms of defects per hundred units shall be 2.5 for major defects and 6.5 for total (major and minor combined) defects.

TABLE I. End item visual examination

Examine	Defect	Classification Major	Minor
Finish	Color not as specified		201
	Blistered, peeled, chipped or area of no film		202

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual examination (cont'd)

Examine	Defect	Classification Major	Minor
Finish (cont'd)	Poor touch-up, orange peel, color separation, smudge, scale, scratched, stained, overspray, sag, imprint or foreign matter imbedded		203
Design, construction and workmanship, general (applicable to all components and assemblies)	Any component or part missing or not specified type or size	101	
	Fractured, split, punctured, torn, dented, creased, deteriorated or malformed	102	
	Component misplaced, or not in proper alignment		204
	Component loose		205
	Sharp burr or edge or sliver		206
	Any operation omitted or not properly performed	103	
	Any functioning component that is inoperative or will not operate as intended	104	
	Any functioning component that requires abnormal force to operate or not interchangeable		207
	Any adjustable assembly that cannot be adjusted		208
	Any assembly not properly adjusted		209
	Any component not readily accessible for servicing where required		210
Welding	Missing, incomplete, burn holes, cracked, fractured, not fused	105	
	Undercut, not smooth and uniform or scale or flux deposits not removed		211
Soldering (when applicable)	Missing, not adherent or incomplete		212
	Not clean (flux residue not removed, pinholes in solder)		213
Bolts, nuts, screws, studs and other types of threaded fasteners	Broken, stripped, fractured or not tight		214

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual examination (cont'd)

Examine	Defect	Classification Major	Minor
Rivets (when required)	Broken, not peened or insufficiently peened or loose		215
Electrical assembly	Wiring cut, abraded, or not properly installed or joined	106	
	Adequate slack not provided for wiring to relieve strain		216
Gages, instruments, controls, thermometer, etc.	Not properly mounted or not specified type or capacity		217
	Not free of foreign matter		218
Marking	Missing, incomplete, not legible, not specified type or size, not in proper location		219

4.4.4 End item dimensional examination. The end items shall be examined for conformance to the dimensions specified on the applicable drawings. Only those dimensions that can be evaluated without damaging or disassembling the end items shall be examined. Any dimension not within the specified tolerance shall be classified as a defect. The lot size shall be expressed in units of assembled bath units. The sample unit shall be one complete bath unit. The inspection level shall be S-2 and the AQL, expressed in terms of defects per hundred units, shall be 4.0.

4.4.5 End item testing. Each end item shall be tested as specified in 4.5.1. One item selected at random from the first lot offered for inspection shall be tested as specified in 4.5.2. Failure to pass either test shall be cause to reject the effected end item.

4.4.6 Packaging examination. The fully packaged end items shall be examined for the defects listed below. The lot size shall be expressed in units of shipping containers. The sample unit shall be one shipping container fully packaged. The inspection level shall be S-2 and the AQL, expressed i terms of defects per hundred units, shall be 2.5.

Examine	Defect
Marking (exterior and interior)	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

Materials	Any component missing, damaged, or not as specified
Workmanship	Inadequate application of components, such as: incomplete sealing or closure of flap, improper taping, loose strapping or inadequate stapling Bulged or distorted container
Content	Number per container is more or less than required

4.4.7 Palletization examination. The fully packaged and palletized end items shall be examined for the defects listed below. The lot size shall be expressed in units of palletized unit loads. The sample unit shall be one palletized unit load, fully packaged. The inspection level shall be S-1 and the AQL, expressed in terms of defects per hundred units, shall be 6.5.

Examine	Defect
Finished dimensions	Length, width, or height exceeds specified maximum requirement
Palletization	Pallet pattern not as specified Interlocking of loads not as specified Load not bonded as specified
Weight	Exceeds maximum load limits
Marking	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application

4.4.8 Inspection of shipping container. When shipping containers are required to comply with MIL-C-104, examination for defects in the closure and strapping shall be in accordance with the applicable requirements of MIL-C-104.

4.4.9 Code and standard compliance. Certification that the pump total head-capacity characteristic curve complies with the performance curve specified in 3.5.1 shall be furnished and acceptable to the Government representative.

4.5 Methods of inspection.

4.5.1 Performance heater, water test. The complete water heater shall be connected to a source of water that shall supply a minimum rate of 16 gpm, through the boiler outlet. Thermometers shall be located in the inlet and

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

outlet water connections of the heater. The heater shall be operated for 15 minutes with the burner fuel pressure maintained at 100 psi gage. At the completion of this test, the complete heater assembly shall be examined for water leaks including the removal of the front cover and burner assembly to allow for examination of the firebox. Any nonconformance with the requirements of 3.5.5 for heater temperature rise, fuel pump pressure, combination pressure and temperature control, and leakage shall constitute failure of this test.

4.5.2 Overload and reset switch test. One burner, blower motor, overload and reset switch when assembled with the complete water heater shall be tested to determine compliance with 3.5.6, as follows:

(a) The blower wheel shall be restrained from turning, until the overload switch opens the electrical circuit.

(b) After a suitable period to allow for the thermal element of the switch to cool, the switch shall be reset manually to determine resumption of motor operation. Any nonconformance with the overload and reset switch requirements of 3.5.6 shall constitute failure of this test.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or Commercial as specified (see 6.2).

5.1.1 Level A preservation. All preservation shall be in accordance with the method and material requirements of MIL-P-116 or as hereinafter specified. Varnish specified hereinafter shall conform to MIL-V-13811. Tape hereinafter specified shall conform to type IV, class 1 of PPP-T-60. All exposed surfaces of the tape shall be coated with varnish. The color of the tape shall be of a contrasting color to the surface to which applied. The tape shall not be applied directly to plastic gage faces and dials. Such surfaces shall be protected with kraft paper or cushioning material prior to application of the tape.

5.1.1.1 Drainage of water system. The entire water system of the unit, including the water heater, water pump, line strainer, shower stands, hoses, etc., shall be thoroughly drained, blown out and dried with compressed air. All valves and petcocks shall be left open. A red tag shall be wired in a conspicuous place indicating that the entire water system has been completely drained.

5.1.1.2 Drainage of fuel system. The fuel lines, including the burner fuel lines, fuel pump, fuel filter and all connections, shall be completely drained and thoroughly dried and replaced. The exterior surfaces of all flexible fuel lines shall be coated with varnish. The fuel hoses with the

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

barrel plug assembly shall be coiled and secured with tape. The fuel pump shall be filled with diesel oil fuel conforming to VV-F-800 and the inlet pump fitting capped.

5.1.1.3 Cleaning. All uncoated and unpainted ferrous metal surfaces of the bath unit and components shall be cleaned in accordance with the process C-1 of MIL-P-116, and thoroughly dried prior to application of preservative.

5.1.1.4 Repainting and recoating. Painted and permanently coated surfaces from which the paint or permanent coating has been removed or which are defective shall be repainted or recoated with material identical with the original.

5.1.1.5 Preservation application.

5.1.1.5.1 Water pump. The water pump, drained as specified in 5.1.1.1, shall be cleaned and preserved in accordance with the applicable requirements of MIL-P-10603.

5.1.1.5.2 Water heater. The combustion chamber, exhaust tubes, exhaust pipe, and burner nozzles, cleaned as specified in 5.1.1.3, shall be fogged with type I or II preservative of MIL-L-21260. The shutter assembly shall be coated with preservative specified herein. The blower assembly and exhaust port shall be sealed with a combination of barrier-material conforming to type I or II, grade A of MIL-B-121, and tape. The fuel pressure and temperature gage glasses, all inlets and outlets, sight glasses, and electrical receptacle covers shall be sealed with tape.

5.1.1.5.3 Shower stand and hose assembly. The drained and dried shower stand assemblies shall be disassembled by removing legs and hoses. Each shower nozzle shall be sealed with tape. All open ends of the shower heads, legs and hoses shall be sealed with tape.

5.1.1.5.4 Electric cords. The receptacle ends of the electric cords shall be sealed with tape.

5.1.1.6 Securing of components. The water heater and pump shall be secured to the plywood base with the holddowns provided. The shower stands shall be secured to the base with straps provided. The firehoses and suction hoses shall be coiled and secured with straps provided. The electric cords shall be coiled and secured with straps provided. The ground rod sections shall be disassembled and the three sections, together with the ground wire, secured together with tape, cord, or twine. The water strainer, shower stand legs, and ground rod shall be placed within the burner exhaust duct and the ends of the duct sealed with tape.

5.1.2 Level C preservation. The bath unit shall be preserved-packed to afford adequate protection against corrosion, deterioration, and damage during shipment from the supply source to the first receiving activity. The contractor may use his standard practice when it meets these requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

5.2 Packing. Packing shall be level A, or Commercial as specified (see 6.2).

5.2.1 Level A packing. Each bath unit, preserved as specified in 5.1, shall be packed in a crate constructed, closed, and bolted to conform to type II, class 1 or 2, style A of MIL-C-104, except that floorboards or load bearing members shall not be required. The plywood base shall be utilized as the floor of the crates. The plywood base shall abut the headers and be bolted directly to the skids with not less than four 3/8-inch diameter carriage bolts. The bolts shall set in not less than 6 inches from each end of the plywood base and shall be centered in the skids. The firehoses, suction hose, and electric cords, coiled and secured as specified in 5.1.1.6, shall be stacked on the plywood base of the bath unit and secured. The burner exhaust duct, packaged as specified in 5.1.1.6, shall be anchored in an unused portion of the crate in accordance with the applicable requirements of the appendix of MIL-C-104.

5.2.2 Commercial packing. Bath units, preserved as specified in 5.1, shall be packed in accordance with ASTM D 3951.

5.3 Marking. In addition to any special marking required by the contract or purchase order, unit packs, shipping containers, and palletized unit loads shall be marked in accordance with MIL-STD-129 or ASTM D 3951, as applicable.

5.4 Palletization. When specified (see 6.2), bath units, packed as specified in 5.2 and 5.2.1, shall be palletized on a 4-way entry pallet in accordance with load type Ia of MIL-STD-147. Pallet types shall be type I (4-way entry), type IV, or type V in accordance with MIL-STD-147. Each prepared load shall be bonded with primary and secondary straps in accordance with the bonding means C and D or film bonding means F or G. Pallet patterns shall be in accordance with the appendix of MIL-STD-147. Interlocking of loads shall be effected by reversing the pattern of each course. If the container is of a size which does not conform to any of the patterns specified in MIL-STD-147, the pallet pattern shall first be approved by the contracting officer.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The portable bath unit is a self contained unit for use in the field. The unit is designed to take water from streams, rivers, lakes and the like by means of a pump and to heat it sufficiently to furnish normal bath temperature water to the shower heads.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

6.2 Acquisition requirements. Acquisition documents must specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. When a first article is required (see 3.1, 4.3, and 6.3).
d. Source and delivery of GFP when furnished (see 3.8 and 6.4).
e. When certification of qualification test for welders is not required (see 3.9.1).
f. Levels of preservation and packing (see 5.1 and 5.2).
g. Type and class of unit load required (see 5.2.1).
h. When palletization is required (see 5.3).

6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of Federal Acquisition Regulation (FAR) 52.209. The first article should be a preproduction sample. The contracting officer should specify the appropriate type of first article and the number of units to be furnished. The contracting officer should also include specific instructions in acquisition documents regarding arrangements for selection, inspection, and approval of the first article.

6.4 Government-furnished property. The contracting officer should arrange to furnish the property listed in 3.8.

6.5 Subject term (key word) listing.

Cleansing station
Spray nozzles
Transportable

6.5 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodians:

Army - GL
Air Force - 99

Review activities:

Army - MD, ME
Air Force - 84
DLA - CS

Preparing activity:

Army - GL

(Project 4510-0244)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-B-52075G	1991 March 29

3. DOCUMENT TITLE

BATH UNIT, PORTABLE, 8-SHOWER HEAD, M-1958

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial	(2) AUTOVON
U.S. Army Natick RD&E Center	508-651-4531	256-4531
c. ADDRESS (Include Zip Code) Commander, U.S. Army Natick RD&E Center ATTN: STRNC-UXT Natick, MA 01760-5017	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	

Source: https://assist.dla.mil -- Downloaded: 2026-[illegible]
Check the source to verify that this is the current version before use.