MIL-C-51051D(MU)
22 September 1969
SUPERSEDING
MIL-C-51051C(MU)
23 May 1969

MILITARY SPECIFICATION

COMPRESSOR, RECIPROCATING,

POWER-DRIVEN, FLAME THROWER,

3 1/2 CFM, AN-M4

1. SCOPE

1.1 This specification covers an air compressor for charging pressure cylinders.

2. APPLICABLE DOCUMENTS

2.1 Government documents. The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

NN-P-530 - Plywood, Flat-Panel.
TT-W-572 - Wood Preservative.
PPP-B-601 - Box, Wood, Cleated-Plywood.
PPP-B-636 - Box, Fiberboard.
PPP-F-320 - Fiberboard, Corrugated and Solid Sheet Stock (Container Grade), and Cut Shapes.

MILITARY

MIL-L-6085 - Lubricating Oil, Instrument, Aircraft, Low Volatility.
MIL-C-3600 - Compressors, Air and Gas (Except Oxygen), Packaging of.
MIL-E-10062 - Engines = Preparation for Shipment and Storage of.

STANDARDS

FEDERAL

Fed Test Method Std No. 151 - Metals; Test Methods.

MILITARY

MIL-STD-129 - Marking for Shipment and Storage
MIL-STD-210 - Climatic Extremes for Military Equipment.

FSC 1040

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:04Z
Check the source to verify that this is the current version before use.

DRAWINGS

US ARMY MUNITIONS COMMAND

EDGEWOOD ARSENAL

DL68-13-1522 - Compressor, Reciprocating, Power-Driven, Flame Thrower, 3-1/2 CFM, An-M4.
DL68-13-5189 - Packaging.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal, shall apply.

UNIFORM CLASSIFICATION COMMITTEE

Uniform Freight Classification

(Application for copies of these ratings, rules, and regulations should be addressed to Uniform Classification Committee, 202 Union Station, 516 West Jackson Boulevard, Chicago, Illinois 60606.)

THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Displacement Compressors, Vacuum Pumps and Blowers.

(Copies may be obtained from the American Society of Mechanical Engineers, 345 East 47th Street, New York 17, New York.)

3. REQUIREMENTS

3.1 Materials and components.

3.1.1 Materials. All materials cited on Drawing DL68-13-1522 or on the subsidiary drawings shall conform to the specifications listed thereon, or to the specific characteristics set forth on the drawings.

3.1.2 Components. All components of the unit shall conform to the specifications and drawings listed on Drawing DL68-13-1522 and subsidiary drawings.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:04Z
Check the source to verify that this is the current version before use.

3.2 Definitions.

3.2.1 Unit. The unit or compressor unit is defined as the assembly shown on Drawing E68-13-1522.

3.2.2 Compressor. The compressor is defined as the component sub-assembly of the compressor unit that performs the air compression function. It is exclusive of the engine, frame, controls, and all other associated unit accessory equipment.

3.3 Unit.

3.3.1 General. The compressor unit shall be completely self contained and shall consist of an air cooled engine direct coupled to a three stage, three cylinder air cooled reciprocating air compressor. The complete unit shall be equipped with all accessories necessary for operation. The complete unit weight, less the gasoline and oil, shall not exceed 68 pounds. The unit shall be designed for a minimum of 1000 hours operation.

3.3.2 Assembly. The compressor unit shall be assembled as shown on Drawing E68-13-1522. A minimum clearance of 1 inch between all compressor exterior surfaces and the inside contour of the protective frame shall be maintained except that any between the fan guard and frame will be acceptable. Unless otherwise specified, lock washers shall be used with screws, bolts and nuts to prevent loosening of components.

3.3.3 Rating. When operating at 3600 revolutions per minute (rpm), the unit shall deliver standard air (68° F, 14.7 pounds per square inch absolute barometric pressure and 36 percent relative humidity) at a minimum of 3-1/4 cubic feet per minute (cfm) of free air and a minimum pressure of 2000 pounds per square inch gage (psig) (see 6.3). When operating as above, the compressor shall not require more than 2.3 brake horsepower and not overload any components of the unit. The high pressure air flow from the after cooler to the moisture separator shall be within 15° F of the ambient temperature. The air delivery shall be measured by using the low pressure discharge nozzle method specified in ASME Power Test Code for Displacement Compressors, Vacuum Pumps and Blowers, or by the bottle pump-up method, when tested as specified in 4.4.4.1.

3.3.4 Lubrication. All moving parts of the unit normally requiring lubrication shall have readily accessible means provided for such lubrication and shall be designed for use with standard military lubricants. Grease and oil seals shall be provided with maximum accessibility for replacement. The lubricant sumps shall be provided with easy to read oil level indicators and accessible drains. All lubricating fittings shall be of the type suitable for use with standard lubricating equipment. Satisfactory compressor operation shall result when the compressor crankcase is serviced with oil conforming to MIL-I-6085.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:04Z
Check the source to verify that this is the current version before use.

3.3.5 Instruction plates and tags. The compressor unit shall be equipped with instruction plates or tags, suitably located, describing procedure to be followed in operating and servicing. The instruction plates shall be etched or stamped of aluminum with raised bright lettering on black filled background. Plates or tags shall include but not be limited to the following:

(a) Compressor nomenclature plate
(b) Operating instructions plate
(c) Compressor crankcase filler cap plate indicating use of MIL-L-6085 oil only
(d) Engine crankcase filler pipe tag indicating "oil"
(e) Engine fuel tank plate or tag indicating "gas"

3.3.6 Water separator.

3.3.6.1 Cycling. The separator with relief valve blocked off, shall be cycled from 0 to 3000 psig in a maximum period of 5 seconds. The pressure shall be held for 20 seconds then released to 0 psig in a maximum period of 5 seconds. The pressure shall be cycled at both temperature extremes specified on Drawing D68-13-5145. The separator shall show no evidence of permanent deformation or leakage when tested as specified in 4.3.3.1(a).

3.3.6.2 Capacity. The separator shall be attached to an AN-M4 compressor. With the separator discharge volume and pressure maintained, the separator shall remove all liquid carry-over (oil and grease) as specified on Drawing D68-13-5145 when tested in accordance with 4.3.3.1(b).

3.3.6.3 Pressure relief valve. An automatic pressure relief valve shall be provided with a 7/16-20UNF-3A threaded connection which will mate with the threads of the water separator cap (Dwg D68-13-1545). The valve shall allow the compressor to run continuously without exceeding a pressure of 2550 psig when outlets are closed and other safety devices are inoperative. The valve shall not permit air leakage (see 4.3.3.9) in excess of 3 cubic centimeters per minute of free air when the pressure in the system is 2000 $\pm$ 50 psig when tested as specified in 4.4.4.1.

3.3.7 Publications. The supplier shall furnish operating and maintenance publications with each compressor unit as specified in the contract or order (see 6.2).

3.4 Regular production unit. The supplier shall be permitted to run-in the compressor unit before performing acceptance test. At ambient conditions the unit shall deliver its rated capacity conforming to 3.3.3 when operated for a minimum of 6 hours as follows:

(a) Forty-five minutes with no load
(b) Fifteen minutes under load.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

Air delivery measurement shall be recorded at 1 hour intervals in accordance with 4.4.3 when tested as specified in 4.4.4.1.

3.5 Reliability data. Following acceptance of the compressor unit, the unit shall be operated at normal ambient temperature in accordance with table I and tested as specified in 4.4.4.2.

Table I. Reliability operating

Number of cycles	Length of cycle	Shut down time between cycles	Total operating time
24	15 minutes min full load 45 minutes max no load	15 ± 5 minutes	24 hours
9	1 hour min full load 3 hours max no load	3 ± 1/2 hour	36 hours
4	2 hours min full load 8 hours max no load	16 hours max	40 hours

The above cycles shall be done in sequence as listed in table I in a maximum of 200 hours. The shut down period shall not be considered as part of the operating time. Following each full load time period the pressure relief valve shall be automatically actuated in accordance with 4.4.4.2.

3.6 Identification. The compressor units shall be identified with serial numbers in sequence (see 6.2).

3.7 Preproduction. Prior to the start of regular production, a preproduction sample of compressors shall be produced in accordance with this specification for examination and test (see 4.3).

3.7.1 Component evaluation. Prior to assembly of the compressor, (see 3.2.2) all components subject to wear shall be dimensionally examined in accordance with manufacturer's drawings. Following all preproduction tests the compressor shall be disassembled, and all components previously examined shall be dimensionally reexamined for excessive wear and for scoring and damage. The data shall be recorded in table form showing the drawing dimension, component dimension prior to assembly and after testing. The preproduction tests shall be performed in sequence as listed under 4.3. Unless otherwise stated, during the preproduction tests the compressor shall operate against an outlet pressure of 2000 psig minimum.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

3.7.2 Performance. The compressor unit when serviced for ambient conditions shall deliver (see 4.4.3) the rated capacity in accordance with the requirements specified in 3.3.3 and also perform the following:

(a) Operate in accordance with 3.7.10 without replacement of major components.
(b) Pressurize a 208 ± 3 cubic inch container with air from 0 to 2000 psig in a maximum period of 5-1/2 minutes under the following atmospheric conditions:

(1) Temperature 32° to 95° F.
(2) Relative humididty no less than 40 percent.
(3) Barometric pressure 14.7 ± 0.2 psi.

3.7.3 Inclined position operation. At ambient conditions, the unit shall develop and maintain the rated capacity specified for a minimum of 1 hour in each of the following positions when tested as specified in 4.3.3.2.

(a) Compressor higher than engine with the long axis of the unit 15 degrees to the horizontal.
(b) Engine higher than compressor with the long axis of the unit 15 degrees to the horizontal.
(c) Unit inclined 15 degrees about the long axis and to the right.
(d) Unit inclined 15 degrees about the long axis and to the left.

3.7.4 Rain operation. At an ambient temperature of 70° to 90° F the unit shall operate continuously at rated capacity for each of the following time intervals under the specified conditions, when tested as specified in 4.3.3.3:

(a) One hour minimum operation with simulated rainfall of 2 ± 1/2 inch per hour impacted on all exposed surfaces.
(b) One hour minimum operation with simulated rainfall of 2 ± 1/2 inch per hour blowing horizontally at a rate of 20 ± 5 miles per hour (mph) against one side of the unit.
(c) Rainfall as in (b) impacting on the other side and each end of the unit. One hour operation under each of these three conditions.

After completion of this test examination of the crankcase oil shall show no evidence of water in access of that attributed to normal condensation.

3.7.5 Salt spray. The unit shall show no evidence of detrimental corrosion or excessive deterioration when subjected to salt spray in accordance with Federal Test Method Standard No. 151, method 811, except as follows: The test period shall be 48 hours when tested as specified in

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.3.3.4. At the end of the test period the unit shall be returned to ambient conditions (salt deposits may be removed by rinsing with tap water) and be operated within 1 hour. Operational period at rated capacity shall not be less than 1 hour.

3.7.6 High temperature operation. The unit complete with gasoline in the tank shall be hot soaked at a temperature of 155° ± 10° F for a minimum period of 16 hours. The temperature shall then be lowered to 115° ± 10° F and the unit soaked for a minimum period of 16 hours. At the end of this soak and at the same ambient temperature, the unit shall develop and maintain the rated capacity specified in 3.3.3 for a minimum of 12 hours when tested as specified in 4.3.3.5.

3.7.7 Blowing sand and dust. In a blowing sand and dust contaminated atmosphere, the unit shall develop and maintain the rated output specified in 3.3.3, when tested as specified in 4.3.3.6. During operation the compressor air intake filter shall remove no less than 95 percent of all harmful particles entering the filter under the most severe environmental conditions defined in MIL-STD-210, except the temperature shall be 70° ± 5° F for both sand and dust. Replacement or filter cleaning shall be permitted provided that the intervals between replacement or cleaning shall be no less than 1 hour and the total operating time required to change or clean the filter shall be no more than 4 hours. The wind velocity shall be 30 mph in place of the 40 mph specified in the applicable paragraphs of MIL-STD-210.

3.7.8 Low temperature operation. The unit complete with gasoline in the tank shall be cold soaked at a temperature of minus 65° - 10° F for a minimum period of 16 hours. The temperature shall then be raised to minus 40° - 5° F and the unit soaked for a minimum period of 16 hours. At the end of this soak and at the same ambient temperature the unit shall be preheated, develop and maintain the rated capacity specified in 3.3.3 for a minimum of 12 hours when tested as specified in 4.3.3.7.

3.7.9 Humidity. The unit shall show no deleterious effects when stored, for 360 hours at a temperature of 115° ± 5° F and 95 percent humidity. At the end of the storage period the unit shall be returned to ambient temperature conditions (wiping, air blast or oven permitted) and be operated within 1 hour after removal from storage. Operational period at rated capacity shall not be less than 1 hour. The unit shall develop and maintain the rated capacity specified in 3.3.3 when tested as specified in 4.3.3.8.

3.7.10 Endurance. After completion of the tests outlined in 4.3.3.1 through 4.3.3.8 the compressor unit shall be operated for a total of 500 hours as follows (see 4.3.3.9):

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

(a) 100 hours at ambient conditions for alternate periods of 15 + 5 minutes delivering against a minimum of 2000 psig pressure and 40 + 5 minutes against zero pressure.
(b) 300 hours at ambient conditions delivering against a minimum of 2000 psig pressure. For this portion of the endurance run an electric drive having a speed of 3600 ± 100 rpm may be substituted in lieu of the gasoline engine.
(c) 100 hours operating for alternate periods as specified in (a) above.

During the endurance test 208 ± 3 cubic inch container shall be pressurized with air from 0 to 2000 psig at 1 hour intervals. Following pressurization of the container, pressurization shall continue until relief valve functions.

3.7.11 Test report. One reproducible master and 20 copies of a test report shall be furnished by the contractor containing but not limited to the following:

(a) Description and photographs of each test set up.
(b) Failures of parts if any, operating time on parts and photographs of those failing parts.
(c) Time required to make repairs, if any.
(d) Logs maintained during testing (see 4.4.3).

3.8 Workmanship. The compressor unit shall be free from contamination (rust, foreign matter, oil or grease) and damage such as cracks, dents or deformation which could affect its use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.

4.1.1 Supplier's responsibility. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to specified requirements.

4.1.2 Objective evidence. The supplier shall provide objective evidence acceptable to the contracting officer that the requirements of 3.1 and section 5 for which specific inspection has not been provided in this specification have been satisfied.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (4.3)
(b) Quality conformance inspection (4.4)

4.3 Preproduction inspection.

4.3.1 Sample. A preproduction sample of two compressors shall be produced using the same methods, materials, and equipment that will be used in regular production.

4.3.2 For examination and nondestructive tests. The preproduction sample shall be examined and tested for all the specific requirements listed in this specification.

4.3.3 Preproduction tests (see 6.3).

4.3.3.1 Water separator.

(a) The separator shall be cycled for the required number of cycles at the specified pressure and temperature for the required period of time.

(b) Capacity. From the separators discharge air, the average amount of liquid carry over past the moisture separator shall be determined during periods of high average, and low humidity operating conditions. This test shall be run prior to the separator capacity portion of the preproduction test.

4.3.3.2 Inclined position. The compressor unit shall be operated for the specified times in each of the required positions. The air delivery shall be measured at the beginning and end of each operating period in each position.

4.3.3.3 Rain. Compressed air shall be exhausted outside the test chamber during this test and the stream of air shall be observed during the last 5 minutes of each step for evidence of visually detectable moisture.

Step I - The compressor unit shall be placed in a test chamber maintained at the specified temperature. The specified rainfall shall be impacted on all exposed surfaces. The unit shall be operated for the required period.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

Step II - With the specified rainfall continuing, a wind blowing horizontally at the required velocity shall be introduced against one side of the unit. This condition shall be maintained for the required period with the unit operating.

Step III - The compressor unit shall be rotated 90 degrees until each end and other side of the unit has been exposed to the condition specified in step II.

Step IV - The compressor crankcase shall be drained and observed for evidence of water.

4.3.3.4 Salt spray. The compressor unit shall be placed in a test chamber (not operating but in operating condition) for the required time and conditions.

4.3.3.5 High temperature. The unit when subjected to the specified temperature, for the specified time shall maintain the rated capacity for the specified time. At one hour intervals, the air delivery shall be measured. As soon as practical after each air delivery measurement the relief valve shall be automatically actuated. In addition the relief valve shall be checked for leakage using the water displacement method.

4.3.3.6 Blowing sand and dust. The compressor unit, serviced for operation above 32° F, shall be operated in a blowing sand and dust contaminated atmosphere in accordance with MIL-STD-210 for the operating period. The air delivery and sand and dust measurement shall be checked at one hour intervals. Random samples of air entering the intake filter of the unit and corresponding samples of air leaving the filter shall be taken or the filter shall be tested as to a separate item to satisfy the requirements.

4.3.3.7 Low temperature. The unit when subjected to the specified temperature, for the specified time shall maintain the rated capacity for the specified time. At one hour intervals the air delivery shall be measured. As soon as practical after each air delivery measurement the relief valve shall be automatically actuated.

4.3.3.8 Humidity. The compressor unit shall be placed in a test chamber (not operating but in operating condition) for the required time and conditions.

4.3.3.9 Endurance. Data listed in 4.4.3 shall be taken at one hour intervals for the required hours of operation specified in 3.7.10. The data shall be recorded on log sheets which coordinate all the required data chronologically with appropriate remarks. The remarks shall include a record of all stops and adjustments. The amount of fuel and lubricants consumed during the tests shall be recorded at suitable intervals.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.3.3.10 Acceptance/rejection criteria. The preproduction models shall comply with all the applicable requirements and tests specified in this specification to be acceptable. For operational reasons, if failure occurs during individual test, repairs may be made, the test may be continued, pending an investigation of the test failure. Engine failure shall not be cause for rejection, the engine shall be replaced and the test continued. The preproduction models after passing all tests and found to be acceptable, shall be reworked to place them in new condition and submitted for regular production acceptance. The supplier shall obtain written approval from the contracting officer prior to proceeding with regular production.

4.4 Quality conformance inspection.

4.4.1 For examination and nondestructive test. Each unit shall be examined and tested for all the applicable requirements of this specification.

4.4.2 Reliability data. One compressor unit shall be selected at random by the Government inspector from every forty units or fraction thereof produced and tested for compliance with 3.5. To expedite the testing required, the selected unit may be taken at random from the first 5 units produced in each sample lot. Failure of the reliability test unit shall be cause for rejection of the lot from which the unit was elected.

4.4.3 Tests. Whenever air delivery is specified, it shall be measured by using the low pressure discharge nozzle method specified in ASME Power Test Code for Displacement Compressors, Vacuum Pumps and Blowers, or by the bottle pump-up method. A complete log shall be kept for every compressor test as follows:

(a) All data required or applicable as stated in ASME Power Test Code for Displacement Compressors, Vacuum Pumps and Blowers for either test method specified above.
(b) Actual pressure achieved when pressure relief valve actuates.
(c) Record of fuel and oil consumption.
(d) Any unusual occurrence or malfunctioning observed.
(e) Ambient temperature, barometric pressure and relative humidity during each container pressurizing cycle, during endurance test and reliability test only.
(f) Temperature of the high pressure air.
(g) Compressor crankshaft speed (rpm).
(h) Amount of liquid collected at separator during each container pressurizing cycle, during preproduction test only.
(i) Lubricating oil (compressor and engine) temperature.
(j) Test time:

(1) Compressor operating time.
(2) Compressor down time.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

4.4.4 Tests (see 6.3).

4.4.4.1 Rating. After the run-in, if any, the unit shall be serviced for operation at ambient temperature and shall be operated continuously for the specified airflow, pressure and time. At the required intervals the air delivery shall be measured. During the first and last 5 minutes of the test, all air piping joints shall be saturated with a soap solution and examined for evidence of leakage. A stream of bubbles from soap-saturated joints shall indicate leakage. Operation of the relief valve shall be induced as required to determine correct functioning. Upon completion of the test each unit shall be cleaned and drained prior to preparation for delivery.

4.4.4.2 Reliability. After acceptance of the regular production unit, the unit shall be serviced for operation at ambient temperature and operated as required in table I. At the required intervals the air delivery shall be measured. During the first and last 5 minutes of the test, all air piping joints shall be saturated with a soap solution and examined for evidence of leakage. A stream of bubbles from soap-saturated joints shall indicate leakage. Operation of the relief valve shall be induced as required to determine correct functioning. Upon completion of the test each unit shall be cleaned and drained prior to preparation for delivery.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging (see 6.2).

5.1.1 Level A.

5.1.1.1 Compressor unit. The compressor unit shall be preserved and packaged in accordance with level A of MIL-C-3600.

5.1.1.2 Technical manual. The manual shall be packaged in accordance with method IC-3. Preservative is not required.

5.1.2 Level B.

5.1.2.1 Compressor unit. The compressor unit shall be preserved and packaged in accordance with level B of MIL-C-3600.

5.1.2.2 Technical manual (see 5.1.1.2).

5.1.3 Level C.

5.1.3.1 Compressor unit. The compressor unit shall be preserved and packaged in accordance with level C of MIL-C-3600 except the engine shall be preserved in accordance with type II, level C of MIL-E-10062.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

5.1.3.2 Technical manual. The technical manual shall be enclosed in a polyethylene bag.

5.2 Packing.

5.2.1 Level A. The compressor unit assembly and technical manual, preserved and packaged as specified in 5.1.1 shall be packed within a cleated-plywood box conforming to style A of PPP-B-601. The packaged manual shall be firmly secured to the compressor unit. Plywood used in construction of boxes shall conform to type 1, CS 35, group A or PS-1 exterior type group B of NN-P-530. The boxes, or wood components thereof, shall be preservative treated by being completely immersed in wood preservative conforming to TT-W-572 for a minimum period of 3 minutes except the plywood may be preservative treated in accordance with PPP-B-601. Preservative treated boxes shall not be loaded or marked unless dry. The box shall be of minimum size to contain the item. Filler pads fabricated from fiberboard (V3c), conforming to PPP-F-320 shall be used as required to prevent movement of the item during handling and shipping.

5.2.2 Level B. The compressor unit assembly and technical manual, preserved and packaged as specified in 5.1.2, shall be packed in the same manner as specified in 5.2.1, except wood preservative treatment of boxes is not required.

5.2.3 Level C. The compressor unit and technical manual, packaged in accordance with 5.1.2, shall be packed in a fiberboard box conforming to domestic class, variety DW, grade 275 minimum, of PPP-B-636. The box shall be closed in accordance with method II of the appendix to PPP-B-636. The pack shall conform to the Uniform Freight Classification rules and regulations.

5.3 Marking. In conjunction with information furnished in the contract, marking shall be as specified herein.

5.3.1 Unit package marking. The preserved unit and the technical manual package shall be marked with the appropriate identification marking, in accordance with MIL-STD-129.

5.3.2 Shipping container (wood box) marking. The shipping container shall be marked in accordance with Drawing D68-13-1588.

5.4 Palletization. When specified in the contract or order (mandatory for level A shipment) compressors, packed as specified, shall be palletized in accordance with Drawing D68-13-1589.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. The compressor unit is intended to furnish air under pressure for portable flame throwers. It is further intended that the design of compressor provide for 1000 hours of operating before major repair or overhaul.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number and date of this specification.
(b) Level of preservation, packaging, and packing required.
(c) The requirements for preparation of operating and maintenance publications.
(d) When packaging data sheet is required.
(e) Paint color.
(f) Cover color.
(g) Engine will be Government furnished (GFE).
(h) Address marking information.
(i) Identification information.
(j) Any special marking applicable to order in effect.
(k) Preproduction.

(1) Time allowed for supplier's submission of samples of Government test and evaluation.
(2) Name and address of test facility and shipping instructions when testing is performed by the Government.
(3) Time required for the Government to notify the supplier whether or not to proceed with regular production.

6.3 Precautions. Because of the hazards attending the testing of equipment under high pressure, suppliers are advised to exercise all necessary precautions to protect personnel while testing.

Custodian:

Army - MU

Preparing activity:

Army - MU(EA)

Project No. 1040-A105

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

TO DETACH FORM - CUT ON THIS LINE

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

ORGANIZATION

CITY AND STATE | CONTRACT NUMBER

MATERIAL PROCURED UNDER A
☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?
   ☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)* | DATE

DD FORM 1 JAN 66 1426 REPLACES EDITION OF [illegible] WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding Officer
Edgewood Arsenal
ATTN: SMUEA-QAES
Edgewood Arsenal, Maryland 21010

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:04Z
Check the source to verify that this is the current version before use.