MIL-C-51172(MU)
12 December 1963
(See section 6)

MILITARY SPECIFICATION

COMPRESSOR, RECIPROCATING, 50 CFM, 3000 PSI

1. SCOPE

1.1 This specification covers one type of air compressor.

2. APPLICABLE DOCUMENTS

2.1 Government documents. The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-116	-	Preservation, Methods of.
MIL-T-704	-	Treatment and Painting of Materiel.
MIL-L-2104	-	Lubricating Oil, Internal-Combustion Engine, Heavy-Duty.
MIL-P-3542	-	Primer, Pressure-Sensitive Tape.
MIL-C-3600	-	Compressors, Air and Gas (Except Oxygen), Packaging of.
MIL-L-10295	-	Lubricating Oil, Internal-Combustion Engine, Sub-Zero.
MIL-W-12332	-	Welding, Resistance, Spot and Projection; For Fabricating Assemblies of Low Carbon Steel.
MIL-W-13779	-	Welding, Metal-Arc: Steels, Constructional, Readily Weldable, For Low-Stressed Joints.
MIL-C-17504	-	Coating Compound, Acrylic, Clear.
MIL-L-21260	-	Lubricating Oil, Internal-Combustion Engine, Preservative.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129 - Marking For Shipment and Storage.
MIL-STD-130 - Identification Marking of U. S. Military Property.

DRAWINGS

EDGEWOOD ARSENAL

D81-8-884 - Compressor, Reciprocating, 50 CFM, 3000 PSI.

PUBLICATIONS

DEPARTMENT OF THE ARMY

PP-CmlC-E1A - Provisioning Procedures for Edgewood Arsenal Equipment.
EP-3 - Technical Manual Requirements for Edgewood Arsenal Equipment.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

NATIONAL BUREAU OF STANDARDS

Handbook H28 - Screw Thread Standards For Federal Services.

(Copies may be obtained from the Superintendent of Documents, Government Printing Office, Washington 25, D. C.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

UNIFORM CLASSIFICATION COMMITTEE

Uniform Freight Classification Rules

(Application for copies of these freight classification rules should be addressed to the Uniform Classification Committee, 202 Union Station, Chicago 6, Illinois.)

THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Displacement Compressors, Vacuum Pumps and Blowers

(Copies may be obtained from the American Society of Mechanical Engineers, 345 East 47th Street, New York 17, N.Y.)

SOCIETY OF AUTOMOTIVE ENGINEERS

SAE Handbook

(Copies may be obtained from the Society of Automotive Engineers, 485 Lexington Avenue, New York 17, N.Y.)

3. REQUIREMENTS

3.1 Materials and components.

3.1.1 Materials. All materials used in the manufacture of the air compressor shall conform to the specifications forming a part of this specification. Materials not definitely specified shall be of an accepted commercial type and grade suitable for the purpose intended. Material shall be free from defects and imperfections that might affect the serviceability of the finished products.

3.1.2 Components. All components used in the manufacture of the air compressor shall conform to the specifications forming a part of this specification. Components not definitely specified shall be of an accepted commercial type and grade and of the manufacturer's latest design. All components shall be in accordance with sheet form military standards (MS Standards) when applicable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

3.2 Design. The air compressor shall be base-mounted, high pressure, air-cooled, and equipped with all accessories necessary for operation under the conditions specified in this specification. All compressors procured under this specification from one supplier shall be physically and mechanically identical. Design shall avoid conditions which may be hazardous or deleterious to personnel or equipment. The compressor shall be capable of developing and maintaining its rated output for no less than 200 hours without maintenance (see 3.2.1 and 6.1). The compressor shall be of the positive displacement type, having a minimum of 5 stages with a maximum of 6 cylinders, a maximum compression ratio of 4 to 1, and capable of operating continuously without servicing for a minimum period of 12 hours at extreme temperatures (see 3.2.2.2 and 3.2.2.3). Safety features shall be comparable with standard commercial practice for this type equipment. Use of special tools for maintenance and overhaul operations shall be kept to a minimum. All parts subject to wear or service failure shall be readily replaceable. Cylinder cooling areas shall be adequate to prevent excessive heating. The crankcase shall be provided with readily accessible means of filling, draining, and determining oil level, unless sealed anti-friction bearings are used. All covers for access openings shall be oil and dust tight.

3.2.1 Rating. The compressor shall be capable of delivering a minimum of 50 cubic feet per minute (cfm) of free air at a minimum pressure of 3,000 pounds per square inch gage (psig) when operating at its rated speed, not exceeding 1800 rpm, while not absorbing more than 50 horsepower (hp) when tested as specified in 4.6.1.1. The compressor shall be capable of pressurizing a 5 cubic foot minimum pressure vessel from 0 to 3000 psig in a maximum time of 20 minutes when operated at its rated speed and horsepower.

3.2.2 Initial production. The first two compressors manufactured in accordance with this specification that have been submitted for inspection shall be the initial production sample.

3.2.2.1 Storage. The compressor shall be capable of withstanding storage in any ambient temperature ranging from minus 65°F to 75°F to plus 155°F to 165°F when tested as specified in 4.6.1.2 and 4.6.1.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

3.2.2.2 Low temperature operation. The compressor shall be capable of starting and maintaining continuous operation at minus 25°F to 35°F and comply with 3.2.1 when tested as specified in 4.6.1.2.

3.2.2.3 High temperature operation. The compressor shall be capable of starting and maintaining continuous operation at plus 115°F to 125°F and comply with 3.2.1 when tested as specified in 4.6.1.3.

3.2.2.4 Rain. The compressor shall be capable of starting and maintaining continuous operation in a simulated rainfall of 2 ± 1/2 inches per hour with a wind blowing horizontally at a rate of 20 ± 5 miles per hour (mph) in an ambient temperature of 75° ± 5°F and comply with 3.2.1 when tested as specified in 4.6.1.4.

3.2.2.5 Inclined position. The compressor shall be capable of starting and maintaining operation when inclined in any position and comply with 3.2.1 when tested as specified in 4.6.1.5.

3.2.3 Limiting weight. The total dry weight of the air compressor shall not exceed 1100 pounds.

3.2.4 Mounting and limiting dimensions. The compressor shall be designed for base mounting and within the limiting dimensions shown in Drawing D81-8-884.

3.2.5 Rough handling. The compressor shall be capable of withstanding damage and comply with 3.2.1 when tested as specified in 4.6.1.6.

3.2.6 Lifting provisions. The compressor shall be provided with a lifting eye not less than 3 inches inside diameter and a maximum outside diameter of 6 1/2 inches. The lifting eye assembly shall be of sufficient strength to carry not less than 2 1/2 times the weight of the compressor. The lifting eye assembly shall hoist the compressor in its normal position.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

3.3 Intercooler. An intercooler shall be provided, having sufficient heat transfer capacity to reduce the temperature of the air leaving each stage to 175°F maximum when the compressor is operating at an ambient temperature of 125° ± 5°F. A safety valve shall be provided at or before the inlet of each intercooler. A 1/8 inch NPT female threaded pressure gage port shall be provided at or before the inlet of each intercooler. If condensate traps are integral to the intercooler, 1/4 inch NPT female threaded condensate drain ports shall be provided at lowest point. If condensate traps are not part of intercooler, an air outlet must be located at the lowest point of the intercooler.

3.4 Aftercooler. An aftercooler shall be provided that will reduce the temperature of compressed air at 3,000 psig to a maximum temperature of 150°F when operating in an ambient temperature of 115° + 10°F. Under normal operating conditions 60° to 80°F at 3,000 psig, the compressor shall be capable of delivering air at a maximum temperature of 140°F. A safety valve shall be provided at or before the inlet of the aftercooler. A 1/8 inch NPT female threaded pressure gage port shall be provided at or before the inlet of the aftercooler. If a condensate trap is integral to the aftercooler, a 1/4 inch NPT female threaded condensate drain port shall be provided at the lowest point. If the condensate trap is not part of the aftercooler, an air outlet must be provided at the lowest point of the aftercooler.

3.5 Traps. When traps are not part of intercooler or aftercooler, a 1/4 inch NPT female threaded drain port must be provided at the lowest point in each trap.

3.6 Automatic temperature control. A means of automatically controlling the outlet temperature of the air shall be provided. In subfreezing weather the outlet air temperature shall not be below plus 40°F when tested as specified in 4.6.1.2.

3.7 Moisture separator. A moisture separator suitable to prevent any visible carry-over of moisture and oil in the compressed air shall be provided. A blow-down drain cock port shall be provided to allow for connection to an instrument panel control. The drain cock port shall be 1/4 inch NPT female threaded and of such design that the unit need not be shut down to drain the separator when connected to an instrument panel control. The port shall be located at the side of the unit. The moisture separator can be combined in the aftercooler traps.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

3.8 Automatic unloading system. The compressor shall be equipped with an automatic unloading system set to unload at a maximum pressure of 3,200 psig when tested as specified in 4.6.1.1.

3.9 Air filter. The air being inducted into the first stage of the air compressor shall be filtered. The filter shall be accessible and remove no less than 95 percent by weight of all fine grade dust entering the filter without reduction in air intake below the minimum requirements when tested as specified in 4.6.2.2. The air filter may be either the oil-bath or the dry type and shall be of such capacity that servicing at 4 hour intervals shall be sufficient under fine grade dust concentration of 0.025 gram per cubic foot of airflow when tested as specified in 4.6.2.2.

3.10 Pressure relief valve. An automatic pressure relief valve shall be installed in the discharge (high pressure) system of the compressor, set to relieve fully at a maximum pressure of 3500 psig. The relief valve shall start to open at a minimum pressure of 3300 psig. It shall be completely closed at any pressure below 3300 psig when tested as specified in 4.6.2.3. The valve shall have sufficient capacity to permit the compressor to run continuously with outlets closed and other safety devices inoperative without building the pressure in excess of 3500 psig. A rupture disc safety valve that will relieve air pressure at 3800 ± 100 psig shall also be provided in the discharge (high pressure) system of the compressor.

3.11 Drive. The drive shall be as specified in Drawing D81-8-884.

3.12 Fasteners. The type and size of the bolts, screws, nuts, washers, hardware, and similar standard parts shall be kept to a minimum. Lock washers shall be secured to bolts or screws when practical. Drain plugs shall be removable with one standard type tool. All fastenings shall be tight and capable of withstanding vibration and rough handling without loosening or shearing.

3.13 Technical publications.

3.13.1 Provisioning list. The supplier shall prepare a provisioning list in accordance with PP-CmlC-E1A.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:05Z
Check the source to verify that this is the currentversion before use.

3.13.2 Manuals. The supplier shall prepare technical manuals (including parts list) in accordance with EP-3.

3.14 Treatment and painting. All parts of the compressor that are normally painted in commercial practice shall be treated and painted with a prime coat only in accordance with type A of Specification MIL-T-704, except that parts subject to high temperature shall be treated and painted in accordance with the standard practice of the manufacturer.

3.15 Lubrication. All moving parts of the compressor normally requiring lubrication shall have readily accessible means provided for such lubrication and shall be designed for use with standard military lubricants. Wherever practical, permanently lubricated components shall be employed to minimize servicing. The lubricant sumps shall be provided with easily read oil level indicators and accessible drains. All lubricating fittings shall be of a type suitable for use with standard lubricating equipment. Sub-zero lubricating oil shall conform to Specification MIL-L-10295. All other lubricating oil shall conform to Specification MIL-L-2104. Where the use of high pressure lubricating equipment of 1000 psig or above will damage grease seals or other parts, a suitable warning shall be affixed to the compressor in a conspicuous location. Grease and oil seals shall be provided with maximum accessibility for replacement.

3.16 Identification marking. Equipment assemblies and parts shall be marked for identification in accordance with Standard MIL-STD-130. Each compressor shall be serially numbered. Additional identification plates required by using services shall be as specified (see 6.2).

3.17 Instruction plates. The compressor shall be equipped with instruction plates, suitably located, describing procedures to be followed in operating and servicing. The instruction plates shall be of the same material as the identification plates.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

3.18 Welding.

3.18.1 Spot resistance. All spot resistance welding shall conform to Specification MIL-W-12332.

3.18.2 Metal arc. All metal-arc welding shall conform to Specification MIL-W-13779.

3.19 Screw threads. All screw threads shall conform to National Bureau of Standards Handbook H-28.

3.20 Test report. One reproducible master and 20 copies of a test report in connection with operation and testing of the initial production compressor shall be furnished by the supplier containing, but not limited to, the following:

(a) Description and photographs of each test set-up.
(b) Failures of parts, operating time on parts, and photographs of these failing parts.
(c) Time required to make repairs.
(d) Logs maintained during testing.

3.21 Workmanship. The compressor shall be free from damage such as dents, cracks or deformation which could affect its intended use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

4.2 Special provisions.

4.2.1 Alternative inspection. The supplier may utilize any alternative inspection procedure which will provide equal or better assurance of quality by submitting a written proposal with justification and obtaining written approval from the Government prior to instituting the procedure. In case of dispute, the procedures of this specification will govern.

4.2.2 Objective evidence. The supplier shall provide objective evidence acceptable to the contracting officer that the requirements of 3.1, 3.2, 3.2.3, 3.2.4, 3.2.6, 3.3, 3.4, 3.5, 3.7, 3.11, 3.12, 3.13, 3.14, 3.16, 3.17, 3.18, 3.19, 3.20 and section 5 for which specific inspection has not been provided in this specification have been satisfied.

4.3 Initial production inspection.

4.3.1 Examination and tests. The initial production sample shall be examined and tested for all the requirements of this specification (except 4.6.2).

4.3.2 Acceptance/rejection criteria. The initial production sample shall comply with all the applicable requirements of this specification to be acceptable.

4.4 Regular production.

4.4.1 Lotting. A lot shall consist of the like components produced by one manufacturer from the same materials under essentially the same manufacturing conditions.

4.4.2 Sampling components for examination and tests. Sampling shall be conducted in accordance with Standard MIL-STD-105.

4.5 Inspection provisions.

4.5.1 Component examination and tests. Sample components and the level A preparation for delivery shall be examined for all the requirements of the drawing, this specification and the classification of defects as applicable. Testing shall be in accordance with 4.6.2.2 and 4.6.2.3 and Standard MIL-STD-105 using an AQL of 0.25 percent defective.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

4.5.2 Compressor. Each compressor shall be examined and tested in accordance with 4.6.2.1.

4.5.3 Classification of defects.

4.5.3.1 Preparation for delivery (section 5).

Categories	Defects
Critical:	None defined
Major:	AQL 2.5 percent defective
101	Openings not processed as specified
102	Nameplates not processed as specified
103	Item improperly secured to prevent movement
104	Marking illegible or incorrect

4.6 Tests.

4.6.1 Initial production.

4.6.1.1 Rating. The compressor shall be serviced for operation above 32°F and operated continuously if practical for a minimum period of 200 hours. If continuous operation is not practical, it shall be operated a minimum period of 6 hours per working day until it has completed a 200 hour run. A maximum of 1 hour down time following 12 hours of operating time will be allowed for servicing. During the 200 hour run, lubricating oil shall be changed at intervals recommended by the manufacturer and the moisture separator drained at his recommended intervals. Pressurization of the 5 cubic foot pressure vessel shall be accomplished every 3 hours to determine compliance with 3.2.1. During the last 100 hours of this test the compressor shall be loaded and unloaded six times every hour recording only the loading and unloading pressures. A complete log shall be kept during the run to determine the cfm in accordance with ASME Code for Displacement Compressors, Vacuum Pumps and Blowers.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

During the first 100 hours of operation, readings will be taken every hour of the following:

(a) Revolutions per minute.
(b) Final discharge pressure.
(c) Cubic feet per minute.
(d) Intercooler in and out temperatures.
(e) Aftercooler in and out temperatures.
(f) Barometric pressure.
(g) Ambient temperature, with a mercury thermometer or thermocouple.
(h) Relative humidity.
(i) Intercooler pressures.
(J) Lubricating oil temperature.
(k) Oil pressure.

The readings obtained for (b) and (k) above should be read from pressure gages having a 1 percent accurate reading. The reading obtained for (f) above should be read from a mercury well type barometer. The readings obtained for (d), (e), and (J) above should be read from temperature gages having insulated thermocouples. The reading obtained for (h) above should be read from a mercury wet and dry thermometer. Certification shall be furnished that all test instruments were calibrated 30 days prior to test.

4.6.1.2 Low temperature. The compressor shall be serviced for low temperature operation. The compressor, together with a 5-cubic foot pressure vessel, shall be cold soaked at a temperature of minus 65°F to 75°F for a minimum period of 16 hours. The temperature shall be raised to minus 25°F and the compressor soaked for a minimum period of 16 hours. At the end of this soak the compressor shall be operated continuously in an ambient temperature of minus 25°F to 35°F for a minimum period of 8 hours. The 5 cubic foot pressure vessel shall be pressurized, every 2 hours, from 0 to 3000 psig during this test to determine compliance with 3.2.1. The compressor may be preheated for a maximum period of 1/2 hour before being operated for this test. A complete log similar to that specified in 4.6.1.1 shall be kept during the run. In addition the log report shall also provide for outlet temperature recording for compliance with 3.6.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

4.6.1.3 High temperature. The compressor shall be serviced for high temperature operation. The compressor, together with a 5-cubic foot minimum capacity pressure vessel, shall be hot soaked at a temperature of 155°F ± 10°F for a minimum period of 16 hours. The temperature shall be dropped to 115°F ± 10°F and the compressor soaked for a minimum period of 16 hours. At the end of this soak the compressor shall operate continuously in an ambient temperature of 115° ± 10°F for a minimum period of 8 hours. The 5 cubic foot pressure vessel shall be pressurized, every 2 hours, from 0 to 3000 psig during this test to determine compliance with 3.3.1. A complete log similar to that specified in 4.6.1.1 shall be kept during the run.

4.6.1.4 Rain. The compressor, serviced for operation above 32°F, shall be rain-tested as follows to determine compliance with 3.2.1:

(a) The compressor shall be placed in a test chamber maintained at a temperature of 75°F ± 5°F. A simulated rainfall of 2 ± 1/2 inches per hour shall be impacted on all exposed surfaces. The compressor shall be operated for a minimum period of 1 hour in this position.

(b) With simulated rainfall continuing at the rate of 2 ± 1/2 inches per hour, a wind blowing horizontally at the specified rate shall be introduced against one side of the compressor. This condition shall be maintained for a minimum period of 1/2 hour with the compressor operating.

(c) The compressor shall be rotated 90 degrees until each side of the compressor has been exposed to the condition specified in preceding step b. All sides of the compressor shall be exposed consecutively, with the compressor operating, for a minimum period of 1/2 hour each.

4.6.1.5 Inclined position. The compressor shall be operated one time for the length of time required to pressurize the pressure vessel in each of the following positions to determine compliance with 3.2.1:

(a) Compressor drive end higher than the undriven end with the long axis of the compressor at a minimum of 15 degrees to the horizontal.

(b) Compressor undriven end higher than the drive end with the long axis of the compressor at a minimum of 15 degrees to the horizontal.

(c) Compressor inclined at a minimum of 15 degrees to the right of the long axis.

(d) Compressor inclined at a minimum of 15 degrees to the left of the long axis.

A complete log similar to that specified in 4.6.1.1 shall be kept during the run.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

4.6.1.6 Rough handling. The compressor shall be placed on a truck in such a manner as to restrict sidewise movement, but permit free vertical movement. The compressor shall be transported over unimproved roads and hilly terrain at speeds up to 30 miles per hour for a minimum distance of 100 miles. The compressor shall be visually inspected and operated at full load for a minimum period of 30 minutes to detect any mechanical failure and to determine compliance with 3.2.1. A complete log similar to that specified in 4.6.1.1 shall be kept during the run.

4.6.2 Regular production.

4.6.2.1 Compressor. Each compressor shall be serviced for operation above 32°F following the supplier's recommended break-in period. The compressor shall be operated for a minimum period of 8 hours at the rated speed and horsepower specified in 3.2.1. The automatic unloading system shall be induced to function to determine compliance with 3.8. The pressure relief valve shall be tested for its ability to provide full flow of pressure from the compressor at a maximum system pressure of 3500 psig to determine compliance with 3.11. The moisture separator shall be operated to determine compliance with 3.7. Each compressor shall pressurize a five cubic foot pressure vessel every 2 hours to determine compliance with 3.2.1. A complete log similar to that specified in 4.6.1.1 shall be kept during the break-in and 8 hour test. Upon completion of test, each compressor shall be cleaned and drained prior to preparation for delivery. If the design of the automatic unloading system is not provided with a means for by-passing the automatic unloading system, the supplier shall provide, for test purposes, a method for by-passing the automatic unloading system to determine compliance with 3.11.

4.6.2.2 Air filter. The air filter shall be tested for efficiency and dust capacity in accordance with the SAE Air Cleaner Test Code.

4.6.2.3 Pressure relief valve. Each pressure relief valve shall be tested, prior to installation on a compressor, as follows: Each valve shall be connected to a source of regulated air pressure controllable from 0 to 3600 psig. The air pressure shall be slowly applied to the valve at the rate of 500 psig in 30 seconds until 3000 psig is reached, then increase the pressure in increments of 25 psig until the valve unseats to determine compliance with 3.10.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY (For packaging of stocked repair parts, see 6.4)

5.1 Cleaning and drying. After test runs have been completed and before the application of a preservative, all surfaces to which a preservative is to be applied shall be cleaned and dried in accordance with Specification MIL-P-116, using cleaning process C-1 and the most applicable of drying procedures listed therein.

5.2 Preservation and packaging. Levels shall be as specified (see 6.2).

5.2.1 Level A. Except as otherwise specified herein, the compressor including components, maintenance tools, and repair parts accompanying equipment shall be preserved and packaged in accordance with the applicable requirements of Specification MIL-P-3600.

5.2.1.1 Repainting. Damaged portions of painted areas shall be treated and repainted in accordance with the applicable requirements of 3.15.

5.2.1.2 Pressure-sensitive tape application. Prior to the application of pressure-sensitive tape, metal surfaces to which the tape will adhere shall be coated with pressure-sensitive tape primer conforming to Specification MIL-P-3542.

5.2.1.3 Tag waterproofing. All tags shall be waterproofed by coating with a clear acrylic coating compound conforming to Specification MIL-C-17504.

5.2.1.4 Name plates. Name plates shall be coated with the same material as specified in 5.2.1.3.

5.2.1.5 Compressor cooling fins. If not otherwise protected, the cooling fins of the compressor shall be coated with type P-10 preservative oil conforming to grade 2 of Specification MIL-L-21260.

5.2.1.6 Technical publications. Technical publications shall be packaged in accordance with method IC-1 or IC-3 of Specification MIL-P-116.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

5.2.2 Level C. The compressor, including components, repair parts, maintenance tools and technical publications shall be cleaned, dried as specified in 5.1; preserved as applicable and packaged in accordance with the manufacturer's commercial practice suitable for shipment from the supply source to the first receiving activity for immediate use.

5.3 Packing. Levels shall be as specified (see 6.2).

5.3.1 Level A. The compressor, including components, processed as specified in 5.2 shall be packed together in a wood crate in accordance with the applicable level A requirements of Specification MIL-P-3600.

5.3.2 Level C. The compressor, including components, repair parts, maintenance tools, and technical publications, processed as specified in 5.2, shall be packed together in a manner to insure carrier acceptance and safe delivery at first destination. Containers shall be in accordance with Uniform Freight Classification Rules or regulations of other carriers applicable to the mode of transportation.

5.4 Marking. In addition to any special marking required by the contract or order, unit packages, intermediate packages, and shipping containers shall be marked in accordance with Standard MIL-STD-129.

6. NOTES

6.1 Intended use. This compressor will be installed in a flame thrower service unit or on a skid-mounted assembly to be driven by an engine. It is used to furnish compressed air to charge flame thrower pressure vessels. The compressed air is used as a propellant of the thickened flame thrower fuel.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Level or levels of preservation, packaging, and packing.
(c) Additional identification plates required.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.

6.3 Supersession data. This specification supersedes Edgewood Arsenal Purchase Description 196-131-787, dated 12 September 1962.

6.4 Repair parts packaging. When repair parts packaging is required for items authorized for stocking as repair parts, the repair parts packaging data sheets covering the applicable components of the compressor shall be used. (Copies of repair parts packaging data sheets may be obtained from the Director of Engineering and Industrial Services, ATTN: Chief, Design Branch, U. S. Army Edgewood Arsenal, Edgewood Arsenal, Maryland - 21010.)

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1040-A022Y

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:05Z
Check the source to verify that this is the current version before use.