INCH-POUND

MIL-F-51531A(EA)
10 October 1991
SUPERSEDING
MIL-F-51531(EA)
13 December 1989

MILITARY SPECIFICATION

FLUID CONTAINER, FILLED (FOR M13 DECONTAMINATING APPARATUS)

This specification is approved for use by the U.S. Army Chemical Research, Development and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers one type of filled fluid container which provides 14 liters of decontaminating agent for dispensing.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, U.S. Army Chemical Research, Development and Engineering Center, ATTN: SMCCR-PET-S, Aberdeen Proving Ground, MD 21010-5423 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 4230

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:06Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

BB-N-411 - Nitrogen, Technical

MILITARY

MIL-D-50030 - Decontaminating Agent, DS2

STANDARDS

MILITARY

MIL-STD-1168 - Ammunition Lot Numbering

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

U.S. ARMY CHEMICAL RESEARCH, DEVELOPMENT AND ENGINEERING CENTER

DRAWINGS

5-51-575 - Fluid Container, Filled

SPECIAL PACKAGING INSTRUCTIONS (SPI)

P5-51-575 - Fluid Container, Filled

QUALITY ASSURANCE PROVISIONS

702-1-2 - Chemical Agent Resistant Coating (CARC) System for Decontamination Items

(Copies are available from Commander, U.S. Army Information Systems Command, ATTN: ASQNC-ARI-IOT, Rock Island, IL 61299-7210.)

2.2 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:06Z
Check the source to verify that this is the current version before use.

document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Materials and components.

3.1.1 Materials. All materials cited on Drawing 5-51-575 and on the subsidiary drawings shall conform to the specifications and drawings listed thereon.

3.1.2 Components. All components of the filled fluid container shall conform to the specifications and drawings listed on Drawing 5-51-575 and subsidiary drawings.

3.2 Assembly and filling.

3.2.1 Assembly. The filled fluid container shall be assembled in accordance with Drawing 5-51-575.

3.2.2 Filling. Immediately prior to filling, the container shall be purged through the hose coupling opening for at least 1 minute at a flow rate of 50 liters per minute with dry nitrogen conforming to type I, grade A or B, class 2 of BB-N-411 and then immediately filled through the hose coupling opening with DS2 decontaminating agent conforming to MIL-D-50030 and then immediately closed in accordance with 3.2.1. The flow rate shall be measured at the inlet after the flow has been established through the container. The vent shall be open throughout the filling process. The filling and closing operation shall be performed with a flow of the same dry nitrogen maintained over the hose coupling and vent plug opening (see 6.4, 6.5 and 6.6).

3.2.3 Container fill. The fluid container shall contain not less than 14.0 liters, nor greater than 14.5 liters (13.65 to 14.14 kilograms) of DS2 decontaminating agent when tested in accordance with 4.4.6.1.

3.2.4 Chemical and physical characteristics of DS2. The contents of the filled fluid container shall meet the *Chemical and physical characteristics* requirements specified in MIL-D-50030 when tested in accordance with 4.4.6.2.

3.3 Leakage. The filled fluid container shall not leak when tested in accordance with 4.4.6.3.

3.4 Fluid container assembly (Drawing 5-51-538).

3.4.1 Lifting handle strength. The lifting handle shall support a load of at least 150 pounds for a minimum of 5 seconds without weld tears, or distortion of handle parts when tested in accordance with 4.4.6.4.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

The grade shall be absolute and ... secure the boxes together.

3.4.2 Burst strength. The fluid container assembly shall not burst or rupture when subjected to a minimum internal hydrostatic pressure of 40 pounds per square inch gage (psig) for at least 5 minutes when tested in accordance with 4.4.6.4.2.

3.4.3 Leakage. The fluid container assembly shall not leak when subjected to a minimum internal pressure of 15 psig, for a minimum of 15 seconds when tested in accordance with 4.4.6.4.3.

3.4.4 Drop strength. The fluid container shall not leak when dropped from a height of 4 feet onto solid concrete so as to strike on the weakest structural seam. The container shall be filled to 98 percent capacity with water, when tested in accordance with 4.4.6.4.4.

3.5 Plug assembly leakage (Drawing 5-51-578). The plug assembly for the fluid container assembly shall not leak when subjected to 10 psig, for a minimum of 15 seconds, when tested in accordance with 4.4.6.5.

3.6 First article. Unless otherwise specified in the contract, a sample of filled fluid containers and fluid container assemblies shall be subjected to the first article inspection specified in 4.3 prior to the start of regular production.

3.7 Workmanship. The filled fluid container and its components shall be free from foreign matter (such as water, grease, oil or viscous material), rust, damage, cracks or sharp edges.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

4.1.2 Contractor assurance of compliance. The contractor's quality program or detailed inspection system shall provide assurance of compliance of all characteristics with the applicable drawing, special packaging instruction, and specification requirements using, as a minimum, the conformance criteria specified herein.

4.1.3 Alternative inspection provisions. Alternative inspection procedures, methods, or equipment, such as statistical process control, tool control, and other types of sampling procedures may be used by the contractor when they provide, as a minimum, the level of quality assurance required by the inspection provisions specified herein. Prior to applying such alternative procedures, methods, or equipment, the contractor shall describe them in a written proposal submitted to the Government for evaluation and approval. (See 6.3.) When required, the contractor shall demonstrate that the effectiveness of each proposed alternative is equal to or better than the quality assurance provisions specified herein. In cases of dispute as to whether the contractor's proposed alternative provides equal quality assurance, the provisions of this specification shall apply. All approved alternative inspection provisions shall be specifically incorporated into the contractor's quality program or detailed inspection system, as applicable.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) First article inspection (see 4.3)
(b) Quality conformance inspection (see 4.4)

4.3 First article inspection.

4.3.1 Inspections to be performed. As determined by the Government, the first article sample items shall be examined and tested in accordance with this specification using either the first article procedures in 4.3.3 or other first article procedures which will be provided by the Government. As determined by the Government, the sample first article items may be subjected to any or all of the examinations and tests specified in this specification and be inspected for compliance with any or all of the requirements of the applicable drawings and special packaging instructions.

4.3.2 Sample. The first article sample shall consist of 25 filled fluid containers (Drawing 5-51-575) and 10 fluid container assemblies (Drawing 5-51-538) manufactured and packaged (when military packaging is required) using the same methods, materials, equipment, and processes as will be used during regular production. The first article sample shall be submitted for inspection and approval in accordance with the terms of the contract.

4.3.3 Inspection procedure.

4.3.3.1 For examination. The first article sample of filled fluid containers and fluid container assemblies shall be examined for conformance to all drawing, and, when applica-

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

ble, SPI requirements. These examinations shall be conducted prior to any tests specified in 4.3.3.2 and 4.3.3.3.

4.3.3.2 For nondestructive test.

4.3.3.2.1 Filled fluid container (Drawing 5-51-575). The first article sample of filled fluid containers shall be tested for container fill (4.4.6.1) and leakage (4.4.6.3).

4.3.3.2.2 Fluid container assembly (Drawing 5-51-538). The first article sample of fluid container assemblies shall be tested for lifting handle strength (4.4.6.4.1) and leakage (4.4.6.4.3). Plug assemblies shall be tested for leakage (4.4.6.5) prior to the assembly of first article fluid container assemblies.

4.3.3.3 For destructive test.

4.3.3.3.1 Filled fluid container (Drawing 5-51-575). Following examination and nondestructive tests, five filled fluid containers selected at random from the first article sample shall be tested for chemical and physical characteristics (4.4.6.2).

4.3.3.3.2 Fluid container assembly (Drawing 5-51-538). Following examination and nondestructive tests, five fluid container assemblies in the first article sample shall be tested for burst strength (4.4.6.4.2) and the remaining five fluid container assemblies shall be tested for drop strength (4.4.6.4.4).

4.3.3.4 Protective finish for fluid container assembly. Inspection of the fluid container assembly for conformance to CARC requirements shall be in accordance with QAP 702-1-2.

4.3.4 Acceptance criteria. If any first article sample item fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate inspection upon any failure to comply with any of the requirements. The contractor shall obtain written approval from the contracting activity prior to proceeding with regular production.

4.4 Quality conformance inspection.

4.4.1 Lotting. A lot shall consist of those like items produced at the same place, utilizing the same batches of materials, lots of components, process runs, fabrication techniques, assembly methods, tools, equipment and facilities, but shall not exceed one month's production. Each lot shall be controlled and identified in accordance with MIL-STD-1168. No more than one manufacturing lot of DS2 shall be used in any one lot of filled fluid containers.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

4.4.2 Sampling. Sampling shall be conducted in accordance with the classification of characteristics in 4.4.5 and, when specified, table I. Samples shall be selected at random.

4.4.3 Inspection procedure. Every item in the lot shall be inspected for critical characteristics. The lot represented shall be rejected when nonconformance to a critical characteristic is found. Sample items and, when applicable, the packaging thereof shall be examined and tested in accordance with the classification of characteristics in 4.4.5. Failure of any sample item to conform to any characteristic in the classification of characteristics based on the sampling and acceptance criteria specified therein shall be cause for rejection of the lot represented.

4.4.4 Inspection characteristics. Critical characteristics are characteristics whose nonconformance to specified requirements is likely to result in hazardous or unsafe conditions for individuals using, maintaining, or depending upon the product or whose nonconformance to specified requirements is likely to prevent performance of the tactical function of a major end item. Major characteristics are characteristics whose nonconformance to specified requirements is likely to result in failure or to reduce materially the usability of the item for its intended purpose. Minor characteristics are characteristics whose nonconformance to specified requirements is not likely to reduce materially the operation or usability of the item for its intended purpose.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

TABLE I. Sampling

Lot size	Inspection levels and sample sizes										
	I	II	III	IV	V	VI	VII	VIII	IX	X	XI
2 to 8	*	*	*	*	*	*	*	*	5	3	2
9 to 15	*	*	*	*	*	*	13	8	5	3	2
16 to 25	*	*	*	*	*	20	13	8	5	3	3
26 to 50	*	*	*	*	32	20	13	8	5	5	5
51 to 90	*	*	*	50	32	20	13	8	7	6	5
91 to 150	*	*	125	50	32	20	13	12	11	7	6
151 to 280	*	*	125	50	32	20	20	19	13	10	7
281 to 500	*	315	125	50	48	47	29	21	16	11	9
501 to 1200	*	315	125	75	73	47	34	27	19	15	11
1201 to 3200	1250	315	125	116	73	53	42	35	23	18	13
3201 to 10000	1250	315	192	116	86	68	50	38	29	22	15
10001 to 35000	1250	315	294	135	108	77	60	46	35	29	15
35001 to 150000	1250	490	294	170	123	96	74	56	40	29	15
150001 to 500000	1250	715	345	200	156	119	90	64	40	29	15
500001 and over	1250	715	435	244	189	143	102	64	40	29	15

*Indicates one hundred percent inspection. If sample size exceeds lot size, perform one hundred percent inspection.
Accept the lot represented on zero nonconforming characteristics and reject the lot represented on one or more nonconforming characteristics for all inspection levels.

4.4.5 Classification of characteristics. Quality conformance examinations and tests shall be as specified in the following classification of characteristics paragraphs. When specified herein, accept on 0 and reject on 1 attributes sampling inspection shall be performed on the designated characteristics using the stated levels in table I for selection of sample sizes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

CLASSIFICATION OF CHARACTERISTICS

PARAGRAPH	TITLE	SHEET 1 OF 1	DRAWING NUMBER 5-51-575
4.4.5(a)	Fluid container, filled		NEXT HIGHER ASSY

CATEGORY	CHARACTERISTIC	SAMPLING AND ACCEPTANCE CRITERIA	REQUIREMENT PARAGRAPH	INSPECTION METHOD
Critical				
1	Leakage	100 percent	3.3	4.4.6.3
Major				
101	Container fill	100 percent	3.2.3	4.4.6.1
102	Chemical and physical characteristics of DS2	Table I, Level IX	3.2.4	4.4.6.2*
103	Specified components correctly assembled	Table I, Level VII	3.1.2	VI
104	Closures torque correct	Table I, Level VII	3.1.2	CE
105	Nitrogen purge correct	Table I, Level VII	3.2.2	VI
106	Heat shrinkable tubing correctly applied	Table I, Level VII	3.1.2	VI
107	Protective finish evident	Table I, Level VII	3.1.2	VI
Minor				
201	Labels evident, correct and correctly assembled	Table I, Level IX	3.1.2	VI
202	Workmanship	Table I, Level IX	3.7	VI

NOTES:
CE - Commercial inspection equipment
VI - Visual inspection
* Destructive test

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

CLASSIFICATION OF CHARACTERISTICS

PARAGRAPH	TITLE	SHEET 1 OF 1	DRAWING NUMBER
4.4.5(b)	Fluid container assembly		5-51-538
			NEXT HIGHER ASSY 5-51-575

CATEGORY	CHARACTERISTIC	SAMPLING AND ACCEPTANCE CRITERIA	REQUIREMENT PARAGRAPH	INSPECTION METHOD
Critical	None defined			
Major				
101	Lifting handle strength	5; Acc 0, Rej 1	3.4.1	4.4.6.4.1
102	Burst strength	5; Acc 0, Rej 1	3.4.2	4.4.6.4.2*
103	Leakage	100 percent**	3.4.3	4.4.6.4.3
104	Drop strength	Table I, Level X	3.4.4	4.4.6.4.4*
105	Weldments correct	Table I, Level VII	3.1.2	VI and CE
106	Height dimension	Table I, Level VII	3.1.2	CE
107	Length, width and radius dimension correct	Table I, Level VII	3.1.2	CE
108	Protective finish evident	Table I, Level VII	3.1.2	VI
Minor				
201	Specified components correctly assembled	Table I, Level IX	3.1.2	VI
202	Labels evident, correct and correctly located	Table I, Level IX	3.1.2	VI
203	Workmanship	Table I, Level VII	3.7	VI

NOTES:

CE - Commercial inspection equipment
VI - Visual inspection
* Destructive test
**Any container that leaks shall be rejected.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

CLASSIFICATION OF CHARACTERISTICS

PARAGRAPH	TITLE	SHEET 1 OF 1	DRAWING NUMBER
4.4.5(c)	Top reservoir assy		5-51-523
			NEXT HIGHER ASSY 5-51-538

CATEGORY	CHARACTERISTIC	SAMPLING AND ACCEPTANCE CRITERIA	REQUIREMENT PARAGRAPH	INSPECTION METHOD
Critical	None defined			
Major				
101	Lock clip location correct	Table I, Level VII	3.1.2	CE
102	Lifting handle location correct	Table I, Level VII	3.1.2	CE
103	Weld and braze correct	Table I, Level VII	3.1.2	VI
104	Lifting handle strength*	5; Acc 0, Rej 1	3.4.1	4.4.6.4.1
Minor				
201	Workmanship	Table I, Level IX	3.7	VI

NOTES:

CE - Commercial inspection equipment

VI - Visual inspection

* Alternate test; test shall be imposed either as above or in accordance with 4.4.5(b), Category Major 101

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

CLASSIFICATION OF CHARACTERISTICS

PARAGRAPH	TITLE	SHEET 1 OF 1	DRAWING NUMBER
4.4.5(d)	Plug assembly		5-51-578
			NEXT HIGHER ASSY 5-51-538

CATEGORY	CHARACTERISTIC	SAMPLING AND ACCEPTANCE CRITERIA	REQUIREMENT PARAGRAPH	INSPECTION METHOD
Critical	None defined			
Major				
101	Leakage	5; Acc 0, Rej 1	3.5	4.4.6.5
102	Specified components undamaged and correctly assembled	Table I, Level VII	3.1.2	VI

NOTES:
CE - Commercial inspection equipment
VI - Visual inspection

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:06Z
Check the source to verify that this is the current version before use.

CLASSIFICATION OF CHARACTERISTICS

PARAGRAPH	TITLE	SHEET 1 OF 1	DRAWING NUMBER
4.4.5(e)	Adapter assy		5-51-565
			NEXT HIGHER ASSY 5-51-523

CATEGORY	CHARACTERISTIC	SAMPLING AND ACCEPTANCE CRITERIA	REQUIREMENT PARAGRAPH	INSPECTION METHOD
Critical	None defined			
Major				
101	Specified components correctly assembled	Table I, Level VII	3.1.2	VI
102	Length	Table I, Level VII	3.1.2	CE
103	Welding correct	Table I, Level VII	3.1.2	CE
Minor				
201	Workmanship	Table I, Level IX	3.7	VI

NOTES:
CE - Commercial inspection equipment
VI - Visual inspection

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

CLASSIFICATION OF CHARACTERISTICS

PARAGRAPH	TITLE	SHEET 1 OF 1	DRAWING NUMBER
4.4.5(f)	Adapter assy		5-51-566
			NEXT HIGHER ASSY 5-51-523

CATEGORY	CHARACTERISTIC	SAMPLING AND ACCEPTANCE CRITERIA	REQUIREMENT PARAGRAPH	INSPECTION METHOD
Critical	None defined			
Major				
101	Specified components correctly assembled	Table I, Level VII	3.1.2	VI
102	Brazing correct	Table I, Level VII	3.1.2	VI
Minor				
201	Workmanship	Table I, Level IX	3.7	VI
202	Crimped end opening correct	Table I, Level IX	3.1.2	VI

NOTES:
CE - Commercial inspection equipment
VI - Visual inspection

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

CLASSIFICATION OF CHARACTERISTICS

PARAGRAPH	TITLE	SHEET 1 OF 1	DRAWING NUMBER
4.4.5(g)	Packaging - Packing - Palletization		SPI P5-51-575
			NEXT HIGHER ASSY

CATEGORY	CHARACTERISTIC	SAMPLING AND ACCEPTANCE CRITERIA	REQUIREMENT PARAGRAPH	INSPECTION METHOD
Critical	None defined			
Major				
101	Item completely clean and dry prior to unit packing	Table I, Level VII	5.2	VI
102	Fiberboard pads evident and correct	Table I, Level VII	5.2	VI and CE
103	Unit pack container and closure evident and correct	Table I, Level VII	5.2	VI and CE
104	Unit pack container marking evident, correct and undamaged	Table I, Level VII	5.2	VI and CE
105	Shipping container and closure correct and undamaged	Table I, Level VII Table I, Level VII	5.2 5.2	VI and CE VI and CE
106	Special markings evident, correct and legible	Table I, Level VII	5.2	VI and CE
107	Banding straps evident and undamaged	Table I, Level VII	5.2	VI and CE
Minor				
201	Pallet correct and undamaged	Table I, Level IX	5.2	VI and CE

NOTES:
CE - Commercial inspection equipment
VI - Visual inspection

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

4.4.6 Tests (see 6.4). Unless otherwise specified, tests shall be performed at room temperature, 20° to 30°C (68° to 86°F), as follows:

4.4.6.1 Container fill. Weigh the container before and after filling to determine fill weight.

4.4.6.2 Chemical and physical characteristics of DS2. Take a 1-liter specimen of DS2 from the filled fluid container and immediately test in accordance with the tests for *Chemical and physical characteristics* requirements specified in MIL-D-50030 (see 6.4).

4.4.6.3 Leakage. Place the filled closed container, without coupling cap and heat shrinkable tubing, on a side under water in a vacuum chamber so that no more than 1-inch of water covers the container (see 6.6). The water shall contain phenolphthalein (0.5 percent by weight phenolphthalein in methanol diluted to 10 milliliters of methanol per liter of water having a pH of 6.5 to 7.5). The filled container and water shall be at ambient temperature. Reduce the pressure in the vacuum chamber to 87 millimeters of mercury or less absolute. Hold the vacuum for at least 1-minute and observe the seams and threaded areas of the container for bubbles and pink coloration of the water. Any bubbles or pink coloration of the water at the seams or threaded areas of the container shall be considered evidence of leakage.

4.4.6.4 Fluid container assembly (Drawing 5-51-538).

4.4.6.4.1 Lifting handle strength. Secure the top reservoir or the container assembly and apply the specified static load uniformly over the handle for the specified time. Examine lifting handle and top-reservoir, or lifting handle and container assembly as applicable.

4.4.6.4.2 Burst strength. Plug all openings to affect a seal within the fluid container. Attach a source of hydrostatic pressure into the container through a fitting and apply the specified hydrostatic pressure for the specified time. Note: The container sides may be supported in a fixture during this test. See 6.7 for precautions regarding high pressure.

4.4.6.4.3 Leakage. With the fluid container openings sealed and with the specified air pressure introduced into the container through a fitting, submerge the container in water containing a wetting agent to a depth of no more than 3 inches below the surface for the specified time and observe for leakage. A steady stream of bubbles shall be an indication of leakage.

4.4.6.4.4 Drop strength. Fill the container with water and seal in accordance with note 4, Drawing 5-51-575. Drop the container as specified on bottom seam diagonally opposite from the vent/coupling area.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

4.4.6.5 Plug assembly leakage (Drawing 5-51-578). Attach a source of air pressure through an airtight fitting to the open end of plug assembly and apply specified air pressure. Submerge assembly in water to a depth of no more than 3 inches and examine for leakage for the specified time. A steady stream of bubbles shall be an indication of leakage.

5. PACKAGING

5.1 Interplant shipment (see 6.8). Military packaging as specified in 5.2 is not applicable for interplant shipment. The filled fluid container shall be packaged and marked to provide adequate protection from physical damage from the supply source to the first receiving activity for immediate use or further processing. Shipping containers shall be in compliance with the rules and regulations applicable to the mode of transportation.

5.2 Repair or replacement parts. For all shipments, other than interplant shipments (see 6.8), packaging (preservation, unit packing, packing and marking) shall be as specified in SPI P5-51-575.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The filled fluid container is intended to be used as a major component of the M13 Portable, 14 Liter, Decontaminating Apparatus which is used for dispensing DS2 decontaminating agent in the field.

6.2 Acquisition requirements. Acquisition documents must specify the following:

(a) Title, number, and date of this specification
(b) Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1).
(c) First article:

(1) First Article Inspection and Report requirements.
(2) Delivery schedule for First Article Report.
(3) Destination and delivery schedule of First Article Samples when testing is performed by the Government.
(4) First Article Test report approval time.

(d) Production

(1) Destination and delivery schedule requirements.
(2) Production and inspection report requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.

(e) Shelf life code (see section 5).
(f) Palletization required (see 5.2).

6.3 Submission of alternative inspection provisions. Proposed alternative inspection provisions should be submitted by the contractor to the procuring contracting officer for evaluation and approval by the technical activity responsible for preparation of this specification.

6.4 Sampling, testing, handling precautions for DS2. Warning: DS2 is a combustible liquid (Flash Point 168°F) and should not be stored near open flames or heat sources. DS2 is classified as a corrosive liquid as it contains sodium hydroxide and diethylenetriamine which are caustic in nature. DS2 is a toxic chemical with an ammonia-like odor and should be handled in a well ventilated environment and with appropriate protective clothing and equipment (i.e. corrosive resistant gloves, boots, apron, an industrial faceshield or splash-proof chemical goggles, and full facepiece respirator with amine cartridge). Use copious amounts of water for eye or skin contact. If DS2 is ingested, administer as much milk or water as possible, but do not induce vomiting. Spills should be neutralized with sodium bisulfate, absorbed with vermiculite and containerized as quickly as possible. Fires involving DS2 can be extinguished with CO_2, water spray, or alcohol foam.

6.5 Nitrogen blanket. As DS2 is degraded by carbon dioxide and moisture in the air, it is necessary to preserve the DS2 with a blanket of dry nitrogen.

6.6 Container seal. The opening used for filling and the vent opening should be closed securely immediately after filling, as shown on Drawing 5-51-575. The leakage test should be conducted on the filled fluid container before the coupling cap and heat shrinkable tubing are installed. After the leakage test, the container should be dried and all excess moisture removed (especially from the coupling plug) prior to installing coupling cap and heat shrinkable tubing as shown on Drawing 5-51-575.

6.7 Caution. Due to the hazards inherent in testing with high pressures, contractors are advised to take all necessary precautions to protect personnel while testing.

6.8 Interplant shipment. Packaging and marking for interplant shipment is for supplies and materials that do not directly enter the military supply system. Typical interplant shipments are shipments from a vendor to a subcontractor or a prime contractor, or between contractors and subcontractors, or from a vendor or contractor to a military arsenal, plant or other activity for evaluation, immediate use, or further processing as specified in the applicable contract.

6.9 Subject term (key word) listing.

Chemical agents
Decontamination

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:06Z
Check the source to verify that this is the current version before use.

Decontamination equipment
DS2

6.10 Changes from previous issues. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:

Army - EA

Preparing activity:

Army - EA

Project No. 4230-A094

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:06Z
Check the source to verify that this is the current version before use.