INCH-POUND

MIL-T-52296D
26 July 1991
SUPERSEDING
MIL-T-52296C
13 October 1983

MILITARY SPECIFICATION

TRANSOM ASSEMBLY: 60-TON UNIVERSAL TRANSOM

This specification is approved for use within the USA Belvoir Research, Development, and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a transom assembly and its components to be used with a trestle assembly (MIL-T-52150).

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards, form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development, and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

PPP-B-601	-	Boxes, Wood, Cleated Plywood.
PPP-B-636	-	Boxes, Shipping, Fiberboard.

MILITARY

MIL-T-704	-	Treatment and Painting of Materiel.
MIL-C-3774	-	Crates, Wood, Open, 12,000 and 16,000 Pound Capacity.

STANDARDS

FEDERAL

FED-STD-595	-	Colors.

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	-	Marking for Shipment and Storage.
MIL-STD-889	-	Dissimilar Metals.
MIL-STD-1186	-	Cushioning, Anchoring, Bracing, Blocking, and Waterproofing; with Appropriate Test Methods.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Document Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Government drawings. The following Government drawings form a part of this specification to the extent specified herein. Unless otherwise specified, the issues are those in effect on the date of the solicitation.

DRAWINGS

ME

TA13207E9701	-	Transom Assembly.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development, and Engineering Center, ATTN: STRBE-JBS, Fort Belvoir, VA 22060-5606.)

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers and Welding and Brazing Operators.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 3953	- Strapping, Flat Steel and Seals.
D 4675	- Selection and Use of Flat Strapping Materials.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN WELDING SOCIETY (AWS)

A5.1	- Carbon Steel Covered Arc Welding Electrodes.
A5.10	- Aluminum and Aluminum Alloy Bare Welding Rods and Electrodes.
A5.18	- Carbon Steel Filler Metals for Gas Shielded Arc Welding.
D1.1	- Structural Welding Code - Steel.
D1.2	- Structural Welding code - Aluminum.

(Application for copies should be addressed to American Welding Society, 345 East 47th Street, New York, NY 10017.)

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION (NMFTA)

National Motor Freight Classification Rules.

(Application for copies should be addressed to the American Trucking Association, Inc., ATTN: Traffic Order Section, 2200 Mill Rd., Alexandria, VA 22314.)

UNIFORM CLASSIFICATION COMMITTEE (UCC)

Uniform Freight Classification Rules.

(Application for copies should be addressed to the Uniform Classification Committee, Rm 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

(Non-Government standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The transom assembly and its components shall be as shown on Top Assembly TA13207E9701 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are engineering design drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the transom assembly. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Material shall be new and unused.

3.3.1 Material deterioration and control. The transom assembly shall be fabricated from compatible materials, inherently corrosion and deterioration resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operating and storage environment to which the item may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals, as defined in MIL-STD-889, shall be electrically insulated from one another to minimize or prevent galvanic corrosion.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with component and subcomponent, and shall make information available upon request to the contracting officer or designated representative.

3.4 Welding electrodes.

3.4.1 For steel. Welding electrodes for steel shall conform to ANSI/AWS A5.1 or A5.18, classification E60 or E70 series, size as required.

3.4.2 For aluminum. Welding electrodes for aluminum shall conform to ANSI/AWS A5.10, classification ER4043, size as required.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

3.5 Identification marking. The transom assembly or components, as applicable, shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.6 Treatment and painting. The transom assembly or components, as applicable, except pins, bolts, and threaded portions of threaded components and parts shall be cleaned, treated, and painted in accordance with MIL-T-704, type G, except that the color number designation shall be 34094 in accordance with FED-STD-595. The contact surfaces of all dissimilar metals shall be painted prior to assembly.

3.7 Stenciling. The nomenclature, National stock number, weight, and cube shall be stenciled on each transom assembly. The letters "NET WT" shall precede the numerals in the weight and the letters "CU" shall precede the cubic displacement. Markings shall be gothic-type capitals and Arabic numerals 3/4 inch high. Stenciling shall conform to MIL-T-704.

3.8 Workmanship.

3.8.1 Steel fabrication. Steel may be cut by shearing, sawing, or flame cutting. Burned surfaces of flame-cut material shall be ground or machined to remove cooling checks. All bends shall be made by use of metal dies or fixtures to insure uniformity in size and shape. All burrs shall be removed.

3.8.2 Aluminum fabrication. Aluminum used in the fabrication of the transom assembly shall be free from kinks and sharp bends. Straightening of material shall be done by methods that will not cause injury to the metal. Surfaces and edges of all finished members shall be smooth and free from kinks, bends, and winds. All bends of a major character shall be made with metal dies or fixtures to insure uniformity of size and shape. Sharp instruments shall not be used for marking bend lines. Aluminum shall not be cut by methods using heat. Aluminum less than 3/8 inch thick may be cut by shearing; aluminum 3/8 inch thick and over shall be cut by routing or by high-speed saws. Shearing and sawing shall be done neatly and accurately.

3.8.3 Bolted connections. Bolt holes shall be punched or drilled, and all burrs shall be removed.

3.8.4 Riveted connections.

3.8.4.1 Rivet holes. Holes for countersunk rivets shall be of such depth and angle that the rivet head shall fill the hole without projection or recession.

3.8.4.2 Riveting. Components shall be bolted in position before riveting. Jigs or frames shall be used to maintain alignment and tolerance. Countersunk rivets shall be flush with the surrounding surface. Heads of driven rivets shall be uniform in shape and concentric with the rivet shank axis, and shall have full bearing on the surfaces of the joined members. Rivets shall fill the holes in the joined members. Caulking or redriving of rivet heads shall not be permitted. Rivet tension shall not be created by driving in incorrectly fitted members. A rivet with a head deficient in size, not uniform in shape, off-center, loose, burned, or misshapen in any way shall be considered defective. Defective rivets shall be removed without injury to the

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

joined metal. Rivets shall not be heated in excess of 950 °F and shall be driven at a temperature of not less than 850 °F. Rivets may be driven cold, immediately after quenching, in which case a hole diameter 1/64 inch smaller than for a hot-driven rivet of the same size is required.

3.8.5 Welding and welders.

3.8.5.1 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the provisions of the appropriate AWS or ASME Codes. All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wirebrushed clean.

3.8.5.1.1 Steel welding. Where embrittlement of the joined metal may result, preheating or annealing or both shall be employed.

3.8.5.1.2 Aluminum welding. Aluminum members to be welded may be preheated for welding to a temperature of not more than 400 °F. Aluminum welds may be filed, wirebrushed, or chipped but shall not be hammered.

3.8.5.2 Welders and Welding Operators. Before assigning any welder or welding operator to welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder or welding operator has passed qualification tests as prescribed by one of the following listed codes for the type of welding operations to be performed and that such qualifications is effective as defined by the particular code:

ASME Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators.
AWS D1.1, Structural Welding Code - Steel.
AWS D1.2, Structural Welding Code - Aluminum.

Contractors who make only horizontal welds need not qualify welders for "all position welding". In the event of evidence of poor welds, the Government reserves the right to require recertification of any welder or welding operator. The test results shall be made available for review by the contracting officer or the contracting officer's representative.

3.8.6 Interchangeability. Transom assemblies shall be fabricated to be duplicates within the tolerances specified and shall be interchangeable.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.1.2 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the Quality Assurance Provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.5 and 6.6).

4.2 Classification of inspections. Inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The first article transom assembly or component(s), as applicable, shall be examined in accordance with 4.4.2.1 and for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination shall be in accordance with MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.4.2 Examination.

4.4.2.1 Individual. Each transom assembly shall be inspected for conformance to the dimensions covered by the Quality assurance provisions (QAP) shown on the drawings under "Major - 100 percent inspection". Nonconformance to any of these dimensions shall constitute failure of this examination and shall be cause for rejection.

4.4.2.2 Samples. Samples selected in accordance with 4.4.1 shall be examined for the major and minor defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

4.5 Inspection procedure.

4.5.1 Examination. The transom assembly or components, as applicable, shall be examined as specified herein for the following defects:

Major

101. Components missing or not as specified (see 3.1).
102. All dimensions designated major on the QAP other than those under 100 percent inspection not as specified (3.1.1).
103. Materials not as specified (see 3.3).
104. Materials are not resistant to corrosion and deterioration or treated to be resistant to corrosion and deterioration for the applicable storage and/or operating environment (see 3.3.1).
105. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other (see 3.3.1.1).
106. Contractor does not have documentation available for identification of material, material finishes or treatments (see 3.3.1.2).
107. Workmanship not as specified (see 3.8).
108. Rivets not as specified (see 3.8.4).
109. Weld defects such as flux inclusions, spatter, under-cutting, porosity, incorrect size, or lack of fusion with parent metal (see 3.8.5).
110. Welding and welds not as specified (see 3.8.5.1).
111. Welders and welding operators not certified as specified (see 3.8.5.2).

Minor

201. All dimensions not designated major on the QAP not as specified (3.1.1).
202. Identification marking incorrect, missing, or illegible (see 3.5).
203. Treatment and painting not as specified (see 3.6).
204. Stenciling not as specified (see 3.7).

4.6 Inspection of packaging.

4.6.1 First article pack inspection.

4.6.1.1 Examination. The first article pack shall be examined for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.1.2 Test. The first article pack of crated transom assemblies for level A or B shall be subjected to the rail-impact test as specified in MIL-STD-1186, appendix A. At the conclusion of the first article pack test, the pack shall be examined. Any shifting of contents, loosening or breaking of holddowns, ties, stays, blocking, or bracing, or any visual damage to the components shall constitute failure of the first article pack and shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. Presence of one or more defects shall be cause for rejection.

112.	Containers not as specified for level A or B. Each incorrect container shall be considered one defect (see 5.2).
113.	Blocking, bracing, and anchoring not in accordance with the referenced document for level A or B (see 5.2.1).
114.	Loose nuts, bolts, screws, and washers not secured to the item for which intended for level A or B (see 5.2.1.1 and 5.2.2.1).
115.	Components procured separately not secured within the box in accordance with the referenced document for level A or B (see 5.2.1.1 and 5.2.2.1).
116.	Strapping not as specified for level A (see 5.2.1.1).
117.	Gross weight or size exceeds the limitations of the fiberboard box for level B (see 5.2.2.1).
118.	Fiberboard box not sealed and reinforced as specified for level B (see 5.2.2.1).
119.	Packing not in accordance with the referenced document as specified for level C shipment (see 5.2.3).
120.	Marking missing, illegible, incorrect, or incomplete for level A, B, or C (see 5.3).

5. PACKAGING

5.1 First article pack. Unless otherwise specified (see 6.2), the contractor shall furnish a first article pack for examination and test within the time frame specified, to prove prior to starting production packaging that the applied packing, and marking comply with the packaging requirements of this specification. Examination and test shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The first article pack may be accomplished utilizing either the first article item or production item. If the first article item is utilized, any packing shall be removed by the contractor at no expense to the Government, when requested by the Government to facilitate comparison between the first article item and the production items.

5.2 Packing. Packing shall be level A, B, or C as specified (see 6.2).

5.2.1 Level A. Each completely assembled transom assembly (with pins in place) shall be packed in a crate conforming to MIL-C-3774, nailed assembly, skid-type base. Blocking, bracing, and anchoring shall be in accordance with MIL-STD-1186 and the appendix to the crate specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

5.2.1.1 Components procured separately from the transom assembly. When the transom latch, shackle assembly, spring holder assembly, transom pin, transom latch pin, and pin adapter are procured separately from the transom assembly, the items of like description shall be packed together in a close-fitting box conforming to PPP-B-601, overseas type, style optional. Loose nuts, bolts, screws, or washers involved shall be secured to the item for which intended to prevent their loss. The components shall be secured within the box in a manner to prevent free movement in accordance with MIL-STD-1186. The box shall be closed and strapped in accordance with the appendix to the box specification. Strapping shall be in accordance with ASTM D 3953, type 1 or 2, zinc-coated, size as applicable, and ASTM D 4675.

5.2.2 Level B. Each completely assembled transom assembly (with pins in place) shall be packed as specified in 5.2.1.

5.2.2.1 Components procured separately from the transom assembly. When the transom latch, shackle assembly, spring holder assembly, transom pin, transom latch pin, and pin adapter are procured separately from the transom assembly, the items of like description shall be packed together in a close-fitting box conforming to PPP-B-601, domestic type, style optional or PPP-B-636, V3c. Loose bolts, nuts, screws, or washers involved shall be secured to the item for which intended to prevent their loss. The components shall be secured within the box in a manner to prevent free movement in accordance with MIL-STD-1186. The gross weight or size of fiberboard boxes shall not exceed the limitations of the box specification, and the boxes shall be waterproof sealed and reinforced with bands of reinforced tape in accordance with the appendix to the box specification.

5.2.3 Level C. Each completely assembled transom assembly (with pins in place) and all of its components shall be packed in a manner to assure carrier acceptance and safe delivery to destination at lowest ratings in compliance with Uniform Freight Classification Rules or with National Motor Freight Classification Rules.

5.3 Marking. (see 6.7) In addition to any special marking specified in the contract or purchase order (see 6.2) shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The 60-ton universal transom assembly is a component of a trestle assembly to be used in the assembly of fixed and floating bridges and in reinforcing existing fixed bridges. This item is a component of the following Supply Catalogs (SC) SC 5420-97-CL-E03, E35, E36 and E46.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issues of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

c. When a first article is required for inspection and approval and the number of units required (see 3.2).
d. When a first article pack is not required (see 5.1).
e. Time frame required for submission of the first article pack (see 5.1).
f. Level of packing required (see 5.2).
g. Any special marking (see 5.3).

6.3 First article. When a first article inspection is required the item(s) should be a preproduction model. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of the first article test results and disposition of the first articles. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 First article pack. Any changes or deviations of production packs from the approved first article pack will be subject to the approval of the contracting officer. Approval of the first article pack will not relieve the contractor of his obligation to pack and mark the transom assembly or separately procured components in accordance with this specification.

6.5 Quality assurance provisions (QAP) records. The contracting officer should require the contractor to maintain records of all QAP inspections. A suggested paragraph is as follows:

> "The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, corrected action taken when applicable".

6.6 Definitions.

6.6.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of this specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.7 Levels of packaging. Preservation is not required, but for purposes of preservation/packing level marking, preservation shall be designated as level A.

6.8 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

6.9 Subject term key word listings.

Bridge
Transom
Trestle

Custodian:
Army - ME

Review activity:
Navy - MC
DLA - CS

Preparing activity:
Army - ME

Project 5420-0179

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-T-52296D	910726

3. DOCUMENT TITLE

Transom Assembly: 60-Ton Universal Transom

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER		
a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial	(2) AUTOVON
	(703) 664-5717	354-5717
c. ADDRESS (Include Zip Code) US Army Belvoir RDE Center ATTN: STRBE-TSE Ft. Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340	AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 20261126104:07Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:07Z
Check the source to verify that this is the current version before use.