INCH-POUND

MIL-T-52369B
9 October 1991
SUPERSEDING
MIL-T-52369A(ME)
28 May 1971

MILITARY SPECIFICATION

TOWER ASSEMBLY: CABLEWAY, MEDIUM

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a track-cable-support tower assembly.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir, Research, Development, and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

PPP-B-601	-	Boxes, Wood, Cleated-Plywood.
PPP-B-621	-	Boxes, Wood, Nailed and Lock-Corner.

MILITARY

MIL-P-116	-	Preservation, Methods of.
MIL-T-704	-	Treatment and Painting of Materiel.
MIL-C-3774	-	Crates, Wood; Open, 12,000 and 16,000 Pound Capacity.
MIL-C-52950	-	Crates, Wood, Open and Covered.

STANDARDS

FEDERAL

FED-STD-595	-	Colors.

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	-	Marking for Shipment and Storage.
MIL-STD-889	-	Dissimilar Metals.
MIL-STD-1186	-	Cushioning, Anchoring, Bracing, Blocking and Waterproofing; With Appropriate Test Methods.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Document Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Government drawings. The following Government drawings form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those in effect on the date of the solicitation.

DRAWINGS

ME

TA13208E5020	-	Tower Assembly: Cableway, Medium.

(Copies of drawings, publications, and other Government documents required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir, Research, Development, and Engineering Center, ATTN: STRBE-JB, Fort Belvoir, VA 22060-5606.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY FOR TESTING AND MATERIAL (ASTM)

D 3953 - Strapping, Flat Steel and Seals.
D 4675 - Selection and Use of Flat Strapping Materials.

(Applications for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN WELDING SOCIETY (AWS)

A5.1 - Covered Carbon Steel Arc Welding Electrodes.
A5.18 - Carbon Steel Filler Metals for Gas Shielded Arc Welding.
D1.5 - Bridge Welding Code.

(Application for copies should be addressed to the American Welding Society, 550 N.W. LeJeune Road, P.O. Box 351040, Miami, FL 33135.)

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION, INC. (NMFTA)

National Motor Freight Classification Rules.

(Application for copies should be addressed to the American Trucking Associations, Inc., ATTN: Traffic Order Section, 2200 Mill Road, Alexandria, VA 22314.)

UNIFORM CLASSIFICATION COMMITTEE (UCC)

Uniform Freight Classification Rules.

(Application for copies should be addressed to the Uniform Classification Committee, Rm 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

(Non-Government standards and other publications are normally available from the organizations which prepare or which distribute the documents. These

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The tower assembly or tower components, as specified (see 6.2), shall be in accordance with top assembly TA13208E5020 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are engineering design drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the supplier or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the supplier and shall be subject to all provisions of this specification.

3.3.1 Material deterioration prevention and control. The tower assembly shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operating and storage environments to which the tower assembly may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with component and subcomponent, and shall make information available upon request to the contracting officer or designated representative.

3.4 Welding electrodes. Welding electrodes for structural steel shall conform to AWS A5.1 or A5.18, E60XX series or E70XX series.

3.5 Identification marking. The tower assembly components shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

3.6 Cleaning, treatment, and painting. The tower assembly components, shall be cleaned, treated, and painted as specified on the drawings except that the color number designation shall be 34094 in accordance with FED-STD-595.

3.7 Stenciling. The nomenclature, Federal stock number, weight, and cube shall be stenciled on each tower component which is metal stamped except pivot pins. The letters "NET WT" shall precede the numerals in the weight and the letters "CU" shall precede the cubic displacement. The required information shall be stenciled with 1/2-inch characters on one angle near the center of the tower section and on one of the side plates of the tower base. Stenciling shall conform to MIL-T-704.

3.8 Workmanship.

3.8.1 Steel fabrication. Steel used in the fabrication of the tower components shall be free from lamination, kinks, and sharp bends. The straightening of material shall be done by methods that will not cause injury to the metal. Corners shall be square and true. Flame cutting with a tip suitable for the thickness of metal may be employed instead of shearing or sawing. Burned surfaces of flame-cut material shall be ground or machined sufficiently to remove ash and cooling checks. All bends shall be made with metal dies or fixtures to insure uniformity of size and shape. Precautions shall be taken to avoid overheating, and heated metal shall be allowed to cool slowly. All burrs, rough edges and edges of holes shall be ground smooth.

3.8.2 Riveting. Components shall be bolted in position before riveting. Jigs or frames shall be used to maintain alignment and tolerance. Rivets shall be free from slag or scale when driven. Heads of driven rivets shall be uniform in shape and concentric when the rivet shank axis, and shall have full bearing on the surfaces of the joined members. Rivets shall fill the holes in the joined members. Caulking or redriving of rivet heads shall not be permitted. Rivet tension shall not be created by driving in incorrectly fitted members. A rivet with a head deficient in size, not uniform in shape, off-center, loose, burned, or misshapen in any way shall be considered defective. Defective rivets shall be removed without injury to the joined metal. Automatic or squeeze-type riveters shall be permitted for driving rivets, where practicable, provided the pressure employed does not cause distortion of the material. In lieu of automatic or squeeze-type rivet machines, pneumatic rivet hammers may be used. Steel rivets may be driven hot or cold. Hot steel rivets shall be heated uniformly throughout their length and driven while at a light cherry color.

3.8.3 Welders and welding.

3.8.3.1 Welders and welding operators. Before assigning any welder or welding operator to welding work covered by this specification, the supplier shall provide the contracting officer with certification that the welder or welding operator has passed qualification tests as prescribed by either of the following listed codes for the materials joined and the type of welding operation to be performed and that such qualification is effective as defined by the particular code:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

AWS D1.5 - Bridge Welding Code.
ASME Boiler and Pressure Vessel Code, Section IX.

In the event of evidence of poor welds, the Government reserves the right to require recertification of any welder or welding operator. The test results shall be made available for review by the contracting officer or the contracting officer's representative.

3.8.3.2 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the provisions of the ASME or AWS Codes. All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed, and the deposit and adjoining base metal shall be wire brushed clean.

3.8.3.3 Jigs and fixtures. Components, except for minor parts, shall be assembled in steel jigs or frames and welded while securely held in position. Minor parts may be held securely and tightly in position by any means that will insure secure and correct positioning. The jigs or frames shall be designed so that distortion of the parts will be held to a minimum.

3.8.4 Interchangeability. Components of like description shall be fabricated to be duplicates within the tolerances specified and shall be interchangeable.

3.8.5 Assembly. The tower assembly components shall be capable of being assembled into a tower and erected, using not less than three intermediate sections per tower, and there shall be no misfits or interference of mating parts.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the Quality Assurance Provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance or rejection (see 6.5 and 6.6).

4.2 Classification of inspections. Inspection shall be classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The tower assembly or tower component shall be examined in accordance with 4.4.2.1 and for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Test. The tower assembly shall be tested as specified in 4.5.2. Failure of the test shall be cause for rejection. When individual tower components are procured separately, the test shall not apply.

4.4 Quality conformance inspection.

4.4.1 Sampling for examination. Sampling for examination shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found, and rejected when one or more defects are found.

4.4.2 Examination.

4.4.2.1 Individual. Each tower assembly or tower component, as applicable, shall be inspected for conformance to the dimensions covered by the Quality Assurance Provisions (QAP) shown on the drawings under "Major - 100 percent inspection". Nonconformance to any of these dimensions shall constitute failure of this examination and shall be cause for rejection.

4.4.2.2 Samples. Samples selected in accordance with 4.4.1 shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. The tower or tower component shall be examined for the following defects:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

Major

101. All dimensions designated major on the QAP other than those under 100 percent inspection not as specified (see 3.1).
102. Material not as specified (see 3.3).
103. Components missing or not as specified (see 3.1.1).
104. Materials are not resistant to corrosion or deterioration or treated to be made resistant to corrosion or deterioration for the applicable storage and operating environment as specified (see 3.3.1).
105. Dissimilar metals as specified in MIL-STD-889 are not effectively insulated from each other as specified (see 3.3.1.1).
106. Contractor does not have documentation available for identification of material, material finishes, or treatments (see 3.3.1.2).
107. Workmanship not as specified (see 3.8).
108. Riveting not as specified (see 3.8.2).
109. Welders and welding operators not certified as specified (see 3.8.3.1).
110. Weld defects such as flux inclusions, spatter, undercutting, porosity, incorrect size, or lack of fusion with parent metal (see 3.8.3.2).
111. Welding and welds not as specified (see 3.8.3.2).

Minor

201. All dimensions not designated major on the QAP not as specified (see 3.1.1).
202. Identification marking incorrect, missing, or illegible (see 3.5).
203. Treatment and painting not as specified (see 3.6).
204. Stenciling not as specified (see 3.7).

4.5.2 Assembly test. The components shall be assembled into a tower with not less than three intermediate sections per tower. The assembled towers shall be erected and checked for assembly alignment and fit. Interference of mating members or incorrect fit at joints shall constitute failure of this test.

4.6 Inspection of packaging.

4.6.1 First article pack inspection.

4.6.1.1 Examination. Examine the first article pack for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.1.2 Test. The first article pack of a crated tower assembly or of tower components for level A shall be subjected to the railroad-car test as specified for guided-impact tests in accordance with MIL-STD-1186, appendix A. The car shall strike a string of five empty cars with draft gear extended and the brakes set, at a speed of not less than 10 miles or more than 11 miles per hour. At the conclusion of the first article pack test, the pack shall be examined. Any shifting of contents, loosening or breaking of holddowns, ties,

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

stays, blocking or bracing, or any visual damage to the components shall constitute failure of the first article pack and shall be cause for rejection.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. Presence of one or more defects shall be cause for rejection.

112.	Disassembly not as specified (see 5.2.1.1).
113.	Unpainted surfaces not coated with preservative as specified (see 5.2.1.2).
114.	Small components not packaged as specified for level A or B (see 5.2.1.3).
115.	Blocking, bracing, and anchoring not in accordance with the referenced documents for level A or B (see 5.3.1 and 5.3.1.1).
116.	Preservation not as specified for level C (see 5.2.3).
117.	Crates not as specified for level A (see 5.3.1 and 5.3.1.1).
118.	Strapping not zinc-coated for level A (see 5.3.1).
119.	Packing not in accordance with the referenced document for level C (see 5.3.2).
120.	Marking missing, illegible, incorrect, or incomplete (see 5.4).

5. PACKAGING

5.1 First article pack. The supplier shall furnish a first article pack for examination and test within the time frame specified (see 6.2) to prove prior to starting production packaging and packing, that the applied preservation, packaging, packing and marking comply with the preparation for delivery requirements of this specification. Examination and test shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The first article pack may be accomplished utilizing either the preproduction tower assembly or a production tower assembly or tower components, as applicable. If the first article tower assembly is utilized, any preservation, packaging, and packing shall be removed by the supplier at no expense to the Government when requested by the Government to facilitate comparison between the first article tower assembly and the production tower assembly.

5.2 Preservation. Preservation shall be level A, B, or C as specified (see 6.2).

5.2.1 Level A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

5.2.1.1 Disassembly. The tower assembly shall be disassembled into the various sections. Bolts, nuts, and washers involved shall be reinstalled in mating parts and secured to prevent loss or packaged as specified in 5.2.1.3.

5.2.1.2 Unprotected surfaces. Unpainted metal surfaces of components such as bolts, nuts, pins, washers, sheaves, and bearings shall be coated with type P-1 preservative. The preservative shall conform to the applicable specification listed in and shall be applied in accordance with MIL-P-116.

5.2.1.3 Small components. Small components, other than the tower sections, shall be packaged together in close-fitting boxes conforming to PPP-B-621, class 2, style optional; or PPP-B-601, overseas type, style optional. The contents shall be secured within the boxes to prevent free movement or damage.

5.2.2 Level B. Preservation shall be as specified in 5.2.1 for level A except boxes specified in 5.2.1.3 shall be domestic type or class as applicable.

5.2.3 Level C. The tower assembly shall be disassembled and unprotected surfaces coated with preservative as specified in 5.2.1 and 5.2.2. Small components shall be packaged together in a manner to assure protection against damage from the supplier to the initial destination.

5.3 Packing. Packing shall be level A or C, as specified (see 6.2).

5.3.1 Level A. Each complete tower assembly shall be packed in a crate conforming to MIL-C-3774, type I, style A. Blocking, bracing, and anchoring shall be in accordance with the appendix to the crate specification and in accordance with MIL-STD-1186. Strapping shall be in accordance with ASTM D 3953, type 1 or 2, zinc-coated, size as applicable and ASTM D 4675.

5.3.1.1 Individual tower components. Individual tower components when procured separately shall be packed together in crates conforming to MIL-C-52950. Blocking, bracing, and anchoring shall be in accordance with the appendix to the applicable crate specification and in accordance with MIL-STD-1186.

5.3.2 Level C. Complete tower assemblies, and individual tower components when procured separately, shall be packed or prepared for shipment in a manner to assure carrier acceptance and safe delivery to destination at lowest ratings in compliance with Uniform Freight Classification rules or National Motor Freight Classification rules.

5.4 Marking. In addition to any special marking specified in the contract or purchase order (see 6.2), marking shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

6.1 Intended use. The tower assemblies are intended for use as the supports for the track cables of the medium cableway. This item is a component of the following Supply Catalog (SC) SC 5420-97-CL-E04.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. Whether complete tower assemblies or components are required (see 3.1).
d. Time frame required for submission of first article (see 3.2).
e. Time frame required for submission of first article pack (see 5.1).
f. Level of preservation and level of packing required (see 5.2 and 5.3).
g. Any special markings required (see 5.4).

6.3 First article. When a first article inspection is required, the item(s) should be a preproduction model. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of the first article test results and disposition of the first articles. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 First article pack. Any changes or deviations of production packs from the approved first article pack will be subject to the approval of the contracting officer. Approval of the first article pack will not relieve the supplier of his obligation to preserve, package, pack, and mark the tower assemblies in accordance with this specification.

6.5 Quality assurance provisions (QAP). The contracting officer should require the supplier to maintain records of all QAP inspections. A suggested paragraph is as follows:

> "The supplier shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, corrected action taken when applicable."

6.6 Definitions.

6.6.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of the specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

the design objectives of the product and assure interchangeability of repair parts.

6.7 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

6.8 Subject term (key word) listing.

Bridge
Cableway
Tower

Custodians:
Army - ME

Preparing activity:
Army - ME

Reviewing activity:
DLA - CS

Project 5420-0185

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-T-523698	2. DOCUMENT DATE (YYMMDD) 911009

3. DOCUMENT TITLE
Tower Assembly: Cableway, Medium

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (if applicable) (2) AUTOVON	7. DATE SUBMITTED

8. PREPARING ACTIVITY

a. NAME Gerry Harlow	b. TELEPHONE (Include Area Code) (1) Commercial (703) 664-1806	(2) AUTOVON 354-1806
c. ADDRESS (Include Zip Code Army Belvoir RDE Center N: STRBE-TSE Fort Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:08Z
Check the source to verify that this is the current version before use.