MIL-H-52641A(ME)
18 April 1979
SUPERSEDING
MIL-H-52641(ME)
19 November 1969

MILITARY SPECIFICATION

HEATER, ELECTRIC, 1,500 WATTS,

115 VOLTS, AC, WITH FAN

This specification is approved for use by the Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers a base-mounted electric space heater with blower.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

QQ-S-781	- Strapping, Steel, and Seals.
PPP-B-601	- Boxes, Wood, Cleated-Plywood.

FSC 4520

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:28Z
Check the source to verify that this is the current version before use.

PPP-B-636	- Boxes, Shipping, Fiberboard.

MILITARY

MIL-P-116	- Preservation-Packaging, Methods of.
MIL-V-173	- Varnish, Moisture-and-Fungus-Resistant, (for Treatment of Communications, Electronic and Associated Equipment).
MIL-P-514	- Plates, Identification, Instruction and Marking, Blank.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-W-8611	- Welding, Metal Arc and Gas, Steels, and Corrosion and Heat Resistant Alloys; Process for.
MIL-P-15024/6	- Plates, Tags and Bands for Identification of Equipment.

STANDARDS

FEDERAL

FED. STD. No. 595	- Colors.

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-461	- Electromagnetic Interference Characteristics Requirements for Equipment.
MIL-STD-810	- Environmental Test Methods for Aerospace and Ground Equipment.
MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.

DRAWINGS

ME

TA13217E6150	- Heater, Space, Electric, 115 Volts, AC, 1500 Watts.

(Copies of specifications, standards and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:28Z
Check the source to verify that this is the current version before use.

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

SOUTHERN CALIFORNIA AIR POLLUTION CONTROL DISTRICT

Rule 102 - Photochemically Reactive Solvents.

(Application for copies should be addressed to the Southern California Air Pollution Control District, 434 South San Pedro Street, Los Angeles, CA 90013.)

AMERICAN WELDING SOCIETY, INC.

D1.1 - Structural Welding Code, Section 5, Qualification.

(Application for copies should be addressed to the American Welding Society, Inc., 2501 N.W. 7th Street, Miami, FL 33125.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Boiler and Pressure Vessel Code, Section IX, Welding Qualification.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

3. REQUIREMENTS

3.1 Description. The heater shall be in accordance with Top Assembly TA13217E6150 and as specified herein. The heater shall weigh not more than 40 pounds.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the heater. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request for inspection by the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:28Z
Check the source to verify that this is the currentversion.before use.

3.2 First articles.

3.2.1 Preproduction models. The contractor shall furnish two heaters for examination and test within the time frame specified to prove, prior to starting production, that his production methods will produce heaters that comply with the requirements of this specification (see 6.3). Examination and tests shall be those specified in 4.3 and shall be subject to surveillance and approval by the Government.

3.2.2 Initial production. When specified (see 6.2), the contractor shall furnish to the Government one or more heaters for inspection as specified in 4.4.

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Material not specified shall be selected by the contractor and shall be subject to all provisions of this specification (see 6.5). Materials subject to atmospheric corrosion or rust shall not be treated with a temporary treatment such as grease or oil in order to meet environmental condition requirements. Materials shall be free from defects or imperfections which might affect the serviceability or appearance of the finished heater.

3.4 Operation. The heater shall be capable of continual operation when connected to 115 volt, single phase, ac power, both 50 and 60 Hertz. The heater shall have a heating capacity of 1500 plus or minus 100 watts.

3.5 Environmental requirements.

3.5.1 Operating. The heater shall operate in the "FAN" mode in any ambient temperature from plus 110° F to minus 50° F, and shall operate in the "HEAT" mode in any ambient temperature from plus 85° to minus 50°F.

3.5.2 Storage. The heater shall not be damaged and its operation shall not be impaired by storage at ambient temperatures of plus 155° F for periods up to 4 hours daily and minus 50° F without solar radiation for periods up to 3 consecutive days.

3.5.3 Humidity. The heater shall show no peeling of paint, corrosion, malfunctioning, damage, electrical shorts, or other irregular operation after exposure to humidity as specified in MIL-STD-810, Method 507.1, Procedure I, except the maximum temperature shall be 155° F.

3.6 Reliability. Two heaters shall operate for an accumulated total of not less than 4000 hours without failure or malfunctioning of the heater or components and without requiring maintenance other than cleaning.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:28Z
Check the source to verify that this is the current version before use.

3.7 Selector switch and thermostat control. The selector switch shall control the heater as follows: When the switch is in the "OFF" position, all components of the heater shall be de-energized and inoperative. When the switch is in the "FAN" position, the fan motor shall start and operate and the heating element shall be de-energized and inoperative. When the switch is in the "HEAT" position with the thermostat adjusted to a temperature higher than ambient, the fan motor and the heating element shall be energized and operative. When the switch is in the "HEAT" position with the thermostat adjusted to a temperature lower than ambient, the fan motor shall be energized and operative and the heating element shall be de-energized and inoperative.

3.8 Wiring. Wiring shall be laced together in compact harnesses and attached to frame members with insulated clamps at close intervals to insure a neat and orderly cable run. Cable and wires shall not be spliced at any point throughout the length of their runs. Wiring shall not be attached to panels or other components that require removal during maintenance except for actual electrical connections to components. Electrical isolators shall be used between all wiring and metal components to prevent abrasive action to wire insulation.

3.9 Electromagnetic interference. The electromagnetic interference emission and susceptibility characteristics of the heater shall conform to MIL-STD-461A, Notice 1, Table A-1 of the Appendix.

3.10 Fungus and moisture resistance. The electrical circuitry, including all components and connections except as specified below, shall be protected from the effects of fungus growth and moisture by an overall treatment with a varnish conforming to MIL-V-173, composition as specified in 3.10.1 with 1 percent copper 8-quinolinolate (by weight) based on the nonvolatile content of the varnish:

(a) Components or circuit elements that are inherently fungus and moisture resistant or which are hermetically sealed need not be treated.
(b) Components or circuit elements whose functions will be adversely affected by the varnish coating shall not be treated.

When used, the varnish shall be applied by spray, brush, or a combination of both to give a dry-film thickness of not less than 1 mil to component or element surfaces previously cleaned and prepared so that the surfaces are free from all foreign matter which would interfere with the adherence or function of the varnish.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:28Z
Check the source to verify that this is the current version before use.

3.10.1 Composition. Composition I shall be used unless Composition II must be used in order to comply with local air pollution regulations in the application of the varnish. When Composition II is used, the contractor shall provide evidence to the Government that the use of Composition II is required, and shall certify that the Composition II material complies with Rule 102 - Southern California Air Pollution Control District.

3.11 Identification marking. The heater shall be identified in accordance with MIL-STD-130. The marking shall be applied to the heater on identification plates conforming to MIL-P-15024/6, Type H, Style III, Size 12.

3.11.1 Other markings. The heater shall be equipped with markings identifying items that are involved in its operation and handling such as controls, fuses, and input power connections.

3.12 Instruction plates. Each heater shall be equipped with instruction plates including warnings, diagrams, and cautions conspicuously describing any special or important procedures to be followed in operating and servicing the heater. The instruction plates shall conform to MIL-P-514, Type III, Composition C, Grade A, Class 1, size optional. The words "Warning" and "Caution" shall be red, matching color No. 31136 of FED. STD. No. 595.

3.12.1 Schematic and wiring diagram. A schematic diagram and a connection (wiring) diagram shall be mounted on the inside of a removable panel of the heater. The diagram shall portray the complete operational and functional sequence of the circuit for analysis and maintenance of the heater. The connection (wiring) diagram shall portray the physical location of all wiring interconnections in the same relationship as when they are installed. Identification markings of wires, instruments, control devices, circuit-breakers, fuses, and connections shall be shown in both diagrams.

3.13 Treatment and painting. All metal parts, except those otherwise specified herein, shall be cleaned, treated, and painted in accordance with MIL-T-704, Type A, color as specified (see 6.2).

3.14 Stenciling. The weight of each heater shall be stenciled on each side of the heater case in such a manner as to be discernible. The height of the figures shall be at least 1 inch. All stenciling shall conform to MIL-T-704.

3.15 Technical publications. Such technical publications as are specified shall be furnished (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:28Z
Check the source to verify that this is the current version before use.

3.16 Workmanship.

3.16.1 Metal fabrication. Sheet metal and structural members used in fabrication shall be straight and free from laminations. The forming and straightening of material shall be done by methods that will not change the physical properties of the materials. Sheet metal and structural members may be cut by shearing or sawing. Corners shall be square and true. All bends shall be made with metal dies or fixtures to insure uniformity of size and shape.

3.16.2 Bolted connections. Boltholes shall have the burrs removed. Washers or lockwashers shall be provided where required, and all bolts, nuts, and screws shall be tight.

3.16.3 Riveted connections. Rivet holes shall have the burrs removed. Rivets shall fill the holes. Rivet heads shall be full, concentric with the rivet holes, and in full contact with the surface of the member.

3.16.4 Welders and welding.

3.16.4.1 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

AWS D1.1 Structural Welding Code, Section 5, Qualification.
ASME Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

Contractors who only make horizontal welds need not qualify welders for "all position welding". Subject to approval by the Government, contractor's standard welder qualification may be substituted in lieu of the above codes provided that the contractor's procedure is equivalent to the above codes. The contractor shall be responsible for determining that automatic welder equipment operators are capable of producing quality welds.

3.16.4.2 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, or any other foreign matter. Welds shall transmit stress without permanent deformation or failure when the parts are subjected to proof and service loading. All welding shall conform to MIL-W-8611 and shall be done prior to painting.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:28Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

4.1.2 Disassembly inspection. Heaters failing a performance test shall be disassembled by the contractor in the presence of a Government representative. Each disassembled part shall be inspected in detail for compliance with this specification and reference drawings in regard to materials, dimensions and tolerances. Parts not complying with such requirements shall be rejected.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Initial production inspection (see 4.4).
(c) Quality conformance inspection (see 4.5).
(d) Inspection comparison (see 4.7).
(e) Inspection of packaging (see 4.8).

4.3 Preproduction inspection.

4.3.1 Examination. The heater shall be examined as specified in 4.6.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. The heater shall be tested as specified in 4.6.2 through 4.6.2.5. Failure of any test shall be cause for rejection.

4.4 Initial production inspection. When specified (see 3.2.2), initial production heaters will be selected at random by the Government from the first 5 heaters being produced from production tooling and will

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:28Z
Check the source to verify that this is the currentversion before use.

be examined as specified in 4.6.1 and tested as specified in 4.6.2 through 4.6.2.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Acceptance of an initial production heater shall not exclude the remaining heaters from the quality conformance inspection and acceptance provisions specified in Section 4.

4.4.1 Inspection failure. Failure of an initial production heater to meet any requirement specified herein during and as a result of the examinations specified in 4.6.1 or the tests specified in 4.6.2 through 4.6.2.2 shall be cause for rejection of the initial production heater and shall be cause for refusal by the Government to continue acceptance of production heaters until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on heaters previously accepted and produced under the contract. Any deficiencies found as a result of the initial production examinations and tests will be considered prima facie evidence that all heaters accepted prior to the completion of initial production testing are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.5 Quality conformance inspection.

4.5.1 Sampling. Sampling for examination and tests shall be in accordance with MIL-STD-105, Inspection Level S-3.

4.5.2 Examination. Samples selected in accordance with 4.5.1 shall be examined as specified in 4.6.1. AQL shall be 2.5 percent defective for major defects and 4.0 percent defective for minor defects.

4.5.3 Tests. Samples selected in accordance with 4.5.1 shall be tested as specified in 4.6.2.6. AQL shall be 2.5 percent defective.

4.6 Inspection procedure.

4.6.1 Examination. The heater shall be examined as specified herein for the characteristics listed in Table I:

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:28Z
Check the source to verify that this is the current version before use.

TABLE I - EXAMINATION SCHEDULE

NUMBER	CHARACTERISTIC	REQUIREMENT PARAGRAPH
MAJOR		
101	Dimensions that affect form, fit or function.	3.1
102	Weight of heater not as specified.	3.1
103	Material not as specified.	3.3
104	Installation of wiring not as specified.	3.8
105	Electrical circuitry not protected from the effects of moisture and fungus growth.	3.10
106	Instruction plates missing or not as specified.	3.12
107	Schematic and wiring diagram plates missing or not as specified.	3.12.1
108	Metal fabrication not as specified.	3.16.1
109	Bolted connections not as specified.	3.16.2
110	Riveted connections not as specified.	3.16.3
111.	Welders not certified as specified.	3.16.4.1
112	Welding not as specified.	3.16.4.2
MINOR		
201	Identification or instruction markings missing or not as specified.	3.11
202	Identification plates missing or not as specified.	3.11.1
203	Treatment and painting not as specified.	3.13
204	Stenciling missing or not as specified.	3.14
205	Technical publications missing or not as specified.	3.15

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:28Z
Check the source to verify that this is the current version before use.

4.6.2 Tests. Unless otherwise specified herein, tests shall be conducted at prevailing room ambient temperature, utilizing 60 Hertz power.

4.6.2.1 Performance. Connect the heater to a 115 volt, single phase, 60 Hertz, ac power supply. With the control switch in the "OFF" position determine if heating elements and the fan motor are de-energized. Place the control switch in the "FAN" position and determine if the fan motor is energized and that the heating element is de-energized. Place the control switch in the "HEAT" position with the thermostat adjusted 2°F or more above ambient temperature and determine if the heating element and the fan motor are energized. Place the control switch in the "HEAT" position with the thermostat adjusted 2°F or more below ambient temperature, and determine if the fan motor is energized and the heating element is de-energized. Nonconformance to 3.7 shall constitute failure of this test.

4.6.2.2 Capacity. With the heater connected to the power supply specified in 4.6.2.1, operate the heater for 1 hour. At the end of 1 hour of operation measure the watts input to the heater. Nonconformance to 3.4 shall constitute failure of this test.

4.6.2.3 Environmental.

4.6.2.3.1 High temperature. Subject the heater to a temperature of plus 155° F for a period of 8 hours. At the conclusion of the exposure period, reduce the chamber temperature to plus 110° F and examine the heater for deterioration, corrosion, or damage. After completion of the examination and while maintaining the chamber temperature at plus 110° F soak the heater for a period of 1 hour. After completion of the soaking period, and while at 110° F operate the heater with the control switch in the "FAN" position for not less than 1 hour. Turn the control switch to the "OFF" position for 1 minute, then restart and operate the heater with the control switch in the "FAN" position for a period of not less than 15 minutes. Repeat this 15 minute cycle two more times. Nonconformance to 3.5.1 and 3.5.2 shall constitute failure of this test.

4.6.2.3.2 Low temperature. Subject the heater to a temperature of minus 50° F for a continuous period of 72 hours. While maintaining the minus 50° F ambient temperature, start the heater in the heating cycle and operate the heater for not less than 1 hour. Nonconformance to 3.5.1 and 3.5.2 shall constitute failure of this test.

4.6.2.3.3 Humidity. Conduct the humidity test as specified in MIL-STD-810, Method 507, Procedure I, except that the maximum temperature shall be 155° F. The heater shall not be operated during exposure. Nonconformance to 3.5.3 shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:28Z
Check the source to verify that this is the current version before use.

4.6.2.4 Reliability. Two heaters with all components shall be operated as specified in 4.6.2.4.2 until a total of 4000 hours actual heating time has been accumulated. After the completion of 4000 hours accumulated heating time, the heaters shall be tested as specified in 4.6.2.2. Nonconformance to 3.6, 3.7, and 3.4 shall constitute failure of this test.

4.6.2.4.1 Records. The power input characteristics, volts, amperes and watts, shall be recorded at the beginning of the tests and every 60 plus or minus 10 hours thereafter.

4.6.2.4.2 Procedure. This test shall be conducted at any prevailing ambient temperature. The heater shall be set up on an automatic test stand designed to operate the heater at normal capacity under a cyclic operation of 45 minutes on and 15 minutes off. If at any time the data specified in 4.6.2.4.1 varies by more than 10 percent from that obtained at the beginning of the test, the applicable heater components shall be given a detailed inspection to determine the cause of the variations. The control switch shall be tested as specified in 4.6.2.1 every 500 hours.

4.6.2.5 Electromagnetic interference. The preproduction model shall be tested to determine conformance with 3.8. The contractor shall furnish the contracting officer a plan of tests and a report of tests as required by MIL-STD-461. Disapproval of the plan or the report shall constitute failure of this test.

4.6.2.6 Individual performance. Operate the heater in any ambient temperature between 50° F and 80° F for not less than 30 minutes, using 60 Hertz power. During this time, test the selector switch as specified in 4.6.2.1. Nonconformance to 3.7 shall constitute failure of this test.

4.7 Inspection comparison. When an initial production inspection is specified, the Government may select heaters at any time during the contract production period and subject these heaters to the examination specified in 4.6.1 and the tests specified in 4.6.2 through 4.6.2.2 to determine that the quality of the selected heater is equal to the quality standards established during initial production inspection. The inspection will be performed by the Government at a site selected by the Government. Heaters will be selected at random from those which have been accepted by the Government and will not include the previously inspected preproduction models and initial production heaters.

4.7.1 Inspection failure. Failure of any heater when inspected as specified in 4.7 may be considered cause for refusal by the Government to continue acceptance of heaters until objective evidence furnished by the

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:28Z
Check the source to verify that this is the current version before use.

contractor reveals that corrective action has been taken to eliminate the condition which caused the rejection.

4.8 Inspection of packaging.

4.8.1 Quality conformance inspection of pack.

4.8.1.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.8.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.8.1.3 Examination. Samples selected in accordance with 4.8.1.2 shall be examined for the characteristics listed in Table II. AQL shall be 2.5 percent defective for major defects and 4.5 percent defective for minor defects.

TABLE II - EXAMINATION SCHEDULE-PACKAGING

NUMBER	CHARACTERISTIC	REQUIREMENT PARAGRAPH
MAJOR		
113	Preservation not Level A, Level B, or Commercial as specified (see 6.2).	5.1
114	Each complete heater not preserved for Level A as specified.	5.1.1
115	Each complete heater not preserved for Level B as specified.	5.1.2
116	Each complete heater not preserved for Commercial as specified.	5.1.3
117	Packing not Level A, Level B or Commercial as specified (see 6.2).	5.2
118	Heaters not packed for Level A as specified.	5.2.1
119	Heaters not packed for Level B as specified.	5.2.2
120	Heaters not packed for Commercial as specified.	5.2.3
MINOR		
206	Marking for Military packaging not as specified.	5.3.1
207	Marking for Commercial packaging not as specified.	5.3.2

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:28Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 Preservation. Preservation shall be Level A, Level B or Commercial as specified (see 6.2).

5.1.1 Level A. Each complete heater in the vendor's carton shall be preserved in accordance with MIL-P-116, Method IC-1 and shall then be placed in a close-fitting box conforming to PPP-B-636, W5c, style optional. Box closure shall be in accordance with the appendix to the box specification, Method V.

5.1.2 Level B. Each complete heater shall be preserved in accordance with MIL-P-116, Method III, using a close-fitting box conforming to PPP-B-636, W5c, style optional. Box closure shall be in accordance with the appendix to the box specification, Method V.

5.1.3 Commercial. Each complete heater shall be preserved in accordance with MIL-STD-1188.

5.2 Packing. Packing shall be Level A, Level B or Commercial as specified (see 6.2).

5.2.1 Level A. Heaters, preserved as specified in 5.1, shall be packed in close-fitting boxes conforming to PPP-B-601, Overseas Type, style optional. Strapping shall conform to QQ-S-781, Class 1, Type I or IV, size as applicable. Unless otherwise specified (see 6.2), strapping shall be Finish B. When specified (see 6.2), strapping shall be Finish A.

5.2.2 Level B. Packing shall be as specified in 5.2.1 for Level A, except that boxes shall be Domestic Type and strapping shall be Finish A.

5.2.3 Commercial. Heaters, preserved as specified in 5.1, shall be packed in accordance with MIL-STD-1188.

5.3 Marking.

5.3.1 Military packaging. Marking shall be in accordance with MIL-STD-129.

5.3.2 Commercial packaging. Marking shall be in accordance with MIL-STD-1188.

6. NOTES

6.1 Intended use. Space heaters covered by this specification are intended for heating offices, work shops, and other areas.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:28Z
Check the source to verify that this is the current version before use.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Time frame required for submission of preproduction models (see 3.2.1).
(c) When initial production inspection is required and number of heaters to be furnished, when applicable (see 3.2.2).
(d) Color required (see 3.13).
(e) Technical publications required (see 3.15).
(f) Degree of preservation and degree of packing required (see 5.1 and 5.2).
(g) When Finish A strapping is required (see 5.2.1).

6.3 Preproduction models. Any changes or deviations of production heaters from the approved preproduction models during production will be subject to the approval of the contracting officer. Approval of the preproduction models will not relieve the contractor of his obligation to furnish heaters conforming to this specification.

6.4 Electromagnetic interference. Heaters covered by this specification have been designed to meet the electromagnetic compatibility requirements of MIL-E-55301, tactical support class.

6.5 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of the specification (see 3.3).

Custodian:
Army - ME

Review activities:
Army - ER
DLA - CS

User activity:
Army - CE

Preparing activity:
Army - ME

Project 4520-A248

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:28Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/ vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

MIL-H-52641A(ME) Heater, Electric, 1,500 Watts, 115 Volts, AC, with Fan

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:28Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314

U.S. MAIL

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Mobility Equipment Research
and Development Command
ATTN: DRDME-DS
Ft. Belvoir, VA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:28Z
Check the source to verify that this is the current version before use.