MILITARY SPECIFICATION

PRIMING ASSEMBLY DEMOLITION, M15 PARTS, LOADING, ASSEMBLY AND PACKING

1. SCOPE

1.1 This specification contains requirements not required by the drawings and covers quality assurance requirements for the fabrication, loading, assembling and packing for one type of Priming Assembly, Demolition, M15.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

QQ-S-781 —Strapping, Flat; Steel
PPP-B-566 —Boxes, Folding, Paperboard
PPP-B-601 —Boxes, Wood, Cleated Plywood
PPP-B-636 —Boxes, Fiber
PPP-B-676 —Boxes, Set-up, Paperboard

MILITARY

MIL-A-2550 —Ammunition and Special Weapons; General Specification for
MIL-I-45208 —Inspection Requirements, General Specification for
MIL-I-45607 —Inspection Equipment, Supply and Maintenance of
MIL-C-373 —Clipcord, Detonating, M1

STANDARDS

MILITARY

MIL-STD-105D—Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-109 —Quality Assurance Terms and Definitions.
MIL-STD-129 —Marking for Shipment and Storage
MIL-STD-1235 —Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

ORDNANCE CORPS

8861112—Priming Assembly, Demolition, M15.

PUBLICATIONS

ORDNANCE CORPS

IEL-8861112—Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings, publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

2.2 **Other publications.** The following documents forms a part of this specification to the extent specified herein. Unless otherwise indi-

FSC 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

cated, the issue in effect on date of invitation for bids or request for proposal shall apply.

CODE OF FEDERAL REGULATIONS

49 CFR 71–90—Interstate Commerce Commission Rules and Regulations for the Transportation of Explosives and other Dangerous Articles.

(The Interstate Commerce Commission Regulations are now a part of the Code of Federal Regulations (1949 Edition and revisions) available from the Superintendent of Documents, Government Printing, Washington 25, D.C.).

3. REQUIREMENTS

3.1 Material. The material and parts shall be in accordance with the applicable drawings and specifications.

3.2 The booster assembly shall comply with all the requirements specified on Drawing 8861119 and all drawings referenced thereon, and with all requirements specified in applicable specifications. The explosive charge shall have the minimum weight, when tested as specified in 4.3.1.

3.3 **Workmanship.** All parts and assemblies shall be fabricated and loaded in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, grease, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions. The supplier is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL–STD–109 in order to define terms used herein. The provisions of Specification MIL–A–2550 shall apply.

4.1.1 *Contractor quality assurance system.* The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL–I–45208.

4.1.2 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

(a) A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.

(b) Number of units of product inspected.

(c) Results obtained for all inspection performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

(e) Certificates of analysis on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

(f) Number of items in the lot.

(g) Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

in another agent of the certifying organization.

4.1.3 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL–I–45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Inspection provisions.

4.2.1 *Lot formation.* A lot shall consist of priming assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting safety, performance, or fit, as determined by the Government, shall not necessitate changing the lot interfix number. Each lot shall contain:

(a) Parts or parts assemblies of one lot interfix number from one manufacturer.
(b) Detonating fuse from not more than 2 lots from one manufacturer.
(c) RDX from not more than one lot interfix number from one manufacturer.
(d) PETN from not more than one lot interfix number from one manufacturer.

4.2.2 *Examination.* Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL–STD–105D except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL–STD–1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.25 percent for each major defect and an AQL of 0.40 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.2.4.

4.2.2.1 *Cup booster* (see dwg. 8861120 covering a detail of dwg. 8861119).

Categories	*Defects*	*Method of inspection*	*Code No. (see 6.2)*
Critical:	None defined.		
Major:	None defined.		
Minor:	AQL 2.5 percent		
201.	Dimension, min, length outside	Gage	01001
202.	Width, outside dimension, min.	Gage	01002
203.	Width, inside dimension, max.	Gage	01003
204.	Wall thickness of bottom, min.	Gage	01004
205.	Evidence of poor workmanship (see 3.3)	Visual	01005

4.2.2.2 *Booster, assembly* (see dwg. 886119, covering a detail of dwg. 8861112).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined.		
Major:	AQL 0.25 percent		
101.	Length of void space, min. after loading	Gage	02001
Minor:	AQL 1.5 percent		
201.	Width, outside diameter after loading	Gage	02002

Source: https://assist.dla.mil -- Downloaded: 202640-23T00:05Z
Check the source to verify that this is the current version before use.

202.	Cut, puncture or tear in cup	Visual	02003
203.	Marking omitted, misleading, or improper	Visual	02004
204.	Evidence of poor workmanship (see 3.3)	Visual	02005

4.2.2.3 *Priming assembly, demolition, M15* (see dwg. 8861112).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Detonating fuse improperly assembled	Visual	03001
102.	Adhesive rubber improperly applied or missing	Visual	03002
103.	Fuse not bottoming on charge	Visual-Manual	03003
104.	Crimp missing or defective	Visual-Manual	03004
Minor:	AQL 2.5 percent		
201.	Assembled length, max.	Gage	03006
202.	Adapter missing	Visual	03007
203.	Adapter improperly assembled	Visual	03008
204.	Booster missing	Visual	03009
205.	Detonating cord clip missing	Visual	03009
206.	Detonating cord clip improperly assembled	Visual	03010
207.	Evidence of poor workmanship (see 3.3)	Visual	03011

4.2.3 *Testing.*

4.2.3.1 *Weight* (see dwg. 8861119), *Major defect, Code No. 02006.* The minimum weight of the booster charge (see 3.2) shall be determined for each lot of booster assemblies, at the time of loading. A sample of 50 booster cups (empty) shall be selected at random from each of said lots, before loading and marked for identification and tested as specified in 4.3.1 using equipment in accordance with 4.2.4. If one or more samples fail to comply with the specified requirements, the lot shall be rejected.

4.2.4 *Inspection Equipment.* Index of Inspection Equipment Number IEL–8861112 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.2.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement of parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and wherever inspection equipment drawings are needed.

4.2.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL–I–45607.

4.2.4.3 *Government use of contractor's inspection and test equipment.* The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of it's accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

4.3 **Test methods and procedures.**

4.3.1 *Determination of weight of the booster charge.* The weight shall be determined as follows: weigh each of the marked empty booster cup samples to the nearest 0.1 miligram. Record and identify weight and return sample at random to the regular pro-

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

duction lot. After regular production loading of booster cup, in accordance with the requirements of applicable drawings and specifications, select marked, loaded booster assembly samples and weigh to the nearest 0.1 miligram and record. Calculate the weight of booster charge as follows:

Weight = A subtracted from B.
Where: A = Weight of empty booster cup.
B = Weight of loaded booster assembly.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 *Packaging for shipment.* Each shipping container shall be packed in a manner which will insure arrival at destination in satisfactory condition. The priming assemblies shall be wrapped and cushioned to the extent necessary to provide protection from hazards of contamination and physical damage encountered in handling and storage. In no event, shall the priming assembly be coiled to form a kink in the detonating fuse or to form a coil less than a 2 inch radius. The shipping container shall be in accordance with the rules and regulations of the code of Federal Regulations Title 19—Transportation; Interstate Commerce Commission; Explosive and other Dangerous Articles.

5.1.2 *Marking for shipment.* Each shipping container shall be marked to insure safe handling, as required by the rules and regulations of the Code of Federal Regulations Title 49—Transportation; Chapter I—Interstate Commerce Commission, Parts 71 to 78, Explosive and Other Dangerous Articles. In addition, marking shall be as specified in Standard MIL–STD–129, except as may be modified by the contracting officer.

5.2 Data cards. Data card information shall be as specified in Specification MIL–A–2550.

6. NOTES

6.1 Ordering data. Procurement documents shall specify the following:

(a) Title, number and date of this specification.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of 6.3.1 through 6.3.7.

6.3.1 *Inspection Equipment Lists.* Inspection Equipment Lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "contractor design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection Equipment List codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5, and 6.3.6 will be designated in the Inspection Equipment List by the following codes:

CDOF	—Contractor's design responsibility on Ordnance format; ORDM–608–12.
CDCF	—Contractor's design responsibility on contractor format.
OD	—Ordnance design.
ODMU	—Ordnance design, mandatory for use.
CE	—Commercial equipment.
SCD	—Specification Control Drawing.

6.3.3 *Ordnance designs.* Ordnance designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

equipment. The contractor need provide no design when an Ordnance design is listed for an item of inspection equipment. Ordnance designs fall into two basic classifications: mandatory and non-mandatory. When an Inspection Equipment List references mandatory Ordnance designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawings.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic, or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication of procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial inspection equipment but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDOF shall comply with the format and requirements of ORDM 608–12, and, in addition, contain the detail and information specified above.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

Custodian:

Army—MU

Preparing activity:

Army—MU

Project No. 1375–A725

Source: https://assist.dla.mil -- Downloaded: 202610-23T00:05Z
Check the source to verify that this is the currentversion before use.