MIL-B-37295A
17 August 1978
SUPERSEDING
MIL-B-37295
15 August 1975

MILITARY SPECIFICATION

BATH, WATER, DENTAL IMPRESSION MATERIAL, LOW TEMPERATURE

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a low temperature, electrically heated, thermostatically controlled water bath suitable for tempering dental materials.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bid or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

PPP-B-636 - Boxes, Shipping, Fiberboard.

MILITARY

MIL-M-7298 - Manual, Technical, Commercial Equipment.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Defense Personnel Support Center, Directorate of Medical Materiel, DPSC-ATT, 2800 South 20th Street, Philadelphia, PA 19101, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 6520

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

STANDARDS

FEDERAL

FED-STD-66 - Steel, Chemical Composition and Hardenability.
FED-STD-151 - Metals, Test Methods.

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129 - Marking for Shipment and Storage.

DRAWING

DEFENSE PERSONNEL SUPPORT CENTER (DPSC)

24376 Bath, Water, Dental

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bid or request for proposal shall apply.

UNDERWRITERS' LABORATORIES, INC. (UL)

Underwriters' Laboratories, Inc. Standards

(Application for copies should be addressed to the Underwriter's Laboratories, Inc., 207 East Ohio Street, Chicago, IL 60611, 333 Pfingsten Road, Northbrook, IL 60062, 1285 Walt Whitman Road, Melville, LI, NY 11746, 1655 Scott Blvd., Santa Clara, CA 95050.)

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

C73.11 - Plugs and Receptacles - General Purpose, 125 Volts, 15 Amperes, 2 Pole, 3 Wire, Grounding Type.

(Application for copies should be addressed to the American National Standards Institute, 1430 Broadway, New York, NY 10018.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Fire and casualty hazards.

3.1.1 Prior to delivery, the contractor shall submit proof to the contracting agency that the equipment he will supply under this specification conforms to the applicable requirements of Underwriters' Laboratories, Inc. (UL) Standards. The label or listing of the UL may be accepted as evidence that the equipment conforms to this requirement.

3.1.2 In lieu of the label or listing, the contractor may submit independent proof satisfactory to the contracting agency, prior to delivery, that his equipment conforms to UL Standards.

3.1.3 Compliance with UL requirements regarding fire and casualty hazards does not absolve the contractor from complete compliance with the requirements of this specification in order to secure the acceptance of this commodity.

3.2 Materials. Materials shall conform to the applicable requirements specified herein. Materials not specifically designated shall be of high commercial quality throughout and shall be entirely suitable for the intended purpose.

3.3 Design and construction. The water bath shall be a low temperature water bath and shall be capable of heating water to a thermostatically controlled temperature ranging from 90 to 160 degrees Fahrenheit (^{o}F). The configuration and fit of all components shall eliminate any cracks and crevices in which materials might collect, and the bath shall be readily cleanable by conventional means. The water bath shall be suitable for operation on 115 volt, 60 hertz alternating current. The water bath shall be in compliance with Defense Personnel Support Center (DPSC) Drawing No. 24376.

3.3.1 Cabinet. The cabinet shall be a spot welded assembly of a frame stamping, a top stamping, and a ground clip, together with the necessary angles and weld nuts. The frame and top stampings shall be fabricated of no. 22 (.031 inch) U.S. Standard Gauge 18-8 stainless steel sheets. The exterior of the cabinet shall be finished in a no. 4 or brush finish.

3.3.2 Heating element. The strip heater shall be attached in the well of the cabinet with screws and shall be spatially suspended by spacers. The strip heater shall be rated at 211 watts plus or minus 10 percent at 115 volt, 60 hertz alternating current. The heater shall consist of nickel chromium alloy wire, imbedded in compressed refractory material and enclosed in a chrome steel housing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

3.3.3 Main switch. The on-off switch shall be a four position, double pole, single throw, rotary switch with a 15 ampere, 125 volt alternating current rating and shall serve as a total disconnecting switch. An on-off switch knob shall be keyed to the switch and imprinted "ON-OFF-ON-OFF" at the four reciprocating positions of the switch.

3.3.4 Thermostat. The thermostat shall be of the strut-type construction and shall be enclosed in a stainless steel case. The thermoswitch shall be mounted on the wall of the cabinet well and the adjusting stem shall protrude through an elongated hole in the front panel of the cabinet. The thermoswitch shall have a 10 ampere, 155 volt AC rating.

3.3.5 Dial. The dial may serve a multiple function as a temperature reference and as an identification nameplate (see 3.7). The dial shall be placed over the thermoswitch stem and shall be mounted on the front panel of the cabinet. The temperature numbers shall be printed at intervals of 20°F or less starting at 100°F or less and ending at 160°F or more. A thermoswitch knob shall be attached to the thermoswitch stem and shall be rotatably adjustable to the temperature selections.

3.3.6 Pilot lights. The two pilot lamps shall be of the neon type with a nylon body and a red plastic lens. One pilot lamp shall indicate only when the thermoswitch contacts are closed and activating the strip heater. The other pilot lamp shall indicate continuously when the on-off switch is turned to "ON".

3.3.7 Bottom panel. The bottom panel shall be fabricated of no. 16 (.050 inch) B&S Gauge aluminum sheet. The bottom panel shall be securely attached to the cabinet. Each corner of the bottom panel shall have a securely attached leg with a polyethylene cap to properly contact the surface on which it is resting without wobble or other imbalance.

3.3.8 Thermal protection. A thermal cut-off device shall be provided as a built-in safety factor that shall effectively provide a current interruption in the event of a thermoswitch malfunction. The device shall be mounted to the iside of the bottom panel below the strip heater. The device shall respond by opening the electrical circuit at a temperature of 200-220°F at its position inside the bottom panel (see 3.4.4).

3.3.9 Electrical cord. The cord set shall be a 3-wire, no. 16 or 18 gauge, type HSJ or HSJO, rubber jacketed heater cord, no less than 6 feet in usable length. A 3-prong vinyl plug shall be attached to one end and shall be suitable for use with receptacles specified in American National Standards Institute (ANSI) Standard C73.11. The opposite end of the cord shall enter the underside of the unit through a nylon strain relief. The cord shall be suitably slit back and stripped for attachment of terminals for connection to the on-off switch and to the ground clip.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

3.3.10 Basin. The rectangular basin shall be drawn from one piece of No. 22 (.031 inch) U.S. Standard Gauge AISI Type 304 stainless steel of FED-STD-66. The basin shall be furnished with a rolled bead on the top edge to provide a finger grip for removal. The basin shall contain a single embossed rib on its bottom for reinforcing and an embossed water level line on one side, 9/16 ± 1/16 inch from the top. The interior shall be satin finished and the exterior shall be finished by either electro-polish, bead blast, or any other method which shall impart a clean appearance not necesssarily devoid of draw marks. The basin shall be placed into the well of the cabinet and shall rest on the strip heater and basin support attached to the bottom of the well. The basin shall be lightly forced forward and into mechanical contact with the thermoswitch by two pair of slots at the rearward part of the well. When the material between the slots is deformed, the spring action shall exert and maintain sufficient force to hold the basin against the thermoswitch.

3.3.11 Thermometer. The thermometer shall be 6 ± 1/2 inches long and 1/4 ± 1/32 inch in diameter. The thermometer shall be graduated from 0 to 220°F, engraved in 2° divisions and numbered every 20 degrees. A rubber washer shall be placed over the thermometer to abut with the button top and a rubber tube shall be placed protectively over the mercury bulb. The thermometer shall be suspended in the loop of the thermometer holder which shall be rotatably adjustable in the attached 18-8 stainless steel holder support. The positioning of the thermometer in the holder shall allow for adequate immersion of the bulb in the properly filled basin.

3.3.12 Lifting platform. The lifting platform shall be fabricated of wire and shall be formed and twisted to accept an open end cloth bag cover. Two cloth covers shall be furnished with each water bath.

3.4 Performance.

3.4.1 Dielectric strength. The water bath shall be capable of withstanding, without failure, the dielectric test specified in 4.5.2.

3.4.2 Temperature control. The thermoswitch knob shall be adjustable to compensate for differences between the dial and thermometer readings. The thermostat shall maintain the stabilized temperature of the water bath within plus or minus 3°F, when tested to as specified in 4.5.3.

3.4.3 Temperature of components and table top. The maximum temperature of the components and the table top shall be as specified in table I, when tested as specified in 4.5.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

TABLE I. Maximm temperature of components and table top.

Location	Maximum Temperature (Degrees Fahrenheit)
Table (below strip heater)	100
Bottom panel (center)	180
Front of Cabinet (center)	180
Top of Cabinet (at Basin)	180
Side of Cabinet (at wall)	180
Rear of Cabinet (at wall)	180
Thermoswitch Knob	138
Pilot Lamp Wires	200
Wires at Strip Heater	300
On-Off Switch	200
Cord Set (inside at Strain Relief)	194

3.4.4 Thermal protection. The thermal cut-off shall interrupt the electrical circuit at 210 ± 10°F, when tested as specified in 4.5.6.

3.5 Operational test. The water bath shall operate satisfactorily when tested as specified in 4.5.4.

3.6 Service data. The contractor shall furnish, with each unit, two copies each of a technical manual which contains complete instructions for installation, operation, and maintenance and lists of component parts. The manual shall comply with the requirements of MIL-M-7298. As soon as practicable after award of the contract or purchase order, the contractor shall furnish to the Contracting Officer, two preliminary copies of his proposed technical manual for review and comment by the Directorate of Medical Materiel, Defense Personnel Support Center. The preliminary manuals shall be submitted sufficiently early to permit adequate review by the Directorate of Medical Materiel, Defense Personnel Support Center (based on a maximum period of 30 days for such review) and to allow incorporation by the contractor of any required revisions and corrections in the final manual without delaying delivery under the contract or purchase order. In addition, the Contractor shall furnish 15 copies of the approved technical manual to the Contracting Officer for distribution. Should the supplier have furnished acceptable manuals for the identical item within two years preceding the date of the contract and propose to furnish manuals identical with those previously accepted, then the requirements for review of drafts and submission of 15 additional copies may be waived upon request to the Contracting Officer. Waiver of submission of drafts and submission of 15 additional copies shall be at the option of the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

3.7 Identification marking. Each water bath shall have a corrosion-resisting metal or pressure sensitive tape nameplate permanently affixed thereto. The plate shall bear the model or style designation, voltage, watts, frequency (optional), and the name or registered trademark of the manufacturer. The markings on the plate shall be permanent and legible.

3.8 Workmanship. Workmanship shall be first class throughout. All exposed surfaces shall be smooth and free of sharp edges. Water baths shall be free from defects which detract from their appearance or impair their serviceability. Welds shall be clean and free from cracks and other imperfections. Screws shall be properly formed and tightened.

3.9 Drawings. The drawings forming a part of this specification are specification control drawings. The supplier shall be responsible for preparing his own shop drawings. Where tolerances prescribed could cumulatively result in improper design, the supplier shall provide a product with dimensions within the tolerances prescribed on the drawing to insure proper design, function, fit, assembly, and operation of the item. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Records. Records of examinations and tests performed by or for the contractor shall be maintained by the contractor and made available to the Government, upon the Government's request, at any time, or from time to time, during the performance of the contract and for a period of 3 years after delivery of the supplies to which such records relate.

4.1.2 Inspection. Inspection, as used in this specification, is defined as both examination (such as visual and auditory investigation without the use of special laboratory appliances or procedures) and testing (determination by technical means of physical and chemical properties) of the item.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

4.1.3 Certificates of quality. Certificates of quality, supplied by the manufacturer of the steel and packaging materials, may be furnished in lieu of actual performance of such testing by the contractor, provided lot identity has been maintained and can be demonstrated to the Government. The certificate shall include the name of the contractor, the contract number, the name of the manufacturer or supplier, the NSN, the Item Identification, the name of the component or material, the lot number, the lot size, the sample size, the date of testing, the test method, individual test results, and the specification requirements.

4.2 Classification of inspection. The inspection of the water bath shall be classified as follows:

a. First article inspection.
b. Quality conformance inspection.

4.3 First article inspection. When a first article is specified in the procurement document, first article inspection shall consist of all examinations specified in 4.4.2 and all testing specified in 4.5, and shall apply to the first article sample only (see 6.1).

4.4 Quality conformance inspection. Quality conformance inspection shall consist of all examinations specified in 4.4.2, and the testing specified in 4.5.1 through 4.5.4, and shall apply to those samples selected in accordance with 4.4.1 and 4.4.3. Quality conformance inspection shall be performed by the supplier in accordance with 4.1.

4.4.1 Sampling for examination. Sampling for examination shall be conducted in accordance with MIL-STD-105. The inspection levels and acceptable quality levels (AQL's) shall be as indicated in table II. Unit of product for examination purposes shall be one complete water bath.

TABLE II. Sampling and acceptance criteria for examination.

Type defect	Inspection level	AQL (percent defective)
For visual examination		
Major	II	1.0
Minor	II	2.5
For dimensional examination	S-2	2.5

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

4.4.2 Examination. The water bath shall be examined to determine compliance with all requirements contained in the specification, and shall be examined for visual defects, including, but not limited to, those listed in table III.

TABLE III. Classification of defects.

Categories	Defects
Major	
101	Any component missing or damaged.
102	Design and construction not as specified.
103	Gauge of metals not as specified.
104	Welds not clean and free from cracks or other imperfections.
105	Exposed surfaces not smooth and free of sharp edges.
Minor	
201	Finish not as specified.
202	Screws not fully tightened.
203	Identification marking not as specified.

4.4.2.1 Dimensional examination. The water bath shall be examined for defects in dimensions. Any dimension not within the tolerance specified shall be classified as a defect.

4.4.2.2 Examination for preparation for delivery. An examination shall be made to determine whether the packaging, packing, and marking comply with the requirements of Section 5. Defects shall be scored as specified in table IV. Sampling shall be in accordance with MIL-STD-105. The sample unit shall be one container fully prepared for delivery. The lot shall be the number of containers offered for inspection at one time. The inspection level shall be S-2 and the acceptable quality level shall be 4.0 defects per hundred units.

TABLE IV. Examination for preparation for delivery.

Examination	Defect
Containers	Not as specified.
Quantity	Quantity in interior packages and shipping containers not as specified.
Packaging & Packing Materials	Any component missing or damaged.
Workmanship	Inadequate application of components, such as incomplete closure of container flaps, tape improperly applied, or containers distorted.
Markings	Omitted, incorrect, illegible, improper location, sequence, or method of application.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

4.4.3 Sampling for testing. Sampling for testing shall be in accordance with MIL-STD-105 and table V, except that the acceptance number shall be zero for all sample sizes. The unit of product shall be one complete water bath for tests specified in table V.

TABLE V. Sampling and acceptance criteria for testing.

Characteristic	Requirement	Test procedure	Inspection level
Dielectric strength	3.4.1	4.5.2	100%
Temperature control	3.4.2	4.5.3	S-2
Operational test	3.5	4.5.4	100%

4.4.4 Sampling for raw material testing. In the absence of certificates of quality, sufficient amount of each lot of metal used in the construction of the stainless steel basin of the water bath shall be selected for chemical analysis as specified in 4.5.1.

4.4.5 Sample unit usage. Where feasible, the same sample unit shall be used for the determination of two or more test characteristics.

4.5 Tests. Tests shall be conducted to determine compliance with specification requirements.

4.5.1 Chemical analysis. In the absence of certificates of quality for the raw material, chemical analysis shall be conducted in accordance with method 111 or method 112 of FED-STD-151. In case of dispute, method 111 shall be used for referee analysis.

4.5.2 Dielectric strength. The electrical components shall be tested after complete assembly and shall withstand, without failure, a dielectric test of twice the rated voltage plus 1,000 volts or a total of 1,250 volts applied for one minute. This test shall be made on each of the individual lines of the circuit, using the metal frame as the other leg or ground of the 1,250 volt test.

4.5.3 Temperature control. The basin shall be filled with water to the water level mark and the thermometer shall be placed in the holder to immerse the bulb of the thermometer in the water. The thermoswitch shall be adjusted progressively until 120°F is indicated on the thermometer and the water temperature has stabilized. The variation in temperature above and below the 120°F stabilized temperature observed on the thermometer shall be recorded.

4.5.4 Operational test. The water bath shall be given an operational test by turning the heater on with the thermostat set at 120°F and observing if all components, except thermal cut-off, are functioning properly.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

4.5.5 Temperature of components and table top. A right angle simulator shall be constructed of solid hardboard such as 1/2 inch plywood. The table portion shall measure no less than 34 inches square. The rear and side walls shall be equal to the table in width and no less than 30 inches in height. The assembled room simulator shall be painted non-reflecting black. An iron-constantan thermocouple shall be attached to metallic parts by brazing and to non-reflecting components by tape. The bath to be tested shall be placed in the corner of the room simulator at one inch from the vertical walls. The basin shall be filled with water to the water level line, the on-off switch shall be turned to "on", and the thermoswitch knob shall be rotated clockwise to the stop for maximum temperature condition. The voltage shall be regulated to 115-116 volts, 60 hertz alternating current, with an amperage of 1.6 to 2.0 and ambient temperature of 75 $\pm$ 3°F. The equilibrium temperatures shown by the thermocouple sensors at the locations enumerated in table I shall be observed and recorded after 90 minutes of operation.

4.5.6 Thermal protection. On completion of the test in 4.5.5, the thermoswitch shall be shunted out of the circuit. The unit shall continue to operate without thermostatic control and the water shall be permitted to evaporate completely. The unit shall be permitted to heat to the 200 to 220°F level measured at the thermal cut-off device. The temperature at which the electrical circuit is interrupted shall be observed and recorded.

5. PACKAGING

5.1 Packaging. Packaging shall be level A or C, as specified (see 6.1).

5.1.1 Level A.

5.1.1.1 Unit package. The accessories shall be wrapped in kraft paper or other suitable material and placed in the basin. The basin shall be wrapped in kraft or other suitable material and placed in the unit. The unit, along with the thermometer and instructions, shall be placed in a polyethylene bag and the bag closure secured with tape. The bag shall be packaged in a box conforming to PPP-B-636, class domestic. The unit shall be cushioned within the box with air caps or other suitable material. Closure of the box shall be as specified in the appendix of the box specification.

5.1.2 Level C. Units shall be packaged in standard commercial containers of the size and kind commonly used, which will afford the degree of protection required for shipment and use of the product for its intended purpose.

5.2 Packing. Packing shall be level A, B, or C, as specified (see 6.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

5.2.1 Level A. Twelve unit packages shall be packed in an exterior container designed for a type 2 load and constructed in accordance with PPP-B-636, type CF, class weather-resistant. Closure, waterproofing, and strapping shall be as specified in the appendix of the box specification.

5.2.2 Level B. Twelve unit packages shall be packed in an exterior container designed for a type 2 load and constructed in accordance with PPP-B-636, type CF, class domestic. Closure of the box shall conform to method I or II, as specified in the appendix of the box specification.

5.2.3 Level C. The subject commodity shall be packed in substantial commercial containers of the type, size, and kind commonly used for the purpose, so constructed as to insure acceptance and safe delivery by common or other carriers to point of delivery called for in the contract or purchase order.

5.3 Marking.

5.3.1 Unit package. Each unit package shall be marked as specified in MIL-STD-129. The contract or purchase order number and name of contractor shall also be shown.

5.3.2 Exterior container. Exterior containers shall be marked as specified in MIL-STD-129.

6. NOTES

6.1 Ordering data. Purchasers should select the preferred options permitted herein and include the following information in procurement documents:

a. Title, number, and date of this specification.
b. When a first article is required (see 4.3 and 6.2).
c. Selection of applicable levels of packaging and packing (see 5.1 and 5.2).

6.2 First article. When a first article is required, it shall be tested and approved under the appropriate provisions of the Defense Acquisition Regulations. The contract or purchase order specifies the quantity, procedure for delivery, and other specific instructions for inspection and approval of the first article.

6.3 This specification covers the following item appearing in the Federal Supply Catalog:

National Stock Number	Item Identification
6520-01-004-2658	BATH, WATER, DENTAL IMPRESSION MATERIAL, Thermostatically Controlled, 90° to 160°F, 115 volt, 60 Hz, AC

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

6.4 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness of the changes.

Custodians:
Army - MD
Navy - MS
Air Force - 03

Review activity:
DoD-MB

Preparing activity:
DLA-DM

Project No. 6520-1483

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/ vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE
MIL-B-37295A BATH, WATER, DENTAL IMPRESSION MATERIAL, LOW TEMPERATURE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A
☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?
   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:23Z
Check the source to verify that this is the current version before use.