MILITARY SPECIFICATION

CENTRAL OFFICE, TELEPHONE, MANUAL AN/TTC-7(#) (UNITS OF)

Paragraph 1.2 Correct the listed items to read as follows:

"(j) Cords.

(3) Cord CD-393( ).
(4) Cord CD-409( ).
(5) Cord CD-413( ).
(6) Cord CD-414( ).

(k) Dummy Plug, Telephone (Signal Plug)."

Paragraph 2.1 Under Drawings delete the following:

"SC-D-4309—Cord CD-413 ( ) and Cord CD-414( )."

Paragraph 2.1 Under Drawings add the following:

"SC-DL-339840—Power Distribution Panel SB-1032( )/TTC.
SC-DL-339963 —Lead, Test CX-6100 ( )/G(__ft__in).
SC-DL-339964 —Test Set, Telephone TA-1361( )/G.
SC-D-92995 —Cord Assembly CD-413( ).
SC-D-108692 —Cord CD-413( ) and Cord CD-414 ( )."
SM-D-143201 —Electrical Power Cable Assembly CX-3694( )/U.
SM-B-183266 —Sleeve, Key (Plug, Signal).
SM-B-183298 —Sleeve, Plug (Trouble Cap).
SM-C-339884 —Electrical Power Cable Assembly CX-4845( )/U.
SM-C-339953 —Electrical Power Cable Assembly CX-4762( )/U.
SM-C-339954 —Electrical Power Cable Assembly CX-3692( )/U.
SM-B-339971 —Dummy Plug, Telephone (Signal Plug).

Paragraph 3.2a. Replace with the following:

"3.2 Construction.

(a) Physical construction of the following units on contract shall be constructed in accordance with the listed drawings:

SM-C-339954 —(1) Electrical Power Cable Assembly CX-3692( )/U
SM-D-143201 —(2) Electrical Power Cable Assembly CX-3694( )/U
SM-C-339953 —(3) Electrical Power Cable Assembly CX-4762( )/U
SM-C-339884 —(4) Electrical Power Cable Assembly CX-4845( )/U
SM-DL-339840—(5) Power Distribution Panel SB-1032( )/TTC
SC-DL-339964 —(6) Test Set, Telephone TS-1361 ( )/G
SC-DL-339963 —(7) Lead, Test CX-6100( )/G(ft-in)

FSC 5805

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:00Z
Check the source to verify that this is the current version before use.

SM–B–339971 —(8) Dummy Plug, Telephone (Signal Plug)
SM–B–183266 —(9) Sleeve, Key (Plug, Signal)
SM–B–183398 —(10) Sleeve, Plug (Trouble Cap)

Paragraph 3.3. Delete.

Paragraph 3.4. Replace with the following:

"3.4 Parts, materials, and processes; general. The parts, materials and processes shall be in accordance with this specification and the drawing requirements."

Paragraph 3.9.2.3b Table 1. Opposite "Operator's Telephone and Position and Grouping Circuit" delete "0.3db." Opposite "Relays RS and FS Normal (Magneto)" change "0.2db" to read "0.5db."

Paragraph 3.9.2.3.c(1), Change "6.0db" to read "6.5db."

Paragraph 3.9.2.3c(2), Change "6db" to read "6.5db."

Paragraph 3.9.2.4a, Replace with the following:

"3.9.2.4a Crosstalk. Crosstalk lose between voice frequency circuits shall be –50db minimum at 3500cps, –57db minimum at 1000cps and 60db or more at 300 cps when measured as specified in 4.5.4.4."

Paragraph 3.19 in line 3, change "are hor" to read "are not."

Paragraph 4.1, Replace with the following:

"4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements."

Paragraph 4.5.3.7. Following this paragraph add the following:

"4.5.3.8 *Recall and cord circuit test.*

(a) Insert the plug of one of the cords part way into the recall jack until the sleeve of the plug makes contact with the sleeve of the jack. The associated supervisory lamp shall light.

(b) Seat the plug firmly in the recall jack. The associated supervisory lamp shall be extinguished.

(c) Remove the plug from the recall jack. The associated supervisory lamp may or may not flash but should be extinguished when the plug is completely out of the jack. If the supervisory lamp does not go out, the equipment fails the test.

(d) Repeat this test for each of the calling and answering supervisory cords on the switchboard."

Paragraph 4.6.3

(a) In the first line change, "The major components, in their transit cases_____" to read "The major units, except SB–1032/TTC and SB–249/TTC, in their transit cases_____."

(b) At the end of this paragraph add the following:

"The SB–249/TTC and SB–1032/TTC in their transit cases shall be subjected to this test in the vertical position with their bases resting on the table of the package tester for a period of ½ hour."

Paragraph 6.7 Replace with the following:

6.7 Verification inspection. Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance

Source: https://assist.dla.mil -- Downloaded: 2026l0-18T03:00Z
Check the source to verify that this is the currentversion before use.

provisions established in this specification and the contract. The amount of varification inspection by the Government will be adjusted to make minimum utilization of the contractor's quality control system and the quality history of the product."

Notice: Delete.

Custodian:
Army—EL

Preparing activity:
Army—EL
Project No. 5805–A050

☆ U. S. GOVERNMENT PRINTING OFFICE: 1984—745967

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:00Z
Check the source to verify that this is the current version before use.

To detach this form, cut along this line

SPECIFICATION ANALYSIS SHEET

Form Approved Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

B RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES" IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 APR 63 1426 REPLACES NAVSHIPS FORM 4063, WHICH IS OBSOLETE

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:00Z
Check the source to verify that this is the current version before use.

FOLD

HEADQUARTERS
U. S. ARMY ELECTRONICS MATERIEL SUPPORT AGENCY
FORT MONMOUTH, NEW JERSEY 07703

OFFICIAL BUSINESS

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

Commanding Officer
U. S. Army Electronics Materiel Support Agency
Fort Monmouth, New Jersey 07703

FOLD

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:00Z
Check the source to verify that this is the current version before use.