MIL-M-14274A(EL)
22 January 1975
Superseding
MIL-V-14274(SigC)
23 March 1956

MILITARY SPECIFICATION
MULTIPLIER, ELECTRICAL INSTRUMENT TS-265( )/UP

This specification is approved for use by all departments and agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers Multiplier, Electrical Instrument, TS-265( )/UP, a portable, general purpose test equipment designed to step down high alternating current voltages by a known stepdown ratio of 10 to 1 or 100 to 1 to allow pulses to be observed on a oscilloscope.

2. APPLICABLE DOCUMENTS

2.1 Documents. The following documents of the issue in effect at date of invitation for bids, form a part of the specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

NN-P-71	Pallet, Material-Handling, Wood, Stringer Construction, 2 Way, And 4 Way (Partial)
QQ-S-781	Strapping, Steel, Flat And Seals
PPP-T-76	Tape, Pressure Sensitive Adhesive Paper, Water Resistant (for Carton Sealing)
PPP-T-97	Tape, Pressure-sensitive Adhesive, Filament Reinforced
PPP-F-320	Box, Corrugated, And Solid, Sheet Stock (Container Grade), And Cut Shapes
PPP-B-585	Box, Wood, Wirebound
PPP-B-601	Box, Wood, Cleated Plywood
PPP-B-621	Box, Wood, NailedAnd Lock Corner
PPP-B-636	Box, Shipping, Fiberboard

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-P-116	Preservation-packaging, Methods Of
MIL-P-11268	Parts, Materials, And Processes Used In Electronic Equipment
MIL-M-13231	Marking Of Electronic Items
MIL-F-14072	Finishes For Ground Signal Equipment
MIL-P-19644	Plastic Molding Material (Polystyrene Foam, Expanded Bead)
MIL-P-26514	Polystyrene Foam, Rigid Or Plastic, For Packaging

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures And Tables For Inspection By Attributes
MIL-STD-129	Marking For Shipment And Storage
MIL-STD-147	Palletized Unit Loads; 40 In x 48 In 4-Way Partial And 4-Way Pallets
MIL-STD-252	Wired Equipment Classification Of Visual And Mechanical Defects
MIL-STD-810	Environmental Test Methods

DRAWINGS

ELECTRONICS COMMAND

SC-DL-146384	Multiplier, Electrical Instrument TS-265( )/UP
SC-A-46439	List of Accessories for Package Tester

(Copies of specifications, standards and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity, or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Description. Multiplier, Electrical Instrument TS-265( )/UP is a portable, self-contained voltage divider including Connector Adapter UG-1017/U, Cord CG 107A, two test leads and Case CY-1388/U. This equipment is designed for dividing a.c. voltages in the range of 5 to 50 kilovolts.

3.2 First article samples. The contractor shall furnish three (3) complete first article samples for approval provided the invitation for bid and the contract require first article approval.

3.3 Construction. The equipment shall be constructed in accordance with SC-DL-146384 and the requirements specified herein.

3.4 Parts, materials and processes general. In addition to the requirements of this specification, the requirements of MIL-P-11268, including the selection of requirements therein, shall apply.

3.4.1 Finish, protective. The equipment shall be finished in accordance with MIL-F-14072 and the applicable drawings. This includes finish of hardware, such as screws, etc. and necessary touch up after mounting.

3.4.2 Marking. Marking shall conform to MIL-M-13231.

3.5 Serial numbers. Serial numbers are required.

3.6 Preconditioning

3.6.1 Bounce preconditioning. Each TS-265( )/UP produced including first article shall be subjected to the bounce preconditioning of 4.6.1. After bounce preconditioning, the equipment shall be inspected for loose or broken parts or controls. If a failure occurs, the loose or broken parts or control shall be repaired or replaced and the test repeated. Bounce preconditioning shall be performed prior to electrical preconditioning and Group A inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

3.6.2 Electrical preconditioning. Each TS-265( )/UP produced including first article shall be subjected to the electrical preconditioning of 4.6.2. Electrical preconditioning shall be performed after bounce preconditioning and prior to Group A inspection. The equipment shall meet the requirements of paragraph 3.7.4 after being subjected to the test of paragraph 4.6.2. If indicated in the contract or purchase order, a failed analysis report shall be submitted as required in the contract or purchase order.

3.7 Electrical

3.7.1 Continuity Test. Each equipment shall be subjected to the Continuity Test of 4.7.1. No evidence of open or shorted circuits shall occur.

3.7.2 Ratio Test. Each equipment shall be tested in accordance with the requirements of 4.7.2. The deviation of the output ratio voltage shall not exceed ±5 percent.

3.7.3 Voltage Breakdown Test. Each equipment shall be tested in accordance with the requirements of 4.7.3. There shall be no evidence of insulation breakdown or sparking as a result of this test.

3.7.4 Operational. When specified, the equipment shall be subjected to the tests and requirements of paragraph 3.7.2 and 4.7.2.

3.8 Service conditions. The equipment shall be constructed so that no fixed part shall become loose, cracked, flaked, pitted or blistered, no movable part or control shall be shifted in setting, position or adjustment, and no permanent degradation shall be caused in performance below that specified herein when subjected to the following conditions (see 4.8).

3.8.1 Temperature. The Multiplier shall be subjected to temperature extremes specified below.

3.8.1.1 Low temperature. The equipment shall meet the electrical requirements of 3.7.4 when subjected to the low temperature extreams of -4°F operating and -65°F storage. Testing shall be in accordance with 4.8.1.1 at times specified in 4.8.1.1.

3.8.1.2 High temperature. The equipment shall meet the electrical requirements of 3.7.4 when subjected to the high temperature extreams of 125°F operating and 160°F storage. Testing shall be in accordance with 4.8.1.2 at times specified in 4.8.1.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

3.8.2 Shock Bench Handling. The multiplier shall show no evidence of physical damage except minor surface abrasion and shall meet the requirements of 3.7.4 when tested in accordance with 4.8.2.

3.8.3 Humidity. The equipment shall exhibit no physical damage or electrical degradation while being subjected to the humidity test specified, and shall meet the requirements of 3.7.4 after being tested in accordance with 4.8.3.

3.8.4 Fungus. After the fungus test of 4.8.4, the equipment shall be visually examined, using a 10- power magnifier. The equipment shall show no more than six (6) minute unrelated spots, each no greater than 0.015 square inch in area, of sparse microbial growth (see 6.5) and sporulation (see 6.5) on or within each cubic foot, or fraction thereof, of equipment assembly volume. Isolated instances of partial tubular germination (see 6.5) shall not be included in this evaluation.

3.8.5 Vibration. The equipment shall show no evidence of breakage or loosening of parts and shall meet the requirements of 3.7.4 after being tested in accordance with 4.8.5.

3.9 Visual and mechanical. The multiplier shall meet the requirements of MIL-STD-252 as specified in 4.9.

3.10 Interchangeability. Like units, assemblies; subassemblies, and replaceable parts shall be physically and functionally interchangeable, without modification of such items or of the equipment. Individual items shall not be handpicked for fit or performance. Reliance shall not be placed on any unspecified dimensions, rating, characteristics, etc. Where selection of a component having special characteristics is required, such selection shall be made from qualified or standard parts where possible and the specific characteristics of the selected part shall be defined (see 4.10).

3.11 Workmanship. The multiplier shall be manufactured and assembled in accordance with the applicable portions of the following:

a. In MIL-P-11268

General requirements for plastic material and parts Wiring and cabling including:
Slack
Protection
Clearance
Connections, general
Grounding, general
Flux and cleaning agents for soldering
Process for soldering
Cleaning of equipment
General process for securing of parts
Mechanical operation of controls
Tropicalization of material
Shielding of wire and cable
Self tapping screws

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

b. In this specification

Marking
Finish
Interchangeability

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspection. Inspection shall be classified as follows

a. First article inspection (Does not include preparation for delivery) (see 4.3).

b. Inspection covered by subsidiary documents (see 4.4).

c. Quality conformance inspection.

(1) Quality conformance inspection of equipment before preparation for delivery (see 4.5).

(2) Quality conformance inspection of preparation for delivery (see 4.11).

4.3 First article. Unless otherwise specified in the contract or purchase order, the first article inspection shall be performed by the contractor.

4.3.1 First article units. The contractor shall furnish three (3) first article units of the complete Multimeter TS-265( )/UP.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

4.3.2 First article inspection. The first article inspection shall consist of the inspections specified in subsidiary documents covering the items listed in 4.4, preconditioning specified in 4.6, and the inspections specified for Group A, Group B, and Group C (see Tables I, II and III, respectively). The inspections shall be performed in the following order: 4.4, 4.6, Group A and Group B for all units; and designated units for specific subgroups within Group C in accordance with 4.5.3.1. After completion of Group C environmental tests, conforming units shall be reinspected and shall pass all Group A inspections.

4.3.3 First article data. The first article test plan and test report(s) shall be as required in the contract or purchase order.

4.4 Inspections covered by subsidiary documents. The following shall be inspected under the applicable subsidiary documents as part of the inspection required by this specification, and the inspection requirement specified in the contract or purchase order.

Item	Where required
Parts, materials, and processes-general	3.4
Finish, protective	3.4.1
Marking	3.4.2

4.5 Quality conformance inspection of equipment before preparation for delivery. The contractor shall perform the inspection specified in 4.4, 4.6 and 4.5.1 through 4.5.4. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements.

4.5.1 Group A inspection. Each unit on contract or purchase order shall be inspected for conformance to the inspections specified in Table I. Discrete lots shall be formed from units that pass this inspection. Factors of lot composition not defined herein, or in the contract or purchase order, shall be in accordance with MIL-STD-105. Each lot shall be subjected to sampling inspection, utilizing the procedures of MIL-STD-105, using the general inspection levels, and the AQL's indicated in Table I.

4.5.1.1 Order of inspection within Group A. Group A inspection shall be performed in any order which is satisfactory to the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

Table I. Group A inspection

Inspection	Req. Para.	Insp. Para.	AQL Major	AQL Minor
Visual and Mechanical	3.9	4.9	1 dphu *	4 dphu
Electrical				
Continuity	3.7.1	4.7.1	1 dphu for the group	
Ratio	3.7.2	4.7.2		**

* Deficiencies per hundred units.
** All electrical deficiencies are major.

4.5.2 Group B inspection. This inspection, including sampling, shall conform to Table II and to the Level S4 special procedures for small sample inspection of MIL-STD-105. Group B inspection shall be performed on inspection lots that have passed Group A inspection, and on samples selected from units that have been subjected to and meet the Group A inspection.

4.5.2.1 Order of inspection within Group B. Group B inspection shall be performed in any order which is satisfactory to the Government.

Table II. Group B inspection

Inspection	Req. Para.	Test Para.	AQL
Interchangeability	3.10	4.10	4 dphu *
Voltage breakdown test	3.7.3	4.7.3	2.5 dphu *

* Defects per hundred units.

4.5.3 Group C inspection. This inspection shall consist of the inspection specified in Table III and shall be performed on sample units that have been subjected to and met Group A and B inspection. Sample units shall be selected in accordance with 4.5.3.1.

4.5.3.1 Sampling for inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

4.5.3.1.1 Three (3) samples of the complete equipment shall be selected at random, one (1) sample for each Subgroup 1 through Subgroup 3 in Table III. The samples shall be selected at the start of the contract from the first quality conformance inspection lot. These samples shall constitute the Group C requirement for the first 100 units produced.

4.5.3.1.2 Thereafter, three (3) samples of the complete equipment shall be selected at random, one (1) sample for each Subgroup 1 and two (2) samples for each Subgroup 2 in Table III from every 500 units and fraction thereof produced.

4.5.3.2 Evaluation of samples submitted to individual Group C inspection. After samples referenced in 4.5.3.1 have been subjected to an individual Group C inspection test and prior to subjection to the next Group C test (unless otherwise specified in the individual test) the sample shall be subjected to and meet requirements and tests of 3.7.4.

4.5.3.3 Order of inspection within Group C. Group C inspection shall be performed in the order specified in 4.5.3.1.

4.5.3.4 Group C failures. Actions required relative to Group C failures shall be as specified in the contract or purchase order.

Table III. Group C inspection

Inspection	Sample Selection	Req. Para.	Test Para.
Subgroup 1	(1) for first 100		
Low Temperature	(1) for each 500 and fraction	3.8.1.1	4.8.1.1
High Temperature	produced thereafter	3.8.1.2	4.8.1.2
Humidity		3.8.3	4.8.3
Subgroup 2	(1) for first 100		
Vibration	(2) for each 500 and fraction	3.8.5	4.8.5
Shock, bench handling	produced thereafter	3.8.2	4.8.2
Subgroup 3			
Fungus	(1) for first 100	3.8.4	4.8.4

4.5.4 Reinspection of conforming Group B and C samples units. Unless otherwise specified, sample units which have been subjected to and passed both Group B and Group C inspection may be accepted on contract or order provided all damage is repaired and the sample units are subjected to and pass Group A inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

4.6 Preconditioning.

4.6.1 Bounce preconditioning. Each multiplier shall be placed in its normal operating position on the table of a package tester of suitable capacity as made by the L. A. B. Corporation, Skaneateles, New York, with accessories as per Model 1000-SC and SC-A-46439, or equal. The package tester, shafts in phase, shall have a speed such that it is just possible to insert a 1/32 inch thick strip of material under one corner or edge of the equipment under test to a distance of 3 inches as the equipment bounces. The equipment shall be subjected to this preconditioning for 1 minute and shall meet the requirements of 3.6.1.

4.6.2 Electrical preconditioning (Burn-in and debugging). Each multiplier shall be operated in accordance with the conditions of 3.6.2 by applying the 10 volt 2500 Hz. output of a square wave generator to the "RATIO 100:1" input jack, J103 for 12 hours at an ambient temperature of 77°F ± 5°F. Each multiplier shall then be operated by applying the 10 volt 2500 Hz output of a square wave generator to the "RATIO 10:1" input jack, J102 for 12 hours at an ambient temperature of 77°F ± 5°F. The equipment shall be subjected to this preconditioning and shall meet the requirements of 3.6.2.

4.7 Electrical requirements. Testing instruments shall be calibrated to an accuracy of at least five (5) times the accuracy of the equipment under test.

4.7.1 Continuity test. Electrical continuity of cables, wiring, and connections, including ground connections to chassis, shall be verified by a point to point test.

4.7.2 RATIO test.

a. Connect the output of the pulse generator to the RATIO 100:1 input jack J103; use the test lead (36 inch) and the ground lead that extends from the voltage divider.

b. Set the pulse generator frequency to approximately 2500 Hz.

c. Connect the vertical terminals of the oscilloscope across the output of the pulse generator.

d. Connect the output coaxial cable into the RATIO 100:1 coaxial connector J101.

e. Adjust the output of the square wave generator for 10 volt output; measure the output with the oscilloscope.

f. Adjust the oscilloscope controls for steady and sharp display of the square wave on the oscilloscope screen.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

g. Remove the power from the pulse generator and from the oscilloscope.

h. Disconnect the oscilloscope from the pulse generator and connect it to the output coaxial cable of the voltage divider.

i. Apply the power to both the pulse generator and the oscilloscope.

j. Set the oscilloscope controls to calibrate and measure a voltage of one one-hundredth of the voltage that was obtained in e. above (0.1 volts).

k. The vertical amplitude of the leading edge of the tilted square wave pattern shall measure 0.1 volt ±5 percent. See 3.7.2.

l. Repeat the procedures given in a. through i. above for the 10:1 voltage-dividing ratio section; use the RATIO 10:1 input jack J102 and the output RATIO 10:1 coaxial connector J100.

m. Set the oscilloscope controls as necessary to calibrate and measure 1-volt input.

n. The vertical amplitude of the leading edge of the tilted square wave pattern shall measure 1 volt ±5 percent. See 3.7.2.

4.7.3 Voltage breakdown.

a. Connect the ground lead of the voltage divider to the ground connection of the high-voltage supply.

b. Connect the test lead (18 inch) between the output of the high-voltage supply and the 100:1 input jack J103 of the voltage divider.

c. Turn on the high-voltage supply and gradually increase the output voltage to 50 kv as indicated on the meter scale of the high-voltage supply.

d. Maintain 50 kv across the input terminals for 1 minute.

e. Requirements of 3.7.3 shall be met.

4.8 Service conditions. (See 3.8).

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

4.8.1 Temperature test. The following tests shall be conducted with the test set in a temperature chamber in the order specified. Suitable provisions shall be made to pass the required electrical connections through the walls of the chamber. To check temperature stabilization, place a thermocouple in good thermal contact on the largest internal mass centrally located or in any other location deemed necessary by the Government inspector. Temperature stabilization is defined as being accomplished when the temperature of the equipment, verified by three thermocouple readings, does not change by more than 1°F in any one half hour period.

4.8.1.1 Low temperature. The equipment in its normal operating configuration shell be subjected to the low temperature test specified in Procedure I, Method 502 of MIL-STD-810, with temperature in Step 2 held for 4 hours and in Step 4 until temperature stabilization is reached. Inability of the equipment to meet the requirements of 3.8.1.1 shall constitute failure of this test.

4.8.1.2 High temperature. The equipment in its normal operating configuration shall be subjected to the high temperature test specified in Procedure I, Method 501 of MIL-STD-810, with temperature in Step 3 held for 4 hours. Inability of the equipment to meet the requirements of 3.8.1.2 shall constitute failure of this test.

4.8.2 Shock, bench-handling. The equipment shall be subjected to the shock, bench-handling test specified in Procedure V, Method 516 of MIL-STD-810. Inability of the equipment to meet the requirements of 3.8.2 shall constitute failure of this test.

4.8.3 Humidity. The equipment in the normal operating configuration shall be subjected to the humidity test specified in Procedure II, Method 507 of MIL-STD-810, with test measurements during the 24 to 28 hour period and last 5 hour period of each cycle in Step 6. Inability of the equipment to meet the reauirements of 3.8.3 shall constitute failure of 3.8.3 shall constitute failure of this test.

4.8.4 Fungus. The equipment shall be subjected to the fungus test specified in Method 508, Procedure I, of MIL-STD-810. There shall be abundant growth colonization (6.5) on 50 percent or more of the area of the control item after 14 and 28 days. No cleaning of the equipment is permitted for 72 hours prior to the fungus test. Handling prior to and during testing, shall be accomplished without contamination of the equipment. Inability of the equipment to meet the requirements of 3.8.4 shall constitute failure of this test.

4.8.5 Vibration. The equipment shall be subjected to the vibration test specified in Part 1, Procedure X1, Method 514 of MIL-STD-810. Inability of the multimeter to meet the requirements of 3 8.5 shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

4.9 Visual and mechanical. The equipment shall be examined for the defects listed in MIL-STD-252 and shall meet the requirements of 3.3 and 3.9.

4.10 Interchangeability. The dimensions listed below shall be measured to determine conformance to the physical interchangeability requirement of 3.10. When a listed dimension is not within specified or design limits, it shall be considered a major defect.

a. External and internal dimensions of case, cover and insertable assemblies, when such dimensions affect mating of parts.

b. Dimensions of cavities, when such dimensions affect insertion of items.

c. Location of hinges and fasteners on separable parts or assemblies which must mate, such as case, covers, and mountings.

d. Location and spacing of test terminals.

4.11 Quality conformance inspection of preparation for delivery. Preparation for delivery shall be inspected in accordance with MIL-P-116 to determine conformance to the requirements of Section 5.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C, as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Cleaning. Multiplier, Electrical Instrument TS-265( )/UP shall be cleaned in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying. Multiplier, Electrical Instrument TS-265( )/UP shall be dried in accordance with the applicable procedure of MIL-P-116.

5.1.1.3 Preservation application. None required.

5.1.1.4 Unit packaging. Unit packaging shall be in accordance with the methods prescribed in MIL-P-116 as specified herein

5.1.1.4.1 Technical literature. Each technical literature shall be packaged method IC-1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

5 1.1.4.2 Multiplier, Electrical Instrument TS-265( )/UP. Each multiplier shall be individually packaged method III as follows Place the test leads, cords and adapter in the spaces provided in the case and secure with fasteners provided. Close the cover of the case and secure the latches. Cushion the unit on all surfaces with cells or pads or both fabricated of fiberboard conforming to PPP-F-320, type CF, class weather-resistant, variety SW, grade W5c, designed and fabricated to protect all projections and absorb the shock of impact in handling and transit. As an alternate, cushioning material may be fabricated of plastic molding material conforming to MIL-P-19644 or polyurethane foam conforming to MIL-P-26514. Place the cushioned item within a close-fitting fiberboard box conforming to PPP-B-636, W5c. Place the technical literature, packaged as specified in 5.1.1.4.1, on top of the contents, directly under the lid of the box. Close the box in accordance with the appendix of the box specification.

5.1.2 Level C. Multiplier, Electrical Instrument TS-265( )/UP shall be preserved and packaged in a manner that will afford adequate protection against physical and environmental damage during shipment, handling and limited instransit storage.

5.2 Packing. Packing shall be level A, B or C, as specified. Shipping containers for all levels shall be capable of stacking and supporting superimposed loads during shipment and storage without damaging the container(s) or its contents (see 6.2).

5.2.1 Level A.

5.2.1.1 Consolidation. A quantity of Multiplier, Electrical Instrument TS-265( )/UP, packaged as specified in 5.1, shall be packed within a close-fitting fiberboard box conforming to PPP-B-636, type CF, class weather-resistant. Box closure shall be as specified in the appendix of the box specification. To facilitate palletization, fiberboard boxes shall be uniform in size and contain equal quantities of the packaged items to the greatest extent practicable.

5.2.1.2 Palletized load. A quantity of containers, packed as specified in 5.2.1.1, shall be placed on a pallet, load type I, conforming to MIL-STD-147 except that the pallet shall be softwood conforming to NN-P-71, type IV, size 2. A fiberboard cap shall be employed over the load having two sides extending down the stacked load at least 12 inches to accommodate marking requirements. The cap shall be fabricated of fiberboard conforming to PPP-F-320, class weather-resistant, W5s or V3c. The load shall be "bonded" to the pallet by strapping conforming to QQ-S-781, type I, finish A or shrink film.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

5.2.1.3 Less than palletized load. When quantities per destination are less than a pallet load, the containers packed as specified in 5.2.1.1 shall be waterproofed with tape conforming to PPP-T-76, in accordance with the taping requirements of the appendix of the box specification. A quantity of the waterproofed containers shall be packed within a close-fitting box conforming to PPP-B-601, overseas type; PPP-B-621, style 4, class 2; or PPP-B-585, style 2 or 3, class 3. When the gross weight exceeds 200 pounds, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, 3 x 4 inch skids, laid flat, shall be applied in accordance with the requirements of the container specification, or if not specified in the specification, in a manner which will adequately support the item and facilitate the use of material handling equipment. Closure and strapping shall be in accordance with the applicable container specification or appendix thereto except that metal strapping shall conform to QQ-S-781, type I, finish A.

5.2.2 Level B.

5.2.2.1 Consolidation. A quantity of Multiplier, Electrical Instrument TS-265( )/UP, packaged as specified in 5.1, shall be packed as specified in 5.2.1.1.

5.2.2.2 Palletized load. A quantity of containers, packed as specified in 5.2.2.1, shall be palletized as specified in 5.2.1.2.

5.2.2.3 Less than palletized load. When quantities per destination are less than a pallet load, the containers packed as specified in 5.2.2.1 shall be reinforced by pressure-sensitive filament tape conforming to PPP-T-97, type IV as specified in the appendix of the box specification. No further packing shall be required.

5.2.3 Level C.

5.2.3.1 Consolidation. A quantity of Multiplier, Electrical Instrument TS-265( )/UP, packaged as specified in 5.1, shall be packed as specified in 5.2.1.1, except that the fiberboard boxes shall be class domestic.

5.2.3.2 Palletized load. A quantity of containers, packed as specified in 5.2.3.1, shall be palletized as specified in 5.2.1.2, except that the fiberboard cap shall be class domestic.

5.2.3.3 Less than palletized load. When quantities per destination are less than a pallet load, the containers packed as specified in 5.2.3.1 shall be used as the shipping container. No further packing shall be required.

5.3 Marking. In addition to any special marking required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with MIL-STD-129.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. Multiplier, Electrical Instrument TS-265( )/UP, is a portable, general purpose test equipment to step down high alternating current voltages by a known step down ratio of either 10 to 1 or 100 to 1.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification and any amendment thereto.

b. Level of preservation and packaging and packing (see Section 5).

c. When rough handling and functional tests are required.

d. Quantity of first articles required.

e. Place of final inspection.

f. Technical literature required.

g. Quantity of tools and running spare parts required.

6.3 Nomenclature and type designation. The contractor should apply for nomenclature in accordance with the applicable clause in the contract. The parentheses in the type designation will be deleted or replaced by a letter identifying the particular design for example: SG-12F/U.

6.4 Verification inspection. Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance provisions established in this specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product, and will normally be identified by the categories listed below:

a. Type A. The total of that inspection set forth in the quality assurance provisions of this specification or the contract. Included in this category is that amount of inspection referred to as normal and tightened inspection by MIL-STD-105.

b. Type B. That inspection set forth in the quality assurance provisions of this specification or the contract reduced to amount under the reduced inspection provisions of MIL-STD-105.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

c. Type C. A reduced inspection procedure resulting in a material reduction in the amount of inspection set forth in the quality assurance provisions of this specification. The amount of inspection is less than that proviaed for in Type B and is based upon a consistently acceptable product resulting from a planned quality control system voluntarily employed by the contractor in the production of the product.

6.5 Definitions.

6.5.1 Branching. Branching is a connected arrangement of filaments (hyphae) formed by shoots or secondary stems growing from the main stem or filament (hypha).

6.5.2 Growth colonization. Growth colonization is a mass of individual plants, generally of one species, living together; or a group of hyphae which is formed from one spore or cell and may be one individual plant. Colonization which completely covers the surface of the nutrient material constitutes abundant growth.

6.5.3 Microbial growth. Microbial growth is the growth of very minute organisms. Such organisms when present in large numbers may provide a colony visible to the naked eye.

6.5.4 Sporulation. Sporulation is the formation of minute unicellular reproductive or dormant bodies, called spores.

6.5.6 Tubular germination. Tubular germination is partial growth by the production of hyphae, which are tubular shapeed fungal filaments. Tubular germination constitutes restricted individual spore growth not proceeding to colonization.

Custodian:
Army - EL

Preparing activity:
Army - EL

Project No. 6625-A527

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army
Headquarters
U.S.Army Electronics Command
Fort Monmouth, New Jersey 07703

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding General
U.S.Army Electronics Command
ATTN AMSEL- RD-TS
Fort Monmouth, New Jersey 07703

FOLD

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.

To detach this f cut along this line

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No 22-R255

INSTRUCTIONS This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost Comments and the return of this form will be appreciated Fold on lines on reverse side staple in corner and send to preparing activity Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements

SPECIFICATION MIL-M-1427A MULTIPLIER ELECTRICAL INSTRUMENT TS-265()/UP

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1 HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A GIVE PARAGRAPH NUMBER AND WORDING

B RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2 COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3 IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4 REMARKS *(Attach any pertinent data which may be of use in improving this specification If there are additional papers attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED

ESC-FM 1068-68

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T03:01Z
Check the source to verify that this is the current version before use.