MILITARY SPECIFICATION

JACK, HYDRAULIC, TRIPOD, 10-TON CAPACITY, TYPE B-6

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

* 1.1 This specification covers one type of adjustable tripod jack with 10 ton capacity, designated type B-6.

2. APPLICABLE DOCUMENTS

* 2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

Federal

NN-P-530	Plywood, Flat Panel
MMM-A-260	Adhesive, Water-Resistant, (for Sealing Waterproofed Paper)
PPP-B-601	Boxes, Wood, Cleated-Plywood
PPP-B-621	Boxes, Wood, Nailed and Lock-Corner
PPP-B-1055	Barrier Material, Waterproofed, Flexible

Military

MIL-P-116	Preservation-Packaging, Methods of
MIL-H-5606	Hydraulic Fluid, Petroleum Base, Aircraft, Missile and Ordnance
MIL-H-81019	Hydraulic Fluid, Petroleum Base, Ultra-Low Temperature

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: HQ AFLC CASO/LODS, Federal Center, Battle Creek MI 49016 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 20260-17T08:28Z
Check the source to verify that this is the current version before use.

STANDARDS

Military

MIL-STD-129	Marking for Shipment and Storage
MIL-STD-130	Identification Marking of US Military Prorerty
MIL-STD-808	Finishes, Protective, and Codes, for Finishing Schemes for Ground and Ground Support Equipment
MIL-STD-831	Test Reports, Preparation of

DRAWINGS

US AIR FORCE

50J25178	Jack Assembly - Hand, Hydraulic, Folding Tripod, 10 Ton Canacity, Tyne B-6
7545352	Requirements for Finishes, Protective and Codes for San Antonio ALC Ground and Ground Support Equirment

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 General. The requirements specified on Drawing 50J25178 are applicable as requirements of this specification. Additional requirements shall be as specified herein.

3.1.1 In the event the requirements of the drawing and this specification conflict, the requirements of this specification shall govern.

* 3.1.2 The jack shall be serviced with hydraulic fluid conforming to MIL-H-5606.

3.2 Preproduction sample. Prior to beginning quantity production, preproduction sample shall be subjected to preproduction testing. (See 4.3.1 and 6.2).

* 3.3 Identification of product. The jack shall be marked for identification in accordance with MIL-STD-130. The nameplate shall contain the following information:

JACK, HYDRAULIC, TRIPOD, 10-TON CAPACITY
Type B-6
Specification MIL-J-7400C
Part No. 50J25178
Mfr's. Serial No.
Contract or Order No.
Stock No.
Mfr's name or trade-mark
US

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T08:28Z
Check the source to verify that this is the current version before use.

3.4 Workmanship. The jack, including all parts and accessories, shall be fabricated and finished in a thoroughly workmanlike manner. Particular attention shall be given to freedom from blemishes, defects, burrs, and sharp edges; accuracy of dimensions, and marking of parts and assemblies.

* 3.5 Finishes and protective coatings. Cleaning, painting, plating, anodic films and chemical treatments shall be in accordance with MIL-STD-808 in conjunction with Air Force Drawing 7545352.

4. QUALITY ASSURANCE PROVISIONS

* 4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of tests. The inspection and testing of the jack shall be classified as follows:

a. Preproduction tests. (See 4.3)

b. Acceptance tests. (See 4.4)

4.3 Preproduction tests.

* 4.3.1 Sampling instructions. The preproduction test sample shall consist of one jack representative of the production jack. It shall be tested at a laboratory designated by the procuring activity or, when so stated in the contract, at the contractor's plant under the supervision of the procuring activity. (See 6.2) A test report shall be prepared in accordance with MIL-STD-831 and three copies furnished the procuring activity.

4.3.2 Tests. The preproduction tests shall consist of the acceptance tests and the following tests.

* 4.3.2.1 Low temperature. The jack assembly shall be placed in a test chamber and cooled to -54° Centigrade (C) for a period of 72 hours. At the end of this period, while at -54°C, the jack ram shall be raised to its maximum extension and pumped until the bypass relief valve operates. The lowering valve shall be opened, and the ram shall retract with not more than 50 pounds applied to the ram. For this test, the jack shall be serviced with hydraulic fluid conforming to MIL-H-81019. The time and number of full strokes necessary to fully extend the ram shall be recorded at both 21° and -54°C. The time and strokes necessary to fully extend the ram at -54°C shall be not more than double the time and strokes required at 21°C.

4.3.2.2 Life. The life test shall consist of 200 cycles of raising a 10-ton load vertically, and 50 cycles of raising a 10-ton load vertically with a 1.5-ton horizontal load applied to the top of the screw extension. One cycle shall consist of raising the ram from the collapsed height to the fully extended position and returning it to the collapsed position. The horizontal load shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T08:28Z
Check the source to verify that this is the current version before use.

be graduated from zero in the collapsed position to 1.5 tons in the fully extended position. Failure of any part of the jack during this test shall be cause for rejection.

4.4 Acceptance tests. The acceptance tests shall consist of individual tests and sampling tests.

4.4.1 Individual tests. Each jack shall be subjected to the following tests.

4.4.1.1 Examination of product. Each jack shall be inspected to determine compliance with the requirements specified herein with respect to workmanship, marking, and compliance with the drawing.

4.4.1.2 Ram test. Each ram of the assembled jack shall be tested by applying a minimum hydraulic pressure of 3,000 pounds per square inch (psi). Any leaking of hydraulic fluid shall be cause for rejection.

4.4.1.3 Pump test. Each pump shall be tested by sealing the pump outlet and operating the pump until the bypass valve opens. The bypass valve shall be adjusted as specified on the drawing.

4.4.2 Sampling test. Five jacks which have been manufactured under essentially the same conditions shall be selected at random from each lot of 50 or fraction thereof on the order and subjected to the following test.

4.4.2.1 Staticproof. The jack shall be tested by raising a 15-ton load vertically from the lowest position to the fully extended position. At the fully extended position, under a 10-ton load a horizontal load of 1.5 tons shall be applied to the top of the screw extension. Failure of any part of the jack during this test shall be cause for rejection.

4.4.3 Rejection and retest. When sampling tests are specified on a number of items that are selected as representative of a certain lot, and one or more of this number fails to meet the specified test, acceptance of all items shall be withheld until the extent and cause of failure is determined. For operational reasons, individual tests may be continued pending investigation of a sampling test failure, but the final acceptance of the product is contingent upon the Inspector's decision regarding the overall conformance of the product to specification requirements. If investigation indicates that the defects may exist on items previously accepted, full particulars concerning the defect(s) found, including recommendations for correction, shall be furnished to the procuring activity.

* 4.5 Inspection of preparation for delivery. Preservation, packaging, packing and marking shall be inspected to determine compliance with the requirements of Section 5.

5. PACKAGING

5.1 Preservation. Exterior surfaces of the jack not treated for corrosion resistance shall be protected from corrosion in accordance with MIL-P-116, Method I.

5.2 Exterior packing.

* 5.2.1 Domestic packing. Each jack shall be packed, with legs disassembled and with the ram fully retracted, in a wood box conforming to PPP-B-601 or PPP-B-621. When plywood is used, it shall be in accordance with NN-P-530.

Source: https://assist.dla.mil -- Downloaded: 20261017T08:28Z
Check the source to verify that this is the current version before use.

type II, class 2. Boxes shall be uniform in size and shall be designed to enclose the contents in a snug tight-fitting manner. Each jack shall be securely blocked and braced within the box in order to prevent damage to contents during shipment and handling.

* 5.2.2 Overseas packing. Each box specified in 5.2.1 shall be lined with a case liner of waterproof barrier material conforming to PPP-B-1055, and the seams shall be sealed with water-resistant adhesive conforming to MIL-A-260.

* 5.3 Marking of shipments. The exterior shipping container shall be marked in accordance with MIL-STD-129. The identification shall be composed of the following information listed in the order shown:

Stock No. or other identification number as specified in the purchase document *
JACK, HYDRAULIC, TRIPOD, 10-TON CAPACITY
Type B-6
MIL-J-7400C
Part No. 50J25178
Manufacturer's Part No.
Contractor Order No.

*NOTE: The contractor shall enter the National Stock No. specified in the purchase document or as furnished by the procuring activity. When the National Stock No. is not provided or available from the procuring activity, leave space therefor and enter the Stock No. or other identification when provided by the procuring activity.

* 5.3.1 Reinspection dates. Reinspection marking shall be as specified by the procuring activity.

6. NOTES

* 6.1 Intended use. The type B-6 jack is intended for use as an aircraft wing and fuselage jack.

* 6.2 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.

b. Whether domestic or overseas shipment is required. (See 5.2)

c. Where the preproduction test samples should be sent, the activity responsible for testing, and instructions concerning the submittal of the of the test reports. (See 4.3.1)

* 6.3. International agreement. Certain provisions of this specification are the subject of international agreement (ABC Air Std 11/7A). When amendment revision, or cancellation of this specification is proposed which will affect or violate the international agreement concerned, the preparing activity will take appropriate action through international standardization channels including departmental standardization offices, if required.

* 6.4 Reclaimed materiels. The use of reclaimed materiels shall be encouraged to the maximum extent possible.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T08:28Z
Check the source to verify that this is the current version before use.

6.5 Changes from previous issue. The margins of this specification are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodians:
Air Force - 99
Navy - AS

Review activity:
Air Force - 99

Preparing Activity:
Air Force - 99

(Project 1730-0224)

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T08:28Z
Check the source to verify that this is the current version before use.

practicable, the design and construction of the drawing unit shall permit