MIL-C-60458 (MU)
27 October 1967 M
Supersedes
PA-PD-2781
1 February1966

MILITARY SPECIFICATION

CARTRIDGE, 105MM, HE, ROCKET ASSISTED, XM548, DELAY ASSEMBLY FOR

1. SCOPE

1.1 This specification covers the quality assurance provisions for the delay assembly parts and loading, assembly and packing for the 105MM Rocket Assisted Cartridge, XM548.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or requests for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-E-463	- Ethyl Alcohol, for Ordnance Use.
MIL-A-2550	- Ammunition and Special Weapons, General Specification for.
MIL-C-13739	- Composition, Delay.
MIL-I-45607	- Inspection Equipment, Supply and, Maintenance of.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-109	- Quality Assurance Terms and Definitions.
MIL-STD-1168	- Lot Numbering of Ammunition.
MIL-STD-1235	- Single or Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

FSC: 1315

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:21Z
Check the source to verify that this is the current version before use.

DRAWINGS

ARMY

9212402 - Delay Assembly for 105MM RAP.
9212403 - Washer.
9212404 - Housing.

PUBLICATIONS

ARMY

ET-9212402 - Equipment Tabulation.

(Copies of specifications standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.

3. REQUIREMENTS

3.1 Material. - Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts and assemblies. - The parts and assemblies shall comply with all requirements specified on drawing 9212402, 9212403, and 9212404 and with all requirements specified in applicable specifications.

3.3 Pyrotechnic Composition. - The flash, delay, and igniter composition shall comply with applicable drawing requirements.

3.3.1 Process (see 6.4).-The delay composition shall be manufactured using conventional wet blending techniques and shall employ ethyl alcohol, grade III or V of MIL-E-463 as a blending medium and passed through a No. 16 mesh screen to provide initial granulation.

3.3.2 Particle Size. - The dried delay composition shall be sieved and shall be retained on an 80 mesh screen.

3.3.3 Moisture content. - The moisture content of the flash, delay, and igniter composition at the time of loading shall not exceed 0.05 percent when tested in accordance with 4.4.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:21Z
Check the source to verify that this is the current version before use.

3.4 Flight Test

3.4.1 Pyrotechnic Material Acceptance (see 4.3.3.4.1) - plus 70°F - After conditioning at 70°F for a period of 12 hours, minimum the delays shall be fired at a proving ground as specified in 4.4.1.1. The average delay time shall be 15.75 seconds plus or minus 0.75 seconds and the standard deviation of the delays shall not exceed 0.50 seconds.

3.4.2 Delay Assembly Accetpance

3.4.2.1 Plus 155°F - After conditioning at 155°F for a period of 24 hours minimum, the delay assembly shall be flight tested at a proving ground (see 4.4.1.2.1). The average delay time shall be 12.5 seconds plus or minus 1.5 seconds and the standard deviation shall be no greater than 0.8 seconds.

3.4.2.2 Minus 65°F - After conditioning at minus 65°F for a period of 24 hours minimum, the delay assembly shall be flight tested at a proving ground (see 4.4.1.2.2). The average delay time shall be 20.0 seconds plus or minus 1.5 seconds and the standard deviation shall be no greater than 0.8 seconds.

3.5 Pyrotechnic Porosity test. - The pressure recorded at the exit end of the delay assembly, 80 seconds after application of the nitrogen gas, shall not be greater than 135 P.S.I. above the zero pressure reference. The pressure recorded at the exit end of the delay assembly, 110 seconds after application of the nitrogen gas, shall be no less than 10 P.S.I. and no greater than 200 P.S.I. above the zero pressure reference. The test shall be conducted in accordance with 4.4.2.

3.6 Workmanship. - All parts and assemblies shall be fabricated and loaded in a thorough workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, rust and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

3.7 First Article Inspection. - This specification makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

3.8 Crimp strength. - The washer crimp shall be capable of withstanding a 500 pound minimum load when tested as specified in 4.3.3.5.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:21Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified within this specification.

b. Number of units of product inspected.

c. Results obtained, by defect code, for all inspections performed.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 Government verification.-Using the contractor's written quality assurance procedure, this detailed specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals, all quality assurance operations performed by the contractor. Verification will be performed to the extent

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:21Z
Check the source to verify that this is the current version before use.

necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 First Article Inspection

4.2.1 Submission. - The contractor shall submit a first article sample as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2. The first article sample shall consist of 10 delay housings which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures, and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including statements of findings/certificates of conformancd for materials, (see 4.1.1.1.e). A sample containing known defects will not be submitted unless specifically authorized by the contracting officer. A first article sample or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.

4.2.2 Inspection to be performed. - Components will be subjected by the Government to any or all of the examinations or tests specified in 4.3.2 of this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection. - If any delay housing fails to comply with any or all of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly orcomponent in the sample to comply with any of the stated requirements. In the event of rejection the Government reserves the right to require the contractor to take corrective action and submit a new first article sample or portion thereof. Until a first article sample is accepted the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:21Z
Check the source to verify that this is the currentversion before use

4.3 Inspection Provisions

4.3.1 Lot formation. - The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantityof units from which the sample was drawn and shall not be construed to represent any prior or s;ubsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process using the same materials and methods, in accordance with the same drawings, same drawings revisions, same specifications and same specification revisions. Changes to the process, specification, or drawings, not affecting safety, performance, interchangeability, or storage, as determined by the Governmnet, shall not be deemed to alter the homogeneity of the lot. Inspection lots shall comply with MIL-STD-105. Unless otherwise approved by the contracting officer, the inspection lot size of end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period nor more thanthe largest monthly quantity contractually scheduled for delivery during the contract period. Inspection lots of components or subassemblies, other than the items of delivery, shall be homogeneous and of a size mutually convenient to both the contractor and the Government inspector. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each lot of loaded delay assemblies shall contain:

a. Intert parts from one interfix lot number from one manufacturer.
b. Flash composition from not more than one lot.
c. Delay composition from not more than one lot.
c. Igniter composition from not more than one lot.

4.3.2 Examination. - Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL-STD-105 except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL-STD-1235 maybe used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using and AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Once agreement has been reached as to which method will be used (group or individual) that method will be used for all classification of defects listed in this specification. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:21Z
Check the source to verify that this is the current version before use.

4.3.2.1 Housing (see dwg. 9212404 covering a detail of dwg. 9212402).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.00 percent		
101.	Pitch diameter	Gage	01001
102.	Diameter of grooves near end surfaces	Gage	01002
103.	Diameter of two holes	Gage	01003
104.	Diameter of counterbore	Gage	01004
105.	Width of middle groove	Gage	01005
106.	Depth of two holes	Gage	01006
107.	Effective thread length minimum	Gage	01007
108.	Outside diameter	Gage	01008
Minor:	AQL 6.5 percent		
201.	Concentricity of thread	Gage	01009
202.	Overall length	Gage	01010
203.	Perpendicularity of end surface containing counterbore	Gage	01011
204.	Distance end surface to middle groove	Gage	01012
205.	Major diameter of thread	Gage	01013
206.	True position of two holes	Gage	01014
207.	Depth of counterbore	Gage	01015
208.	Concentricity of counterbore	Gage	01016
209.	Width of grooves nearest end surfaces	Gage	01017
210.	Distance end surface containing counterbore to O ring groove	Gage	01018
211.	Chamfer on thread missing	Visual	01019
212.	Knurl in middle grooves missing	Visual	01020
213.	Surface finish of grooves nearest end surfaces improper	Visual	01021
214.	Surface finish of outside diameter improper	Visual	01022
215.	Chamfer on end surface missing	Visual	01023
216.	Concentricity of O ring grooves	Gage	01024
217.	Protective finish damaged or incomplete	Visual	01025
218.	Marking missing or illegible	Visual	01026
219.	Distance end surface to thread shoulder	Gage	01027

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:21Z
Check the source to verify that this is the current version before use.

220.	Distance thread shoulder to O ring groove	Gage	01028
221.	Surface finish of 2 holes improper	Visual	01029
222.	Evidence of poor workmanship	Visual	01030

4.3.2.2 Washer, Delay (see dwg. 9212403 covering a detail of dwg. 9212402).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Outside diameter	Gage	02001
Minor:	AQL 1.5 percent		
201.	Inside diameter	Gage	02002
202.	Surface finish improper	Visual	02003
203.	Protective finish missing or damaged	Visual	02004
204.	Evidence of poor workmanship	Visual	02005

4.3.2.3 Delay assembly, prior to loading delay composition (see dwg. 9212402).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	None defined.		
Minor:	AQL 0.65 percent		
201.	Flash composition removed from sidewall	Visual	03001

4.3.2.4 Delay Assembly prior to loading igniter composition (see dwg. 9212402).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Distance end of housing to delay composition	Gage	04001
Minor:	None defined.		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:21Z
Check the source to verify that this is the current version before use.

4.3.2.5 Delay Assembly, after crimping (see dwg. 9212402).

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Washer or crimp missing or incomplete	Visual	05001
2.	Flash or igniter composition missing	Visual	05002
Major:	AQL 0.40 percent		
101.	Depth of washer, min	Gage	05003
102.	Flash composition beyond surface X	Visual	05004
Minor:	AQL 1.00 percent		
201.	Excess composition on external surfaces	Visual	05005
202.	Evidence of poor workmanship	Visual	05006

4.3.3 Testing

4.3.3.1 Consolidation load.-Major defect - Code No. 06001.- The contractor shall provide adequate controls to assure the compliance of each lot with the specified load requirement. For verification each consolidation machine shall be calibrated at the end of each 8 hours of production or portion thereof. In addition a suitable warning device shall be assembled to each consolidation machine and calibrated at the same time as the consolidation machine. If, during the loading of the delay the pressure drops below the applicable consolidation load requirement, that delay shall be rejected.

4.3.3.2 Mositure Content. - Major defect - Code No. 07001 - The contractor shall provide adequate controls to assure the compliance of each lot with the specified moisture content requirement. For verification a sample of delay, igniter and flash composition from each 8 hours production and from each new container shall be selected to perform a moisture content analysis. If any sample fails to meet the requirements of 3.3.3, the 8 hours production represented by the sample or the new container of material shall be rejected.

4.3.3.3 Porosity test. - Major defect - Code No. 05007 - This test shall be conducted 100 percent in accordance with 4.4.2. If any delay assembly fails to comply with the requirement of 3.5 the delay assembly shall be rejected and removed from the lot.

4.3.3.4 Flight Test

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:21Z
Check the source to verify that this is the current version before use.

4.3.3.4.1 Pyrotechnic material acceptance. - Major defect - Code No. 08001 - Each lot of delay compositions shall be divided into four pound sublots. One delay shall be loaded from each sublot of delay composition and the delay assemblies submitted to the Government for flight test. The delays loaded from each delay composition lot shall remain grouped together to determine compliance with 3.4.1. If the delays fired for material acceptance fails to meet the burning rate requirement of 3.4.1 the lot of delay composition shall be rejected. If the delay fails to function or functions in bore, the flash, delay, and igniter composition lots shall be rejected. The test shall be conducted in accordance with 4.4.1.1.

4.3.3.4.2 Lot Acceptance

4.3.3.4.2.1 Plus 155°F - Seven loaded delays shall be selected at random for this test. If the sample fails to meet the requirements of 3.4.2.1, Major defect, Code No. 05008, or if any delay fails to function, Critical defect, Code No. 05010, or if any delay functions in bore, Critical defect, Code No. 05011, the lot shall be rejected. The test shall be conducted in accordance with 4.4.1.2.1.

4.3.3.4.2.2 Minus 65°F - Seven loaded delays shall be selected at random for this test. If the sample fails to meet the requirements of 3.4.2.2, Major defect, Code No. 05009, or if any delay fails to function, Critical defect, Code No. 05012, or if any delay functions in bore, Critical defect, Code No. 05013, the lot shall be rejected. The test shall be conducted in accordance with 4.4.1.2.2.

4.3.3.5 Crimp Strength - Major defect - Code No. 09001. - At the beginning of production an inert delay housing shall be crimped on each crimping device usig the same technique as in regular production. After crimping, the delay housing shall be sectioned perpendicular to the longitudinal axis and the load applied axially to the crimp from the sectioned end. A tool manufactured to the same diameter as the delay washer shall be used in applying load to the crimp. If the crimp fails to meet the applicable load requirement, the crimping device shall be adjusted until the delay meets the requirement of 3.8. The process shall then be monitored to assure that proper crimp strength is maintained throughout production.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:21Z
Check the source to verify that this is the current version before use.

4.3.3 Inspection Equipment - Equipment Tabulation number ET-9212402 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to documentation. - Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 Supply and maintenance. - Supply and maintenance of equipment listed on the ET shall be in accordance with specification MIL-I-45607.

4.3.4.3 Government use of contractor's inspection equipment. The contractor shall make available to the Government all inspection equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment and verification of its accuracy shall be supplied by the contractor for the performance of examination of test by the Government.

4.4 Test Methods and Procedures

4.4.1 Flight test

4.4.1.1 Pyrotechnic material acceptance. - The loaded delay assemblies shall be assembled to a modified M1 shell as specified in the applicable equipment list. A rocket selector cap shall be assembled to the delay and the complete round, including propellant charge conditioned at 70°F plus or minus 5° for 12 hours, minimum. In conducting this test, an XM-108 Primer, M14 series Cartridge case and M1 multi perforated propellant assessed to produce an average muzzle velocity of 1800 feet per second plus or minus 5 feet per second shall be utilized. The chamber pressure required to obtain 1800 feet per second shall be no greater than 38000 P.S.I. The complete round shall be removed from the conditioning chamber, the rocket selector cap removed and the shell fired from an M103 or M137 Cannon in less than 3 minutes from removal from the conditioning box.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:21Z
Check the source to verify that this is the current version before use.

A smear camera shall be mounted near the muzzle to film the shell and determine presence of the delay at the muzzle. Equipment used in determining delay time shall be capable of recording the time within .1 second. In the event the equipment fails to record the delay time and the delay expulsion was not observed visually, the shell shall be recovered to determine if the delay functioned.

4.4.1.2 Lot Acceptance Test

4.4.1.2.1 Plus 155°F - The loaded delay assemblies shall be assembled to a modified M1 shell as specified in the applicable equipment list. A rocket selector cap shall be assembled to the delay and the complete round, including propellant, conditioned at 155°F plus or minus 5°F for 24 hours, minimum. In conducting the test, an XM-108 Primer, an M14 series cartridge case and M67 propelling charge (zone 1 thru 7) shall be utilized. The complete round shall be removed from the conditioning chamber, the rocket selector cap removed and the shell fired from an M103 or M137 Cannon in less than 3 minutes from removal from the conditioning chamber. The recording of burning time and presence of thy delay at the muzzle shall be as specified in 4.4.1.1.

4.4.1.2.2 Minus 65°F. - This test shall be conducted as specified in 4.4.2.1 except that the conditioning temperature for the complete round, including propellant, shall be minus 65°F.

4.4.2 Porosity test. - Each delay assembly shall be assembled to the required test equipment specified on the applicable equipment list. Nitrogen gas under a pressure of 1000 P.S.I.G. plus or minus 50 P.S.I. shall be applied to two delay columns and the pressure at the exit end recorded at 0.5 seconds, 80 seconds and 110 seconds. The pressure reading at 0.5 seconds shall be recorded and used as the zero erference.

4.4.3 Determination of moisture. - The moisture content of the flash, delayed igniter composition shall be determined in accordance with 4.4 of Specification MIL-C-13739.

5. PREPARATION FOR DELIVERY

5.1 Packaging, Packing and Marking. - Packaging, packing and marking of loaded delay assemblies shall be in accordance with Improvised Packing No. 57/67.

6. NOTES

6.1 Ordering data. - Procurement documents shall specify the following:

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:21Z
Check the source to verify that this is the currentversion before use.

a. Title, number and date of this specification.
b. Data cards. - Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. - The contractor shall design inspection equipment as required by the referenced inspection Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Inspection equipment lists. - Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Inspection equipment list codes. - The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs. - Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:21Z
Check the source to verify that this is the currentversion before use.

6.3.4 Contractor designs. - Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to MIL-D-1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high contrast reproductions. Contractors shall submit one copy of final designs as a rolled set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor designs. - All submitted designs shall contain a reference to the applicable five digit Code Number contained in Section 4 of this specification. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND4. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

6.4 Vinyl Achohol Acetate Resin (VAAR) Solids Determination.- The concentration of solids in the VAAR solution may change upon storage due to the evaporation of solvent. VAAR solids content in the delay blend meeting for this material can only be obtained if the solution to solids weight ratio is known. Prior to blending the delay composition a sample of VAAR solution should be tested to determine this ratio. The test procedure should be conducted as specified in 6.4.1.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:21Z
Check the source to verify that this is the current version before use.

6.4.1 Method of determination. - Transfer approximately 10 grams of VAAR solution to a tared evaporating dish. Obtain the weight of the dish and sample to the nearest milligram. Place the dish containing the sample in an oven maintained at 105 + 5°C. Allow at least 1 1/2 hours for complete volatilization of the solvent. Remove the dish, with contents, from the oven and allow it to cool in a desiccator for 30 minutes. Obtain the weight of the dish and contents.

Calculation:

$$\text{Ratio of solution to solids weight} = \frac{A - B}{C - B}$$

Where:
A = Weight of evaporating dish with sample
B = Weight of evaporating dish
C = Weight of evaporating dish and contentsafter drying

6.5 Submission of First Article Sample. - Instructions as to the location for evaluation of first article samples shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issu according. All inquiries should be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-NI.

6.6 Submission of test data. - In addition to the normal distribution of records, one copy of all test data shall be forwarded to each of the following:

Commanding Officer
Picatinny Arsenal
ATTN: SMUPA-ND4 and SMUPA-DS2
Dover, New Jersey

Custodian:
Army-MU

Preparing Activity:
Army-MU

Project Number 1315-A-573

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:21Z
Check the source to verify that this is the current version before use.