MIL-F-60988B(MU)
9 April 1973
SUPERSEDING
MIL-F-60988A(MU)
20 March 1969

MILITARY SPECIFICATION

FUZE, PD, M551

LESS BOOSTER

1. SCOPE

1.1 This specification covers the metal parts for one type of fuze designated as Fuze, PD, M551, less Booster.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

QQ-Z-325	-	Zinc Plating (Electro-deposited)
QQ-P-416	-	Plating, Cadmium (Electro-deposited)

MILITARY

MIL-P-116	-	Preservation, Method of
MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-T-10727	-	Tin Plating, Electrodeposited or Hot Dipped for Ferrous and Non-Ferrous Metals
MIL-I-45607	-	Inspection Equipment, Supply and Maintenance of

FSC: 1390

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

MIL-C-60940 - Cup, Lead Assembly

STANDARDS

FEDERAL

FED-STD-151 - Metals; Test Methods

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-331	-	Fuze and Fuze Components, Environmental and Performance Tests for
MIL-STD-1168	-	Lot Numbering of Ammunition
MIL-STD-1235	-	Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

8862121 - Fuze, PD, M551, Less Booster

PUBLICATIONS

ARMY

ET-8862121 - Equipment Tabulation

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

3. REQUIREMENTS

3.1 Material.-Material shall be in accordance with the applicable drawings and specifications.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:22Z
Check the source to verify that this is the current version before use.

3.2 Parts.-The fuze parts shall comply with all requirements specified on Drawing (dwg.) 8862121, all associated drawings and with all requirements specified in applicable specifications.

3.3 Transportation vibration.-The fuze assembly shall be safe and operable.

3.4 X-ray examination of sample fuze assemblies prior to jolt and jumble tests.-The fuze assembly shall be x-rayed and shall not be armed or partially armed (as evidenced by the detonator moving any degree from the safe position).

3.5 Jolt and Jumble.-The fuze assembly shall withstand the jolt and jumble test without having any explosive elements explode, fuze come apart, fuze arm or become hazardous to anyone handling them.

3.6 Waterproofness.-A continuous stream of air bubbles shall not emerge from the fuze.

3.7 Verification of heat treatment of centerplate.-The centerplate shall be subjected to a bend test to verify that correct heat treat procedures have been followed. A force of 52 lbs minimum shall be applied to bend all three legs of the centerplate forward .080 $\pm$ .005 inch.

3.8 Functioning.-The fuze assembly shall function satisfactorily.

3.8.1 Safety.-There shall be no premature burst (see 6.7) or evidence thereof in any of the test firings.

3.9 Non-functioning.-The fuze assembly shall not function.

3.10 Workmanship.-All parts and assemblies shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agents.

3.11 Qualification test for M55 detonator.-The detonator shall function the test cartridge high order.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

3.12 Submission of results of contractor-conducted examinations and tests.-The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. (See 6.6)

3.13 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2. (See 6.1) The first article sample shall consist of the following:

a. Three hundred thirty-four (334) fuze assemblies.
b. One hundred ten (110) of each sub-assembly.
c. One hundred (100) of each component.

All parts and completed assemblies submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in new regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as directed by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed.-Assemblies and components will be subjected by the Government to any or all of the examinations or tests specified in this specification and any or all requirements of the applicable drawings.

4.2.2.1 Quantities for first article inspection.-After classification of defects and other inspections have been performed as specified in 4.2.2, the following quantities shall be subjected to the indicated tests:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.2.2.1.1 Qualitative spot test for cadmium (when applicable) Five (5) rotor springs and ten (10) lock springs shall be subjected to this test.

4.2.2.1.2 Stake of pinion assembly.-The 110 pinion assemblies shall be subjected to this test.

4.2.2.1.3 Stake of verge assembly.-The 110 verge assemblies shall be subjected to this test.

4.2.2.1.4 Stake of firing pin and spring assemblies .-The 110 firing pin and spring assemblies shall be subjected to this test.

4.2.2.1.5 Non-arming of centerplate assembly.-The 110 centerplate assemblies shall be subjected to this test.

4.2.2.1.6 Arming of centerplate assembly.-After completion of test specified in 4.2.2.1.5, the 110 centerplate assemblies shall be subjected to this test.

4.2.2.1.7 Arming delay time and non-arming of housing assembly.-The 110 housing assemblies shall be subjected to this test.

4.2.2.1.8 Non-arming of centrifugal lock of housing assembly.-The 110 housing assemblies shall be subjected to this test.

4.2.2.1.9 Arming of centrifugal lock of housing assembly .-After completion of test specified in 4.2.2.1.8, the 110 housing assemblies shall be subjected to this test.

4.2.2.1.10 Push out test of hammerweight assembly of centerplate assembly.-Thirty-seven (37) centerplate assemblies and the hammerweight assemblies on each of the three legs of each assembly shall be subjected to this test.

4.2.2.1.11 Security of stake of hammerweight assembly.-The 110 hammerweight assemblies shall be subjected to this test.

4.2.2.1.12 Salt spray.-The number of samples of the applicable parts shall be as specified in their respective finish specification. (see 2.1)

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:22Z
Check the source to verify that this is the currentversion before use.

4.2.2.1.13 Force test of hammerweight pin of centerplate assembly.-Thirty-seven (37) centerplate assemblies and the hammerweight pin on each of the three legs of each assembly shall be subjected to this test.

4.2.2.1.14 Security of rotor assembly.-The 110 rotor assemblies shall be subjected to this test.

4.2.2.1.15 Push test of simulated setback pin into retainer setback pin.-The 100 setback pin retainers shall be subjected to this test.

4.2.2.1.16 Fracture test of die cast adapter (when applicable).-The 110 adapters shall be subjected to this test.

4.2.2.1.17 X-ray examination of sample fuze assemblies prior to jolt and jumble tests.-Prior to subjecting the sample fuze assemblies to the tests specified in 4.2.2.1.18 and 4.2.2.1.19, the fuze assemblies shall be subjected to this test.

4.2.2.1.18 Jolt.-Twelve (12) fuze assemblies shall be subjected to this test.

4.2.2.1.19 Jumble.-Twelve (12) fuze assemblies shall be subjected to this test.

4.2.2.1.20 Non-functioning.-Ten (10) fuze assemblies shall be subjected to this test.

4.2.3 Rejection.-If any assembly or component fails to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.2.4 Remaining first article inspection samples

4.2.4.1 Transportation vibration.-The three hundred (300) fuze assemblies shall be subjected to this test.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:22Z
Check the source to verify that this is the currentversion before use.

4.2.4.2 Torque of fuze assembly.-After completion of test specified in 4.2.4.1, seventy-five (75) fuze assemblies shall be subjected to this test. If two (2) or more fuze assemblies fail to comply with the applicable requirement, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article sample or portion thereof. Until a first article sample is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.2.4.3 Waterproofness.-The seventy-five (75) fuze assemblies used in the torque test shall be subjected to this test. If two (2) or more fuze assemblies fail to comply with the applicable requirement, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article sample or portion thereof. Until a first article sample is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.2.4.4 Functioning.-After completion of tests specified in 4.2.4.1 and 4.2.4.3, the three hundred (300) fuze assemblies shall be subjected to this test. If eight (8) or more fuze assemblies fail to comply with the applicable requirement, or one (1) premature burst occurs, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article sample or portion thereof. Until a first article sample is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot: as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:22Z
Check the source to verify that this is the currentversion before use.

sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot of fuzes shall contain:

a. Detonators from one interfix lot number from one manufacturer.
b. Lead cup assemblies from one interfix lot number from one manufacturer.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Individual defects will have an AQL of 0.40 Percent for each major defect and an AQL of 0.65 Percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Pin firing (See dwg. 8837940 covering a detail of dwg. 8837939)

Categories	Defects	Method of Inspection (See 4.3.3.1)	Code No. (See 6.2)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

Critical: None defined

Major:			
101.	Profile of firing pin point	Gage	01001

Minor: None defined

4.3.2.2 Housing assembly, prior to insertion of setback pin (See dwg. 8837946 covering a detail of dwg. 8862121)

Categories	Defects	Method of Inspection	Code No.
Critical:	100% Inspection		
1.	Rotor in armed position	Visual/Probe	02001
Major:			
101.	Discernible bluge on detonator	Visual	02002

Minor: None defined

4.3.2.3 Housing assembly (see dwg. 8837946 covering a detail of Dwg. 8862121)

Categories	Defects	Method of Inspection	Code No.
Critical:	100% Inspection		
1.	Rotor fails to remain in unarmed position when centrifugal lock is retracted	Visual/Manual	03001
2.	Setback pin not through rotor	Visual	03002
3.	Setback pin retainer missing	Visual/Probe	03003
4.	Two (2) or more leaves will not contact setback pin (see 4.3.2.14)	Visual	03004
Major:			
101.	One (1) leaf will not contact setback pin (see 4.3.2.14)	Visual	03005

Minor: None defined

4.3.2.4 Pin, setback (see dwg. 8861216 covering a detail of dwg. 8837946)

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:22Z
Check the source to verify that this is the currentversion before use.

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:			
	101. Length to flange, along smallest diameter	Gage	04001
Minor:	None defined		

4.3.2.5 Pinion assembly (see dwg. 8837948 covering a detail of dwg. 8837946)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:			
	101. Total length, minimum (min)	Gage	05001
Minor:	None defined		

4.3.2.6 Verge assembly (see dwg. 8837961 covering a detail of dwg. 8837946)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:			
	101. Total length, min.	Gage	06001
Minor:	None defined		

4.3.2.7 Retainer, setback pin (see dwg. 8876212 covering a detail of dwg. 8837946)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:			
	101. Depth	Gage	07001
	102. Diameter, retaining mounds	Gage	07002

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:22Z
Check the source to verify that this is the currentversion before use.

103.	Concentricity retaining mounds diameter with center diameter	Gage	07003
104.	Center diameter	Gage	07004
Minor:			
201.	Any retaining mounds missing	Visual	07005
202.	Evidence of poor workmanship (see 3.10)	Visual	07006

4.3.2.8 Adapter (See dwg. 8837944)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:			
101.	Total length	Gage	08001
102.	Knurl missing	Visual	08003
103.	Inside diameter of adapter	Gage	11007
104.	Small outside diameter of adapter	Gage	11009
Minor:			
201.	Evidence of poor workmanship (See 3.10)	Visual	08004

4.3.2.9 Adapter (see dwg. 9242549) (When Applicable)

Categories	Defects	Method of Inspection (See 4.3.3.1)	Code No.
Critical:	None defined		
Major:			
101.	Total length	Gage	47001
102.	Inside diameter	Gage	47002
103.	Knurl missing	Visual	47003
104.	Small outside diameter	Gage	47004
105.	Weight incorrect	Balance	47005
106.	Wall thickness at flat (both sides)	Gage	47008
Minor:			
201.	Evidence of poor workmanship (See 3.10)	Visual	47006
202.	Mismatch	Visual	47007

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.3.2.10 Fuze assembly, prior to assembling lead cup assembly (see dwg. 8862121)

Categories	Defects	Method of Inspection	Code No.
Critical:	100% Inspection		
1.	Setback pin retainer missing	Visual/Probe	09001
2.	Setback pin missing or retracted (see 4.3.2.14.2)	Gage	09002
Major:	None defined		

4.3.2.11 Fuze assembly (see dwg. 8862121)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:			
101.	Outside diameter, max.	Gage	11001
102.	Length, end of penthouse to rear face of adapter flange, max.	Gage	11002
103.	Total length, max.	Gage	11003
104.	Pitch diameter of thread	Gage	11004
105.	Major diameter of thread	Gage	11005
106.	Concentricity of large outside diameter with pitch diameter including perpendicularity	Gage	11006
Minor:			
201.	Outside diameter of penthouse, max.	Gage	11011
202.	Marking misleading or unidentifiable	Visual	11012
203.	Evidence of poor workmanship (see 3.10)	Visual	11013

4.3.2.12 Inner pack (see dwg. 9205332).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:			

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:22Z
Check the source to verify that this is the currentversion before use.

101.	Incorrect number of trays	Visual	12001
102.	Incorrect number of fuzes	Visual	12002
103.	Fuze inverted	Visual	12003
104.	Marking of bag misleading or unidentifiable	Visual	44001
105.	Bag torn or perforated	Visual	44002
106.	Bag improperly sealed	Visual	44003
107.	Corners of tube liner not blunted	Visual	13005
Minor:			
201.	Empty tray missing on top of exposed fuzes	Visual	12004
202.	Fillers missing (when applicable)	Visual	12005

4.3.2.13 Sealed outer fiber box (see dwg. 9230367)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:			
101.	Box damaged	Visual	45001
Minor:			
201.	Contents loose	Manual	45002
202.	Marking misleading or unidentifiable	Visual	45004

4.3.2.14 Defect standards, Code No. 14001

4.3.2.14.1 Examination for contact of setback pin retainer leaves (see 4.3.2.3).-Each assembly in which one (1) or more leaves of the setback pin retainer apparently will fail to contact the setback pin shall be subjected to the following procedure:

1. The setback pin shall be operated.
2. Visual examination shall be conducted to determine whether leaves contact the setback pin.

If two (2) or more leaves fail to contact the setback pin, the assembly shall be classed a Critical defective. If one (1) leaf fails to contact the setback pin, the assembly shall be classed a Major defective. Assemblies subjected to examination in accordance with this procedure shall not be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.3.2.14.2 Examination for setback pin.-The position of the setback pin shall be classified a Critical defect if the setback pin is less than .071 inches from the exposed surface of the lower shaft plate. (See 4.3.2.10)

4.3.3 Testing

4.3.3.1 Dimensional control of stamped parts .-In place of the normal sampling associated with the classifications of defects, and with the approval of the Contracting Officer, a sample of at least ten (10) parts may be dimensionally inspected to qualify the tool used in the stamping process for use in production. In addition, a random sample of five (5) parts shall be selected from the last portion of each hour's production for dimensional inspection as a control of the tool during production.

If any defective parts are found during qualification of the tool, the tool producing the defective part shall not be used in production.

If any defective parts are found when inspection is performed for control of the tool, the tool producing the defective part shall be removed from production. Further, that portion of production since the last tool control check shall be returned to the contractor for corrective action.

All tools removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the Contracting Officer to substantiate the request.

4.3.3.2 Dimensional control of cast parts.-In place of the normal sampling associated with the Classification of Defects and with the approval of the Contracting Officer, a sample of at least three (3) parts (as cast) from each cavity may be dimensionally inspected to qualify a new or reworked cavity for use in production or as a control of the cavity during production. Inspection for control of each cavity during production shall be performed on the above quantities from each cavity after production of 5000 parts. Individual cavity identification must be provided.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

If any defective parts are found during qualification of the cavity, the cavity producing the defective part shall not be used in production. If any defective parts are found when inspection is performed for control of the cavity, the cavity producing the defective part shall be removed from production. Further, that portion of production since the last control check shall be returned to the contractor for corrective action.

All cavities formerly removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test specified above. The contractor may request a change of inspection frequency providing he presents objective evidence to substantiate the request to the Contracting Officer.

4.3.3.3 Check test for deterioration of detonators (see applicable detonator specification) Major Defect, Code No. 16001 .-If the total time between original acceptance of any lot and the assembly of that lot into the fuze exceeds two years, or if the detonators have been subjected to adverse conditions, however brief, at any time since previous tests, the detonator lot shall be subjected to and must satisfactorily pass, the check test for deterioration specified in applicable detonator specification immediately before the detonator lot is assembled into the fuze. This test shall be performed by the contractor on detonators selected by the Government inspector at the facility assembling the detonator into the fuze. (See 6.4)

4.3.3.4 Check test for deterioration of lead cup assemblies (See MIL-C-60940) Major Defect, Code No. 17001 .-If the total time between original acceptance of any lot and the assembly of that lot into the fuze exceeds two years, or if the lead cup assemblies have been subjected to adverse conditions, however brief, at any time since previous tests, the lead cup lot shall be subjected to and must satisfactorily pass, the check test for deterioration specified in MIL-C-60940 immediately before the lead cup lot is assembled into the fuze. This test shall be performed by the contractor on lead cups selected by the Government inspector at the facility assembling the lead cup into the fuze. (See 6.4)

4.3.3.5 Qualitative spot test for cadmium (see dwg. 8837960 and 8837969), when applicable, Major defect, Code No. 43001.-Five (5) rotor springs and ten (10) lock springs shall be selected from each lot and subjected to this test. If any part fails to comply

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

with the applicable requirement, the lot shall be rejected. NOTE: For purposes of this test, one lot of springs shall consist of parts manufactured from not more than one roll of spring wire. This test shall be performed as specified in 4.4.1 using equipment in accordance with 4.3.4.

4.3.3.6 Stake of pinion assembly (see dwg 8837948) Major Defect, Code No. 18001.-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter K, single plan, with an AQL of 0.40 percent. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.3.3.7 Stake of verge assembly (see dwg. 8837961), Major defect, Code No. 19001.-Three hundred (300) verge assemblies shall be selected from each lot and subjected to this test. If one (1) or more assemblies fail to comply with the applicable requirement, the lot shall be rejected. The test shall be performed as specified in 4.4.3 using equipment in accordance with 4.3.4.

4.3.3.8 Stake of firing pin and spring assembly (see dwg. 8837939) Major Defect, Code No. 20001.-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter K, single plan, with an AQL of 0.40 percent. The test shall be performed as specified in 4.4.4 using equipment in accordance with 4.3.4.

4.3.3.9 Non-arming of centerplate assembly (see dwg. 8861223) Major Defect, Code No. 21001.-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter K, single plan, with an AQL of 0.40 percent. The test shall be performed as specified in 4.4.5 using equipment in accordance with 4.3.4.

4.3.3.10 Arming of centerplate assembly (see dwg. 8861223) Major Defect, Code No. 22001.-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter K, single plan, with an AQL of 0.40 percent. The test shall be performed as specified in 4.4.6 using equipment in accordance with 4.3.4.

4.3.3.11 Arming delay time (see dwg. 8837946) Critical Defect if assembly arms in less than 225 milliseconds, Major Defect if assembly arms between 225 and 240 milliseconds, and Non-arming of housing assembly, Major Defect, Code No. 23001 .-This test shall be conducted one-hundred percent (100%). If any assembly fails to comply with the requirements specified on the applicable drawing, it shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.7 using equipment in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.3.3.12 Transportation vibration test of centrifugal lock mechanism (see dwg. 8837946) Major Defect, Code No. 24001 .-Twenty (20) unarmed fuze assemblies without setback pins and without detonators, shall be selected from each lot and subjected to this test. Each fuze assembly cover shall be conspicuously marked to indicate absence of setback pin and detonator. Fuze assemblies shall be placed in interplant shipping containers and subjected to this test.

At the outset of the test, the rotor shall be in the fully unarmed position, with the rotor gear in contact with a pin with a diameter of .078 - .001 inches. The centrifugal lock shall be in engagement with the star wheel. The pin shall then be removed and the housing assembly shall be subjected to the test. The amount of travel of each rotor shall be noted. If the travel of any rotor exceeds 36 degrees the lot shall be rejected. All data concerning rotor travel shall be reported to Picatinny Arsenal, ATTN: SMUPA-QA-A-S. The test shall be performed as specified in 4.4.8 using equipment in accordance with 4.3.4.

4.3.3.13 Non-arming of centrifugal lock of housing assembly (see dwg. 8837946) Major Defect, Code No. 25001 .-This test shall be conducted one hundred percent (100%). If any assembly fails to comply with the requirements specified on the applicable drawing, it shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.9 using equipment in accordance with 4.3.4.

4.3.3.14 Arming of centrifugal lock of housing assembly (see dwg. 8837946) Major defect, Code No. 26001 .-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter M, singel plan, with an AQL of 0.25 percent. The test shall be performed as specified in 4.4.10 using equipment in accordance with 4.3.4.

4.3.3.15 Push out test of hammerweight assembly on center-plate assembly (see dwg. 8861223) Major Defect, Code No. 27001 .-Thirty-seven (37) centerplate assemblies shall be selected from each lot and the hammerweight assembly on each of the three legs of each assembly shall be subjected to this test. If two (2) or more hammerweight assemblies fail to comply with the requirement specified on the applicable drawing, the lot shall be rejected. The test shall be performed as specified in 4.4.11 using equipment in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.3.3.16 Security of stake of hammerweight assembly (see dwg. 8861222) Major Defect, Code No. 28001.-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter K, single plan with an AQL of 0.40 Percent. the test shall be performed as specified in 4.4.12 using equipment in accordance with 4.3.4.

4.3.3.17 Salt spray (see applicable drawings) Major Defect, Code No. 29001.-Sampling and rejection shall be in accordance with QQ-P-416, QQ-Z-325 or MIL-T-10727 as applicable. The test shall be performed as specified in 4.4.13 in accordance with 4.3.4.

4.3.3.18 Force test of hammerweight pin of centerplate assembly (see dwg. 8861223) Major Defect, Code No. 30001.-Thirty-seven (37) centerplate assemblies shall be selected from each lot and the hammerweight pin on each of the three legs of each assembly shall be subjected to this test. If two (2) or more hammerweight pins fail to comply with the requirement specified on the applicable drawing, the lot shall be rejected. The test shall be performed as specified in 4.4.14 using equipment in accordance with 4.3.4.

4.3.3.19 Push test of simulated setback pin into retainer setback pin (See dwg. 8876212), Major Defect, Code No. 31001.-One-hundred and twenty-five (125) setback pin retainers shall be selected from each heat-treat batch and subjected to this test. If two (2) or more of each one-hundred and twenty-five (125) fail to comply with the requirement specified on the applicable drawing, the batch represented by the sample shall be rejected. The test shall be performed as specified in 4.4.15 using equipment in accordance with 4.3.4.

4.3.3.20 Push test of retainer out of housing assembly (see dwg. 8837946) Major Defect, Code No. 32001.-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter K, single plan, with an AQL of 0.10 percent. Applies to one (1) pound minimum requirement only. The test shall be performed as specified in 4.4.16 using equipment in accordance with 4.3.4.

4.3.3.21 Verification of heat treat of centerplate (see paragraph (para.) 3.7) Major Defect, Code No. 33001.-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter H, single plan, with an AQL of 1.0 percent. The test shall be performed as specified in 4.4.16 using equipment in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.3.3.22 Security of rotor assembly (see dwg. 8837957) Major Defect, Code No. 34001.-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter K, single plan, with an AQL of 0.40 percent. The test shall be performed as specified in 4.4.17 using equipment in accordance with 4.3.4.

4.3.3.23 Qualification test for M55 detonator (see para. 3.11), Major defect, Code No. 42001.-One hundred (100) detonators shall be randomly selected from each detonator lot, assembled to M551 fuzes and subjected to this test. If one low order occurs out of 100 fuzes functioning, that detonator and lead cup combination shall be rejected for use in M551 fuzes and SMUPA-QA-A-S shall be notified.

NOTE: The detonators selected for this test shall be tested with the lead cup lot with which they will be used. Change in lead cup lot requires retest of detonators. The test shall be performed as specified in 4.4.19.

4.3.3.24 Heat seal test of packing seals (see dwg. 9205332) Major Defect, Code No. 46001.-Sampling and rejection shall be in accordance with MIL-P-116. The test shall be performed as specified in 4.4.20.

4.3.3.25 Fracture test of die cast adapter (see dwg. 9242549), Major Defect, Code No. 48001 (when applicable).-The sampling plan for this test shall be in accordance with MIL-STD-105, Code Letter K, single plan, with an AQL of 0.40 Percent. The test shall be performed as specified in 4.4.21 using equipment in accordance with 4.3.4.

4.3.3.26 X-ray examination of sample fuze assemblies prior to jolt and jumble tests (see 3.4), Critical Defect, Code No. 49001.-The samples selected for the tests specified in 4.3.3.27 and 4.3.3.28 shall be subjected to this test. If any assembly fails the requirement of 3.4, the lot shall be rejected. The test shall be performed as specified in 4.4.22 using equipment in accordance with 4.3.4.

4.3.3.27 Jolt (see para. 3.5), Major Defect, Code No. 35001.-Twelve (12) fuze assemblies shall be selected from each lot and subjected to this test. If any fuze assembly fails to comply with the applicable requirement, the lot shall be rejected. The test shall be performed as specified in 4.4.23 using equipment in accordance with 4.3.4.

4.3.3.28 Jumble (see para. 3.5) Major Defect, Code No. 36001 .-Ninety-six (96) fuze assemblies shall be selected from each lot and subjected to this test. If any fuze assembly fails to comply with the applicable requirement, the lot shall be rejected. The test shall be performed as specified in 4.4.23 using equipment in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:22Z
Check the source to verify that this is the currenversion before use.

4.3.3.29 Verification of heat treat of setback pin retainer (See Dwg. 8876212), Major defect, Code No. 50001.-After completion of test specified in 4.3.3.19, the three (3) setback pin retainers exhibiting the lowest push test force shall be subjected to this test. If any retainer fails to comply with the requirement specified on the applicable drawing, the heat treat batch represented by the sample shall be rejected. The test shall be performed as specified in 4.4.24 using equipment in accordance with 4.3.4.

4.3.3.30 Transportation vibration (see para. 3.3) Major Defect, Code No. 37001.-Eighty (80) fuze assemblies, less booster, shall be placed in their regular shipping container and subjected to this test. The test shall be performed as specified in 4.4.25 using equipment in accordance with 4.3.4.

4.3.3.31 Torque of fuze assembly (see dwg. 8862121) Major Defect, Code No. 38001.-After completion of test specified in 4.3.3.30, seventy-five (75) of the sample shall be subjected to this test. If four (4) or more fuze assemblies fail to comply with the requirement specified on the applicable drawing, the lot shall be rejected. Assemblies which failed this test shall be discarded and replaced with units which had been subjected to tests specified in 4.3.3.30, prior to subsequent testing. The test shall be performed as specified in 4.4.26 using equipment in accordance with 4.3.4.

4.3.3.32 Waterproofness (see para. 3.6) Major defect, Code No. 39001.-After completion of test specified in 4.3.3.30 and 4.3.3.31, seventy-five (75) of the samples shall be subjected to this test. If four (4) or more fuze assemblies fail to comply with the applicable requirement, the lot shall be rejected. Assemblies which failed this test shall be discarded and replaced with units which had been subjected to test specified in 4.3.3.30, prior to subsequent testing. The test shall be performed as specified in 4.4.27 using equipment in accordance with 4.3.4.

4.3.3.33 Functioning (see para. 3.8) Major defect, Code No. 40001.-After completion of tests specified in 4.3.3.30, 4.3.3.31 and/or 4.3.3.32, eighty (80) fuze assemblies assembled to a test cartridge shall be subjected to this test. Accept if two (2) or less assemblies fail to function and no premature burst occurs and reject if five (5) or more assemblies fail to function and one (1) premature burst occurs. When three (3) or four (4) assemblies fail to function in the first sample of eighty (80), an additional eighty (80) assemblies shall be subjected to this test. If a total of six (6) or less in the cumulative sample of one hundred sixty (160) assemblies fail to function and no premature burst occurs, the lot shall be accepted. If a

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:22Z
Check the source to verify that this is the current version before use.

total of seven (7) or more in the cumulative sample fail to function and one (1) premature burst occurs, the lot shall be rejected. The test shall be performed as specified in 4.4.28, using equipment in accordance with 4.3.4.

4.3.3.34 Non-functioning (see para. 3.9) Major Defect, Code No. 41001.-Thirty-two (32) additional fuze assemblies with inert boosters shall be selected from each lot and subjected to this test. If any fuze assembly functions, the lot shall be rejected. The test shall be performed as specified in 4.4.29 using equipment in accordance with 4.3.4.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 8862121 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.1 Government rights to documentation .-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures

4.4.1 Qualitative spot test for cadmium.-The rotor springs and lock springs shall be tested in accordance with the following procedure:

a. Clean the parts in acetone and place twenty-five (25) rotor spring or two (2) lock springs in a clean test tubes. Add 1.0 ml concentrated hydrochloric acid and allow cadmium to dissolve.
b. Decant fluid into a beaker and dilute with distilled water to total 100 ml.
c. Add 50 ml. of saturated hydrogen sulfide.
d. The development of a yellow precipitant indicates the presence of cadmium.

This test is a destructive test. Parts so tested shall not be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:22Z
Check the source to verify that this is the currentversion before use.

4.4.2 Stake of pinion assembly.-The pinion shall be placed in a fixture shown on the Equipment List and the torque specified on dwg. 8837948 shall be applied. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.3 Stake of verge assembly.-The verge assembly shall be placed in a fixture shown on the Equipment List and the load specified on dwg. 8837961 shall be applied. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.4 Stake of firing pin and spring assembly.-The firing pin and spring assembly shall be placed in a fixture shown on the Equipment List and the minimum twist specified on dwg. 8837939 shall be applied. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.5 Non-arming of centerplate assembly.-The centerplate assembly shall be placed in a fixture shown on the Equipment List and the load specified on dwg. 8861223 shall be applied to the push pin. The maximum non-arming travel shall be noted after rotating the assembly at the specified non-arming speed. This test is a non-destructive test. Parts so tested may be returned to the lot.

4.4.6 Arming of centerplate assembly.-The centerplate assembly shall be placed in a fixture and the load applied as specified in 4.4.5. The maximum push pin travel shall be noted after rotating the assembly at the specified arming spped. This test is a non-destructive test. Parts so tested may be returned to the lot.

4.4.7 Arming delay time and non-arming of housing assembly .-An electronic time device and electrically operated retractable simulated setback pin shall be operated simultaneously. A light source shall be concentrated on the detonator hole in the rotor. A photelectric cell shall not trip an electronic circuit before the non-arming time specified. For the arming time the photoelectric cell shall trip an electric circuit by the arming time specified. Other approved methods may be used. This test is a non-destructive test. Parts so tested may be returned to the lot.

4.4.8 Transportation vibration test of centrifugal lock mechanism.-The fuze assembly shall be tested as specified in MIL-STD-331. This test is a destructive test. Parts so tested shall not be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:22Z
Check the source to verify that this is the currentversion before use.

4.4.9 Non-arming of centrifugal lock of housing assembly.- Method 1: The housing assembly shall be mounted in a centrifuge and spun about its axis of symmetry at the rotational speed specified for a minimum of 0.400 seconds. Visually check to see that the rotor has not moved from the unarmed position. When the visual check provides doubtful results, a gage shall be used which simulates the maximum diameter setback pin. An unarmed housing assembly shall be capable of accepting the simulated setback pin through the rotor plate and rotor gear.
Method 2: The housing shall be mounted and spun as in Method 1. Upon completion of spin, a light source shall be concentrated on the rotor through the setback pin check hole in the top plate. A photoelectric cell shall trip an electric circuit. Other approved methods may be used. This test is a non-destructive test. Parts so tested may be returned to the lot.

4.4.10 Arming of centrifugal lock of housing assembly.-The housing assembly shall be mounted in a centrifuge and spun about its axis of symmetry at the rotational speed specified. A light source shall be concentrated on the detonator hole in rotor. A photoelectric cell shall trip an electric circuit. Other approved methods may be used. This test is a non-destructive test. Parts so tested may be returned to the lot.

4.4.11 Push out test of hammerweight assembly of centerplate assembly.-The centerplate assembly shall be placed in a fixture shown on the Equipment List and the force specified on dwg. 8861223 shall be applied. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.12 Security of stake of hammerweight assembly.-The hammerweight assembly shall be placed in a fixture shown on the Equipment List and the force specified on dwg. 8861222 shall be applied. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.13 Salt spray.-The parts selected shall be subjected to the salt spray test in accordance with Standard No. 151, Method 811.1 using a 5% sodium chloride solution. This is a destructive test. Parts so tested shall not be returned to the lot.

4.4.14 Force test of hammerweight pin of centerplate assembly .-The centerplate assembly shall be placed in a fixture shown on the Equipment List and the force specified on dwg. 8861223 shall be applied to the hammerweight pin. This test is a destructive test. Parts so tested shall not be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.4.15 Push test of simulated setback pin into retainer setback pin.-The retainer setback pin shall be placed in a fixture shown on the Equipment List and the force specified on dwg. 8861212 shall be applied to a simulated mean setback pin. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.16 Push test of retainer out of housing assembly.-The housing assembly shall be placed in a fixture shown on Equipment List and the push specified on dwg. 8837946 shall be applied to the retainer. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.17 Verification of heat treat of centerplate.-The centerplate shall be mounted in a steel ring similar to a cover dwg. 8861218. An axial push force shall be applied to the bottom surface along the axial centerline. This force must be applied evenly over a circular area concentric to the axis of the push pin hole, not to exceed .428 inch, in diameter. The magnitude of this force shall be read upon a deflection of the centerplate of .080 ± .005 inch. Other approved methods may be used. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.18 Security of rotor assembly.-The rotor assembly shall be placed in a fixture shown on the Equipment List and the force specified on dwg. 8837957 shall be applied. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.19 Qualification test for M55 detonator.-The detonator and lead cup shall be assembled to a M551 fuze and assembled to a test cartridge (dwg. 9231745). The test cartridge shall be conditioned at -65°F for 16 hours min. and fired in accordance with paragraph 4.4.28.

4.4.20 Heat seal test of packing seals.-This test shall be performed in accordance with MIL-P-116. Seals so tested shall not be returned to the lot.

4.4.21 Fracture test of die cast adapter (when applicable).-The adapter shall be placed in the fixture shown on the Equipment List and the load specified on dwg. 9242549 shall be applied. Observation shall be made for the requirement specified on dwg. 9242549. This test is a destructive test. Parts so tested may not be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:22Z
Check the source to verify that this is the current version before use.

4.4.22 X-ray examination of sample fuze assemblies prior to jolt and jumble tests.-Armed or partially armed fuze assemblies shall be determined by x-ray equipment or any other method satisfactory to the Contracting Officer. This test shall be conducted in two (2) phases:

a. From the top of the fuze assembly down.
b. From the side.

This test is a non-destructive test. Parts so tested may be returned to the lot.

4.4.23 Jolt and jumble.-The fuze assemblies, with a simulated booster assembled, shall be tested in accordance with the procedures specified in MIL-STD-331. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.24 Verification of heat treat of setback pin retainer.-The setback pin retainer shall be subjected to the Knoop hardness reading in accordance with ASTM Test Method D1474-68. This test is a destructive test. Parts so tested shall not be returned to the lot.

4.4.25 Transportation vibration.-The fuze assemblies shall be tested as specified in MIL-STD-331. Assemblies subjected to transportation vibration but not expended in subsequent testing shall not be returned to the lot.

4.4.26 Torque of fuze assembly.-The fuze shall be held firmly and the torque specified on dwg. 8862121 shall be applied to the adapter. The torque shall be applied in a clockwise direction when viewed from the adapter end of the fuze. This test is a non-destructive test. Parts so tested may be returned to the lot.

4.4.27 Waterproofness.-The fuze assembly shall be immersed in water to a depth of not less than 3 inches. The chamber shall be subjected to a vacuum pressure differential of 5 psi min. for a period of not less than 15 seconds. The water shall contain the wetting agent Niaconal NR (sodium alkyl aryl sulfonate) or equal in a concentration of approximately 1 1/2 teaspoonful per gallon of water. This test is a non-destructive test. Parts so tested may be returned to the lot.

4.4.28 Functioning.-The fuze shall be assembled to a test cartridge (dwg. 9231745). The cartridge shall be fired from a launcher for which it is standard to impact at approximately 200 yards from the launcher on a six inch thick loose gravel pad. The gravel pad used shall have a 1/2 inch minimum stone size. Observation shall be made for proper high order functioning. This test is a destructive test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.4.29 Non-functioning.-The fuze shall be assembled to a projectile for which it is standard and then to a loaded cartridge case for which it is standard. The cartridge shall be fired from a launcher for which it is standard against a vertical plywood target placed 45 feet from point of fire. Observation shall be made for non-functioning. This test is a destructive test. Plywood target thickness must resist penetration. Advisory: 3/4 inch thickness.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level C.-The fuzes shall be packed in accordance with dwg. 9205332.

5.2 Packing

5.2.1 Level C.-The containers shall be packed in accordance with dwg. 9230367.

5.3 Shipping.-When shipments of more than one lot are made as a carload, each lot must be kept separate, and the division between lots clearly indicated, to prevent mixing in transit.

5.4 Marking.-Marking shall be in accordance with dwg. 8799112.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (see 6.3.5).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availablility of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings of Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.

MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army design fall into two basic classifications: Mandatory (designated "MU:") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army Designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (see 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category A, Form 3. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor designs.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revisions letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-QA-A-S. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed to the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally, within one month after receipt.

6.4 Cost of check test.-The Contracting Officer will arrange for the contractor to be reimbursed for the expense incurred in the performance of the check test for deterioration of the detonator or lead cup assemblies. The tests shall be conducted at Government expense without cost to the contractor who loaded the detonator or lead cup assemblies or to the contractor

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

assembling the detonator or lead cup assemblies into the fuze, and shall not constitute a basis for rejection against either contractor except where deterioration has occurred as a direct result of carelessness in handling, storage, etc., permitted while the detonator or lead cup assembly lot was under the jurisdiction of either contractor.

6.5 Submission of test data.-In addition to the normal distribution of records, when the fuze is procured by the U.S. Army Munitions Command, one (1) copy of all ballistic data shall be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-QA-A-S.

6.6 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-QA-A-S.

6.7 Premature burst.-A premature burst is considered to have occurred if the round functions in the gun bore or in flight.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1390-A-016

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:22Z
Check the source to verify that this is the current version before use.