MIL-M-60923A (MU)
4 June 1970
SUPERSEDING
MIL-M-60923 (MU)
22 November 1967

MILITARY SPECIFICATION

MINE, APERS, M26

LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of mine designated as Mine, APERS, M26.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATION

MILITARY

MIL-P-116	-	Preservation, Methods of
MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-I-45607	-	Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-286	-	Propellants, Sampling, Examination and Testing
MIL-STD-1168	-	Lot Numbering of Ammunition
MIL-STD-1235	-	Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

US ARMY MUNITIONS COMMAND

8822121	-	Container, Fiber, Ammunition, M406A2, for Mine, Apers, M26, HE, w/Integral Fuze
8822122	-	Box, Packing, Ammunition, for Mine, Apers, M26, HE, w/Integral Fuze
8840286	-	Mine, Apers, M26, HE, w/Integral Fuze

PUBLICATIONS

ARMY

ET-8840286	-	Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

2.2 Other publications.-The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

CODE OF FEDERAL REGULATIONS

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

Title 49 - Transportation, Parts 171-179

(The Code of Federal Regulations is available from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402. Orders should specify 49 CFR 171-179 (latest revision).)

3. REQUIREMENTS

3.1 Materials and parts shall be in accordance with the applicable drawings and specifications.

3.2 Mine.-The mine shall comply with all requirements specified on Drawing (Dwg) 8840286, all associated drawings, and with all requirements specified in applicable specifications.

3.3 Functioning.-The ball float assembly shall be ejected and shall detonate satisfactorily at a burst height between one (1) and nine (9) feet when tested as specified in 4.3.8.

3.3.1 Suitability test (for informational use only).-The mines shall function as specified in 3.3 after conditioning as specified in 4.3.9. The test shall be performed as specified in 4.3.8.

3.4 Workmanship.-All parts and assemblies shall be fabricated, loaded and assembled in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, grease, rust and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches not exposed base material. All required markings shall be neat and sharply defined.

3.5 Submission of results of contractor-conducted examinations and tests.-The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract, (See 6.4)

4. QUALITY ASSURANCE PROVISIONS

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 in order to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified within this specification.
b. Number of units of product inspected.
c. Results obtained, by code number, for all inspections performed.
d. Drawing, specification number and date, together with an identification and date of changes.
e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commerical specifications referenced in any of the contractual documents.
f. Number of items in the lot.
g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 Inspection provisions

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.2.1 Lot formation.-The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the samples was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process using the same materials and methods, in accordance with the same drawings, same drawing revisions, same specifications, and same specification revisions. Changes to the process, specifications, or drawings, not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of the lot. Inspection lots shall comply with MIL-STD-105.

Unless otherwise approved by the Contracting Officer, the inspection lot size of end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period. Inspection lots of components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size mutually convenient to both the contractor and the Government inspector. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each lot of loaded mines shall contain:

a. Parts and part assemblies of one lot interfix number from one manufacturer.
b. Comp B of one lot interfix number from one manufacturer.
c. M9 Ignition cartridge powder of one lot.
d. Delay assemblies of one lot. Each lot of delay assemblies shall contain:

(1) Booster pellets of one lot interfix number from one manufacturer.
(2) Igniter Composition from one batch or accumulation of batches produced in one unchanged process, of which each ingredient shall be from one lot.
(3) Lead azide of one lot interfix number from one manufacturer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.2.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with MIL-STD-105 (ABC-STD-105) except that, unless otherwise specified herein, inspection for Critical defects shall be 100 percent. Contractor's sampling plans, if used, shall be approved by the Government and shall provide, as a minimum, the protection afforded the Government by the sampling plans in MIL-STD-105 (ABC-STD-105). Continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each Major defect and an AQL of 0.65 percent for each Minor defect. In addition, at the option of the procuring activity, defect characteristics of the same classifications, which have been separated into two (2) groups to specifically allow the optional method of inspection in accordance with 4.2.3.1 and 4.2.3.2, may be combined into one (1) group when the option of 4.2.3.1 or 4.2.3.2 is not exercised. The AQL for the combined grouping will be as indicated in the applicable classification of defects paragraph. Equipment necessary for the performance of the inspection listed shall be in accordance with 4.2.4.

4.2.2.1 Plug Sealing (See Dwg. 9251874).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Length of plug body, max.	Gage	30001
102.	Diameter of plug body, min.	Gage	30002
Minor	AQL 1.50 Percent		
201.	Total length, min.	Gage	30003
202.	Large diameter (each end)	Gage	30004
203.	Length of small end	Gage	30005
204.	Evidence of poor workmanship	Visual	30006

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.2.2.2 Pellet, booster (See Dwg 8840331 covering a detail of Dwg 8840328).-

Categories	Defects	Method of Inspection	Code No. (See 6.2)
Critical:	None defined		
Major	AQL 0.40 Percent (See 4.2.3.1)		
101.	Length, minimum (min)	Gage	01001
102.	Part damaged (cracked, chipped or broken edge)	Visual	01002
Minor	*AQL 0.65 Percent (See 4.2.3.1)		
202.	Foreign matter	Gage	01003

*Combined AQL for Minor defects 201 and 202 is 1.00 Percent (See 4.2.2)

4.2.2.3 Cup, booster (See Dwg 8840329 covering a detail of Dwg 8840328).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent (See 4.2.3.2)		
101.	Inside diameter	Gage	02001
Minor	*AQL 1.00 Percent (See 4.2.3.2)		
201.	Depth to bottom	Gage	02002
202.	Thickness through bottom, min	Gage	02003
Minor	AQL 0.65 Percent		
203.	Evidence of poor workmanship (See 3.4)	Visual	02004

*Combined AQL for Minor defects 201, 202 and 203 is 1.50 percent (See 4.2.2)

4.2.2.4 Container, delay (See Dwg 8840334 covering a detail of Dwg. 8840333).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

Major	AQL 0.40 Percent (See 4.2.3.2)		
101.	Total length	Gage	03001
102.	Inside diameter, max	Gage	03002
Minor	*AQL 1.00 Percent (See 4.2.3.2)		
201.	Diameter of hole	Gage	03003
202.	Outside diameter	Gage	03004
Minor	AQL 0.65 Percent		
203.	Evidence of poor workmanship (See 3.4)	Visual	03005

*Combined AQL for Minor defects 201, 202 and 203 is 1.50 Percent (See 4.2.2)

4.2.2.5 Delay charge assembly (See Dwg 8840333 covering a detail of Dwg 8840328).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Depth to tetryl charge, max	Gage	04001
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	04002

4.2.2.6 Delay housing and charge assembly (See Dwg 8840332 covering a detail of Dwg 8840328).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Delay charge assembly inverted	Visual	05001
102.	Crimp missing	Visual	05002
Minor	AQL 1.00 Percent		
201.	Crimp less than 360°	Visual	05003
202.	Evidence of poor workmanship (See 3.4)	Visual	05004

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.2.2.7 Delay assembly (prior to assembling booster cup) (See Dwg 8840328).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.65 Percent		
101.	Booster pellet missing	Visual	06001
102.	Booster pad missing	Visual	06002
103.	Delay charge assembly missing	Visual	06003
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	06004

4.2.2.8 Delay assembly (See Dwg 8840328).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Diameter in crimp groove, max	Gage	07001
102.	Length to housing flange, max	Gage	07002
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	07003

4.2.2.9 Container (See Dwg 8840347 covering a detail of Dwg 8840295).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Width of tab, min	Gage	08001
102.	Location of tab	Gage	08002

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

Minor	AQL 1.00 Percent		
201.	Largest inside diameter propellant cavity	Gage	08003
202.	Evidence of poor workmanship (See 3.4)	Visual	08004

4.2.2.10 Propellant container assembly (See Dwg 8840295 covering a detail of Dwg 8840286).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Total height, max	Gage	09001
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	09002

4.2.2.11 Cup loading assembly (prior to loading) (See Dwg 8840340 covering a detail of Dwg 8840294).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Internal protective coating not dry or inadequate (bare spot)	Visual-Manual	10001
102.	Foreign matter on interior	Visual	10002

Minor: None defined

4.2.2.12 Cup loading assembly (See Dwg 8840340 covering a detail of Dwg 8840294).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

Major	AQL 0.65 Percent		
101.	Depth of delay cavity	Gage	11001
102.	Concentricity of delay cavity diameter with obturator hole, including perpendicularity	Gage	11002
103.	Diameter of delay cavity, max	Gage	11003
104.	Obturator not free of explosive	Visual	11004
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	11005

4.2.2.13 Ball float assembly (See Dwg 8840294 covering a detail of Dwg 8840286).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	Torque of cut-off plug	Test	12001
102.	Location of obturator notch with cut-off plug in delay assembly	Gage	12002
103.	Delay assembly not seated properly	Visual	12003
104.	Flash hole not completely closed by cut-off plug	Visual	12004
105.	Obturator or cup damaged	Visual	12005
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	12006

4.2.2.14 Cover and arming latch assembly (prior to assembling to mine) (See Dwg 8840286).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	O-ring missing (2)	Visual	13001
102.	Grease missing from either O-ring	Visual	13002

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	13003

4.2.2.15 Mine (prior to assembling cover and arming latch assembly (See Dwg. 8840286).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	Propellant container protrusion not seated in obturator notch	Visual	14001
102.	Propellant container above flush	Visual	14002
103.	Red cover on propellant container not visible	Visual	14003
104.	Propellant container assembly damaged	Visual	14004
105.	Disc missing	Visual	14006
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship on interior (See 3.4)	Visual	14005

4.2.2.16 Mine assembly (See Dwg 8840286).-

Categories	Defects	Method of Inspection	Code No.
Critical			
1.	Cotter pin improperly assembled	Visual	15001
2.	Arming latch fingers not seated under cam flange	Visual	15002
Major	AQL 1.00 Percent		
101.	Sealing plug loose or missing	Visual-Manual	15003
102.	Take-up ring insecure	Manual	15004
103.	Trip lever missing	Visual	15005
104.	Arming instructions tag missing or instructions thereon incorrect or illegible	Visual	15006
105.	Coverlocking pin missing	Visual	15007

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

106.	Spool assembly damaged	Visual	15008
107.	Arming latch handle missing	Visual	15009
108.	Marking misleading or unidentifiable	Visual	15010
109.	Arrow on cover ring not aligned with letter "S" on body	Visual	15010
110.	Spool retainer missing	Visual	15012
Minor	AQL 1.00 Percent		
201.	Letter "A" and its recess in body not painted or color improper	Visual	15013

4.2.2.17 Fiber container, prior to closing (See Dwg 8822121).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.65 Percent		
101.	Number of mines incorrect	Visual	16001
102.	Mine inverted	Visual	16002
103.	Insufficient fillers	Visual	16003
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (see 3.4)	Visual	16004

4.2.2.18 Fiber container (sealed) (See Dwg 8822121).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Container damaged exposing contents	Visual	17001
102.	Sealing strip insecure	Visual	17002
Minor	AQL 0.65 Percent		
201.	Marking misleading or unidentifiable	Visual	17003

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.2.2.19 Box, packing (prior to sealing) (See Dwg 8822122).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Fiber container missing	Visual	18001
102.	Insufficient fillers	Visual	18002
Minor:	None defined		

4.2.2.20 Box, packing (sealed) (See Dwg 8822122).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.65 Percent		
101.	Sealing or strapping insecure	Manual-Visual	19001
102.	Box damaged	Visual	19002
103.	Marking misleading or unidentifiable	Visual	19003
Minor:	None defined		

4.2.3 Testing.

4.2.3.1 Dimensional control of booster pellet (See 4.2.2.1 and Dwg 8840331) Code Nos as indicated in 4.2.2.1.-In place of the normal sampling associated with the classification of defects, and with the approval of the Contracting Officer, the defects specified in 4.2.2.1 may be checked as follows:

One (1) pellet from each pelletizing tool used in production shall be subjected to these measurements at the start of each new pellet lot, at the start of production each day, and after every four (4) hours of production each day, and whenever a new, repaired or adjusted pelletizing tool is put into use for production. If any pellet fails to comply with the drawing requirements, the production from that tool shall be stopped and the necessary repairs completed until two (2) consecutively produced pellets comply with the requirements. The inspection equipment used shall be in accordance with 4.2.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.2.3.2 Dimensional control of stamped parts.-In place of the normal sampling associated with the classifications of defects, and with the approval of the Contracting Officer, a sample of at least ten (10) parts may be dimensionally inspected to qualify the tool used in the stamping process for use in production. In addition, a random sample of five (5) parts shall be selected from the last portion of each hour's production for dimensional inspection as a control of the tool during production.

If any defective parts are found during qualification of the tool, the tool producing the defective part shall not be used in production.

If any defective parts are found when inspection is performed for control of the tool, the tool producing the defective part shall be removed from production. Further, that portion of production since the last tool control check shall be returned to the contractor for corrective action.

All tools removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the Contracting Officer to substantiate the request.

4.2.3.3 Moisture content of igniter composition (See Dwg 8840333) Major defect, Code No. 20001.-The contractor shall provide adequate controls to insure compliance with the applicable requirements. The moisture content of each lot of igniter composition shall be determined at the loading station at the time of loading the container. This determination shall be made at least once each eight (8) hours of production. In addition, if the moisture content fails to comply with the requirement specified on the applicable drawing, and loading has not begun, the lot shall be rejected until corrective action has been taken as verified by repeating the moisture content determination. If loading has begun, delay containers loaded with the non-conforming composition shall be rejected. This determination shall be performed as specified in 4.3.1.

4.2.3.4 Quick leak test of sealed barrier (See Dwg 8862514 and MIL-P-116) Major Defect, Code No. 21001.-This test shall be performed using sampling and acceptance procedures specified in MIL-P-116 (para 4.2.2.3.2) with the following exceptions: for normal inspection, use MIL-STD-105, Table I, Special Inspection Level S-3

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

with an AQL of 4.00 percent; for reduced inspection, use Special Inspection Level S-2 of the table with an AQL of 4.00 percent. If any bag assembly fails to comply with the requirements specified on the drawing and MIL-P-116, it shall be classed defective. The test shall be performed as specified in 4.3.2 using equipment in accordance with 4.2.4.

4.2.3.5 Leakage test of propellant container assembly (See Dwg 8840295) Major Defect, Code No. 22001.-Eighty (80) propellant container assemblies shall be selected from each lot and subjected to this test. If two (2) or more assemblies fail to comply with the requirement specified on the applicable drawing, the lot shall be rejected. The test shall be performed as specified in 4.3.3 using equipment in accordance with 4.2.4.

4.2.3.6 Specific gravity of charge in cup loading assemblies (See Dwg 8840340) Major Defect, Code No. 23001.-Two (2) cup loading assemblies shall be selected from each loading machine after every four (4) hours of production and subjected to this determination. If any assembly fails to comply with the specific gravity requirement specified on the applicable drawing, the four (4) hour's production represented by the sample shall be rejected. The test shall be performed as specified in 4.3.4.

4.2.3.7 Torque test of cover assembly on Mine (See Dwg 8840286) Major Defect, Code No. 24001.-Eighty (80) mine assemblies shall be selected from each lot and subjected to this test. If two (2) or more assemblies fail to comply with the requirement specified on the applicable drawing, the lot shall be rejected. The test shall be performed as specified in 4.3.5 using equipment in accordance with 4.2.4.

4.2.3.8 Pull test of cotter pin or mine assembly (See Dwg 8840286) Major Defect, Code No. 25001.-Eighty (80) mine assemblies shall be selected from each lot and subjected to this test. If two (2) or more cotter pins fail to comply with the requirement specified on the applicable drawing, the lot shall be rejected. The test shall be performed as specified in 4.3.6 using equipment in accordance with 4.2.4.

4.2.3.9 Air pressure test of mine assembly (See Dwg 8840286) Major Defects, Code No. 26001.-Eighty (80) mine assemblies shall be selected from each lot and subjected to this test. If two (2) or more mine assemblies fail to comply with the requirement specified on the applicable drawing, the lot shall be rejected. The test shall be performed as specified in 4.3.7 using equipment in accordance with 4.2.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.2.3.10 Functioning (See 3.3) Major Defect, Code No. 27001.- Beginning with the first lot produced and continuing until three (3) consecutive lots have been accepted under the acceptance criteria specified, the Government inspector shall select one hundred fifty (150) mines from each lot for this test. Seventy-five (75) mines shall be tested in the pull phase and seventy-five (75) mines shall be tested in the static load phase. The test shall be performed as specified in 4.3.8. (See 4.2.3.12)

4.2.3.10.1 Rejection.-The lot shall be rejected if:

(a) Five (5) or more mines fail to have their ball float assemblies detonate, or if
(b) Seven (7) or more mines have their ball float assemblies detonate in the body of the mine, or if
(c) Twelve (12) or more mines fail to have their ball float assemblies detonate at the proper height.

4.2.3.11 Functioning (See 3.3) Major Defect, Code No. 27001.- After three (3) consecutive lots have met the criteria of 4.2.3.10, the Government inspector shall select fifty (50) mines from each lot for this test. Twenty-five (25) mines shall be tested in the pull phase and twenty-five (25) mines shall be tested in the static load phase. The test shall be performed as specified in 4.3.8. If any lot fails the following acceptance criteria, the lot shall be rejected.

4.2.3.11.1 Rejection.-The lot shall be rejected if:

(a) Two (2) or more mines fail to have their ball float assemblies detonate, or if
(b) Four (4) or more mines have their ball float assemblies detonate in the body of the mine, or if
(c) Six (6) or more mines fail to have their ball float assemblies detonate at the proper height.

4.2.3.12 Suitability test (See 3.3.1) Code No. 28001.- This test shall be performed on the first lot and shall be performed on each lot when inspection is being performed in accordance with 4.2.3.10. Sixty (60) mines shall be selected from each lot, conditioned, and tested as specified in 4.3.9. This test is for informational purposes only and shall be discontinued when the requirements of 4.2.3.11 are in effect.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.2.3.13 Propellant charge establishment for informational purposes.-Prior to assembly into mines, the propellant charge weight will be established for each lot of delay assemblies by adjusting the charge weight to bracket the midpoint of the requirements of 3.3. A minimum of twenty (20) mines will be used for this establishment. The test shall be performed as specified in 4.3.10.

4.2.3.14 Looseness of mine internal parts (See Dwg 8840286) Major Defect, Code No. 29001.-This test shall be performed 100 percent. Assemblies failing to meet the specified requirements shall be classified defective. The test shall be performed as specified in 4.3.11.

4.2.3.15 Security of Sealing Plug (See Dwg 8840286) Major Defect Code No. 30001.-Eighty (80) mine assemblies shall be selected from each lot and subjected to this test. If two (2) or more sealing plugs fail to comply with the requirement specified on the applicable drawing, the lot shall be rejected. The test shall be performed as specified in 4.3.12 using equipment in accordance with 4.2.4.

4.2.4 Inspection equipment.-Equipment Tabulation (ET) number 8840286 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.2.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction survey and whenever inspection equipment drawings are needed.

4.2.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3 Test methods and procedures.

4.3.1 Moisture content of igniter composition.-The moisture content of the igniter composition shall be determined at the time and place of loading and in accordance with MIL-STD-286, Method 101.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.3.2 Quick leak test of sealed barrier bag.-The sealed barrier bags shall be subjected to the quick leak test using test procedures specified in MIL-P-116. Observation shall be made to determine evidence of leakage in accordance with MIL-P-116.

WARNING: The following tests are conducted on assemblies containing explosives. Test barricades (where used), procedures and equipment shall have prior approval.

4.3.3 Leakage test of propellant container assembly.-The propellant container assembly shall be placed in the fixture specified on the Equipment List and the vacuum specified on Dwg 8840295 shall be applied. This is a destructive test. Parts so tested shall not be returned to the lot.

4.3.4 Specific gravity of charge in cup loading assembly.-The cup assemblies shall be weighed empty, then filled with water and reweighed. The water shall be removed and the assembly loaded with explosive under conditions identical in all respect with those employed in regular production loading of the cups. The delay cavity shall be drilled and the loaded sample weighed. The specific gravity shall be determined as follows:

$$\text{Specific gravity} = \frac{Wt - We}{Wm - We - (Wb - Wt)}$$

where:

We = Weight of empty cup assembly.
Wm = Weight of water-filled cup assembly.
Wt = Weight of loaded cup assembly, with empty delay cavity.
Wb = Weight of loaded cup assembly, with water-filled delay cavity, all weights are in grams

4.3.5 Torque test of cover assembly on mine.-The mine assembly shall be placed in the fixture specified on the Equipment List and the torque specified on Dwg 8840286 shall be applied to the cover assembly. This is a non-destructive test. Parts so tested may be returned to the lot.

4.3.6 Pull test of cotter pin on mine assembly.-The mine assembly shall be placed in the fixture specified on the Equipment List and the pull specified on Dwg 8840286 shall be applied to the cotter pin. This is a non-destructive test. Parts so tested may be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.3.7 Air pressure test of mine assembly.-The mine assembly shall be placed in the fixture specified on the Equipment List and the air pressure specified on Dwg 8840286 shall be applied. This is a non-destructive test. Parts so tested may be returned to the lot.

4.3.8 Functioning.-(This test shall be performed at a Government-owned proving ground.)

4.3.8.1 Vertical force.-The mine assembly, in the safe position, shall be placed in area approximately five (5) feet long and five (5) feet wide and twelve (12) inches deep, consisting of gravel approximately 1/4 inch in size. As an alternative, the mine assembly may be set in a steel cylinder with a steel base used as a holding device, and placed in the ground so that the cover is exposed. The spool assembly may be left off during the test.
Functioning of the mine shall be recorded on film using a film speed of 64 frames per second, minimum. The mine shall be placed in a vertical position in the ground and then rotated to the armed position. CAUTION: The mine is now in the functioning position. All safety regulations shall be observed.
A wheel weighing 24.5 $\pm$ .5 pounds shall be rolled down a track approximately two feet in length, at an incline of 15 degrees, and positioned to pass over the cover. (Optional procedure: A wheel weighing 24.5 $\pm$ .5 pounds shall be rolled over the embedded mine using a level track as a guide. The wheel shall be rolled over the mine at a steady rate using any approved method.) If the mine fails to function on the first attempt, there shall be a waiting period of not less than thirty (30) minutes, then the test area checked for any irregularities, and the test repeated. For purposes of this test, a mine will be classed a dud when it fails to function after the weight has passed over and contacted the cover twice, as determined by the Proof Director. In those instances where the Proof Director determines that the weight has not contacted the cover, it shall be declared, "No-test". Duds shall be destroyed in place in accordance with standing operating procedures.

4.3.8.2 Pull force.-The mine shall be implanted, or mounted in an approved fixture, as specified in 4.3.8.1. The trip level shall be threaded into the cam on the cover assembly of the unarmed mine. Attach a lanyard to the end of the arming latch handle. The lanyard will extend to the barricade. From the end of the arming latch handle measure four (4) feet along the lanyard and attach a six or seven foot nylon cord. Attach the opposite end of the cord to the top of the installed trip lever. The arming latch handle will then be assembled to the lugs on the arming latch. The mine cover shall

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:22Z
Check the source to verify that this is the current version before use.

then be rotated to the armed position by using the arming latch handle to rotate the cover assembly in a clockwise direction, approximately 100 degrees to a fixed stop (slightly past "A" position). CAUTION: The mine is now in the functioning position. All safety regulations shall be observed.
The mine shall be positioned so that the attached arming latch handle now is in the same direction as the lanyard to permit the arming latch to be easily withdrawn from the mine. This procedure is such that a pull on the lanyard will, first, pull the arming latch off the mine and then exert the required force on the trip lever to function the mine.
Functioning of the mine shall be recorded on film using a film speed of 64 frames per second, minimum. If the mine does not function due to breakage of the lanyard or trip lever cord, or due to other causes not attributed to the mine, as determined by the Proof Director, it shall be declared, "No-test" and the mine destroyed in place in accordance with the standard procedure. If the mine does not function after the required force has been exerted on the trip lever, it shall be classed as a dud and destroyed in place in accordance with the standard procedure. (Note - the lanyard and trip lever cord should be examined after each firing for damage.)

4.3.9 Suitability test.-The sixty (60) mines selected shall be conditioned as follows:

a. Twenty (20) mines temperature-conditioned at 165 degrees Fahrenheit (^{o}F) $\pm$ 4°F for 72 $\pm$ 1/2 hours
b. Twenty (20) mines temperature-conditioned at -40°F $\pm$ 4°F for 72 $\pm$ 1/2 hours
c. Twenty (20) mines immersed in water, twelve (12) $\pm$ 2 inches in depth, at a temperature of + 70°F $\pm$ 30°F for 72 $\pm$ 1/2 hours

After conditioning, the mines shall be functioned within fifteen (15) minutes after removal from the conditioning media. The test shall be performed as specified in Test and Evaluation Command (TECOM) Materiel Test Procedures TECP 700-700. Thirty (30) mines consisting of ten (10) mines from each conditioning phase indicated in a, b and c, shall be subjected to the vertical force test and the remaining thirty (30) mines subjected to the pull force test.

4.3.9.1 Submission of results.-Suitability test results, failure analysis reports, and other information, as requested, shall be forwarded for informational purposes only, as specified in 6.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

4.3.10 Propellant Charge establishment.-The mines shall be tested as specified in either 4.3.8.1 or 4.3.8.2 to determine proper charge establishment. Data shall be recorded as specified in 4.3.8. Test results shall be forwarded to Picatinny Arsenal, ATTN: SMUPA-ND3.

4.3.11 Looseness of mine internal components.-Each complete mine assembly shall be manually rotated in a vertical plane to ensure internal components are secure as evidence by the absence of movement of the internal parts.

NOTE: CAUTION, prior to this inspection operation it shall be determined for each mine that the arrow on the cover ring is aligned with the letter "S" on the body.

4.3.12 Security of Sealing Plug.-The mine assembly shall be placed in the fixture specified on the Equipment List and the pull specified on Dwg 8840286 shall be applied to the Seal Plug. This is a non-destructive test. Parts so tested may be returned to the lot.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Level A.-The mines shall be preserved and package in accordance with Dwg 8822121.

5.2 Packing.

5.2.1 Level A.-This mines preserved and packaged as specified in 5.1.1, shall be packed in accordance with Dwg 8822122.

5.3 Marking.-Marking shall be in accordance with Dwg 8822121, 8822122, Code of Federal Regulations, Title 49, Parts 171-179 and Army Regulation AR 380-55.

5.4 Shipping.-When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in MIL-STD-1167.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:22Z
Check the source to verify that this is the current version before use.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.6.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.6. Action required by the contractor with respect to the use of commercial equipment is detailed in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3, 6.3.4 and 6.3.5 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however in connection with non-mandatory designs, and with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (See 6.3.4) or commercial equipment selections (See 6.3.5) must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.6.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:22Z
Check the source to verify that this is the current version before use.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to MIL-D-1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit one copy of final designs as a rolled set. Designs shall be submitted for approval as specified in 6.3.6.

6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors, normally, are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. When commercial inspection equipment requires the use of special fixturing, the design of this fixturing shall be considered as part of the total design, and 6.3.4 shall apply. In the latter case, only those portions of the commercial equipment need be detailed in the designs as are necessary to completely fabricate, calibrate, and operate the total item of inspection equipment. Lists and fixturing designs shall be submitted for approval as specified in 6.3.6.

6.3.6 Submission of contractor designs.-All submitted designs shall reference the applicable five-digit code number contained in Section 4 of this specification. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as Critical and Major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the Contracting Officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs, Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:22Z
Check the source to verify that this is the current version before use.

6.4 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1345-A230

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
PICATINNY ARSENAL
DOVER, NEW JERSEY 07801

OFFICIAL BUSINESS

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

COMMANDING OFFICER
United States Army
Picatinny Arsenal
ATTN: SMUPA-ND
Dover, New Jersey 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION | CITY AND STATE

CONTRACT NO. | QUANTITY OF ITEMS PROCURED | DOLLAR AMOUNT $

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)* | DATE

DD FORM 1 OCT 64 1426

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:22Z
Check the source to verify that this is the current version before use.