MILITARY SPECIFICATION

TRUCK, CARGO; 5-TON, M656

1. SCOPE

1.1 Scope. This specification covers the high mobility general and special purpose 5-ton multi-fuel engine powered, eight-wheel, eight-wheel drive, military truck having single tires on all wheels. This vehicle shall swim inland water-ways, operate cross-country, and be air transportable.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

Federal

O-A-548	-	Antifreeze, Ethylene Glycol, Inhibited.
JJ-B-185	-	Belt, Seat, Passenger, Type, Automotive.
RR-W-410	-	Wire, Rope and Strand.
CCC-C-428	-	Cloth, Duck, Cotton: Fire, Water, Weather, and Mildew Resistant.

Military

MIL-P-514	-	Plates: Identification, Instruction and Marking Blank.
MIL-L-2104	-	Lubricating Oil, Internal Combustion Engine (Heavy Duty).
MIL-E-55301	-	Electromagnetic Compatibility.
MIL-V-62038	-	Vehicles, Wheeled: Preparation for Shipment and Storage of.

STANDARDS

Federal

FED. STD. NO. 595 - Colors.

Military

MIL-STD-130	-	Identification Marking of U. S. Military Property.
MIL-STD-193	-	Painting Procedures, Tactical Vehicles (Tracked and Wheeled).
MIL-STD-210	-	Climatic Extremes for Military Equipment.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:23Z
Check the source to verify that this is the current version before use.

MIL-STD-281 - Automobiles, Trucks, Truck-Tractors, Trailers and Trailer Dollies; Preservation and Packaging of.
MIL-STD-642 - Identification Marking of Administrative Combat, and Tactical Transport Vehicles.
MIL-STD-814 - Requirements for Tiedown, Suspension and Extraction Provision on Military Material For Air Delivery.

PURCHASE DESCRIPTION
DAPD-833 - Tire, Pneumatic: Wide Base, for Military Ground Vehicles.
DAPD-292 - Engine, Multi-fuel: 6-Cylinder, 195 H. P., LDS-465-1A.

PUBLICATIONS
Engineering Parts Lists (EPL)
8736700 - Engineering Parts List for Truck, Cargo; 5-Ton, 8x8, M656.
Master Lists
8736700 - Master List of Supplementary Quality Assurance Provisions for Truck, Cargo, 5-Ton, 8x8, M656.
8736700 - Master List of Inspection Equipment Drawings for Truck, Cargo, 5-Ton, 8x8, M656.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Preproduction vehicle. When specified (see 6.2), a preproduction model of the complete vehicle to be furnished under this specification shall be produced prior to the manufacture or fabrication of vehicles in quantity. The vehicle, when complete, shall be submitted to the Government for examination and tests to determine conformance to the requirements of this specification. Vehicle submitted by the contractor shall be fully representative of vehicles proposed to be supplied by the vehicle manufacturer from production facilities and tooling under the supply contract.

3.2 First production vehicle. One of the first 10 vehicles produced under the contract shall be submitted to representatives of the procuring activity for inspection and tests specified herein, to determine conformance to the requirements of this specification. Acceptance of the first production vehicle shall not establish the acceptability of the remaining vehicles under contract in conflict with the acceptance levels specified herein. Vehicle sample submitted by the contractor shall be fully representative of units proposed to be furnished throughout the duration of the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.2.1 Workmanship and reliability. The workmanship shall be of a quality to assure that the vehicle and components thereof are free from any defects that compromise, limit or reduce the vehicle or component capabilities herein specified. Vehicles manufactured in accordance with this design shall be subjected to examinations and tests by the Government to prove vehicle capabilities and performance in accordance with the following:

(a) Vehicle shall require only organizational maintenance (first and second echelon) during 10,000 miles of reliability operation.
(b) Vehicle shall require no replacement or major overhaul of any major automotive component during 20,000 miles of reliability operations.

3.2.1.1 Reliability operations. To assure that workmanship and reliability requirements are met during the 20,000 miles of operation, the vehicle with a rated payload and towed load for 50 percent of the mileage shall be capable of operating as follows:

(a) 40 percent on paved roads either concrete or asphalt or any combination of the two.
(b) 30 percent on secondary road.
(c) 30 percent on cross-country terrain.
(d) 8 hours of swimming in calm inland waters.

3.3 Materials. Materials as specified herein and in the referenced drawings, specifications, and standards shall be free from all defects and imperfections that might affect the serviceability and function of the finished product.

3.3.1 Qualified products. With respect to all assemblies and component parts requiring product qualification in accordance with the pertinent specifications or drawings listed on the EPL cited in 3.4, and necessary in the construction of this vehicle, the contractor shall be responsible for using only those products which are listed (by part or drawing number as QPL items) on the QPL in the referenced specification or which have been approved for inclusion on such lists. Manufacturer's inspection records shall specifically list such component(s), name of supplier(s) (as listed on the QPL or in the approval letter), and number and date of the QPL from which the selection was made or date of approval letter when products are approved but not as yet listed on the QPL.

3.4 Construction. Vehicles, components, subassemblies, and assemblies shall be fabricated and assembled into a complete vehicle in accordance with drawings listed or referred to in Engineering Parts List (EPL) 8736700. All parts requiring identification shall be marked in accordance with MIL-STD-130.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.4.1 Seals. When fording or operating amphibiously, the seals shall restrict the entrance of foreign matter into the bearings which are exposed to contamination during those operations. Contamination of lubricants shall not be more than 2 percent by volume. All bearing seals shall restrict the leaking of lubricants from the bearings.

3.4.2 Engine. The engine, conforming to DAPD-292, when installed, shall operate throughout its rated speed range without malfunction, leaking of coolant, lubricants and fuel.

3.4.2.1 Engine air induction system. The air induction system, as installed, shall prevent entrance of foreign matter.

3.4.2.2 Exhaust system. The exhaust system, as installed, shall be gas-tight and leakproof. The concentration of carbon monoxide in the crew and passenger compartments shall not exceed .01 percent.

3.4.3 Transmission. The transmission, part no. 8357182, a detail of EPL for the vehicle, and associated controls, as installed, shall operate throughout all speed and gear ranges without malfunction or loss of lubricants.

3.4.4 Steering unit. The steering unit, as installed, shall operate throughout all ranges of steering without malfunction (wander, side pull), and leakage of lubricants under all vehicle operating conditions.

3.4.5 Fuel system. The fuel system shall maintain a supply of fuel to the engine when vehicle is ascending and descending longitudinal grades of 60 percent in forward and reverse gear, and when traversing side slopes up to 40 percent and with each side of vehicle up slope. The fuel system shall be free from leakage.

3.4.5.1 Fuel tank, lines and connections. Provisions shall be made to assure the internal cleanliness of the fuel tank, lines, and connections of the fuel system prior to initial fueling of the vehicle.

3.4.6 Throttle linkage. Throttle linkage shall be adjusted to permit full range of engine governed speeds. Accelerator pedal shall bottom out to protect the throttle linkage from damage.

3.4.7 Cab. The cab shall provide for the crew safety, visibility, comfort, and ease of ingress and egress for operating personnel. The cab shall permit ready accessibility to the engine compartment, components, removal and replacement of the power unit and other components.

3.4.7.1 Soft top. Unless otherwise specified, the manufacturer shall furnish the soft top for the M656 as shown on applicable drawings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.4.7.2 Seats. The driver's seat shall be adjustable fore or aft without binding and interference. The right hand seat back shall fold forward to form a stable non-skid surface platform for personnel to operate a machine gun when required. Material used for seats and seat backs shall conform to no. 8 of CCC-C-428. The seat belt anchors used shall meet requirements of JJ-B-185.

3.4.7.3 Doors. The cab doors and door windows shall operate without binding and interference and restrict the entrance of driving rain, snow, and sand.

3.4.7.4 Stowage. The provisions made for stowage shall contain and support soft top, cargo paulin, bows, supports, end curtains, vehicular tools and equipment, fire extinguisher, rifle, and waterproof compartment for manuals and other small items without interfering with the operation of the vehicle in any manner.

3.4.8 Body. The body, with self-storing troop seats, bows, paulin and end curtains, shall permit the transporting of mixed loads of personnel and cargo. The paulin and end curtains shall protect cargo and personnel from extreme weather conditions. The tailgate, as installed, shall restrict the entrance of water into the cargo area when vehicle is swimming. The drop sides and tailgate, as installed, shall operate up and down without binding or interfering with other components of the vehicle. Means provided shall permit the ingress and egress of the troops without injury to personnel. The cargo bed shall permit the transporting of current developed shelters, pallets and CONEX containers.

3.4.8.1 Cargo tie-downs. The tie-downs, as installed, shall withstand the restraining forces specified in MIL-STD-814.

3.4.8.2 Troop seats. The sectional troop seats shall form cargo racks, and permit the loading of mixed loads of cargo and personnel.

3.4.8.3 Body.

3.4.9 Rear pintle. The rear pintle, furnished and installed, shall tow like vehicle of equal weight, and withstand a direct pull of 3 times the gross vehicle weight.

3.4.10 Electrical.

3.4.10.1 Alternator voltage. The alternator voltage shall be 28 $\pm$ 0.2 volts after installation in the vehicle and connected to the vehicle electrical system in accordance with the applicable drawings. Thereafter, the voltage spread shall not exceed 1 volt under all vehicle operating conditions (providing the electrical load does not exceed alternator system capacity). The voltage shall be measured at the point where the ignition lead connects to the vehicle electrical system.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.4.10.2 Lights and accessories. The internal and external lights and accessories as specified on applicable drawings shall operate as specified through all vehicle operating conditions. All electrical contacts and connections shall maintain positive contact under all vehicle operating conditions.

3.4.11 Controls. When controls are installed and all adjustments completed, the electrical, mechanical, pneumatic and hydraulic controls shall operate as intended without malfunction throughout all ranges of operation under all vehicle operating conditions.

3.4.12 Adjustment mechanisms. When installed and adjusted, all adjustment mechanisms shall function properly and maintain adjusted settings during all conditions of vehicle operations.

3.4.13 Component rework, welding repairs, and burning. Welding repairs and burning, other than component rework, shall be approved by the procuring activity prior to accomplishing repairs.

3.4.14 Stowed material. All On Vehicle Material (OVM) items shall be capable of being stowed in the spaces provided, and shall not interfere with operations of vehicle or components.

3.4.15 Tires. The tires used on this vehicle shall conform to Purchase Description DAPD-833.

3.5 Break-in run. Each vehicle shall be operated by the contractor for a distance of 15 miles at speeds of between minimum and maximum practicable for a new vehicle.

3.5.1 Condition after run. After completion of the break-in run, the engine shall run smoothly. Prior to vehicle being submitted to the Government for acceptance, the vehicle shall be checked to determine if adjustments are correct, and readjusted if required. There shall be no defects indicative of damaged components or maladjustments that may cause faulty vehicle operation.

3.6 Performance. After the break-in run conducted by the contractor, vehicle, serviced and equipped for prevailing climatic conditions, shall operate as specified herein with and without applicable kits. Performance shall be demonstrated on smooth, relatively level, hard-surfaced roads free of loose material, and cross-country terrain. The vehicle with cross-country payload or with a simulated load of equal weight shall operate on longitudinal grades up to 60 percent headed up and down grade, and side slopes up to 40 percent with each side of vehicle up slope. When vehicle is operating on these grades and slopes with engine operating on grade 30 of MIL-L-2104, the oil pressure shall be not less than 35 psig, at 2400 rpm as indicated on the vehicle oil pressure gage, and oil temperature not to exceed temperatures specified in table II.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.6.1 Extreme climatic operation. The vehicle engine shall start and maintain normal operation in still air having any ambient air temperature from minus 25°F to plus 115°F, without external aid, in altitudes from sea level to an 8000 foot elevation above sea level. The complete vehicle, when in storage, shall withstand climatic extremes as specified in MIL-STD-210, without deterioration that may cause failure of any component part on the complete vehicle.

3.6.1.1 Low temperature operation. When specified (see 6.2), winterization equipment shall be furnished and installed. With winterization equipment installed, the engine shall start and the vehicle shall maintain normal operation in still air having an ambient air temperature of minus 25°F to minus 65°F and a relative humidity of 100 percent, after 24 hours of cold-soaking at the specified temperature.

3.6.1.2 High temperature operation. The vehicle engine shall start and the vehicle shall maintain normal operation in still air having ambient air temperatures and altitudes specified in table I, without external aid, and with a relative humidity as low as 5 percent. The vehicle fuel system shall function without evidence of vapor lock, and the engine coolant temperature shall remain below the boiling point with a pressurized radiator cap.

Table I. Elevation Temperature Chart

Elevation	Minimum ambient air temperature
4000 feet	108°F
5000 feet	100°F
6000 feet	97°F
7000 feet	93°F
8000 feet	90°F

3.6.2 Coolant and lubricant temperatures. The engine coolant and oil temperatures, and transmission, axles, transfer case lubricant temperatures, shall not exceed that specified in table II, when checked during any of the operational requirements with rated cross-country payload.

Table II. Operating Temperatures

Maximum engine coolant temperature measured at coolant outlet with a 7 psigg pressure cap ± 2 psi.	Maximum engine oil temperature measured at gallery	Maximum transmission lubricant temperature measured at sump	Maximum transfer case lubricant temperature measured at sump
220°F	250°F	300°F	300°F

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.6.3 Speeds.

3.6.3.1 Level road speeds. The vehicle with payload shall maintain a speed of not less than 50 miles per hour (mph), and maintain a speed of not more than 2 1/2 mph in low gear without malfunction of any major component that may cause vehicle failure. Drumming, shimmy, and tramping shall not occur throughout these speed ranges.

3.6.3.2 Grade speeds. The vehicle fully equipped and with rated payload, but without towed loads, shall ascend longitudinal grades up to 60 percent at a sustained speed of not less than 2 miles per hour. The vehicle shall be stopped on the 60 percent grade for 1 minute, then proceed negotiating the 60 percent grade.

3.6.3.2.1 With and without towed load. Vehicle with rated cross-country payload and towed load shall negotiate a 3 percent grade at a minimum sustained speed of 30 mph. The vehicle with towed load equal to gross vehicle weight shall negotiate a 20 percent grade at a sustained speed of not less than 4 mph.

3.6.4 Highway operation. The vehicle shall transport the rated payload and towed load (see 6.3) over prepared roads. Performance shall be demonstrated on smooth, dry, relatively level concrete roadway.

3.6.5 Cross-country operation. The vehicle shall transport the rated payload and towed load (see 6.3) over unimproved roads, trails, open fields, hills, and rough cross-country terrain.

3.6.6 Braking ability.

3.6.6.1 Service brakes. The service brakes shall bring a fully equipped vehicle with rated payload to a complete stop on a level paved surface from 20 mph within 30 feet from the point of brake application on a surface free of loose material. The service brakes shall control, stop, and hold vehicle on a hard surface when ascending and descending a grade of 60 percent. Vehicle service brakes shall control vehicle speed when descending a long incline without brake fade.

3.6.6.2 Parking brake. The parking brake shall hold the vehicle with rated cross-country payload when ascending or descending a dry concrete grade of 60 percent.

3.6.6.3 Split-service brake system. When specified and installed (see 6.2), the split-service brake system shall maintain 50 percent of the braking ability in event of a brake system failure.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.6.7 Cramping angle. Front wheel cramping angle shall be not less than 29 degrees measured at the wheel on the inside of the turning circle. Angle stops shall be provided, adjusted (within a tolerance of plus 1 degree, minus 0 degree) to provide the maximum safe cramping angle to the right and to the left. When adjusted, angle stops shall be set so that the angle adjustment cannot be readily altered and will positively limit the cramping angle to the maximum angle intended by the stop adjustments. Number 2 axle stops are not to be set.

3.6.8 Mobility.

3.6.8.1 Adverse and hazardous terrain. The vehicle shall traverse adverse and hazardous terrain consisting of mud, snow, ice, sand, gravel, gullies, ditches, soft grassy and swampy soils, beaches, shores, water crossings, rocky and rough terrain, underbrush, bushes, small trees, and light vegetation.

3.6.8.2 Flexibility. The vehicle shall traverse and rest upon 12 inch high blocks under any wheel or combination of wheels, and cross over vertical step 24 inches in height without part failure, interference, and permanent distortion of the chassis frame.

3.6.8.3 Swimming. The vehicle with and without rated payloads shall swim calm inland waters for a period of not less than 60 minutes without special equipment and adjustments other than preparations specified by applicable instruction plate prior to entering the water. The vehicle shall enter and leave water ways having slopes up to the maximum practicable for the vehicle, but not less than a 20 percent slope without taking water into the cab and cargo compartment that will impair vehicle operation.

3.6.8.4 Leakage. Prior to road operation there shall be no evidence of water entering the cargo compartment during a period of 10 minutes, except when entering the water or splash over. Vehicle shall meet the above swimming requirements at 2,500 mile intervals during the 20,000 miles of operation. The engine shall be stopped for a period of not less than 1/2 minute during swimming operations and then shall restart immediately.

3.6.8.5 Bilge pumps. The cab and cargo body bilge pumps, when installed in the vehicle, shall remove water from their specific areas at a minimum rate of 46 gallons per minute with a 6 foot head. The switches and indicator lights furnished and installed shall operate without failure.

3.6.9 Special kits. When specified (see 6.2), each kit furnished and installed shall meet functional requirements specified herein and in applicable drawings. When one of the special kits (see 6.4) is mounted or installed on vehicle, it shall retain the capability of land operation and swimming ability.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.6.9.1 Winch kit. The winch shall have a rated line pull of 20,000 pounds at a line speed of not less than 15 feet per minute, measured at first layer on a bare drum. The winch shall operate intermittently for not less than 4 hours under all operating conditions. The self-energizing friction type safety brake shall control, stop and hold the rated load. The four-way roller type cable guide shall permit cable operation throughout a pyramid from the cable guide, of 45 degrees right and left, and 45 degrees up and down from horizontal longitudinal axis through the cable guide.

3.6.9.1.1 Wire ropes. The 200 feet of 5/8 wire rope furnished with winch kit shall conform to type I, class 2, construction III of RR-W-410, with a 6 foot end chain and hook assembly fastened to the cable with reusable cleves and fitting.

3.6.9.1.2 Winch overload protection. The overload device shall shear off when the line-pull at first layer on bare drum exceeds 23,000 pounds.

3.6.9.1.3 Winch controls. During winching operations, a manually operated device shall permit free spooling of cable off the drum. The safety device shall preclude inadvertent operation of the free wheeling device. Winch control shall permit selective operation of the winch from within the vehicle cab.

3.6.9.1.4 Snatch block. The snatch block furnished with winch kit shall permit safe operation when operating under a working load of 40,000 pounds. The block locking pins shall positively lock block with rated working load.

3.6.9.2 Coldweather kit (down to -25°F).

3.6.9.2.1 Personnel heater and defroster. With the vehicle operating in ambient temperature down to minus 25°F, the heater system shall maintain plus 40°F for comfort of the personnel crew and defrosting of the windshield. The heating system shall raise the enclosed cab temperature up to 40°F, in not more than 5 minutes. After operating the personnel heater for at least 5 minutes, the defrosting system shall defrost 75 percent of the windshield within 5 minutes. The heater blower motor, two-speed control shall control the heater operation for heating and windshield defogging.

3.6.9.3 Arctic kit (-25°F to -65°F). The arctic kit shall provide the following basic functions. (Each kit shall include an alcohol kit.)

3.6.9.3.1 Special cab closure. The cab closure, when installed, shall provide personnel protection against the elements (wind, rain, sleet, snow) under temperature conditions as low as minus 65°F. In addition, the cab closure shall be a knock down type to insure a minimum size and weight package for crating and shipping. It must also be capable of being readily assembled and installed on the vehicle without the necessity of performing modifications on the vehicle or cab and with the use of common tools. The cab assembly shall have a removable section which will permit suitable installation of the machine gun kit.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:23Z
Check the source to verify that this is the current version before use.

3.6.9.3.2 Personnel heater. Heat to the cab shall be provided in a quantity necessary to raise the mean temperature of the cab to plus 40°F, within one hour of heater operation in an ambient temperature of minus 65°F.

3.6.9.3.3 Defrosting. Personnel heater shall also provide sufficient defroster heat to maintain at least 75% of the windshield free of frost after 15 minutes of operation at minus 65°F. (NOTE: Run personnel heater at full cab heat for 5 minutes before turning on windshield defrosters.)

3.6.9.3.4 Power plant heating (standby heating system after operation of the engine to a stabilized temperature condition). The power plant heating facilities shall be capable of maintaining the temperature of the vehicle batteries and critical sections of the engine and transmission (if necessary) to insure immediate engine re-starting capability while being stored in -65°F ambient temperature without aid of solar radiation, for 16 hours (desirable). The standby heating for the engine starting shall be accomplished using only the vehicle batteries for electrical power and normal vehicle fuel.

3.6.9.3.5 Air system alcohol vaporizer. The air system alcohol vaporizer shall consist of an unbreakable (non-glass) alcohol container, valves, regulators, lines, and fittings to suitably introduce alcohol vapor into the air supply system to assimilate the moisture in the compressed air.

3.6.9.4 Cargo bow height (75") kit. The extended bow height kit shall be used with the basic bows, paulin and end curtains. The kit shall include an exhaust pipe extension to raise the engine exhaust discharge above the cargo paulin.

3.6.9.5 Hand-control air brake kit. The air brake kit and controls, when installed, shall be operated by the driver and shall actuate the brakes and stop light of the vehicle being towed.

3.6.9.6 Slave receptacle kit. The mounted slave kit, when attached to the M656, shall furnish electrical power to or from vehicle as may be required.

3.6.9.7 Vehicle slinging kit. The lifting devices shall accept the cargo 17 ton Marine Corps slings and withstand the weight of entire vehicle with rated 5 ton cross-country payload.

3.6.9.8 Machine gun mount kit. The kit shall be installed on the vehicle cab. The vehicle cab shall be structurally suitable for the installation and use of the mount and the machine gun. The ring mount shall accept either Gun, Machine, Caliber .50, M2 Flex or Gun, Machine, Caliber .30, M37. The cab and mount shall be capable of sustaining a peak trunnion reaction of 6,000 pounds during firing at cyclic rates of 450 ± 50 rounds per minute. The cab and mount shall also withstand vibrations experienced during rough cross-country operation of the vehicle. The mounting height from firing platform (cab seat) to the centerline of the caliber .50 machine gun barrel at 0° elevation shall be approximately 50 inches. The dispersion pattern of the entire system shall not

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

exceed 6.0 mils from a gun locked position and 10.0 mils from a gun unlocked position. The gun shall be operable through 360° of rotation in azimuth and from 60° elevation to 15° depression. The initial torque required for moving the cradle with gun mounted in either azimuth direction shall not exceed 2 ft. lbs.

3.6.9.9 Machine gun to cab adapter kit (soft top). The adapter kit shall include an opening for the machine gun mount assembly and a companion cover to cover the gun ring and carriage and protect personnel from adverse weather conditions when the gun is not mounted.

3.6.9.10 Machine gun compatibility kit (hard top). The kit, when installed, shall cover the opening between the gun mount ring and arctic special cab closure, and cover the gun ring and carriage, and provide protection for the personnel from adverse weather conditions when gun is not mounted.

3.6.9.11 Windshield defogging kit. The kit, when installed, shall provide blown air to the inside of the windshield, without heat.

3.6.9.12 Electrical power kit, 28 volts DC, 100 amperes. The electrical power kit, when installed on vehicle and operating between 1,850 and 8,000 revolutions per minute (RPM), shall supply 100 amperes. The alternator nominal voltage shall be 28 volts ± 0.5 volts at 2,000 rpm after installation in the vehicle and connected to the vehicle electrical system in accordance with applicable drawings. Thereafter, the voltage spread shall not exceed 1 volt under all vehicle operating conditions (providing the electrical load does not exceed alternator system capacity). The voltage shall be measured at the point where the ignition lead connects to the vehicle electrical system. The minimum adjusting range at 2,000 rpm with a 25 ampere load shall be between 27.0 and 30.0 volts.

3.7 Radio suppression. Complete vehicle shall be radio interference suppressed in accordance with tactical vehicle requirements of MIL-E-55301.

3.8 Painting, marking and data plates.

3.8.1 Painting. Unless otherwise specified, the exterior and interior of the vehicle, components, assemblies, subassemblies, and parts that require painting shall be prepared and painted in accordance with MIL-STD-193. Vehicle exterior nonskid paint shall match color chip X24087 of FED. STD. NO. 595, except as required by using service.

3.8.2 Marking. Marking shall be in accordance with MIL-STD-642.

3.8.3 Name, shipping, and identification data plates. All plates shall be in accordance with MIL-P-514 and applicable drawings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.9 Servicing and adjustment. The contractor shall service the vehicle for operational use prior to delivery. Such servicing shall include, as a minimum, the focusing of lights, the proper adjustment of the engine controls electrical system, transmission linkage brake system, steering geometry, and tire pressure. Unless otherwise specified, the chassis, engine and all running gear shall be serviced with lubricants of the proper grades for the climatic conditions at the delivery point. Engine cooling system shall be serviced with a solution of ethylene glycol conforming to type I of O-A-548, and water in equal parts by volume.

3.10 Workmanship. All bolts, nuts or other fasteners shall be torqued as indicated on drawings, or where not specifically detailed on drawings, to the extent consistent with their respective application in commercial vehicles of similar construction.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Contractor's quality control system. Unless otherwise specified by the procuring activity, the contractor shall provide and maintain an effective inspection and quality assurance system acceptable to the Government covering the supplies under the contract. A current written description of the system shall be submitted to the contracting officer prior to initiation of production. The contractor will not be restricted to the inspection station or to the method of inspection listed provided that an equivalent control is included in the approved quality control procedure. The contractor shall notify the Government of and obtain approval for any change to the written procedure that might affect the degree of assurance required by this specification or other applicable documents referenced herein.

4.1.2 Government verification. All quality assurance operations performed by the contractor will be subject to Government verification at unscheduled intervals. Verification will consist of (a) surveillance of the operations to determine that practices, methods and procedures of the written inspection plan are being properly applied, and (b) Government inspection to measure quality of product offered for acceptance. Deviation from the prescribed or agreed upon procedures or instances of poor practices which might have an effect upon the quality of the product will be immediately called to the attention of the contractor. Failure of the contractor to promptly correct deficiencies discovered shall be cause for suspension of acceptance until corrective action has been taken or until conformance of product to specified criteria has been demonstrated.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

4.1.3 Materials and qualified products. The contractor shall provide the Government with evidence that materials (see 3.3 and 3.3.1) used are as specified in the applicable specifications and drawings.

4.1.4 Parts and components. Parts, components and assemblies shall be inspected in accordance with the Master List of Supplementary Quality Assurance Provisions (SQAP's) 8736700.

4.1.5 Preproduction inspection. A preproduction vehicle (see 3.1), when furnished, shall be inspected to ascertain vehicle conformance with the requirements of this specification. Inspection shall be performed at a location approved by the Government. Failure of the preproduction model to comply with any of the requirements specified shall be cause for refusal by the Government to conduct a retest until corrective measures satisfactory to the Government have been taken.

4.1.6 In-process inspection. During fabrication of the first production vehicle of each model (see 3.2), an in-process inspection will be conducted by Government representatives to evaluate conformance of materials and workmanship with drawing and specification requirements. These inspections shall be made at the contractor's or subcontractor's facility prior to the application of primer or paint.

4.1.6.1 Review and evaluation. Review and evaluation of recorded results, processing procedures, inspection systems and plans of quality control, will be conducted on the following: material, welding, surface hardening, heat treatment protective finishes.

4.1.7 First production vehicle inspection. The first vehicle of each model, when complete, shall be inspected by the Government, subsequent to contractor's inspection at the acceptance inspection location specified in contract, to determine conformance to contract and specification requirements.

4.1.7.1 Corrections. Corrections found necessary as a result of above inspections shall be made by the contractor. Failure of the contractor to promptly correct deficiencies called to their attention shall be cause for suspension of acceptance of similar vehicles until corrective action has been made or until conformance of product to prescribed criteria has been demonstrated.

4.1.7.2 Vehicle disposition. Upon completion of inspection and acceptance of the first production vehicle, the vehicle shall remain at the manufacturing facility as a production sample. The vehicle may be released for shipment after 120 days from start of production or when the production run of the particular model has been completed prior to the 120 day time limitation. If the quality level of the subsequently produced vehicles exceed the acceptance standard, the first production vehicle model may be released sooner at the discretion of the purchasing contracting officer. The contractor shall service and maintain the vehicle during this period in accordance with the applicable documents for care and preservation while in storage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

4.2 Inspection provisions.

4.2.1 Vehicle examination and acceptance tests. To determine conformance to 3.5, each completed vehicle (less payload) shall be operated for the distance specified, at place of manufacture by the contractor and subjected to examination (see table III) and to tests specified herein (see table IV). Vehicles shall be driven in reverse gear a minimum of 50 feet. Vehicles shall be free of any defects specified in table III, and shall meet all performance requirements specified herein.

Table III. Examination characteristics

Steering system and components: malfunction, improper installation, assembly, clearance, leaks.
Engine: malfunction, improper installation, assembly, leaks.
Clutch: malfunction, improper installation, assembly.
Transmission: malfunction, improper installation, assembly, leaks.
Prop shafts: malfunction, improper installation, assembly.
Transfer: malfunction, improper installation, assembly, leaks.
Power-take-off: malfunction, improper installation, assembly, leaks.
Compressed air devices: malfunction, improper installation, assembly, leaks.
Rotary pump: malfunction, improper installation, assembly, leaks.
Hydraulic hoist: malfunction, improper installation, assembly, leaks.
Cooling system and components: malfunction, improper installation, assembly, leaks.
Engine Governors: malfunction, improper installation, assembly, leaks.
Fuel system and components: malfunction, improper installation, assembly, leaks.
Instrumentation, switches, warning, indicating and safety devices: malfunction, improper installation, assembly, omission.
Electrical system and components: malfunction, improper installation, assembly, leaks.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

Table III. Examination characteristics (Cont'd)

Axles: malfunction, improper installation, assembly, leaks.
Winch: malfunction, improper installation, assembly.
Windshields and windows: malfunction, fogged, cracked, broken, improper installation.
Wheels and tires: improper installation, assembly, damage.
Intervehicle cable and hose: improper installation, assembly, damage.
Engine lubricating system and components: malfunction, improper installation, assembly, leaks.
Frame structure: improper assembly, weldments.
Tank structure: improper assembly, weldments.
Suspension system and components: malfunction, improper installation, assembly, leaks.
Exhaust system components: improper installation, assembly, leaks.
Controls: improper installation, assembly, clearance.
Shock absorbers: malfunction, improper installation, assembly, leaks.
Coolant: low or improper mixture.
Lubricants: improper levels, types.
Pulleys and fan: malfunction, improper installation, assembly clearance.
Belts: improper installation, assembly, tension.
Wiring and tubing: improper installation, assembly, cooling.
Cab doors, hood items, racks, bows, flooring, seals, benches, hardware, stowage, brackets and boxes: improper fits, installation, assembly, weldments.
Miscellaneous items or accessories: malfunction, improper installation, assembly.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

Table III. Examination characteristics (Cont'd)

Wood treatment: improper.
Fuel & water servicing tank trucks: seams and joints for leaks.
Body: improper fit, installation, assembly, weldments.
Vehicle registration & identification marking: incomplete data, missing, improper location or size.
Sheet metal fabrications: improper assembly, installation.
Paint: improper application, color.
Lube fittings: defective, improperly installed, missing.
Cushions, upholstery, canvas top and curtains: damaged, improper fit and installation.
Trim defects.
Decals, marking, data and instruction plates: incomplete data, missing, improper location or size.
Protective coatings: improper application, coverage, materials.
Record forms and publications: missing or improperly processed.
Lubrication: improper.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

Table IV. Location for tests

Title	Paragraph Numbers	Place of Manufacture	Gov't proving ground
Acceptance tests	4.2.1	X	X
Seals check	4.2.1.1	X	X
Engine and components check	4.2.1.2	X	X
Transmission, steering and components check	4.2.1.3	X	X
Fuel system and components check	4.2.1.4	X	X
Throttle linkage check	4.2.1.5	X	X
Cab check	4.2.1.6	X	X
Body check	4.2.1.7	X	X
Rear pintle check	4.2.1.8	X	X
Alternator voltage, lights and accessories test	4.2.1.9	X	X
Controls and adjustment mechanisms check	4.2.1.10	X	X
Component rework welding, welding repairs, and burning check	4.2.1.11	X	X
Performance and condition after break-in run test	4.2.1.12	X	X
Level road speed test	4.2.1.13	X	X
Braking ability tests	4.2.1.14	X	X
Cramping angle check	4.2.1.15	X	X
Bilge pump check	4.2.1.16	X	X
Servicing and adjustment check	4.2.1.17	X	X
Production vehicle test	4.2.2	X	X
Control tests	4.2.3	X	X
Soft top check	4.2.3.3	X	X
Stowed material check	4.2.3.4	X	X
With and without towed load test	4.2.3.5	X	X
Braking performance test	4.2.3.6	X	X
Split-service brake system test	4.2.3.7	X	X
Swimming test	4.2.3.8	X	X
Special kits check	4.2.3.9	X	X
Inspection comparison tests	4.2.4		X
Air induction system test	4.2.4.2		X
Carbon monoxide concentration test	4.2.4.3		X
Fuel system slope operational test	4.2.4.4		X
Environmental operating conditions tests	4.2.4.5		X
Vehicle operational temperatures test	4.2.4.6		X
Mobility operative tests	4.2.4.7		X
Swimming and bilge pumps operational tests	4.2.4.8		X
Special kits operative tests	4.2.4.9		X
Radio interference suppression test	4.2.4.10		X
Preservation, packaging and vehicle processing	4.3	X	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

4.2.1.1 Seals check. To determine conformance to 3.4.1, during and after the fording operation all bearings subject to water contamination shall be checked. Contamination shall not be more than that specified.

4.2.1.2 Engine and components check. To determine conformance to 3.4.2 and 3.4.2.1, during the period of vehicle operation, the engine and components shall be observed for functional requirements.

4.2.1.3 Transmission, steering, and components check. To determine conformance to 3.4.3 and 3.4.4, during the period of vehicle operation the transmission and steering components shall be observed for functional requirements.

4.2.1.4 Fuel system and components check. To determine conformance to 3.4.5 and 3.4.5.1, during the period of vehicle operation the fuel system and components shall be observed for functional requirements.

4.2.1.5 Throttle linkage check. To determine conformance to 3.4.6, during the period of vehicle operation the throttle linkage shall be observed for functional operation, and after the period the linkage shall be checked for proper adjustment.

4.2.1.6 Cab check. To determine conformance to 3.4.7 through 3.4.7.4, each cab shall be checked for proper mounting, completeness of assembly, and access to the engine and components.

4.2.1.7 Body check. To determine conformance to 3.4.8 through 3.4.8.2, each body and components shall be checked for completeness of assembly and proper mounting or installation.

4.2.1.8 Rear pintle check. To determine conformance to 3.4.9, each pintle shall be checked for proper assembly and installation.

4.2.1.9 Alternator voltage, lights and accessories test. To determine conformance to 3.4.10.1 and 3.4.10.2, the alternator voltage shall be checked at point specified and the voltage shall be as specified. The lights and accessories shall be operated and checked for functional requirements.

4.2.1.10 Controls and adjustment mechanisms check. To determine conformance to 3.4.11 and 3.4.12, the controls shall be operated as required and checked for functional requirements. The adjustment mechanisms shall maintain adjustment under all conditions of vehicle operation.

4.2.1.11 Component rework, welding, welding repairs and burning check. To determine conformance to 3.4.13, all welding repairs and burning operations shall be checked for removal of slag and if approved procedures have been followed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

4.2.1.12 Break-in run and condition after break-in run check. To determine conformance to 3.5 and 3.5.1, each vehicle less payload shall be operated as specified and observed for performance requirements and condition after the break-in run.

4.2.1.13 Level road speed test. To determine conformance to 3.6.3.1, the vehicle less payload shall be operated as specified and observed for speed and performance requirements. Shimmy, wheel tramp or drumming shall not occur over the entire speed range.

4.2.1.14 Braking ability test. To determine conformance to 3.6.6.1 and 3.6.6.2, the ability of the brakes to control stop and hold vehicle shall be as specified. Compliance for brake fade shall be determined by stopping from a speed of 40 miles per hour within a distance of 130 feet, at a deceleration rate of 15 feet per second per second (after from 35 to 40 consecutive brake snubbing applications from a speed of 30 miles per hour to 25 miles per hour at a deceleration rate of 8 feet per second) on the level road and at the end of an 8 to 11 percent downgrade, two miles in length.

4.2.1.15 Cramping angle check. To determine conformance to 3.6.7, the vehicle shall be turned to the right and to the left in specified radius. The axle stops shall be checked for proper adjustment.

4.2.1.16 Bilge pump check. To determine conformance to 3.6.8.5, the bilge pumps on each vehicle shall have the switches turned on and pumps observed for functional requirements.

4.2.1.17 Servicing and adjustment check. To determine conformance to 3.9, the vehicles shall be checked for conformance to requirements specified therein.

4.2.2 Production vehicle test. After inspection, correction and acceptance of the first production vehicle (see 3.2), 2 production vehicles as produced, shall be selected by the Government and shall be subjected to examinations and tests for conformance to this specification and table V 20,000 mile test. The test will require a maximum of 90 days at a Government test site. The contractor shall support the test by providing any vehicle spare parts necessary for the conditions and completion of such a test. Delay in test completion caused by the vehicle breakdown or failure of the contractor to adequately support the vehicle with parts during the tests shall not be the basis for adjustment of the contract delivery schedule or contract price.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

Table V. 20,000 Mile Test

Course	Mileage & speeds	Vehicle payload
Hard surface	8,000 miles paved at varying speeds up to maximum	Highway
Secondary roads	6,000 miles at speeds applicable to conditions of terrain	Cross-country
Hilly cross-country	6,000 miles at speeds applicable to conditions of terrain	Cross-country
Swimming operation	Every 2500 miles during this test	Rated payload

NOTE: Fifty percent of the test of the M656 vehicle only shall be performed while towing loads specified in 6.3.

4.2.2.1 Test failure. Failure of test vehicle to comply with the requirements specified or deficiency of a workmanship or materials nature during or as a result of the 20,000 mile test, shall be cause for rejection of the vehicle. Further, the Government may refuse to continue acceptance of production vehicles until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiency. Any deficiency found during or as a result of 20,000 mile test shall be prima facie evidence that all vehicles already accepted prior to completion of the 20,000 mile test are similarly deficient unless evidence satisfactory to the Government is furnished by the contractor that they are not similarly deficient. Such deficiencies on all vehicles shall be corrected by the contractor at no cost to the Government.

4.2.3 Control tests. Control tests for maintaining control of those requirements whose inspection would be of too long duration to be included under acceptance tests shall be conducted by the manufacturer as specified herein.

4.2.3.1 Frequency. The Government shall select at random for control test one out of each 100 vehicles submitted, but not more than two vehicles in any given 30 day period. Each vehicle selected shall be operated, with designated or simulated payload, for a distance of 50 miles by the contractor. These tests shall be performed in the presence of a Government representative. The contractor shall perform 100 percent inspection of the swimming operation on the first 50 vehicles produced under the contract. The contractor shall swim 1 vehicle per day for a 2 month period. After acceptance of the vehicles for the 2 month period, he shall swim vehicles at the rate of 1 vehicle per month when production is 100 vehicles per month or less, and 2 per month when production is greater than 100 vehicles per month.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

4.2.3.2 Failure. If the vehicle selected fails to pass any of the control tests, the Government inspector shall stop acceptance examination and testing on subsequent lots until such time as conditions causing the failure have been remedied.

4.2.3.3 Soft top check. To determine conformance to 3.4.7.1, when a soft top is furnished and installed in accordance with applicable drawings, the top shall be checked for completeness and proper installation.

4.2.3.4 Stowed material check. To determine conformance to 3.4.14, all manufacturer and depot installed "On Vehicle Material" (OVM) shall be stowed (combat loaded) on the selected vehicle. The equipment shall be removed after the test. The OVM shall be of the latest configuration available to the contractor, and the contractor shall be permitted to unpackage and repackage for domestic shipment only equipment used for test.

4.2.3.5 With and without towed load test. To determine conformance to 3.6.3.2.1, 3.6.4 and 3.6.5, the vehicle selected shall be loaded with rated payload and towing rated towed load, operated as specified and checked for performance requirements.

4.2.3.6 Braking performance test. To determine conformance to 3.6.6.1 and 3.6.6.2, the complete braking system shall perform as specified. Brake fade shall be checked.

4.2.3.7 Split-service brake system test. To determine conformance to 3.6.6.3, the vehicle having this system installed shall be operated with rated payload (see 6.3) and observed for performance requirements.

4.2.3.8 Swimming test. To determine conformance 3.6.8.3 and 3.6.8.4, the vehicle shall be operated as specified and checked for performance requirements and leakage at the frequency specified in 4.2.3.1.

4.2.3.9 Special kits check. To determine conformance to 3.6.9.1 through 3.6.9.12, each specific kit will be installed in accordance with applicable drawings (see 6.4) and tested in accordance with performance requirements of this specification and the applicable drawings. The kit shall be removed and the vehicle shall be restored to its original condition unless otherwise authorized.

4.2.4 Inspection comparison tests. The Government may select vehicles at any time during the contract production period and subject vehicle to all tests listed in table IV and table VI to reveal deficiencies of manufacture or design that may reduce the effective operation of these items in the field and to compare existing quality with previous standards. These tests shall be conducted at Government laboratories or proving grounds designated by the contracting officer. Selection of vehicles shall be on a spot check basis. Vehicle selected shall not include any vehicles previously tested for conformance to 4.2.3 (control tests).

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:23Z
Check the source to verify that this is the current version before use.

4.2.4.1 Test failure. Failure of any vehicle tested to comply with any of the requirements specified in the contract, or any major deficiency of a workmanship or materials nature, occurring during or as a result of the test, may be cause for refusal to continue acceptance of vehicles by the Government until evidence has been provided by the manufacturer that corrective action has been taken to eliminate the conditions.

Table VI. Inspection comparison test (5000 miles)

Course	Mileage and speeds	Vehicle payload
Hard surface	100 miles break-in at speeds up to 30 mph, 1000 miles at variable speed up to 55 mph	Highway
Hilly cross-country	1850 miles at speeds applicable to conditions of terrain	Cross-country
Level cross-country	1850 miles at speeds applicable to conditions of terrain	Cross-country
Belgian block	200 miles at speeds applicable to conditions of terrain	Cross-country

4.2.4.2 Air induction system test. To determine conformance to 3.4.2.1, vehicle shall be operated under such conditions that when the air induction system and air cleaners are checked, it can be determined if air induction system has met its functional requirements.

4.2.4.3 Carbon monoxide concentration check. To determine conformance to 3.4.2.2, the crew compartment shall be checked for concentration of carbon monoxide fumes. Fumes shall not exceed percent specified.

4.2.4.4 Fuel system slope operational test. To determine conformance to 3.4.5, the vehicle shall be operated on side slopes as specified and checked for functional requirements.

4.2.4.5 Environmental operating conditions tests. To determine conformance to 3.6.1 through 3.6.1.2, the vehicle shall be tested as required to assure that the vehicle meets all the operational requirements specified herein.

4.2.4.6 Vehicle operational temperatures tests. To determine conformance to 3.6.2 through 3.6.5, vehicle shall be operated as specified and checked for speed, cross-country, grade speeds and highway performance, and coolant and lubricant temperatures shown in table II.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:23Z
Check the source to verify that this is the current version before use.

4.2.4.7 Mobility operative tests. To determine conformance to 3.6.8 through 3.6.8.2, the vehicle with rated payload and towed load shall be operated as specified and observed for meeting of performance requirements.

4.2.4.8 Swimming and bilge pump operational tests. To determine conformance to 3.6.8.3 through 3.6.8.5, the vehicle shall be operated as specified. Performance and leakage shall be checked. Bilge pump shall be operated during swimming test to determine performance and rate of water removal.

4.2.4.9 Special kits operative tests. To determine conformance to 3.6.9.1 through 3.6.9.12, the special kits when furnished for testing shall be mounted or installed on vehicle and checked for meeting of the performance requirements for the individual kit.

4.2.4.10 Radio interference suppression test. To determine conformance to 3.7, the vehicle shall be subjected to a radio interference suppression test.

4.3 Preservation, packaging and vehicle processing. Material and equipment shall be inspected prior to shipment to assure conformance to the applicable requirements specified in 5.1.

5. PREPARATION FOR DELIVERY

5.1 Vehicle processing. Vehicle and equipment shall be processed for shipment and storage in accordance with MIL-V-62038 to the extent indicated on the applicable vehicle preservation data sheet or other implementation document, as specified by the procuring activity (see 6.2).

6. NOTES

6.1 Intended use. The vehicles covered by this specification are intended for general use by the United States Service in transporting personnel or cargo, or in providing for special tasks, during tactical military operations. The vehicles are intended for use under extreme or unusual conditions of climate, weather, terrain, and military service which include Phase II air lift.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Preproduction model, if required (see 3.1).
(c) Winterization equipment, if required (see 3.6.1.1).
(d) Split-service brake system, if required (see 3.6.6.3).
(e) Special kits, if required (see 3.6.9).
(f) Selection of applicable levels of preservation, packaging and packing (see 5.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

6.3 Vehicle loading. The following vehicle weights and loads are approximate:

Curb weight	Payload	Gross vehicle weight	Rated towed load
Highway	10,000 lbs	-	13,000 pounds
Cross-country	10,000 lbs	-	

6.3.1 Curb weight. Curb weight includes weight of vehicle with all attachments, accessories, OVM and equipment, full complement of fuel, lubricants, and coolant.

6.3.2 Payload. Vehicle payload shall include driver, co-driver, and 16 personnel or 5 tons of cargo.

6.3.3 Towed load. With towed load, the vehicle performance as specified herein shall be met with the M656 towing the rated towed load. Total weight of trailer and cargo shall be limited to the rated towed loads specified herein.

6.4 Special kits. The following special kits shall be furnished when required (see 6.2):

Nomenclature	Drawing Number
Winch kit	11600504
Arctic (-65°) kit	11600505
Cold weather (-25°) kit	11600506
Windshield defogging kit	11600507
Cargo bow height (75") kit	11600508
Air brake hand control kit	11600509
Machine gun mount kit	11600510
Slave receptacle kit	11600511
Vehicle slinging kit	11600512
Hard top machine gun adaption kit	11600607
Soft top machine gun adaption kit	11600608
100 Ampere alternator kit	N. A.

Custodian:
ARMY - AT

Preparing activity:
ARMY - AT

Project No. 2320-A548

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:23Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

MIL-T-62070(AT)

ORGANIZATION	CITY AND STATE

CONTRACT NO	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS (Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)

SUBMITTED BY (Printed or typed name and activity)	DATE

DD FORM 1 APR 65 1426 REPLACES NAVSHIPS FORM 4863, WHICH IS OBSOLETE

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:23Z
Check the source to verify that this is the current version before use.