MIL-T-62132B(AT)
23 January 1976
SUPERSEDING
MIL-T-62132A(AT)
1 March 1971

MILITARY SPECIFICATION

TRUCK CARGO: 8 TON, 4x4 M520, TRUCK, CARGO: 8 TON, 4x4 M877

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a high mobility (GOER type), 8 ton capacity cargo diesel engine driven, two or four-wheel optional drive military truck. This vehicle shall operate cross-country, swim inland waterways, and be air transportable.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bid or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

Federal

VV-F-800	-	Fuel Oil, Diesel.

Military

MIL-P-514	-	Plates, Identification, Instruction and Marking, Blank.
MIL-R-3065	-	Rubber, Fabricated Products.
MIL-A-8421	-	Air Transportability Requirements, General Specification for.
MIL-A-46153	-	Antifreeze, Ethylene Glycol, Inhibited, Heavy-Duty, Single Package.
MIL-V-62038	-	Vehicles, Wheeled: Preparation for Shipment and Storage of.

FSC-2320

Source: https://assist.dla.mil -- Downloaded: 20261O-26T04:23Z
Check the source to verify that this is the current version before use.

MIL-T-62129 - Tire, Pneumatic: For Truck, Logistical Goer Type (tubeless).
MIL-E-62133 - Engine, Diesel: 6 Cylinder, In-line, 213, H.P. Turbo-Supercharged.
MIL-T-62134 - Transmission, Power Shift, Commercial Modified.
MIL-C-62135 - Crane: Material Handling.

STANDARDS

Federal

Fed. Std. No. 595 - Colors.

Military

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-130 - Identification Marking of U. S. Military Property.
MIL-STD-193 - Painting Procedures, Tactical Vehicles, (Tracked and Wheeled).
MIL-STD-210 - Climatic Extremes for Military Equipment.
MIL-STD 417 - Rubber Compositions, Vulcanized General Purpose, Solid (Symbols and Tests).
MIL-STD-461 - Electromagnetic Interference Characteristics Requirements for Equipment.
MIL-STD-642 - Identification Marking of Combat and Tactical Transport Vehicles.
MIL-STD-721 - Definitions of Effectiveness Forms for Reliability, Maintainability, Human Factors, and Safety.
MIL-STD-882 - System Safety Programs for Systems and Associated Subsystems and Equipment Requirements for.
MIL-STD-1472 - Human Engineering Design Criteria for Military Systems, Equipment and Facilities.
MIL-STD-1474 - Noise Limits for Army Materiel.
MS-21313 - Padlock Sets, Individually Keyed, and Keyed Alike.
MS-51326 - Heater, Vehicular Compartment: Liquid Coolant, 30,000 BTU/HR.
MS-53063-5 - Indicator, Air Cleaner, Intake, Restriction Mechanical Type.

Technical Data Package List (TDPL)

11614317 - Truck, Cargo: 8 Ton, 4x4, M520 W/Winch.
11614317-1 - Truck, Cargo: 8 Ton, 4x4, M520 WO/Winch.
11614317-2 - Truck, Cargo: 8 Ton, 4x4, M877 W/Winch and Crane.
11614317-3 - Truck, Cargo: 8 Ton, 4x4, M877 WO/Winch, W/Crane.

DRAWINGS

11614953 - Mounting Kit, Mach Gun, Cal. 50.
11614959 - Rear Canopy and Frame Kit.
11614988 - Arctic Kit.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

11620144 - Trailer Brake Kit.
11624639 - Filter Kit.
11651365 - Light Kit, Rotating Warning.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Preproduction vehicle. When specified (see 6.2), a complete preproduction vehicle(s) to be furnished under this specification shall be produced prior to the manufacture or fabrication of vehicles in quantity. The vehicle(s) when complete shall be submitted to the Government for examination and tests to determine conformance to the requirements of this specification. Vehicle(s) submitted by the contractor shall be fully representative of vehicles proposed to be supplied by the vehicle manufacturer from production facilities and tooling under the supply contract.

3.2 Initial production vehicle(s). The vehicle(s) selected shall be fully representative of vehicles proposed to be furnished under the contract and shall be submitted to the Government for inspection to determine conformance to the requirements of this specification.

3.2.1 Reliability (specified). During the first 25,000 miles of operation, the vehicle shall have a Mean Miles Between Mission Failure (MMBMF) of 1,200 miles. A mission failure is defined as a malfunction which:

(a) Will immobilize the vehicle, produce a critical or catastrophic safety hazard as defined by MIL-STD-882.
(b) Cannot be corrected within one-hour (including diagnostic time) by the crew using on equipment material On Equipment Material (OEM).

3.2.1.1 Vehicle mission. Reliability operation shall be conducted in the ratio of mileage and requirements of mission statement (see 6.5).

3.2.2 Durability (minimum). During the first 25,000 miles of vehicle operation, the engine and transmission shall have a combined probability of 50% of not requiring replacement.

3.2.3 Maintainability. When maintenance procedures specified in the technical manuals are followed and the vehicle is operated as defined in the mission statement, the demonstrated maintainability shall be as follows:

(a) Mean Operator Preventive Maintenance Time shall not exceed 1.40 manhours per mission. This time shall not be included in organizational preventive maintenance time.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

(b) Maximum Operator Corrective Maintenance Time shall not exceed 1.00 manhours per mission without being classified as a mission failure.
(c) The ratio of total corrective and organizational preventive maintenance manhours to operating hours shall not exceed .30.
(d) The ratio of total organizational preventive maintenance manhours to total operating hours shall not exceed .10.
(e) The ratio of total corrective maintenance manhours to operating hours shall not exceed .20
(f) Mean manhours to perform a corrective maintenance action shall not exceed 4.00.
(g) The Mean Time Between Corrective Maintenance Actions shall not be less than 20.0 operating hours.
(h) Inherent Availability (Ai) shall be not less than .91.

$$Ai = \frac{MTBF}{MTBF + MTTR}$$

NOTE: In the above formula, MTBF is expressed in engine hours and MTTR is expressed in clock hours. Where specific hours are not available, appropriate conversion factors (i.e., to change from manhours of maintenance to clock hours of down time) should be used.

3.3 Materials.

3.3.1 Qualified products list (QPL). The contractor shall be responsible for using all assemblies and parts necessary in vehicle construction that are listed as qualified products on the QPL and those approved for inclusion on the QPL. Assemblies and parts determined as QPL items appear on the Engineering List of Specifications cited in 3.4. The contractors manufacturing inspection records shall specifically list all QPL items by part or drawing number(s), name of supplier(s), and number and date of the QPL. When assemblies and parts are approved as qualified products but not as yet listed on the QPL, the contractor shall list the products by number and date of the approval document with name of supplier(s).

3.3.2 Ozone resistant products. Rubber products procured under requirements of MIL-R-3065 are to be ozone resistant to the climatic environment specified herein and by the requirements of MIL-STD-417. Rubber components controlled by detail specifications shall be ozone resistant only when required by the specification referenced on the drawing.

3.4 Construction. Vehicles, components, subassemblies, and assemblies shall be fabricated and assembled into a complete vehicle in accordance with TDPL 11614317, TDPL 11614317-1, TDPL 11614317-2 and TDPL 11614317-3, associated documents, and publications referenced therein. All parts, subassemblies, and assemblies shall be identified in accordance with MIL-STD-130 when specified on drawings.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:23Z
Check the source to verify that this is the current version before use.

3.4.1 Seals.

3.4.1.1 Bearing and lubricant seals. With the vehicle operating under all types of cross-country terrain and during fordings or swimming, the seals shall restrict the entrance of all foreign matter into the bearings, which are exposed to contamination during these operations. Seals shall prevent water contamination of lubricants, and water contamination shall not exceed 2 percent by volume. All bearings seals shall prevent the leakage of lubricants from the bearings.

3.4.2 Special kits. When specified (see 6.2 and 6.4), special kits shall be furnished and shall meet the requirements specified herein.

3.4.2.1 Arctic kit. The arctic kit conforming to 11614988 shall provide a hard top cab for the tractor, heat for the cab, and assure engine starting and operation in ambient temperatures from minus 25°F (4-6 feet above ground) to minus 65°F (measured at ground level).

3.4.2.2 Infra-red filter kit. The infra-red filter kit conforming to 11624639 shall be installed.

3.4.2.3 Gun-ring mounting kit. The gun-ring mounting kit conforming to 11614953 when installed shall permit 360 degrees rotation without interference.

3.4.2.4 Trailer brake kit. The trailer brake kit conforming to 11620144, when installed shall operate the brakes on the towed vehicle independently of the vehicle brakes.

3.4.2.5 Rear canopy and frame kit. The rear canopy and frame kit shall conform to 11614959 (This kit is available for M520 vehicle only).

3.4.2.6 Warning light kit. The warning light kit shall conform to 11651365.

3.4.3 Tire chains. The tire chains when installed shall retain maximum tightness at tire manufacturer's rated pressure to prevent damage to wheel wells and vehicle underbody. Scuffing of body metal shall be considered as damage.

3.4.4 Power steering unit. The power steering unit shall operate without malfunction or leakage of lubricants under all vehicle operating conditions.

3.4.5 Engine. The vehicle performance requirements shall be met when engine conforming to MIL-E-62133 is properly installed in vehicle.

3.4.5.1 Engine air induction system. The engine air induction system as fabricated and properly installed from air cleaner to engine turbo charger intake, shall be free from all weld slag and foreign material. The system shall prevent entrance of all foreign material and withstand pressure up to 5 psi. Air cleaner restriction indicator conforming to MS-53063-5 shall be installed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.4.6 Transmission. The vehicle performance requirements shall be met when transmission conforming to MIL-T-62134 is properly installed in vehicle.

3.4.7 Exhaust system. The exhaust system as installed shall be gastight and leakproof such that during normal vehicle operation the concentration of NO_x in the crew compartment shall not exceed 5ppm and the concentration of carbon monoxide shall not exceed 50ppm.

3.4.8 Fuel tanks and hydraulic reservoir. Provisions shall be made to assure the internal cleanliness of the fuel tanks and hydraulic reservoir prior to initial filling.

3.4.9 Engine stop switch. When the engine stop switch is activated, the engine shall stop within 2 minutes.

3.4.10 Fuel, air, hydraulic lines, and fittings. All fuel, air, hydraulic lines, and fittings shall be internally clean prior to and after making connections and shall be free from leaks. All lines and fittings shall be secured in such a manner to prevent rubbing on adjacent lines or vehicle appendages.

3.4.11 Governor control linkage. Governor control linkage (throttle) shall be adjusted to permit the full range of engine-governed RPM capability. The accelerator pedal travel when fully depressed shall be restricted by adjustment to preclude damage to governor and governor control linkage.

3.4.12 Personnel heater (hot water type). The personnel heater conforming to MS-51326-1 as installed shall maintain temperatures of not less than 40°F within the vehicle cab in ambient air temperatures down to minus 25°F and provide defrosting of the windshield.

3.4.13 Front winch. When specified (see 6.2), the front mounted winch shall have a single line capability of not less than 10,000 pounds on the bare drum. The wire rope for the winch shall be not less than 150 feet in continuous length, without splice or joint and shall be provided with a chain and hook.

3.4.14 Cargo body doors. The doors of the cargo body shall not stick or bind and when closed and locked shall restrict the leakage of water into the stowage and cargo areas of the body within limits specified herein.

3.4.15 Controls. Electrical, mechanical, pneumatic and hydraulic controls shall operate without malfunction throughout all ranges of operation under all vehicle operating conditions.

3.4.16 Adjustment mechanisms. Adjustment mechanisms shall function properly and maintain adjusted settings during all conditions of vehicle operations.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.4.17 Stowage. Stowage provision made shall have the capability to contain the manufacturer's, depot and troop installed Equipment List (EL). Padlocks as required shall conform to MS-21313.

3.4.18 Welding repairs and burning operations. Welding repairs and burning operations of any type or class shall be made only when, and to the extent specifically authorized by procuring activity.

3.4.19 Transportability. The vehicle shall be transportable in phase II air borne operations. The vehicle shall be transportable by ship and landing vessels and transportable by railways without major disassembly. Air transportability shall be for type C141 and C5A aircraft and shall meet requirement of MIL-A-8421.

3.4.20 Tires. Vehicle equipped with tires conforming to MIL-T-62129 shall meet all requirements specified herein.

3.4.21 Soft top. Unless otherwise specified (see 6.2) the contractor shall furnish the soft top enclosure for the crew compartment.

3.4.22 Material handling crane. When specified (see 6.2), the material handling crane conforming to MIL-C-62135 as installed on the left rear wheel well shall lift loads up to 2,500 pounds into or out of the cargo area of the vehicle.

3.4.23 Safety. The vehicle shall be evaluated in accordance with MIL-STD-882 to assure all hazards have been eliminated or reduced to an acceptable level through the utilization of appropriate safety devices.

3.5 Break-in run. Prior to break-in run, each vehicle produced shall be completely assembled and all adjustments completed (except for equipment, component installation and servicing performed by the contractor as a final processing of vehicles for acceptance). Vehicle, including all components requiring lubrication, shall be lubricated. Vehicle shall be serviced with fuel conforming to VV-F-800. Lubricants and fluids shall be as specified in lubrication chart. Specific applications by grades or types for various expected seasonal temperature ranges shall be as specified therein.

3.5.1 Oil pressure. Prior to start of the break-in run, the engine shall be operated at 700 to 800 RPM until lubricating oil is at operating pressure in accordance with MIL-E-62133. If at any time during the break-in run, the engine has been stopped for at least 15 minutes, the engine shall again be operated as above, before continuing the break-in run. Proper oil pressure shall be maintained during operation on level ground, 60% grades and 30% side slopes.

3.5.2 Distance. Each vehicle shall be operated by the contract for a distance of 15 miles consisting of the following types of operation:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

(a) 1st gear, 1/2 mile
(b) 2nd gear, 1 mile
(c) 3rd gear, 1 1/2 mile
(d) 4th gear, 1 1/2 mile
(e) 5th gear, 4 1/2 mile
(f) 6th gear, 6 mile

NOTE: During the above runs, the vehicle shall be stopped and then operated in reverse gear 3 times, 100 feet each time.

3.5.2.1 Condition after run. Affter completion of the break-in run, the engine shall run smoothly. Prior to vehicle being submitted to the Government for acceptance, the vehicle shall be checked to determine if adjustments are correct. There shall be no defects indicative of damaged components that may cause faulty vehicle operation.

3.6 Performance. The complete vehicle, serviced and equipped for existing environmental and climatic condition and carrying a payload of 16,000 pounds, shall meet performance requirements specified herein.

3.6.1 Environmental. The vehicle shall operate in ambient air temperature of plus 125°F (ground surface temperature) to minus 25°F, (4-6 feet above ground) and with special equipment installed, from temperature ranges of minus 25°F (4-6 feet above ground to minus 65°F (ground surface temperature). The complete vehicle when in storage shall withstand climatic extremes as specified in MIL-STD-210, without deterioration that may cause failure of any component part of vehicle.

3.6.2 Grade and slope operation. The vehicle with 16,000 pound payload (without towed load) shall operate in forward and reverse gears on longitudinal grades up to 60% and side slopes up to 30% with each side of the vehicle up slope. As result of the operation no evidence of faulty lubrication, cooling, fuel supply, leakage or other malfunction shall be found.

3.6.3 Engine starting on grades and side slopes. With the vehicle standing on a 60% grade for not less than 2 minutes with engine operating under no load between 800 to 1000 rpm, the engine shall be stopped for no less than 2 minutes. The engine shall restart in not more than 2 minutes when vehicle is headed up and headed down grade respectively. A similiar engine starting test shall be conducted on 30% side slopes with right side and then left side of vehicle up slope.

3.6.4 Cooling system. The engine coolant system and engine and transmission oil coolers as installed shall control the coolant and oil temperatures, to prevent damage to the engine and transmissions, under all conditions of vehicle operation. Temperatures shall not exceed those shown in Table I when vehicle is operated in ambient temperature of plus 125°F.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

Table I. Operating temperatures.

Maximum engine coolant temperature at engine outlet.	Maximum engine oil temperature measured at oil sump drain plug.	Maximum transmission oil temperature measured at converter outlet.
230°F.	250°F.	275°F.

3.6.5 Cruising range. Vehicle with payload weight shall operate for not less than 300 miles at average road speed of 20 mph on hard surface roads over an average rolling terrain without refueling.

3.6.6 Speeds. With 16,000 pound payload, but less towed load, the vehicle shall maintain a speed of not less than 30 mph on level hard-surfaced roads with a grade not greater than ± 1/2 percent, and in low gear maintain a minimum speed of 2 1/2 miles per hour.

3.6.6.1 Towed loads. The vehicle with its 16,000 pounds rated payload shall be capable of towing loads up to 20,000 pounds (GVW). During towed load operations, the vehicle, with payload, shall be operated at not less than 20 mph on a level hard-surface road with a grade of not greater than ± 1/2 percent.

3.6.7 Braking ability.

3.6.7.1 Service brakes. When loaded with payload, the service brakes shall stop vehicle from a speed of 20 mph in not more than 35 feet from point of brake application. Deceleration and stopping distance shall be demonstrated on dry, brushed concrete, level road surface free from loose material with a grade not greater than ± 1/2 percent. The service brake shall hold vehicle on a 60 percent grade when ascending and descending.

3.6.7.2 Parking brake. The parking brake shall hold vehicle loaded with rated payload headed up and headed down on grades of not less than 40 percent.

3.6.8 Steering angle. The power steering mechanism shall be adjusted to permit a turning angle of 60 degrees ± 2 degrees for both left and right turns. These turns shall be made with maximum articulation (roll) between the front and rear units, to either side without interference.

3.6.9 Vehicle articulation. Lateral articulation between the front and rear units shall be 20 degrees ± 2 degrees on each side of the longitudinal centerline. Stops when used shall limit the articulation to 5 degrees ± 3 degrees between the power unit and trailing unit to improve stability during lift and tow operations and during loading for shipment of vehicle by sea, land and air.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

3.6.10 Leakage during swimming. The vehicle with and without rated payload shall swim for a period of not less than 20 minutes. Leakage of water into new vehicle shall not exceed 1 quart per minute, total in tractor and carrier.

3.6.10.1 Bilge pumps. The power unit and trailing unit bilge pumps shall remove water from their specific areas at a minimum pumping rate of 46 gpm as installed.

3.6.11 Electrical system.

3.6.11.1 Voltage alternator-generator. The alternator voltage shall be nominally set at 28 volts at 2,000 rpm with 25 ampere load. The voltage spread shall not exceed ± 5 volt under all vehicle operating conditions providing the electrical load does not exceed alternator capacity of 60 amps. The voltage shall be measure at the point of battery connection to the vehicle electrical system.

3.6.11.2 Lights and accessories. The internal and external lights, including cables and receptacles, shall function throughout all vehicle operating conditions. All electrical contacts and connections shall maintain positive contact under all vehicle operating conditions.

3.7 Radio interference suppression. The complete vehicle shall be radio interference suppressed in accordance with tactical vehicle requirements class IIIA of MIL-STD-461.

3.8 Painting, marking and data plates.

3.8.1 Painting. The exterior and interior of the vehicle, components, assemblies, subassemblies, and parts that require painting shall be prepared and painted in accordance with MIL-STD-193. Vehicle exterior paint and exterior nonskid paint shall match color chip X24087 of Fed. Std. No. 595.

3.8.2 Marking. Marking of vehicle shall be in accordance with drawings and shall conform to MIL-STD-642.

3.8.3 Name, shipping, and identification data plates. All plates shall be in accordance with drawings and shall conform to MIL-P-514.

3.9 Servicing and adjustment. Prior to delivery contractor shall service and adjust each vehicle and its mounted material for operational use including the following: the focusing of lights, the proper adjustment of the engine, running gear, adjustment of brake system, inflation of all tires, complete check of electrical, air and brake systems for proper operation, complete lubrication of chassis, engine, transmission, transfer case, converter, steering gear, winches, axles and all running gear with proper grade of lubricant (per approved lubrication chart) for the climatic condition at the delivery point. Engine cooling system shall be serviced with a solution of ethylene glycol conforming to type I of MIL-A-46153 and water in equal parts by volume.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:23Z
Check the source to verify that this is the current version before use.

3.10 Noise and vibration levels. The noise and vibration levels associated with the vehicle and its elements in required combinationa, shall be controlled under all conditions and usage, to levels of tolerance of personnel in accordance with MIL-STD-1472 and MIL-STD-1474.

3.11 Workmanship. The vehicle shall be constructed and finished in a thorough workmanlike manner. Particular attention shall be paid to neatness and thoroughness of marking the parts, plating, painting, machine-screw assemblage, welding and brazing, and freedom of parts from burrs and sharp-edges. Electric, hydraulic and lube lines shall be located in a manner so as to prevent possible damage by rubbing on adjacent lines or appendages. No condition shall exist which may create a safety hazard to operating or maintenance personnel.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Contractor's inspection or quality control system. Unless otherwise specified by the procuring activity, the contractor shall provide and maintain an effective inspection or quality assurance system acceptable to the Government covering the supplies under the contract. A current written description of the system shall be submitted to the contracting officer prior to initiation of production. The contractor shall notify the Government of any subsequent change to the submitted procedures prior to implementing the change into the system.

4.1.2 Government verification. All quality assurance operations performed by the contractor will be subject to Government verification at unscheduled intervals. Verification will consist of (a) surveillance of the operations to determine that practices, methods and procedures of the written inspection plan are being properly applied, and (b) Government inspection to measure quality of product offered for acceptance. Deviation from the prescribed or agreed upon procedures or instances of poor practices which might have an effect upon the quality of the product will be immediately called to the attention of the contractor. Failure of the contractor to promptly correct defects discovered shall be cause for suspension of acceptance until corrective action has been taken, or until conformance of product to specified criteria has been demonstrated.

4.1.3 Materials and qualified products. The contractor shall provide the Government with evidence that materials (see 3.3, 3.3.1, and 3.3.2) used are as specified in the applicable specifications and drawings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

4.1.4 Parts and components. Parts, components and assemblies shall be inspected in accordance with TDPL-11614317, TDPL-11614317-1, TDPL-11614317-2, and TDPL-11614317-3.

4.2 Preproduction and initial production inspection.

4.2.1 Preproduction inspection. A preproduction vehicle (see 3.1), when furnished, shall be inspected to ascertain vehicle conformance with the requirements of this specification. Inspection shall be performed at a location approved by the Government. Failure of the preproduction model(s) to comply with any of the requirements specified shall be cause for refusal by the Government to accept vehicle until corrective measures satisfactory to the Government have been taken.

4.2.2 Initial production vehicle inspection.

4.2.2.1 Reliability test. Reliability requirement of 3.2.1 will be verified while vehicle is subjected to initial production (comparison) tests. The minimum acceptable value (MAV) shall not be less than 725 Mean Miles Between Mission Failures (MMBMF). This value will be demonstrated at a level of confidence appropriate to the duration of the test.

4.2.2.2 Durability test. Durability requirement of 3.2.2 will be verified while vehicle is subjected to initial production tests.

4.2.2.3 Maintainability. The maintainability of the vehicle as specified in 3.2.3 will be verified during initial production testing.

4.2.2.4 In-process inspection. During fabrication of the initial production vehicle (see 3.2) an in-process inspection will be conducted by a Government representative to evaluate conformance of materials and workmanship to requirements of specified documents. These inspections shall be made at the contractor's or subcontractor's facility, prior to application of primer and paint. Processing, and welding procedures, quality systems and inspection records will be reviewed and evaluated during this inspection.

4.2.2.5 Completed first vehicle inspection. The first production vehicle on each contract shall be road tested and completely inspected by the contractor for conformance to the requirements of contract and specifications. The applicable road test shall be in accordance with Paragraph 4.4.2.1. Upon completion, the contractor shall submit the vehicle (and make available all inspection records and certifications) to the responsible government inspection element at contractor's plant for preliminary inspection.

4.2.2.5.1 Preliminary inspection. The vehicle shall receive a preliminary inspection by the responsible government inspection element. The preliminary inspection shall be completed except for road test requirements of Paragraph 4.4.2.1 which will be conducted jointly during provisional inspection to be accomplished by representatives of USATACOM Quality Assurance Directorate as specified in Paragraph 4.2.2.5.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

4.2.2.5.2 Provisional inspection. The first completed production vehicle shall be subject to provisional inspection at the contractor's plant by representatives of USATACOM Quality Assurance Directorate. The contractor shall further provide any other inspection assistance as may be required. At the time of this inspection, the contractor shall make available his inspection plan, inspection records, and certifications pertinent to the vehicle and components.

4.2.2.6 Repairs of defects. Defects found as a result of above inspections shall be corrected by the contractor at no cost to the Government. Failure of the contractor to promptly correct defects shall be cause for suspension of acceptance of vehicles until corrective action has been accomplished.

4.2.2.7 Vehicle disposition. Upon completion of inspection and acceptance of the preproduction or first production vehicle, the vehicle shall remain at the manufacturing facility as a production sample. The contractor shall service and maintain the vehicle during this period in accordance with the applicable documents for care and preservation while in storage. At the discretion of the Purchasing Contracting Officer, the vehicle may be released for shipment.

4.2.2.8 Initial production test. Unless otherwise specified (see 6.2), to determine conformance to 3.2 through 3.2.3, the quality of vehicles specified in contract will be selected by the Government and shall be subjected to examinations specified in Table III, in addition to road tests specified in Table II and all tests specified in Table IV. The contractor shall support the test by providing any vehicle spare parts necessary for completion of such a test. Delay in test completion caused by vehicle breakdown or failure of the contractor to adequately support the vehicle with parts during the tests shall not be the basis for adjustment of the contract delivery schedule or contract price.

Table II. 25,000 Mile Test

Course	Mileage & speeds	Vehicle payload (see 3.6)
Hard surface	5,000 miles paved at speeds varying up to maximum	Payload
Secondary roads	10,000 miles at speeds applicable to conditions of terrain	Payload
Hilly cross-country	5,000 miles at speeds applicable to conditions of terrain	Payload
Level cross-country	5,000 miles at speeds applicable to conditions of terrain	Paylaod
Swimming operation	8 hours of swimming in calm inland waters	Payload

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

NOTE: Ten percent of the mileage specified for each course shall be performed with towed load (see 3.6.6.1) swimming excepted.

4.2.2.8.1 Test failure. Failure of the test vehicle to meet minimum performance requirements, failure to comply with the requiremeents of a workmanship or materials nature and failure to manufacture the vehicle in accordance with the technical data revealed during or as a result of this test, shall be cause for rejection of the vehicle. Further, the Government may refuse to continue acceptance of production vehicles until evidence has been provided by the contractor that corrective action has been taken to eliminate the defects. Any defects found during or as a result of this test shall be prima facie evidence that all vehicles already accepted prior to completion of test, are similarly defective unless evidence satisfactory to the Government is furnished by the contractor that they are not similarly deficient. Such defects on all vehicles shall be corrected by the contractor at no cost to the Government.

4.3 Inspection provisions.

4.3.1 Lot size. An inspection lot shall consist of all vehicles of one type from one day's production, submitted at one time for acceptance inspection.

4.3.1.1 Sampling for inspection. For the purpose of visual, dimensional, and primary functional inspection, a representative sample shall be selected from each inspection lot in accordance with inspection level II of MIL-STD-105. Before sampling may be accomplished by the contractor, the contractor shall 100% inspect the first 20 vehicles to establish a process average (see 6.7) to allow normal sampling in accordance with MIL-STD-105.

4.3.1.2 Examinations. Visual, dimensional, and primary functional examination shall consist of examination of the vehicle for conformance to the applicable drawings and this specification. Examination shall be performed against the classification of defects and with the acceptable quality levels shown in Table III. The following constitutes a part of the classification of defects (see 6.3 and 6.8):

(a) Any drip constitutes a major defect when the vehicle has been standing idle and the components are at ambient temperature.
(b) Any droplet that occurs at a static fit metal to metal or gasket combination shall constitute a major defect.

4.3.1.3 Unclassified defects. All defects having no bearing on function, safety, interchangeability or life, but are considered departures from good workmanship will be noted in writing. Workmanship deficiencies falling within this category and recurring in 5 consecutive lots or ten lots or more within a thirty-day period will be added to the minor classification with no increase to A.Q.L.'s.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:23Z
Check the source to verify that this is the current version before use.

4.3.1.4 Recurring major deficiencies. A major deficiency (see 6.8) is recurring when the same defect occurs more than once in the same sample or when the defect occurs in two successive samples. A major defect may be considered recurring when the historical inspection records ("P" chart or approved equivalent) reflect such a condition. Recurring major deficiencies shall be cause for the entire lot or lots to be inspected for the recurring deficiencies. The deficiencies shall be corrected when found.

Table III. Classification of Quality Defects

Defect No.	Defects	Method of Inspection
Major	A.Q.L. = 25 Defects/100 Units	
101	Steering mechanism: malfunction; unusual noise leaks (see 6.3)	Visual and functional
102	Engine: malfunction; unusual noise; leaks mounting improper	Visual and functional
103	Clutch: malfunction; unusual noise	Visual and functional
104	Transmission: malfunction; unusual noise; leaks (see 6.3) mounting improper	Visual and functional
105	Drive train: malfunction; misalignment; unusual noise	Visual and functional
106	Transfer case assembly: malfucntion; unusual noise; leaks (see 6.3) mounting improper	Visual and functional
107	Compressed air devices: malfunction; unusual noise; leaks	Visual and functional
108	Bilge pumps: malfunction; unusual noise	Functional
109	Cooling system and components: malfunction; unusual noise; leaks; damage; improper clearance	Visual and functional
110	Governor linkage and engine governor: malfunction; adjustment	Visual and functional
111	Fuel system components: malfunction; damage; leaks (see 6.3)	Visual and functional

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

Table III. Classification of Quality Defects (Cont'd)

Defects No.	Defects	Method of Inspection
112	Instrumentation switches, warning, indicating and safety devices: malfunction; damage	Visual and functional
113	Electrical system and components: malfunction; damaged light connectors	Visual and functional
114	Service, handbrakes, and locks: malfunction; unusual noise; leaks	Visual and functional
115	Windshield: fogged; cracked; broken; folding interference	Visual and functional
116	Tire: damage; not properly inflated	Visual
117	Lubrication system components (engine) damage; leaks (see 6.3)	Visual and functional
118	Body, sheet metal, hardware, storage compartments, brackets: improper fits; assembly or installation; defective weldment	Visual
119	Tanks structure and welding defect	Visual
120	Exhaust system components: damage; leaks	Visual
121	Air cleaner: damage	Visual
122	Seat suspension system components: damage; leaks	Visual and functional
123	Controls: malfunction; clearance improper	Visual and functional
124	Winch and wire rope: malfunction; improper size; damage	Visual and functional
125	Walkway coating: application; improper coverage; location	Visual
126	Miscellaneous items or accessories: malfunction; damage	Visual and functional

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

Table III. Classification of Quality Defects (Cont'd)

Defect No.	Defects	Method of Inspection
Minor	A.Q.L. = 150 Defects/100 Units	
201	Controls: malfunction, adjustment, damage	Visual and functional
202	Coolant: low or improper mixture	Visual and hydrometer
203	Lubricants: levels and types improper (all units)	Visual
204	Wheels and tires: improper size; type and mounting	Visual
205	Pulleys and fan: misalignment; improper mounting or clearance	Visual
206	Bolts: defective, loose	Visual and functional
207	Wiring or tubing: defective; improper assembly or assembly	Visual
208	Brake system components: improper assembly; installation, or protection	Visual
209	Body, doors, access ladder, access covers, ventilators, stowage brackets, tie downs, lashing hooks and lifting devices; improper fits; assembly or installation; defective weldments; bows; flooring; seals, hardware	Visual and functional
210	Sheet metal and welding defects	Visual
211	Electrical system components: improper installation or assembly	Visual
212	Paint: application and color improper	Visual
213	Steering system components: improper installation or clearance	Visual
214	Exhaust system components: improper assembly or installation	Visual

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:23Z
Check the source to verify that this is the currentversion before use.

Table III. Classification of Quality Defects (Cont'd)

Defects No.	Defects	Method of Inspection
215	Cooling system components: improper assembly or installation	Visual
216	Fuel system components: improper assembly or installation	Visual
217	Lube fittings: defective; missing or improperly installed	Visual
218	Insulation and noise suppression: missing; improper application	Visual
219	Mud flaps: improper assembly; damaged	Visual
220	Walkway coating: excessive application	Visual
221	Seat suspension system components: improper installation or assembly	Visual
222	Cushions, seats, straps, canvas tops, and curtains: damaged; improper fit and installation	Visual
223	Miscellaneous items or accessories: missing; improper assembly or installation	Visual and functional
224	Decals, marking, data and instruction plates: incomplete data; missing, improper location or size; vehicle registration and identification marking	Visual
225	Protective coatings: application; missing or improperly processed	Visual
226	Lubrication improper	Visual

4.4 Classification of tests.

(a) Acceptance tests, 4.4.1 through 4.4.1.20.
(b) Control tests, 4.4.2 through 4.4.2.7.
(c) Comparison tests, 4.4.3 through 4.4.3.11.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

4.4.1 Acceptance test. Each complete vehicle shall be subjected to a 15 mile road test by the contractor over hard-surfaced roads with a grade of not greater than ± 1/2 percent. Vehicles (less payload) shall as a minimum comply to the performance requirements specified herein. Each vehicle shall be operated at speeds specified in 3.5.2 and operated in a reverse gear for a minimum of 100 feet 3 times and shall meet all acceptance tests specified at place of manufacture (see Table IV).

4.4.1.1 Test failure. If a vehicle fails to pass any acceptance tests specified herein, the Government inspector shall stop acceptance of subsequent vehicles until evidence has been provided by the contractor that corrective actions have been accomplished.

Table IV. Location of tests

	Requirements	Paragraph	Place of Mfr.	Proving Ground
Preproduction vehicle	3.1	4.2.1	X	
Initial production vehicle inspection	3.2	4.2.2	X	X
Reliability	3.2.1	4.2.2.1		X
Durability	3.2.2	4.2.2.2		X
Maintainability	3.2.3	4.2.2.3		X
In-process (inspection)		4.2.2.4	X	
Completed vehicle inspection		4.2.2.5	X	X
Repair of defects		4.2.2.6	X	
Vehicle disposition		4.2.2.7	X	
Initial production test		4.2.2.8		X
Test failure		4.2.2.8.1		X
Inspection provisions		4.3	X	
Acceptance test	3.4	4.4.1	X	
Power steering unit	3.4.4	4.4.1.2	X	X

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:23Z
Check the source to verify that this is the current version before use.

Table IV. Location of tests (Cont'd)

	Requirements	Paragraph	Place of Mfr.	Proving Ground
Engine & air inductive system check	3.4.5.& 3.4.5.1	4.4.1.3	X	X
Transmission check	3.4.6	4.4.1.4	X	X
Exhaust system check	3.4.7	4.4.1.5	X	X
Fuel tank, engine stop and hyd. reservoir check	3.4.8 & 3.4.9	4.4.1.6	X	X
Fuel, air and hydraulic lines and fittings check	3.4.10	4.4.1.7	X	X
Governor control linkage check	3.4.11	4.4.1.8	X	X
Personnel heater check	3.4.12	4.4.1.9	X	X
Front winch and wire rope check	3.4.13	4.4.1.10	X	
Cargo body	3.4.14	4.4.1.11	X	X
Control, adjustment check	3.4.15 & 3.4.16	4.4.1.12	X	X
Welding repairs & burning operation check	3.4.18	4.4.1.13	X	
Tire check	3.4.20	4.4.1.14	X	X
Break-in run & condition after run check	3.5 thru 3.5.2.1	4.4.1.15	X	
Brake test		4.4.1.16	X	X
Steering & articulation functional test	3.6.8 & 3.6.9	4.4.1.17	X	X
Leakage during swimming test	3.6.10 & 3.6.10.1	4.4.1.18	X	X

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:23Z
Check the source to verify that this is the current version before use.

Table IV. Location of tests (Cont'd)

	Requirements	Paragraph	Place of Mfr.	Proving Ground
Voltage alternator, lights and accessories check	3.6.11.1 & 3.6.11.2	4.4.1.19	X	X
Servicing and adjustment check	3.9	4.4.1.20	X	X
Controls tests		4.4.2	X	
Seals check	3.4.1 thru 3.4.1.1	4.4.2.2	X	X
Special kits check	3.4.2 thru 3.4.2.6	4.4.2.3	X	X
Tire chain check	3.4.3	4.4.2.4	X	X
Front winch and wire rope test	3.4.13	4.4.2.5	X	X
Vehicle operational test		4.4.2.6	X	X
Grade & slope operational test	3.6.2	4.4.2.6.1	X	X
Engine starting on grades & side slope tests	3.6.3	4.4.2.6.2	X	X
Cooling system test	3.6.4	4.4.2.6.3	X	X
Speed test	3.6.6 & 3.6.6.1	4.4.2.6.4	X	X
Braking test	3.6.7.1 & 3.6.7.2	4.4.2.6.5	X	X
Holding on grades test	3.6.7.1 & 3.6.7.2	4.4.2.6.6	X	X
Steering angle and vehicle articulation test	3.6.8 & 3.6.9	4.4.2.6.7	X	X
Bilge pump operational test	3.6.10.1	4.4.2.6.8	X	X

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

Table IV. Location of tests (Cont'd)

	Requirements	Paragraph	Place of Mfr.	Proving Ground
Soft top check	3.4.21	4.4.2.7	X	X
Comparison tests		4.4.3		X
Special kits operational tests	3.4.2 thru 3.4.2.6	4.4.3.2		X
Carbon monoxide concentration test	3.4.7	4.4.3.3		X
Front winch operational test	3.4.13	4.4.3.4		X
Transportability check	3.4.19	4.4.3.5		X
Vehicle performance tests	3.6, 3.6.2 & 3.6.5	4.4.3.6		X
Environmental operating	3.6.1	4.4.3.7		X
Steering angle and vehicle articulation test	3.6.8 & 3.6.9	4.4.3.8		X
Leakage during swimming operational test	3.6.10	4.4.3.9		X
Bilge pump test	3.6.10.1	4.4.3.9.1		X
Radio interference suppression test	3.7	4.4.3.10		X
Noise and vibration level test	3.10	4.4.3.11		X
Painting check	3.8.1	4.5	X	X
Marking check	3.8.2	4.6	X	X
Data plate check	3.8.3	4.7	X	X

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

Table IV. Location of tests (Cont'd)

	Requirements	Paragraph	Place of Mfr.	Proving Ground
Workmanship check	3.11	4.8	X	X
Safety verification	3.4.23	4.9		X
Materiel handling crane check	3.4.22	4.10	X	X
Preservation, packaging and vehicle processing	5.1	4.11	X	

4.4.1.2 Power steering unit check. To determine conformance to 3.4.4, the power steering unit shall be checked to assure proper assembly, installation and leaks.

4.4.1.3 Engine and air induction system check. To determine conformance to 3.4.5 and 3.4.5.1, the engine and engine air induction system shall be checked for proper assembly and installation.

4.4.1.4 Transmission check. To determine conformance to 3.4.6, the transmission shall be checked for proper assembly and installation.

4.4.1.5 Exhaust system check. To determine conformance to 3.4.7, the exhaust system shall be checked for proper installation and for leakage.

4.4.1.6 Fuel tanks, hydraulic reservoir, and engine stop switch check. To determine conformance to 3.4.8 and 3.4.9, the fuel tanks and hydraulic reservoir shall be checked for cleanliness, leaks, chaffing, and vibration. The engine stop switch shall be operated and checked for functional requirements.

4.4.1.7 Fuel, air, hydraulic lines, and fitting check. To determine conformance to 3.4.10, the lines and fittings shall be checked for leaks and signs of excessive vibration and chaffing that could lead to vehicle failure.

4.4.1.8 Governor control linkage check. To determine conformance to 3.4.11, the throttle pedal shall be depressed to stop position and the engine governor control linkage checked to assure that full rack position has been reached without binding or damage to linkages or governor.

4.4.1.9 Personnel heater check. To determine conformance to 3.4.12, the personnel heater shall be checked for proper assembly and installation.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:23Z
Check the source to verify that this is the current version before use.

4.4.1.10 Front winch and wire rope check. To determine conformance to 3.4.13, the winch and wire rope shall be checked for proper assembly and installation.

4.4.1.11 Cargo body check. To determine conformance to 3.4.14, the body shall be checked for proper assembly.

4.4.1.12 Controls, and adjustment provisions check. To determine conformance to 3.4.15 and 3.4.16 all controls shall be operated and checked for proper installation and functional requirement.

4.4.1.13 Welding checks. To determine conformance to 3.4.18 and welding, welding repairs and burning operations shall be checked for removal of slag and if approved procedures have been followed.

4.4.1.14 Tire check. To determine conformance to 3.4.20, the tires shall be checked for proper type and pressures.

4.4.1.15 Break-in run and condition after break-in run check. To determine conformance to 3.5 through 3.5.2.1, each vehicle less payload, shall be operated as specified and observed for performance requirements and conditions after the break-in run.

4.4.1.16 Brake test. The vehicle shall be operated, service and parking brakes checked for meeting functional requirements, except for grade requirements.

4.4.1.17 Steering and articulation functional test. To determine conformance to 3.6.8 and 3.6.9, the vehicle shall be operated and functional checks made.

4.4.1.18 Leakage during swimming test. To determine conformance to 3.6.10 and 3.6.10.1, the vehicle shall be placed or driven into water of sufficient depth to float vehicle; leakage shall not exeeed that specified. Bilge pumps shall be functionally tested.

4.4.1.19 Alternator voltage, lights and accessories check. To determine conformance to 3.6.11.1 and 3.6.11.2, with all lights and accessories functioning, the alternator voltage shall be checked at point specified and voltage shall be as specified. The lights and accessories shall be operated and checked for functional requirements.

4.4.1.20 Servicing and adjustment check. To determine conformance to 3.9, the vehicle shall be checked for conformance to requirements specified therein.

4.4.2 Control tests.

4.4.2.1 Frequency. The Government shall select at random for control test one out of each 40 vehicles or a minimum of one per month if production is less tha 40 vehicles per month. Each vehicle selected shall be operated

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

with designated or simulated payload, for a distance of 50 miles by the contractor. These tests shall be performed in the presence of a Government representative. After completion of test the doors, control devices, and other functional parts shall be tested for functional requirements.

4.4.2.1.1 Failure. If the vehicle selected fails to pass any of the control tests, the Government inspector shall stop acceptance examination and testing on subsequent vehicles until such time as conditions causing the failure have been remedied. Any defects found during or as a result of the test shall be prima facie evidence that vehicles accepted subsequent to the previous acceptable control test vehicle are similarly defective unless evidence satisfactory to the contracting officer is furnished by the contractor that they are not similarly deficient. Such defects on all vehicles shall be corrected by the contractor at no cost to the Government. Another vehicle with corrective actions implemented shall be subjected to the control test.

4.4.2.2 Seals check. To determine conformance to 3.4.1.1 after fording or swimming operations, all bearing subject to water contamination shall be checked. Lubricants shall be drained and examined for water contamination and shall not be more than that specified.

4.4.2.3 Special kits check. To determine conformance to 3.4.2 through 3.4.2.6, one of each 10 samples of a specifie kit furnished shall be installed in accordance with applicable drawings.

4.4.2.4 Tire chains check. To determine conformance to 3.4.3, the tire chains shall be installed and vehicle driven for not less than 2 miles, and retention of tightness and clearance in wheel well checked.

4.4.2.5 Front winch and wire rope test. To determine conformance to 3.4.13, the winch and rope shall be tested with rated load and observed for meeting requirements.

4.4.2.6 Vehicle operational test. The vehicle loaded with rated payload including all stowage and OEM item (see 3.4.17) shall be tested as specified herein. The testing where applicable may be performed during the 50 mile road test. The contractor shall be permitted to unpackage and repackage all stowage and OEM items used for test. Troop installed and depot installed OEM will be furnished by the Government.

4.4.2.6.1 Grade and slope operation test. To determine conformance to 3.6.2, the vehicle shall be operated on 60 percent grades headed up and down, and on 30 percent side slopes with each side of vehicle up slope.

4.4.2.6.2 Engine starting on grades and side slopes test. To determine conformance to 3.6.3, the vehicle shall be placed on specified grades and slopes, and engine stopped then restarted to assure engine meets starting requirements. The fuel and lubrication systems shall function in all positions without failure.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

4.4.2.6.3 Cooling system test. To determine conformance to 3.6.4, during the road test the cooling system shall be checked to assure the system meets cooling requirements. The maximum temperature of the transmission oil, and engine coolant shall be recorded. Engine oil pressure shall also be recorded.

4.4.2.6.4 Speed test. To determine conformance to 3.6.6 and 3.6.6.1, the vehicle loaded with rated payload shall meet the speed requirements.

4.4.2.6.5 Braking test. To determine conformance to 3.6.7.1 and 3.6.7.2, during road test the service and parking brakes shall be checked for functional operation. Stopping distance shall be not more than that specified.

4.4.2.6.6 Holding on grades test. To determine conformance to 3.6.7.1, and 3.6.7.2, the vehicle loaded with rated payload shall be operated on 60 and 40 percent grade as specified, the vehicle shall be stopped and the transmission put in neutral, service and parking brakes shall hold the vehicle on the specified grades.

4.4.2.6.7 Steering angle and vehicle articulation test. To determine conformance to 3.6.8, the vehicle shall be operated over terrain permitting articulation (roll) between the front and rear units. The vehicle shall be turned to check conformance with the requirement specified to the right and the left to assure that there is no binding or interference between the front and trailing units under all conditions of steer and roll. To determine conformance with 3.6.9, stops shall be placed to check the roll limitation as specified.

4.4.2.6.8 Bilge pump operational test. To determine conformance to 3.6.10.1, bilge pumps shall be operated during swimming test to determine performance and rate of water removal.

4.4.2.7 Soft top check. To determine conformance to 3.4.21, the top shall be checked for completeness of assembly.

4.4.3 Comparison test. The Government may select vehicles anytime during a production contract period and subject vehicles to all tests listed on Table IV and Table V to reveal defects of a workmanship or materials nature that may reduce the effective operation of these items in the field and compare existing quality with previous standards. These tests shall be conducted at Government laboratories or proving grounds designated by the contracting officer. Comparison test vehicles shall be combat loaded with all OEM stored in their applicable spaces. Vehicles selected shall not include any vehicles previously tested for conformance to 4.4.2 (Control tests).

4.4.3.1 Test failure. Failure of the test vehicle to meet minimum performance requirements, failure to comply with the requirements of a workmanship or materials nature and failure to manufacture the vehicle in accordance with the technical data revealed during or as a result of this test, shall be cause for rejection of the vehicle. Further, the Government may refuse to continue acceptance of production vehicles until evidence has been provided by the contractor that corrective action has been taken to eliminate the defects. Any

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

defects found during or as a result of this test shall be prima facie evidence that all vehicles already accepted prior to completion of test, are similarly defective unless evidance satisfactory to the Government is furnished by the contractor that they are not similarly deficient. Such defects on all vehicles shall be corrected by the contractor at no cost to the Government.

Table V. Comparison test (5000 miles)

Course	Mileage and speeds	Vehicle payload (see 3.6)
Paved surface (20%)	1000 miles at speeds varying up to max.	8 ton
Secondary roads (36%)	1800 miles at speeds applicable to terrain	8 ton
Hilly cross country (20%)	1000 miles at speeds applicable to terrain	8 ton
Level cross country (20%)	1000 miles at speeds applicable to terrain	8 ton
Belgian block (4%)	200 miles	8 ton
Swimming	2 hours	8 ton

NOTE: Ten percent of the mileage specified for each course shall be performed with towed load (see 3.6.6.1), excluding swimming.

4.4.3.2 Special kits operational tests. To determine conformance to 3.4.2 through 3.4.2.6, when special kits are furnished for testing, they shall be installed on vehicle and tested for meeting performance requirements for the individual kit.

4.4.3.3 Exhaust concentration check. To determine conformance to 3.4.7, the occupied areas of the vehicle shall be checked for concentration of exhaust fumes. Fumes shall not exceed percent specified.

4.4.3.4 Front winch operational test. To determine conformance to 3.4.13, winch shall be operated with rated load and checked for operational requirements and wire rope functional requirements.

4.4.3.5 Transportability check. To determine conformance to 3.4.19, the vehicle shall be checked for transportability requirements.

4.4.3.6 Vehicle performance tests. To determine conformance to 3.6, the vehicle with rated payload shall meet all performance requirements and test results recorded.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

4.4.3.7 Environmental operating conditions tests. To determine conformance to high and low temperature operation of 3.6.1, the vehicle shall be tested as required to assure that the vehicle meets all environmental requirements.

4.4.3.8 Steering angle and vehicle articulation test. To determine conformance to 3.6.8, the vehicles shall be operated over terrain permitting articulation (roll) between the front and rear units. The vehicle shall be turned to check conformance with the requirement specified to the right and the left to assure that there is no binding or interference between the front and trailing units under all conditions of steer and roll. To determine conformance with 3.6.9, stops shall be placed to check the roll limitation as specified.

4.4.3.9 Leakage during swimming operational tests. To determine conformance to 3.6.10, the vehicle shall be operated as specified, performance and leakage checked.

4.4.3.9.1 Bilge pump test. To determine conformance to 3.6.10.1, bilge pumps shall be operated during swimming test to checked performance and rate of water removal.

4.4.3.10 Radio interference suppression test. To determine conformance to 3.7, the vehicle and components shall be subjected to the tactical vehicle suppression requirements of specification specified.

4.4.3.11 Noise and vibration level tests. To determine conformance to 3.10, the applicable sound levels and vibration level instrumentation shall be used to assure the vehicle meets requirements.

4.5 Painting check. To determine conformance to 3.8.1, all applicable surfaces of the vehicle shall be checked for specified treatment, primer and paint requirements at sites specified in Table IV.

4.6 Marking check. To determine conformance to 3.8.2, the vehicle markings shall be checked for specific marking requirement at sites specified in Table IV.

4.7 Data plate check. To determine conformance to 3.8.3, the vehicle data plates shall be checked for specific marking requirements at sites specified in Table IV.

4.8 Workmanship check. In reference to paragraph 3.11, see paragraph 4.3.

4.9 Safety verification. To determine conformance to 3.4.23, the vehicle shall be checked to assure all hazards have been eliminated or reduced to the minimum in operating the vehicle or any of its equipment at sites specified in Table IV.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:23Z
Check the source to verify that this is the current version before use.

4.10 Material handling. To determine conformance to 3.4.22, the material handling crane shall be checked for proper assembly, installation and operation at sites specified in Table IV.

4.11 Preservation, packaging, and vehicle processing. Material and equipment shall be inspected prior to shipment to assure conformance to the applicable requirements specified in 5.1.

5. PREPARATION FOR DELIVERY

5.1 Vehicle processing. Unless otherwise specified (see 6.2), the vehicle and equipment shall be processed for shipment and storage in accordance with MIL-V-62038 to the extent indicated on the applicable vehicle preservation data sheet.

6. NOTES

6.1 Intended use. The vehicle covered by this specification is intended for use by the United States Armed Services primarily as a cargo carrier during tactical military operations. The vehicle is intended for use under extreme climatic conditions, and Phase II air lift.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number and date of this specification.
(b) Preproduction vehicle if required (see 3.1).
(c) Special kits if required (see 3.4.2 and 6.4).
(d) Material handling crane if required (see 3.4.22).
(e) Front winch if required (see 3.4.13).
(f) Quantity of initial production test vehicles required (see 4.2.2.8).
(g) Level of preservation, packaging and processing if other than specified (see 5.1).

6.3 The following definitions shall be used for the classification of defects for leaks:

(a) Weep: - Any non-recurring evidence of fluid beyond the seal.
(b) Seep: - Any recurring evidence of fluid beyond the seat that does not result in formation of a droplet.
(c) Droplet: - Any recurring evidence of fluid beyond the seal that results in formation of a non-falling droplet.
(d) Drip: - Any recurring evidence of fluid beyond the seal where droplet forms and fall.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

6.4 Special kits (see 6.2).

11614953	-	Gun ring mounting kit.
11614959	-	Rear canopy and frame kit.
11614988	-	Arctic kit.
11624639	-	Filter kit - infra-red kit.
11620144	-	Trailer brake kit.
11651365	-	Warning light kit.

6.5 Mission statement. One mission shall consist of 100 miles of operation under these conditions of load, speed, terrain, and environment with special functions described.

Terrain	Distance	Operating schedule Range MPH
Hard surface	20 Miles	0 - 30
Secondary	40 Miles	0 - 30
Level Cross Country	16 Miles	0 - 30
Level Cross Country MUD*	4 Miles	0 - 10
Hilly Cross Country *	20 Miles	0 - 15
Swimming *	Traverse Water Barrier	5 Minute Operation
60% Grades:	1/10 of 1% of Hilly cross country operation	W/O towed load.
30% Side Slopes	1/10 of 1% of Hilly cross country operation	W/O towed load.
Climatic Extremes		
Temperature:	-25°F. to 125°F ambient	
Altitude:	500' to 5,000'	
TRACTOR FUNCTIONS:		
Idle:	30 minutes	
Starts:	One cold, one hot at two minutes, one hot at 15 minutes after shutdown (cold means coolant & oil at ambient, hot at maximum obtained)	
* 4-Wheel Drive:	100% Mud & Swim, cross country as required, all other operation is in 2-Wheel Drive	
Reverse:	10 operations at 130 feet each	
Front winch (once each 10 missions) one overload attempt (110% of rated capacity) followed by recovery of a load at 90% capacity		
CARGO CARRYING FUNCTION:		
Operation:	50% of time at 8 Ton Payload, 25% of time at 4 Ton Payload, and 25% at no load, 10% with towed load.	
When equipped w/MHE Crane:	load and unload 8 Ton palletized cargo every second mission.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.

6.6 TYPICAL VEHICLE LIFE OPERATIONAL PROFILE

MODEL	RENEWAL LIFE MILES - HOURS	AVG M.P.H.	TOTAL MISSIONS	MISSION MILES - HRS
M520	25,000 - 1250	20.0	250	100-5
M559	18,000 - 1250	14.4	182	100-6.9
M553	12,500 - 1250	10.0	250	50-5
M877	25,000 - 1250	20.0	250	100-5

In actual troop use, this will vary due to environmental terrain, and troop mission differences.

6.7 Process average. Sampling may be initiated if the process average value of the first twenty vehicles inspected is less than the A.Q.L. specified in the classification of defects for major and minor defects. Process average shall be computed as follows:

$$\text{Process average} = \frac{\text{Number of defects}}{\text{Number of vehicle inspected}} \times 100$$

If the computed process average exceeds the specified A.Q.L., 100 percent inspection shall be performed and continued until such time that the process average for twenty consecutive vehicles is less than the specified A.Q.L.

6.8 Definitions of recurring major and minor defects. The Government Inspector will verify that a thorough inspection of each vehicle is performed by the contractor not only for the listed characteristics, but also for any other departures from good workmanship. The Government Inspector will assure that all deficiencies encountered during the inspection are enumerated on the Deficiency Sheet for the vehicle. The defects noted on Deficiency Sheet shall contain sufficient description to enable the Government Inspector and the contractor's representative to classify the deficiency in accordance with the classification of defects of the vehicle specification and definitions contained in MIL-STD-105. Corrective action shall be taken for recurring deficiencies.

Custodian:
Army - AT

Preparing Activity:
Army - AT

Project No. 2320-A957

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:23Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION
MIL-T-62132B(AT)

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A
☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?
   ☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426 REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:23Z
Check the source to verify that this is the current version before use.