INCH-POUND
A-A-59111D
December 6, 2019
SUPERSEDING
A-A-59111C
October 31, 2018

COMMERCIAL ITEM DESCRIPTION

SERVICING/DE-ICING MAINTENANCE PLATFORM, HIGH-REACH, TRUCK MOUNTED

The General Services Administration has authorized the use of this commercial item description for all federal agencies by all federal agencies.

1. SCOPE This commercial item description (CID) describes a truck-mounted aerial servicing platform for C-5 and C-17 aircraft maintenance and de-icing. This servicing platform shall conform to the requirements and provide the capabilities specified herein.

2. SALIENT CHARACTERISTICS The high-reach maintenance platform (HRMP) truck shall consist of a heavy-duty truck chassis, supporting frame, articulating aerial tower, work platform, stabilizers, and hydraulic system. The delivery systems, jib-crane, and winch shall be commercially-available items. Maximum gross unit weight shall not exceed 65,000 pounds (including full tank of fuel, operators, and installed equipment). The servicing platform shall be compact with all components arranged for maximum ease of operation and maintenance. The fully-extended articulating boom shall be capable of raising the platform base a minimum of 120 feet from the ground.

2.1 Manuals and media.

2.1.1 Technical manuals. The overall format for the manuals may be military specification, commercial, or a combination of both. Each technical manual shall have a title page. The National Stock Number (NSN) shall be on the title page. Line-art shall be used to the maximum extent possible for illustrations and parts lists.

a. The contractor shall submit digitized technical manuals in lieu of printed paper copies to the Technical Order Manager.

b. The contractor shall validate the technical manuals for accuracy prior to submission to the procuring activity for verification. Any corrections or changes identified by the procuring activity shall be corrected and updated by the contractor. Those re-corrected pages,

Beneficial comments, recommendations, additions, deletions, clarifications, etc. and any data that may improve this document should be sent to: AFLCMC/EZSS, 2145 Monahan Way, Area B, Bldg 28, Wright-Patterson AFB, OH 45433 or emailed to ENGINEERING.STANDARDS@US.AF.MIL. Since contact information can change, you may want to verify the currency of this address information using the ASSIST Online database at https://assist.dla.mil/.

FSC 2320

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

manuals, or changes shall be resubmitted to the procuring activity. The contractor shall submit one complete set of draft manuals to the procuring activity for verification at least 30 days prior to the first production test.

c. Once approved by the procuring activity and a technical order (TO) number is assigned, two complete sets of CDs (or approved digital format) shall be submitted to the procuring activity for stock. The technical manual shall be approved and submitted to the procuring activity 30 days prior to delivery of the first production vehicle.

d. The contractor shall grant the United States Air Force (USAF) a non-exclusive, non-assignable, royalty-free U.S. Government (Government) Purpose License, to scan into CENTRA (the USAF repository) and to reproduce and distribute (either electronically or via hard-medium) copies or facsimiles of manuals produced and distributed by the contractor for this CID. These rights extend to government agencies only. The data contained on the technical manuals is not to be sold, disclosed, or otherwise provided to any other entity or entities outside the government. The license shall remain in effect as long as the vehicles described in the required technical manuals remain under government control and usage. In addition, the contractor shall grant permission for the government to place an Air Force TO number, publication date, distribution warning, and handling and destruction statements on the cover/title pages of the TO.

2.1.1.1 Operator manual. The operator manual shall include all information required for the safe and efficient operation of the vehicle, including the servicing and de-icing equipment, and any special attachments or auxiliary equipment. The operator manual shall include at least the following:

a. Location and function of all controls and instruments shall be illustrated and fully described.

b. Safety information that is consistent with the safety standards set forth in 2.6.

c. Checks and adjustments in preparation for placing the vehicle for service upon receipt from the contractor.

d. Preparation for shipment or storage.

e. Warranty information and period of the warranty for the complete vehicle and for any component warranty that exceeds the warranty of the complete vehicle. Addresses and telephone numbers shall be provided for all warranty providers.

f. General description of and step-by-step instructions for the operation of the vehicle and its servicing and de-icing system(s) and auxiliary equipment.

g. Description of the post-operational procedures (draining, flushing, and related operations).

h. Checklists for the daily maintenance inspection and mission readiness check that the operator is expected to perform, including basic troubleshooting procedures.

i. Procedures for towing a disabled vehicle.

j. Procedures for changing a tire.

k. Schedules for required preventative maintenance and required periodic maintenance.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

l. A line-art drawing of the vehicle, including front, rear, left, and right side views, showing basic dimensions and weights (total vehicle and individual axle weight for the unloaded and fully-loaded vehicle).

m. Identification markings as outlined in SAIA A92.2 are to be installed**.**

2.1.1.2 Service manual. The service manual shall identify any special tools and test equipment required. The manual shall cover troubleshooting, maintenance, minor and major repair procedures. The text shall contain performance specifications, tolerances, fluid capacities, current, voltage, resistance data, test procedures, illustrations and exploded views as required to permit proper maintenance by qualified mechanics. The manual shall contain an alphabetical subject index and a table of contents. The service manual shall contain, where applicable:

a. De-icing and washing system schematic(s).

b. Hydraulic schematic.

c. Pneumatic schematic.

d. Electrical schematic.

e. Winterization schematic.

f. Fuel schematic.

g. Schedules for required preventative maintenance and required periodic maintenance.

h. Location, procedure, and interval for parts of the truck and equipment that require lubrication.

2.1.1.3 Parts manual. The parts manual shall include illustrations and exploded views, as needed, to properly identify all parts, assemblies, subassemblies, and special equipment. All components of assemblies shown in illustrations or exploded views shall be identified by reference numbers that correspond to the reference numbers in the parts lists. All purchased parts shall be cross-referenced with the original manufacturer's name and part number. When the manufacture of a service part requires identification beyond a part number to identify that particular service part, that information shall also be supplied. The parts identification manual shall provide the description and quantity of each item used per vehicle. The size, thread dimensions, torque specifications, and special characteristics shall be provided for all nonstandard nuts, bolts, screws, washers, grease fittings, and similar items. The manual shall contain a numerical index. The parts manual shall contain a list of all of the component vendor names, addresses, and telephone numbers referenced in the parts list.

2.2 Identification and information plates. All data plates shall be permanently marked and constructed of a non-corrosive metal in accordance with MIL-STD-130. All data plates shall be attached using stainless steel or anodized aluminum screws or rivets, or with stainless steel or aluminum banding; if attached to hydraulic cylinders. Attachments shall be in a conspicuous location which is readily viewable to service personnel standing on level ground during all stated procedures. The size of the plates shall not exceed the structure to which it is attached.

2.2.1 Identification plate. An identification plate, in accordance with MIL-STD-130, shall be securely attached to the HRMP in a readily-accessible location. The identification plate shall contain the following information: nomenclature, part number, serial number, date of manufacture, manufacturer’s name, Commercial and Government Entity (CAGE) code, date of warranty

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

expiration, and NSN. The HRMP and any of its components for which the government's unit cost is more than $5,000, is serially managed, or the procuring agency determines is mission essential, shall have Unique Identification (UID) marking, (also known as Item Unique Identification (IUID)). The information, or plates will be permanently affixed on or near the respective components, marked in accordance with MIL-STD-130. UID information shall be included as both a bar-code and legible markings. The "CE" marking shall be affixed in accordance with EU requirements on or adjacent to the identification plate.

2.2.2 Transportation data plate. A transportation data plate shall be securely attached to the HRMP in a readily-accessible location. The plate shall contain at least the following information:

a. Side and rear silhouette views of the HRMP.

b. Horizontal and vertical location of the center of gravity of the HRMP for each air transportable-configuration, marked on the silhouette views.

c. Shipping weight.

d. Loading cubage.

e. Overall height, width, and length.

f. Front and rear axle loads.

g. Tie-down information.

2.2.3 Lubrication data plate. The HRMP shall be provided with a permanently-marked lubrication data plate, constructed of a non-corroding metal, mounted on the exterior surface of the HRMP. The data plate shall direct attention to all lubrication fittings, and components that require lubrication. The plate shall identify the type and grade of lubricant required for operational temperatures specified in 2.3.1.

2.3 Corrosion control and finishes.

2.3.1 Dissimilar metals. Dissimilar metals as defined in MIL-STD-889 shall not be in contact with each other. Metal plating or metal spraying of dissimilar base metals is acceptable to provide electromotive compatible abutting surfaces. The use of dissimilar metals separated by suitable insulating material is permitted, except in systems where bridging of insulation materials by an electrically-conductive fluid can occur.

2.3.2 Finishes and protective coatings. Cleaning, painting, and finishing shall follow the guidelines of MIL-HDBK-808, Type I Exposure, and painted to the manufacturer's standard commercial finish. Materials that deteriorate when exposed to sunlight, weather, or operational conditions normally encountered during the service life of the item shall not be used. Protective coatings that chip, crack, or scale with age or extremes of climatic conditions or when exposed to heat shall not be used. Exposed surfaces of fasteners, handles, and fittings shall also be primed and painted.

2.3.3 Corrosion-resistant delivery system components. All components of the fluid delivery system shall be resistant to water in accordance with SAE AMS 1424, Type I de-icing and Type IV anti-icing and defrosting fluids, and for solutions containing cleaning compound in accordance with MIL-PRF-87937.

2.3.4 Exclusion of water. The design of the HRMP shall be such as to prevent water leaking into, or being driven into, any part of the HRMP interior, when either in an operating or travelling

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

configuration. All windows, doors, panels, covers, and related type openings, shall be provided with sealing arrangements such that the entry of water is minimized when these items are correctly closed. Particular care shall be taken to prevent the wetting of equipment, heat, and sound proofing materials. Sharp corners and recesses shall be avoided so that moisture and solid matter cannot accumulate to initiate localized attack. Sealed floors with suitable drainage shall be provided for storage compartments, engine compartments, and other areas in the HRMP that could collect and retain water.

2.3.5 Fluid traps and faying surfaces. There shall be no fluid traps on the HRMP. Faying surfaces of all structural joints, except welded joints, shall be sealed to preclude fluid intrusion.

2.3.6 Ventilation. Ventilation shall be sufficient to prevent moisture retention and buildup.

2.3.7 Drainage. Drain holes shall be provided to prevent collection or entrapment of water or other unwanted fluid in areas where exclusion is impractical. All designs shall include considerations for the prevention of water or fluid entrapment and ensure that drain holes are located to effect maximum drainage of accumulated fluids. The number, and location of drain holes shall be sufficient to permit drainage of all fluids. The minimum size of the drain holes shall be 0.375 inch.

2.4 Transportability.

2.4.1 Air-transportability. The HRMP shall be air-transportable on C-5 and C-17 aircraft in accordance with the guidelines of MIL-STD-1791. In all transport configurations, the HRMP truck shall be capable of being restrained and withstanding 2.0 G up, 4.5 G down, 3.0 G forward, 1.5 G aft, and 1.5 G lateral accelerations. The unit shall be equipped with pressure relief devices or configured for air transport to prevent any part from becoming a projectile in the event of catastrophic loss of aircraft cabin pressure.

2.4.1.2 Air-transportable configuration. The air-transportable configuration shall include all equipment and no crewmembers. In this configuration the maximum single axle weight is 25,000 pounds. At least 6 inches of sidewall, and 6 inches of overhead clearance shall be maintained between the HRMP and the aircraft at all times, during loading and flight. The restrained HRMP shall allow for loadmaster in-flight access from the front to the rear of the aircraft. Parking and sleeper-shoring shall be permitted according to the guidelines of MIL-STD-1791.

2.4.1.3 Equipment removal/reconfiguration. Preparation and restoration of the unit for air-transportability shall take no more than 30 minutes for two persons using common non-powered hand tools. All equipment removed shall be stored on the truck; caps and plugs shall permit driving and storage in transport configuration.

2.4.2 Tie-down points. Tie-down provisions shall be in accordance with MIL-STD-209. The unit shall be symmetrically restrained during air transport. Tie-down points shall be rated at a minimum of 25,000 pounds and marked for capacity, with a clear opening compatible with MIL-DTL-25959 and MIL-PRF-27260. Each end of each tie-down device shall terminate at a tie-down point and not pass through any other tie-down point. There shall be no interference between tie-down devices and the HRMP.

2.4.3 Manually-operated mechanical lock for air transport. A manually-operated rigid mechanical lock shall be provided, in addition to the interlock system of 2.22.5, to further secure the aerial boom and platform in the stowed position in preparation for air transport.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

2.4.4 Component lifting provisions. Lifting eyes or other hoisting devices with a rating of at least 200 percent of component weight shall be provided on all major components.

2.5 Maintainability. The HRMP and all included systems shall be designed and constructed for ease of maintenance, and shall require:

a. A minimal amount of training needed to establish proficiency in assembly, disassembly, troubleshooting, maintenance, and service.

b. When available, parts and components shall be located or positioned for rapid and simple inspection and recognition of excessive wear and potential failure.

c. Capability of performing maintenance with general-purpose tools and equipment that are normally available commercially. The use of special purpose tools and equipment shall be subject to approval by the procuring activity.

d. The individual engine components (cylinder heads, fuel injection pump, air compressor, and other related components) are removable and replaceable without removal of the engine from the vehicle chassis.

2.6 Safety standards. The vehicle and all furnished accessories shall comply with the following safety standards:

a. All applicable Federal Motor Carrier Safety Regulations (FMCSR) 49 CFR 393 in effect on the date of manufacture.

b. OSHA 29 CFR 1910.

c. SAIA A92.2 and ANSI Z359.1.

2.6.1 Attachment for fall protection. Anchorage for personal fall protection shall be in accordance with 4.9.4 of SAIA A92.2. Each anchor, capable of supporting a static load of 5,000 pounds (2273 kg), shall be provided for appropriate fall protection for an occupant of the platform and increased by a safety factor of 0.2 (20 percent) for each additional occupant. If separate anchors are used for each occupant, each anchor shall be capable of supporting a static load of 5,000 pounds (2273 kg).

2.7 Set up/operating positions. The servicing platform shall be considered set up and ready for operation only after the following conditions are established:

a. The unit shall be placed on an evenly paved area such as a parking ramp.

b. It shall be verified that all weight is off the chassis suspension and transferred to the outriggers; that is, the entire platform load shall be supported entirely on the outriggers.

c. The extended outriggers shall not exemplify evidence of instability or overturning of the unit, with a 1,500 pound load applied to the platform. The boom shall not be activated before this verification has been accomplished.

d. The unit shall be capable of operating only after being leveled by the outriggers. For operation on slopes, the unit shall be capable of being held in position by the elevating and rotating mechanism when the normal operating plane is ±5° from the horizontal.

2.8 Environmental conditions. The HRMP shall operate satisfactorily under the following environmental conditions:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

a. Operating temperatures ranging from -40 to 125 °F, storage temperatures ranging from -40 to 140 °F.

b. Altitude ranging from sea level to 6,000 feet.

c. Self-induced vibration for all output conditions and vibration encountered during shipment and road operation.

d. All forms of precipitation encountered under field operation.

e. Wind loads of at least 7 pounds per square inch (psi), or 40 miles per hour (mph) wind velocity.

2.9 Mobility.

2.9.1 Paved road**.** The fully equipped HRMP loaded to its gross vehicle weight rating (GVWR) shall be capable of traveling at speeds up to 40 mph on a dry level paved road (see 6.2.2.1 of SAE AS8090).

2.9.2 Cross-country terrain. The fully equipped HRMP loaded to its gross vehicle weight rating (GVWR) shall be capable of traveling at speeds up to 20 mph on cross-country terrain (see 6.2.2.4 of SAE AS8090).

2.10 Overall dimensions. The HRMP in the stowed position shall not exceed the dimensions indicated in table I below.

TABLE I. Overall dimensions.

Length	496 inches
Width	102 inches (side mirrors retracted)
Height	153 inches
Weight	65,000 pounds

2.10 Towing connections. Tow hooks, designed to tow disabled HRMP, shall be installed on the frame structure, or on suitable members attached directly to the frame; two shall be installed at the front (one on each side of the frame centerline), and at least one at the rear. Load ratings of the tow hooks shall be at least 200 percent of the tow weight.

2.11 Sound levels.

2.11.1 Cab interior sound level. The HRMP interior sound level shall be in accordance with 49 CFR 393.94.

2.11.2 Vehicle exterior sound level. The HRMP exterior sound level shall be in accordance with 49 CFR 325.

2.12 Field of vision. The operator field of vision shall be in accordance with 49 CFR 393.78 through 393.80.

2.13 Chassis and vehicle components. The chassis shall be a standard truck model or a custom chassis designed with requirements of a de-icing/servicing HRMP. The chassis shall include an enclosed, heated cab for the vehicle driver and a passenger. Standard truck cab equipment, such as heater/defroster, lights, electric wipers and washer, rear view mirrors, et cetera, shall be provided.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

2.13.1 Steering. The HRMP shall be equipped with power steering and be left-hand drive.

2.13.2 Tires and wheels. The truck shall be equipped with tubeless steel belted radial ply tires with non-directional mud and snow type tread. Wheel assemblies shall be identical at all positions. A spare wheel assembly shall be provided and mounted in an easily accessible location. Tires shall be new; retreads, recaps, or re-grooved tires shall not be permitted. Wheel assemblies shall be in accordance with the *Tire and Rim Association Year Book* requirements for this application.

2.13.2.1 Tire pressure. Tire pressure shall be in accordance with MIL-STD-1791 to meet air transportability loading requirements. Tire pressure shall be stenciled above each tire on the HRMP.

2.13.3 Brake system. The braking system on the HRMP shall be in accordance with 3.13.1.7 of SAE ARP1247.

2.13.4 Electrical system. The HRMP shall have a 12- or 24-volt electrical system in accordance with 3.13.1.2 of SAE ARP1247, except where specified.

2.13.5 Starting system. A 12- or 24-volt starting system shall be provided and rated from 25 to 140 °F.

2.13.6 Alternator. The HRMP shall be equipped with a single or dual alternator charging system rated at a minimum of 60-ampere, in accordance with SAE ARP1247. The alternator's output at engine idle speed shall provide for the continuous electrical load of the HRMP. It shall be capable of restoring the energy expended during an engine start in less than 15 minutes of engine idle at -20 °F.

2.14. Engine. The HRMP shall be equipped with a diesel engine approved by the Environmental Protection Agency (EPA). The waiver required to purchase the engines shall be coordinated through the USAF HRMP contracting officer and engineer.

2.14.1. Export engine. The HRMP shall be equipped with a diesel engine compatible with JP-8 and F-24 jet fuels. At a minimum, the engine shall meet a Tier 2-level exhaust and evaporative emissions standard (export engine equivalent) for on-highway engines. This represents the highest level of exhaust and evaporative emissions standards that will permit the use of high-sulfur diesel fuels. In accordance with 40 CFR, 85.1708 the Air Force possesses an EPA waiver to allow for deviation from EPA emissions guidelines. The waiver will be transferred from the Air Force to the engine manufacturer. The transfer process requires the engine manufacturer to supply a decal for the engine stating, "This engine has an exemption for national security under 40 CFR, 1068.225."

2.14.1.1 Engine and related equipment. The engine and related equipment shall be in accordance with 3.13.1.4 of SAE ARP1247.

2.14.1.2 Fuel system and fuel tank(s). The fuel system shall be in accordance with 3.13.1.5 of SAE ARP1247. The HRMP shall have one or two fuel tanks with a minimum usable capacity of 60 gallons. When two tanks are furnished, automatic switching with manual override shall be provided.

2.14.1.3 Engine operating fuels.

2.14.1.3.1 Engine primary fuels. The following shall be primary fuels:

a. JP-5, in accordance with MIL-DTL-5624, -40 to 125 °F ambient air temperature.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

b. JP-8, in accordance with MIL-DTL-83133, -40 to 125 °F ambient air temperature.

c. F-24, in accordance with NATO AFLP-3747, -40 to 125 °F ambient air temperature.

2.14.1.3.2 Engine alternate fuels. The following shall be alternate fuels

a. 1-D S15, 1-D S500, and 1-D S5000 in accordance with ASTM D975, below 60 °F ambient air temperature.

b. 2-D S15, 2-D S500, and 2-D S5000 in accordance with ASTM D975, above 32 °F ambient air temperature.

c. TS-1 in accordance with GOST 10227-86 with JP-8 additives, -40 to 125 °F ambient air temperature.

2.14.1.3.3 Engine emergency fuels. The following shall be emergency fuels:

a. Jet A, Jet A-1 in accordance with ASTM D1655, all ambient temperatures.

Note: Jet A and Jet A-1 may contain corrosion inhibitor/lubricity improver and icing inhibitors which shall result in properties equal to JP-8.

2.14.2 Exhaust system. The exhaust system shall be in accordance with 3.13.1.6 of SAE ARP1247. A vertical exhaust, if furnished, shall be capable of being reached easily by personnel entering or leaving either side of the cab. If a vertical exhaust is provided, it shall be equipped with a hinged rain cap and a ¼ inch hole at the base of the exhaust stack to drain exhaust condensate. In addition, the exhaust system shall be shielded to prevent hydraulic fluid from leaking onto the hot exhaust system in the event of a hydraulic line rupture or leak.

2.14.3 Transmission. A fully automatic transmission with a hydraulic torque converter and at least five forward speeds shall be provided. The normal driving range selector position shall provide at least four gear ratios without movement of the selector.

2.14.4 Engine cooling system. A heavy duty cooling system shall be provided in accordance with SAE ARP1247, which shall maintain engine coolant at a temperature below the boiling point with the unit fully loaded and operated in an ambient air temperature of not less than 125 °F at sea level.

2.15 Hydraulic system. A complete hydraulic fluid system shall be provided, in accordance with 4.6 of SAIA A92.2, consisting of the components required to perform all hydraulically powered operations with the degree of control specified herein. As a part of this system, one male and one female standard commercial quick release connector and cap shall be provided at the platform to power hydraulic tools. The caps shall be suitably tethered to the connector assembly.

2.15.1 Hydraulic cylinders. Hydraulic cylinders shall be designed in accordance with 4.7 of SAIA A92.2.

2.15.2 Hydraulic lines and fittings. Nonflexible metal tubing shall be used in the hydraulic system where flexing is not encountered during operation of the boom assembly. Flexible hose or collector rings shall be used where flexing of hydraulic lines is encountered, and where installation of components require a flexible coupling. Hydraulic hose assemblies shall be in accordance with SAE J1273 and 4.6 of SAIA A92.2.

2.15.3 Hydraulic pump. A hydraulic pump shall be provided with necessary pressure and flow capacities to operate all hydraulically-powered components. While operating at normal rated speed, the pump shall have sufficient capacity to simultaneously elevate the platform (under

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

maximum rated load conditions) from the lowest to the highest position and to rotate the platform 360 degrees in not less than 4 minutes or more than 6 minutes.

2.15.4 Hydraulic fluid reservoir. A hydraulic fluid reservoir shall be provided with a capacity to hold the maximum volume of fluid that will be retained in the reservoir under any position of the boom assembly. Also, a minimum of 20 percent additional air space shall be provided to handle expansion, foaming, and surging of the fluid in the reservoir. The reservoir shall be marked to show use of oil and the maximum oil level in the reservoir with the boom(s) folded and the lines, cylinders, et cetera, full of oil.

2.15.5 Controlling hydraulic pressure rise. A means shall be provided to control hydraulic pressure rise due to thermal expansion of the hydraulic fluid, in accordance with 4.7.5 of SAIA A92.2. The aerial device shall be capable of continuous operation of the unit for periods as long as four hours with 1,500 pounds on the work platform without failure of the hydraulic system.

2.15.6 Hydraulic system protection. The hydraulic system shall be equipped with appropriate devices to prevent motion of the platform in the event of hydraulic line failure in accordance with 4.8 of SAIA A92.2.

2.15.6.1 Emergency lowering of elevated platform. At a minimum, a bleed-down valve, capable of being manually controlled at the base of the boom and on the platform control panel, shall be provided to permit lowering of the platform in the event of a hydraulic line failure. An auxiliary motor or other suitable device is also appropriate to expedite the lowering process. Tooling shall be provided to allow the boom turntable to be rotated away from any object under the work platform during an emergency lowering of the boom/platform.

2.16 Batteries. Each battery shall have a 12 volt potential and be a maintenance-free type battery; addition of water shall not be required during normal service life. The battery cover and vent system shall be designed to prevent electrolyte loss during service and to keep the top of the battery free from electrolyte. The total reserve capacity rating and the total cold cranking rating shall be in accordance with SAE J537.

2.16.1 Battery compartment. The battery box shall have a drain hole and a plug. The battery box shall have positive restraints on cables (applicable models) when removing the box cover.

2.17 Wiring. Wiring for the body shall be in accordance with applicable portions of the General Section of SAE J1292. All wiring exposed to possible physical damage, such as wiring on a compartment floor, or wiring where tools or materials may cause the wire to be frayed or shorted, shall be protected by the use of heavy wall thermoplastic conduit or steel conduit having waterproof connections. Grommets shall be used for all wiring going through any hole or body framework.

2.18 Lights and reflectors. All vehicle lights and reflectors shall be in accordance with 49 CFR 393, subpart B, and shall be of light emitting diode (LED) type. Lighting shall be furnished for night-time operations of sufficient candle power to illuminate ground and platform control panels and front and rear outriggers position, body load-space, and all equipment contained therein.

2.18.1 Floodlights. Two 4.5 inch minimum diameter sealed beam floodlights with universal mounts shall be installed on the HRMP. The floodlights shall be actuated from inside the cab for illuminating the work area. In addition, two 50 candela sealed-beam floodlights shall be mounted on the platform and adjustable to illuminate the front, side, above, and below the platform for night operation. These lights shall be actuated from the basket.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

2.18.2 Beacon. One or more amber, rotating, vehicular warning beacon(s) shall be provided. The beacon(s) shall be mounted with reinforcements at the point of attachment on or near the left front corner of the cab guard for 360° visibility.

2.18.3 Turn signals. The HRMP shall be provided with double-faced front signal units and with single-faced rear units installed in accordance with SAE J588, except the turn signals shall not be mounted on the engine hood. Front side mounted turn signal lamps shall also be furnished to compensate for the lack of double faced front mounted turn signals. A heavy duty flasher for the system shall be furnished; with both visual and audio (bell) indicators. Turn signal controls shall be mounted on the steering column. Turn signals shall be self-canceling, with controller mounted on the steering column.

2.19 Heaters.

2.19.1 Heater connections. A recessed, male, three-prong, 110-volt receptacle in accordance with style D or X of W-C-596 shall be provided for the power plant heaters and mounted and placarded on the outside of the cab. The receptacle shall be in a protected location and shall have a spring-loaded dust cap included as part of its housing. A three-wire connecting cable shall include a matching female connector at the vehicle end and a standard, weatherproof, three-pronged (two power plus one ground) male connector at the other end. A carrier for the connecting cable shall be mounted within the cab or engine compartment and shall provide positive cable retention during vehicle operation.

2.19.2 Power plant heater kit. A power plant heater kit shall be installed on the unit prior to delivery. The kit shall provide standby type winterization and shall include properly selected 110-volt heaters and thermostats. Heaters shall be of sufficient capacity to place the unit in an operating condition at -40 °F within 60 minutes. A warning light in cab shall be provided to indicate when external heater is connected.

2.20 Controls, panels, and gages. The HRMP shall have controls that are conveniently operable by the driver. All panels shall be enclosed in a weatherproof box or compartment. All operating and servicing controls shall be easily operable by personnel wearing heavy arctic gloves and outer clothing; mission oriented protective posture (MOPP) IV gear.

2.20.1 Instruments and gages. All instruments and gages mounted on the control panel shall have the following features:

a. Uniform in appearance.

b. Shock-mounted for instruments subject to error due to vibration.

c. A removable weather-resistant metal cover to provide maximum protection to gages, wiring, electrical connections, and terminals enclosed on the back of the control panel.

d. Lighted instruments and gages.

e. Identified as to their function.

f. Installed in a manner to facilitate removal and servicing.

2.20.2 Ground Controls. In addition to the work platform controls (see 2.20.3), hand operated controls for the boom articulation, platform, and the turntable shall be provided at a ground level control station. The ground controls shall be positioned in a location that provides a clear, unobstructed view of all ranges of motion of the boom and platform during operation. These

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

ground level controls shall override the work platform boom controls in the event of a disabling accident or injury to the operator(s) on the platform. The controls shall be in accordance with 4.3 of SAIA A92.2.

2.20.3 Platform controls. Hand-operated controls for the boom, platform articulation, and the turntable shall be provided on the platform structure. The controls shall be so positioned that the operator can actuate the handles by pushing or pulling them in a horizontal direction. The controls shall be mounted to give operator maximum visibility of the working side of the platform in the direction facing the aircraft. The controls shall be in accordance with 4.3 of SAIA A92.2.

2.21 Outriggers. Four outriggers shall be supplied and ensure adequate stability of the truck when a 1,500 pound load is applied to the work platform. In all extended positions, the outriggers shall be designed in accordance with 4.5 of SAIA A92.2.

2.22 Aerial tower (boom). The aerial tower (boom) shall be designed and manufactured in accordance with SAIA A92.2, and designed for a minimum working load of 1,500 pounds on the platform while in any extended position with the stabilizers extended on even, uneven, and inclined surfaces.

2.22.1 Aerial tower structural components. Aerial tower structural components shall be in accordance with 4.2 of SAIA A92.2. Extension and retraction with the boom in any position shall be smooth without lurching and shall not exceed a maximum deflection of 9 inches at a working load of 1,500 pounds. In the stowed position, the boom shall extend no greater than 4 feet beyond the vertical plane of the truck's front bumper.

2.22.2 Range of platform movement. The aerial assembly shall be capable of a minimum 180° horizontal rotation in either direction from neutral (stowed) position. The boom(s) shall raise the work platform to the height required to position personnel and equipment necessary to perform servicing, maintenance, component replacement, et cetera, on all exterior surfaces of the C-5 aircraft horizontal stabilizer 70 feet above ground level. Each half of the horizontal stabilizer is of a trapezoidal configuration which is 34 feet from tip to root, 8 feet wide at the tip and 21 feet wide at the root. Egress and ingress onto the aircraft from the work platform shall be direct and unobstructed. Handholds and steps shall be provided, if necessary, to enable personnel wearing heavy winter clothing easy and safe entry and exit of the work platform. The aerial assembly shall provide a minimum horizontal reach (radius) of not less than 58 feet, and allow platform to be positioned to within 12 inches (measured to the platform floor) of all upper surfaces of the horizontal stabilizer.

2.22.3 Boom and turntable operation. Boom rotation shall be achieved by a turntable, mounted on a chassis, which swings through a minimum 180° arc in either direction. The turntable assembly shall be rotated by a hydraulically operated motor. The turntable shall be so constructed as to eliminate all side thrust on the motor shaft. The motor shall rotate the loaded platform 360° in not less than 4 minutes and no more than 6 minutes.

2.22.4 Proof-load. The proof-load shall be two times the working load. With the outriggers fully extended, the boom extended in any position, and the platform subject to the proof-load, the vehicle shall not exhibit signs of instability. The load shall not cause permanent deformation of the platform, boom, outriggers, or any other components of the vehicle.

2.22.5 Outrigger and aerial boom interlock system. A combination electrical and mechanical interlock system shall be provided to ensure the boom is properly and safely stowed. Failure to

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

lower the boom and satisfactorily engage the interlock system shall prevent the outriggers from being retracted and shall prevent the vehicle from being put into gear.

2.22.6 Aerial device re-activation indicators. If the operator maneuvers the aerial device into an unallowable position causing the system to lock up, indicators on both the platform control panel and the ground control panel shall clearly show the source of the problem. The platform control panel and ground control panel shall digitally display the angle of the boom in degrees, rounded to the nearest whole number.

2.23 Work platform. The outside dimensions of the working area shall be a minimum of 36 by 96 inches. The platform shall be designed for a normal working load of 1,500 pounds. The platform shall incorporate a means of a minimum 90° articulation, a minimum of 45° right and left of its neutral position to assure interfacing with vertical aircraft surfaces. Replaceable rubber bumpers shall be provided to prevent damage to aircraft surfaces.

2.23.1 Proximity sensors. The platform shall have proximity sensors on each side of the platform to immediately stop the motion of the platform upon contact with all surfaces, to include the aircraft, other structures, or the ground. The maximum force required to actuate the sensor shall be 10 pounds. The sensors shall be activated on all four sides of the platform. All parts shall be secured and covered to prevent the components from damage.

2.23.2 Safety belts. Three positive-type safety belts with quick release features and a rated strength of 500 pounds each shall be provided. The belts shall be designed to allow freedom of movement of the operators in the platform. The safety belt mounting locations should not limit operator's access to horizontal stabilizers.

2.23.3 Guardrails. Two rigid guardrails shall be provided around the perimeter of the work platform. The top rail shall be 42 inches high, plus or minus 3 inches above the platform surface, designed to withstand 300 pounds of force in any direction. The lower guardrail shall be midway between the kick plate and upper guardrail. The lower guardrail of the work platform shall be hinged to provide access from gateways to the platform and horizontal stabilizer. The guardrails shall be in accordance with 4.9.1 of SAIA A92.2.

2.23.3.1 Kick plate. The platform shall include kick plates in accordance with 4.9.1 of SAIA 92.2.

2.23.4 Pneumatic system. A pneumatic system including an air supply line shall be installed from the truck to the platform to deliver air to power standard, commercial grade pneumatic hand tools. Two standard female style quick disconnects with automatic shut-off shall be provided on the work platform and one on the truck. All parts, fittings and components for mounting and safe operation shall be provided. The air supply lines shall be routed with minimum bends and located or guarded from damage during platform use.

2.24 Flooring.

2.24.1 Platform flooring. The work space shall have reinforced, expanded-metal flooring with a clear working area of at least minimum 32 inches from front to back and at least minimum 92 inches from side to side. The upper surface shall provide safe footing to personnel wearing MOPP IV gear; especially heavy arctic boots. No point on the flooring shall deflect more than ¼ inch when subjected to a concentrated vertical load of 300 pounds covering an area of 25 square inches.

2.24.2 Equipment flooring. Equipment flooring shall be of steel tread-plate. All steps and platforms shall have a nonskid self-draining surface.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

2.25 Communication system. A communication system, equipped with voice-activated headsets at both the platform and at the lower controls, shall be provided. With all systems operating simultaneously, the operator positioned in the extended work platform (120 feet) and wearing a voice-activated headset shall be able to clearly communicate with the operator on the ground level (vice-versa).

2.26 Materials handling system. A hydraulically extendable, hydraulically articulated jib-crane and a hydraulically powered winch system shall be furnished at the work platform to provide a means of removing and installing aircraft parts. The system shall be capable of lifting a 1,000 lb load in any position of the jib or the work platform. This system shall be installed in a manner that automatically keeps it level with the work platform at all positions of the boom, and so that it rotates as an integral part of the work platform when the platform is rotated from side to side. It shall also be possible to rotate the un-laden jib on its base independently from the work platform and when not in use, to store it out of the way of operators in the platform. Removal of the jib is not an acceptable form of storage.

2.27 Electrical receptacles. One 120-volt AC, 20-ampere electrical outlet shall be provided on the platform to allow the safe operation of standard commercial hand tools. The electrical circuit shall contain a circuit breaker. It shall have a weatherproof covering with spring hinged doors and shall provide two female receptacles. The power source for the circuit shall have a rating equal to or greater than the maximum continuous current required during operations of all alternating current components.

2.28 Delivery system. All components of the delivery system shall withstand the working pressure specified herein and a hydrostatic pressure of at least twice the specified working pressure without leakage or failure. The system shall deliver a pre-mixed 60/40 (60 percent water/40 percent deicer fluid concentrate specified in 2.3.3) de-icing fluid mixture or Type IV anti-icing fluid in sufficient quantity to meet ambient weather conditions that ensure aircraft air worthiness. A method of selecting either Type I de-icing or Type IV anti-icing fluids shall be provided at the platform. The delivery system shall be designed to accommodate a de-icing truck system pressure up to 260 psig; with a minimum of 15 gallons per minute (gpm) at a working output pressure of 200 psig.

2.28.1 Spray nozzle. A spray nozzle shall be provided. The connection between the delivery hose and spray gun shall allow the gun to swivel on the hose. A means of storing and protecting the nozzle when not in use shall be provided. The nozzle shall be operable by personnel wearing heavy arctic gloves. Delivery of the fluids shall be positively controlled by a lever type valve on the body of the nozzle. The nozzle shall deliver water and fluid at the appropriate gpm flow rate on the spray gun: 20, 50, 70, and 80 gpm are to be measured at the nozzle.

2.28.2 Cleaning compound spray apparatus (wand). A spray gun assembly shall be provided on the compound hose to deliver the cleaning compound fluids at the rate of at least 15 gpm at a working pressure of 200 psi ±10.

2.28.3 Storage box, delivery system components. A box shall be provided to store delivery system components of 2.28.1 and 2.28.2 when not in use. The storage box shall be deck-mounted, low-profile, and weatherproof with a capability to withstand a load of 300 pounds without permanent deformation. In addition, a means of securing contents (e.g., hasp and padlock) of the storage box shall also be provided.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

2.29 Foreign object damage. All loose metal parts, such as pins, shall be securely attached to the vehicle with wire ropes or chains. "Dog tag" style beaded chains shall not be provided. Removable panels, if provided, shall be attached with captive fasteners. Tire valve stem caps shall be made of plastic.

2.30 Workmanship. The HRMP, including all parts and accessories, shall be fabricated in a thoroughly workmanlike manner. Particular attention shall be given to freedom from blemishes, burrs, defects, and sharp edges; accuracy of dimensions, radii of fillets, and marking of parts and assemblies; thoroughness of welding, brazing, soldering, riveting, and painting; alignment of parts; and tightness of fasteners. The HRMP shall be thoroughly cleaned of all foreign matter.

2.31 Welders and welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface parts to be welded shall be free from rust, scale, paint, grease, and other foreign matter and show no splatter. Welds shall be of sufficient size and shape to develop the full strength of the welded parts. Welds shall transmit stress without cracking or permanent distortion when the parts connected by the welds are subjected to test, proof, and service loadings.

2.32 Service bulletins. The contractor shall prepare service bulletins as required, to be issued by Air Force Registration Number, to notify the government of new maintenance problems and/or procedures to be implemented on the contractor’s equipment prior to issuance of permanent changes to the technical manuals. The service bulletins shall also identify any potential safety hazards. Contractor format is acceptable.

2.33 Warranty. The furnished vehicle shall include a 3 year, 150,000 mile engine warranty, a 2 year, 100,000 mile chassis warranty, and a 1 year, unlimited mileage body and specialized equipment warranty.

2.34 Commissioning. A minimum of one day of familiarization training shall be provided at the receiving base following delivery of the vehicle. Commissioning shall consist of driver/operator training and informational overview training for maintenance personnel.

3. REGULATORY REQUIREMENTS

3.1 Recycled, recovered, or environmentally preferable materials. Recycled, recovered, or environmentally preferable materials should be used to the maximum extent possible provided that the material meets or exceeds the operational and maintenance requirements, and promotes economically advantageous life cycle costs. The offer or/contractor is encouraged to use recovered materials to the maximum extent practicable, in accordance with 23.403 of the Federal Acquisition Regulation (FAR). However, used, rebuilt, or refurbished items shall not be provided.

3.2 Green Procurement Program. Green Procurement Program (GPP) is a mandatory federal acquisition program that focuses on the purchase and use of environmentally preferable products and services. GPP requirements apply to all acquisitions using appropriated funds, including services and new requirements. FAR 23.404(b) applies and states the GPP requires 100% of EPA designated product purchase that are included in the Comprehensive Procurement Guidelines list that contains recovered materials, unless the item cannot be acquired: a) competitively within a reasonable timeframe; b) meet appropriate performance standards, or c) at a reasonable price. The prime contractor is responsible for ensuring that all subcontractors comply with this requirement.

4. PRODUCT CONFORMANCE PROVISIONS

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

4.1 Classification of inspections. The inspection requirements specified are classified in 4.1.1 and 4.1.2 below.

4.1.1 First production inspection. The contractor shall provide or arrange for all test equipment and facilities per 4.4.

4.1.2 Conformance inspection. Each production vehicle shall be subjected to the examinations and tests described in 4.4.3.

4.2 Product conformance. The products provided shall meet the salient characteristics of this CID, conform to the producer's own drawings, specifications, standards, and quality assurance practices, and be the same product offered for sale in the commercial marketplace. The government reserves the right to require proof of such conformance. Except as otherwise specified, all testing in which the engine is operated shall be performed using JP-8 of F-24 turbine fuel.

4.3 Commercial item requirement. The vehicle furnished shall comply with the "commercial item" definition of Federal Acquisition Regulation (FAR) 2.101 as of the date of award.

4.4 Inspection requirements.

4.4.1 General inspection requirements. Apparatus used in conjunction with the inspections specified herein shall be laboratory precision type, calibrated at proper intervals to ensure laboratory accuracy.

4.4.2 Test rejection criteria. Throughout all tests specified herein, the vehicle shall be closely observed for the following conditions, which shall be cause for rejection:

a. Failure to conform to design or performance requirements specified herein or in the contractor's technical proposal.

b. Any spillage or leakage of any liquid, including fuel, coolant, lubricant, or hydraulic fluid, under any condition, except as allowed herein.

c. Structural failure of any component, including permanent deformation, or evidence of impending failure.

d. Evidence of excessive wear.

e. Interference between the vehicle components or between the vehicle, the ground, and all required obstacles, with the exception of normal contact by the tires.

f. Misalignment of components.

g. Evidence of undesirable road ability characteristics, including instability in handling during cornering, braking, and while traversing all required terrain.

h. Conditions that present a safety hazard to personnel during operation, servicing, or maintenance.

i. Overheating of the engine, transmission, or any other vehicle component.

j. Evidence of corrosion.

4.4.3 Detailed inspection requirements. Each HRMP shall be examined to verify compliance with the requirements herein. A government approved checklist that identifies each relevant requirement and the inspection results shall be used. Particular attention shall be given to materials, workmanship, dimensions, surface finishes, protective coatings and sealants and their application,

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

welding, fastening, and markings. Proper operation of each HRMP function shall be verified. Each production HRMP shall be inspected to a reduced version of the checklist. The government reserves the right to require the contractor to prove that their product complies with the referenced commerciality requirements and each salient characteristic of this CID.

TABLE II. Required certifications and analyses.

Paragraph Reference	Required Certifications and Analyses
2.4.1 Air transportability, 2.4.1.2 Air transportable configuration, 2.4.1.3 Equipment removal/reconfiguration.	Contractor air transportability analysis (see 4.4.3.1, 4.4.3.2).
2.4.2 Tie-down points.	Contractor air transportability analysis (see 4.4.3.2).
2.4.4 Component lifting provisions.	Contractor air transportability analysis (see 4.4.3.3).
2.8 Environmental conditions.	Contractor certification of the component environmental conditions are in accordance with requirements and capabilities specified herein.
2.14.1 Engine.	Engine manufacturer certification that the engine is in accordance with all applicable requirements, including exhaust emissions standards and fuels. Engine manufacturer application approval for the engine and its installation, including cooling system, lubrication system, and mounting system.
2.20.2 Power plant heater kit.	Contractor certification of the component power plant heater kit are in accordance with requirements and capabilities specified herein.
2.28 Materials handling system.	Contractor certification of the materials handling system are in accordance with requirements and capabilities specified herein.

4.4.3.1 Air transportability analysis. An engineering analysis shall be performed to demonstrate compliance with the air transportability requirements of 2.4. The analysis shall include the tie-downs (see 2.4.2) and all major components and their ability to withstand the accelerations specified in 2.4.1. The evaluation shall also include a dimensional analysis for the HRMP while traversing the ramp and while loaded aboard C-5 and C-17 aircraft. The analysis shall be completed and provided to the government representative 60 days prior to delivery to coordinate air transportability certification with Air Transportability Test Loading Activity (ATTLA).

4.4.3.1.1 Equipment removal/reconfiguration demonstration. A first production HRMP shall be configured for transport on C-5 and C-17 aircraft and then reconfigured for operation to demonstrate compliance with 2.4.1.3. It shall be demonstrated that the forces required do not exceed those allowed in MIL-STD-1472.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

4.4.3.2 Tie-down provision analysis. An engineering analysis shall be performed to demonstrate compliance with the tie-down provision requirements of 2.4.2.

4.4.3.3 Lifting provision analysis. An engineering analysis shall be performed to demonstrate compliance with the lifting provision requirements of 2.4.4.

4.4.3.4 Set up/operating position demonstration. The first production HRMP shall be tested to demonstrate compliance with 2.7.

4.4.3.5 Mobility tests.

4.4.3.5.1 Paved road. The fully loaded first production HRMP shall be driven for a continuous five miles on paved roads, at a maximum speed of 40 mph and an average speed of 30 mph, to demonstrate compliance with 2.9.1. The first production vehicle shall be driven for at least one mile at the maximum speed. Following testing, all loads shall be removed and all structures and surfaces shall be visibly inspected for failure or permanent deformation.

4.4.3.5.3 Cross-country terrain. The fully loaded first production HRMP shall be driven for two miles of cross-country terrain, at a maximum speed of 20 mph and an average speed of 10 mph, to demonstrate compliance with 2.9.2. The first production vehicle shall be driven for at least one mile at the maximum speed. Following testing, all loads shall be removed and all structures and surfaces shall be visibly inspected for failure or permanent deformation.

4.4.3.6 Dimension measurement. The overall length, width, height and weight of the first production HRMP shall be measured to demonstrate compliance with 2.10.

4.4.3.7 Sound level tests.

4.4.3.7.1 Cab interior sound level test. The cab interior sound levels of the first production HRMP shall be measured in accordance with 49 CFR 393.94(c) to demonstrate compliance with 2.11.1.

4.4.3.7.2 Vehicle exterior sound level test. The exterior sound level of the first production HRMP shall be measured in accordance with 49 CFR 325 to demonstrate compliance with 2.11.2.

4.4.3.8 Field of vision measurement. The field of vision of the first production HRMP shall be measured to demonstrate compliance with 2.12.

4.4.3.9 Continuous operation test. The aerial device of the first production HRMP, loaded with a 1,500-pound in the work platform, shall be operated continuously for at least 4 hours, with no external cooling, to demonstrate compliance with 2.15.5.

4.4.3.10 Drift control test. The aerial device of the first production HRMP, with a 1,500-pound load in the work platform, shall be tested to demonstrate compliance with 2.15.6.

4.4.3.11 Platform emergency lowering system demonstration. The platform emergency lowering system of the first production HRMP shall be operated to demonstrate compliance with 2.15.6.1.

4.4.3.12 Stability test. The first production HRMP shall be tested in accordance with 4.5 of SAIA A92.2 to demonstrate compliance with 2.21.

4.4.3.13 Range of platform movement test. The first production HRMP shall be tested to demonstrate compliance with 2.22.2.

4.4.3.14 Boom and turntable operation test. The first production HRMP shall be tested to demonstrate compliance with 2.22.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

4.4.3.15 Proof load test. Each HRMP shall be subjected to a proof load of at least 2 times the working load (minimum of 3,000-pounds), which shall be placed on the platform when the boom assembly is in any extended position and with the outriggers extended on even, uneven, and inclined surfaces. There shall be no indication of permanent distortion or of instability of the unit. Test shall demonstrate compliance with 2.22.4.

4.4.3.16 Interlock system demonstration. The outriggers and aerial boom of the first production HRMP shall be operated to demonstrate that the interlock system complies with 2.22.5.

4.4.3.17 Proximity sensor test. The proximity sensor of the first production HRMP shall be tested to demonstrate compliance with 2.23.1.

4.4.3.18 Communication system demonstration. The communication system of the first production HRMP shall be operated to demonstrate compliance with 2.25.

4.4.3.19 Delivery and spray system test. The delivery and spraying system of the first production HRMP shall be tested to demonstrate compliance with 2.28, 2.28.1, and 2.28.2.

5. PACKAGING

5.1 Packaging. For acquisition purposes, the packaging requirements shall be as specified in the contract or order. When actual packaging of materiel is to be performed by Department of Defense (DOD) personnel, those personnel need to contact the responsible packaging activity to ascertain requisite packaging requirements. Packaging requirements are maintained by the Inventory Control Point's packaging activity within the Military Department or Defense Agency, or within the Military Department's System Command. Packaging data retrieval is available from the managing Military Department's or Defense Agency's automated packaging files, CD-ROM products, or by contacting the responsible packaging activity.

6. NOTES

6.1 Source of documents.

6.1.1 Military documents. Specifications, Standards and Handbooks referenced herein may be obtained from: https://quicksearch.dla.mil or available from the DLA Document Services, 700 Robbins Ave, Bldg. 4, Section D, Philadelphia, PA 19111-5094.

6.1.2 The Code of Federal Regulations (CFR). CFRs may be obtained at: https://www.govinfo.gov/app/collection/cfr or from the Superintendent of Documents, U.S. Government Printing Office, Washington DC 20402.

6.1.3 SAE documents. Copies of SAE documents may be obtained from: http://www.sae.org/servlets/index or from SAE, Inc., 400 Commonwealth Drive, Warrendale PA 15096.

6.1.4 SAIA (Scaffold & Access Industry Association standards). Copies may be obtained at: https://www.saiaonline.org or available from Scaffold & Access Industry Association, Inc., 400 Admiral Blvd, Kansas City, MO 64106.

6.1.5 FARs. Copies of FARs may be obtained from: the Superintendent of Documents, P.O. Box 371954, Pittsburgh, PA 15250-7954. Electronic copies of the FAR may be obtained from: https://www.ecfr.gov/.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.

6.1.6 American National Standards Institute (ANSI). Copies of ANSI standards may be obtained from: 1899 L Street, NW, 11th Floor, Washington, DC, 20036. Electronic copies may be obtained from: https://webstore.ansi.org/.

6.1.7 EPA standards. Copies may be obtained from: 633 3rd Street NW, Washington, DC, 20001. Electronic copies may be obtained from: http://www.epa.gov/.

6.2 Intended use. The HRMP is intended for use as a maneuverable work platform for maintaining, inspecting, servicing, and spraying large aircraft such as the C-5, C-17, C-130, and C-141. Furthermore, the operator will use the platform to egress and ingress the aircraft during maintenance. It may also be used for maintenance of hangar facilities.

6.3 Ordering data. The contract or order should specify the following: title, number, and date of this CID: A-A-59111.

6.4 Key Words.

Articulating Aerial Tower.

Egress/Ingress.

Heavy Duty Chassis.

HRMP.

Work Vehicle.

6.5 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extent of the changes.

Concluding material:

Custodians:
Air Force – 184

Preparing Activity:
Air Force – 184

Reviewer:
DLA – GS

Agent:
Air Force – 110

(Project 2320-2020-001)

NOTE: The activities listed above were interested in this document as of the date of this document. Since organizations and responsibilities can change, you should verify the currency of the information above using the ASSIST Online database at https://assist.dla.mil/.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:01Z
Check the source to verify that this is the current version before use.