MIL-L-10469B(Ord)
26 May 1960
SUPERSEDING
MIL-L-10469A(Ord)
24 June 1959

# MILITARY SPECIFICATION

## LIGHTS, AIMING POST

### 1. SCOPE

1.1 This specification covers the general requirements for aiming post lights commonly used in fire control equipment. Where applicable, aiming post lights may be composed of one or more indicator lamps and one or more snap switches.

### 2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids, form a part of this specification to the extent specified herein.

SPECIFICATIONS

Military

| | |
|---|---|
| MIL-L-11445 | Lights, Aiming Post and Instrument; Packaging of |
| MIL-F-13926 | Fire Control Materiel: General Specification Governing the Manufacture and Inspection of |

STANDARDS

Military

| | |
|---|---|
| MIL-STD-105 | Sampling Procedures and Tables for Inspection by Attributes |
| MIL-STD-130 | Identification Marking of U. S. Military Property |

FSC 1290

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:05Z
Check the source to verify that this is the current version before use.

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

## 3. REQUIREMENTS

3.1 Production model.- At the beginning of production, one light, representative of production, shall be made available to the Government to determine if the light meets all the requirements of this specification.

3.2 Materials.- The materials shall be in accordance with the drawings, material specifications, and general specifications forming a part of this specification.

3.3 Construction.- The light shall be manufactured in accordance with the applicable drawing pertaining thereto. The requirements of this specification are detailed only to the extent considered necessary to insure the inherent quality and the performance capabilities of the product prior to final acceptance by the Government.

3.4 General specifications.- The contractor shall be responsible for adherence to and compliance with the following requirements of Specification MIL-F-13926:

(a) Order of precedence
(b) Protective finished surfaces
(c) Special accuracy
(d) Finish, painting and protective
(e) Workmanship

3.5 Environmental.

3.5.1 Operating temperatures.- The light shall meet all the performance requirements of this specification while exposed to, and thermally stabilized at, ambient temperatures of plus 150 and minus 65 degrees Fahrenheit.

3.6 Methyl methacrylate parts.- In lights containing methyl methacrylate rods, the surface of the rods, unless otherwise specified, shall be highly polished. The rods shall be clear, transparent and without noticeable color. When sandblasting of sections is specified, care shall be taken to protect polished surfaces.

3.7 Electrical.

3.7.1 Continuity.- The light shall demonstrate continuity in accordance with the applicable electrical schematics pertaining thereto.



Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:05Z
Check the source to verify that this is the current version before use.

3.8 Performance.

3.8.1 Flicker.- There shall be no visible flicker when the indicator lamp is slightly jarred.

3.8.2 Switch.- The snap switch shall have positive off and on action.

3.8.3 Rheostat.- When rehostats are utilized the wiper arm of the rheostat shall maintain positive contact with the windings of the rheostat for any setting of the rheostat control.

3.9 Identification marking.- Unless otherwise specified, identification marking shall be in accordance with Standard MIL-STD-130.

4. QUALITY ASSURANCE PROVISIONS

4.1 Contractor inspection.- Unless otherwise specified herein, the supplier is responsible for the performance of all inspection requirements prior to submission for Government inspection and acceptance. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. Inspection records of the examination and tests shall be kept complete and available to the Government as specified in the contract or order.

4.2 Contractor's quality assurance system.- The contractor shall provide and maintain an adequate quality assurance system acceptable to the Government covering the supplies under the contract. A current written description of the system shall be submitted to the contracting officer prior to initiation of production. The written description will be considered acceptable when it provides:

(a) The quality assurance required by the applicable drawings and specifications listed in the contract or order.
(b) Contractor's quality standards of acceptability.
(c) Procedure for continually evaluating product quality.
(d) Procedure for continually reporting evidence of actual product quality.
(e) Measures for preventing any significant departure of product quality from standards.



Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:05Z
Check the source to verify that this is the current version before use.

4.2.1 The contractor will not be restricted to the inspection station or to the method of inspection listed provided that an equivalent control is included in the approved quality assurance procedure. In cases of dispute as to whether or not certain procedures of the system provide equal assurance, the comparable procedure required by this specification shall be used. The contractor shall notify the Government of and obtain approval for any change to the written procedure that might affect the degree of assurance required by this specification and other applicable documents referenced herein.

4.3 Government verification.- All quality assurance operations performed by the contractor will be subject to Government verification at unscheduled intervals. Verification will consist of (a) surveillance of the operations to determine that the practices, methods, and procedures of the written inspection plan are being properly applied, and (b) Government product inspection to measure quality of product offered for acceptance. Deviation from the prescribed or agreed-upon procedures, or instances of poor practices which might have a detrimental affect upon the quality of the product, will be immediately called to the attention of the contractor. Failure of the contractor to promptly correct deficiencies discovered will be cause for suspension of acceptance until correction has been made or until conformance of product to prescribed criteria has been demonstrated. To avoid interference with operations, the contractor will designate a responsible official or officials to whom the Government inspector will report such instances.

4.4 Production model.- Unless otherwise specified in the contract, one light shall be selected by the Government inspector as soon as practicable after the start of production, and be inspected by the contractor under the surveillance of the Government. This inspection shall be conducted at the contractor's facility, or Government approved laboratory, using test equipment authorized for use on the contract. The sample shall be inspected for all requirements of this specification by utilizing examination and testing methods prescribed herein.

4.4.1 Production model failure.- Should the production model fail to pass the prescribed examination and tests, the contractor shall cease those operations which are causing the rejection and shall make the necessary corrections. When corrections in the process have been made, a new production model shall be examined and tested by the contractor under the surveillance of the Government. Acceptance of production lots will not commence until an acceptable production model is submitted and corrective actions have been taken to eliminate deficiencies.



Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:05Z
Check the source to verify that this is the current version before use.

4.5 Inspection provisions.

4.5.1 Inspection of components.- Minimum inspection requirements for components shall be as specified on SQAP's when SQAP's are specified in the contract and shall be the basis for acceptance or rejection by lot. This does not preclude 100 percent inspection and the Government reserves the right to inspect for applicable requirements and to reject individual non-conforming items.

4.5.1.1 When SQAP's are not specified in the contract, component inspection shall be in accordance with written plan of 4.2 and 4.2.1. The plan shall include written instruction for inspection of all positional and functional characterisitics shown on component drawing. Also included in this category are all performance requirements specified in notes directly on the drawings or in separate performance specifications referenced therein that have a bearing on the functional accuracy, interchangeability, and performance of the light.

4.5.1.1.1 Sampling of components covered by 4.5.1.1 may be used in lieu of 100 percent inspection and shall be in accordance with Standard MIL-STD-105. For normal inspection use AQL value 1.5 percent defective in conjunction with Inspection Level II, Sampling Plan Table IV-A of Standard MIL-STD-105. Reduced inspection shall be as outlined in Standard MIL-STD-105.

4.5.2 Government inspection of components will consist of (1) surveillance of contractor's inspection operations to determine whether the inspection methods and procedures of the written description, which should include application of the SQAP, are being properly applied (2) surveillance or verification by Government inspectors of test of assembled end item for requirements of applicable drawing and performance specifications.

4.6 Control of materials.- Materials shall be tested to determine conformance to contractually applicable specifications. Such tests may be conducted in the prime contractor's or subcontractor's facilities, or in other suitably equipped laboratories. The test results shall be available to the Government inspector for review. Certified test reports, identifiable with the material, may be accepted in lieu of repeated tests. The Government reserves the right, in any case, to require retests to assure that the materials are acceptable.

4.7 Lot formation.- Unless otherwise specified by the contracting officer, or his representative, inspection lot sizes and lot formation shall be in accordance with Standard MIL-STD-105.



Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:05Z
Check the source to verify that this is the current version before use.

4.8 Acceptance tests.- The classification of defects in Tables I and II shall constitute the minimum inspection requirements to be performed by the contractor prior to acceptance or rejection by lot. The Government reserves the right to inspect for any applicable requirement, and to reject individual non-conforming items.

4.8.1 Rejected lots shall be screened for all defective characteristics. After corrections have been made and the Government inspector informed of the corrective action taken, the lot shall be resubmitted for acceptance as outlined in Standard MIL-STD-105.

TABLE I - CLASSIFICATION OF DEFECTS

Use Inspection Level II, and Sampling Plan Table IV-A of Standard MIL-STD-105

| MAJOR: AQL 1.5% | Req't Par. | Q.A. Par. | Test Method |
|---|---|---|---|
| 1. Completeness of assy | as per dwgs | | Visual |
| 2. Continuity | 3.7.1 | 4.10.2.1 | Standard Measuring Equip. (SME) |
| 3. Flicker | 3.8.1 | 4.10.2.2 | SME |
| 4. Switch (when applicable) | 3.8.2 | 4.10.2.3 | Visual |
| 5. Rheostat (when applicable) | 3.8.3 | 4.10.2.4 | SME |
| 6. Workmanship | 3.4 | | Visual |
| 7. Improper markings | 3.9 | 4.11 | Visual |

TABLE II - CLASSIFICATION OF DEFECTS

Use Inspection Level I, and Sampling Plan Table V of Standard MIL-STD-105

| MAJOR: AQL 1.5% | Req't Par. | Q.A. Par. | Test Method |
|---|---|---|---|
| 1. Operating temperatures | 3.5.1 | 4.10.1.1 | SME |

4.9 Inspection equipment.



Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:05Z
Check the source to verify that this is the current version before use.

4.9.1 Contractor provisions.- Unless otherwise specified in the contract, the contractor shall provide and properly utilize all gaging, measuring, and testing equipment of the required accuracy for the performance of all inspections, examinations and tests required to be performed by the contractor under this contract. The contractor shall be responsible for the maintenance of the equipment, including surveillance, calibration, and rehabilitation, on a regularly scheduled basis, and shall have available, all calibration equipment and other instrumentation essential for calibration and certification of the inspection equipment. The contractor also shall maintain records of inspection equipment surveillance and calibration, and shall make these records available for review by the Government. The Government reserves the right to certify inspection equipment, and to use it for Government verification inspection or acceptance inspection.

4.10 Test methods and procedures.

4.10.1 Environmental.

4.10.1.1 Operating temperatures.- Unless otherwise specified, the test equipment to be used when performing the temperature tests shall be such that the equipment under test shall not exceed fifty percent of the internal volume of the test chamber, and no portion shall be closer than six inches from any surface of the chamber.

4.10.1.1.1 The lights to be tested shall be placed in the test chamber in their normal operating position. The test shall be conducted in accordance with Procedure I of Specification MIL-F-13926 to the conditions specified in 3.5.1. Upon completion of the specified exposures, the units under test shall be inspected in accordance with the following methods and procedures to determine conformance with the requirements specified herein.

4.10.2 Electrical.

4.10.2.1 Continuity.- A continuity check of the lights shall be made, using standard measuring devices to determine conformance with the requirements specified in 3.7.1.

4.10.2.2 Flicker.- The light shall be securely held in any position and the indicator lamp shall be lighted from a suitable power source. The instrument light shall then be jarred by striking. The lamp shall be visually checked for conformance to the requirements specified in 3.8.1.

4.10.2.3 Switch.- The snap switch for the light shall be visually and operationally checked for conformance to the requirements specified in 3.8.2.



Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:05Z
Check the source to verify that this is the current version before use.

4.10.2.4 Rheostat.- The rheostat control shall be slowly rotated from one extreme position to the other while observing the illumination which shall be constant but with uniform change in brightness as the knob is rotated.

4.11 Identification markings.- The lights shall be visually inspected to determine that all markings are in accordance with those appearing on the end item assembly drawing. All such markings shall be applied in accordance with Standard MIL-STD-130.

5. PREPARATION FOR DELIVERY

5.1 Packaging, packing, and marking.- The aiming post lights shall be packaged, packed, and marked in accordance with Specification MIL-L-11445.

6. NOTES

6.1 Intended use.- Aiming post lights are intended to be used for sighting points in night operation.

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Selection of applicable levels of preservation, packaging, and packing.
(c) Applicable stock number.
(d) Provisions for production model including date of delivery (see 3.1)

6.3 Design information.- Design information regarding specific equipment not covered or referenced by this specification may be obtained from the procuring activity upon the specific request of the contractor.

6.4 Definitions.

6.4.1 Standard measuring equipment (SME).- Standard measuring equipment includes the common hand type measuring devices which are usually stocked by commercial supply houses for ready supply (shelf items), and which are normally used by an inspector to perform dimensional inspection of items under procurement. This category also includes commercial testing equipment.



Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:05Z
Check the source to verify that this is the current version before use.

NOTICE: When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any invention that may in any way be related thereto.

Custodian:

Army-Ordnance Corps

Preparing Activity:

Army-Ordnance Corps



Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:05Z
Check the source to verify that this is the current version before use.