MIL-C-48868D(AR)
AMENDMENT 3
21 December 1987
SUPERSEDING
AMENDMENT 2
10 October 1983

MILITARY SPECIFICATION

CHARGE, PROPELLING, M204 PARTS
AND CONTAINER ASSEMBLY

This Amendment forms a part of Military Specification MIL-C-48868D(AR), dated 7 May 1982, and is approved for use within the U.S. Army Armament, Munitions and Chemical Command, and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 2

2.1.1, under Standards: Delete "MIL-STD-1235 - Single and Multi-Level Continuous Sampling Procedures and Tables for Inspection by Attributes."

2.1.2, under Drawings: Delete "9277371" and substitute "9381562."

PAGE 3

3.4: Delete in its entirety.

3.5: Delete in its entirety.

PAGE 4

* 3.10: Delete in its entirety.

3.14.1: Delete in its entirety add new paragraph as follows:

"3.14.1 Container parts and assemblies. The container parts and assemblies shall be free of dirt, grease, cracks, splits, cuts, tears, rips, holes, soft spots, seam separations or foreign materials."

AMSC N/A FSC 1310

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

Add new paragraph as follows:

"3.15 Fin-boom simulation test. The container assemblies shall satisfactorily pass the fin-boom simulation test as specified in 4.5.10."

PAGE 5

4.3.1, under Quantity Column:

* Delete "128" and substitute "350."

Delete "110" and substitute "10."

4.3.1, under Drawing Column: Delete "9312707" and substitute "9312786."

PAGE 6

TABLE I: Delete "Immersion test and Back pressure test."

TABLE I, Closure: Delete "9312707" and substitute "9312786."

* TABLE I, Container Assembly: Delete "Sequential rough handling test."

* TABLE I, Container Assembly, add the following:

	No. Samples	Req. Para.	Para. Ref.
"Fin-boom simulation test	100*	3.15	4.5.10"

PAGE 7

* 4.4.1 a(1): Delete in its entirety and substitute the following:

"(1) Nitrocellulose from not more than two lots of one lot interfix number from one manufacturer."

PAGE 8

4.4.2.1.1, line 3: Delete "After initial qualification, the procedure shall be accomplished after any set-up change and at intervals of at least once per week per die."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

4.4.2.1.2b: Delete in its entirety.

PAGE 9

4.4.2.2, Special A: Delete reference to Note 1/ and add "100%" under AQL column.

4.4.2.2, Notes: Delete Note 1/ in its entirety.

PAGE 10

4.4.2.3, Special A: Delete reference to Note 1/.

4.4.2.3, Notes: Delete Note 1/ in its entirety.

PAGE 11

4.4.2.4, in drawing number block: Delete "9312707" and substitute "9312786."

PAGE 12

4.4.2.5: Delete Major 102.

4.4.2.5: Delete Major 103.

4.4.2.5, Major 108: Delete ",max."

* 4.4.2.5, add the following:

Major		No. Samples	AQL	Req. Para.	Para. Ref.
"113	Fin-boom simulation test		0.40%	3.15	4.5.10
114	Incomplete bond between container top and bottom		0.40%	3.2	Visual"

4.4.2.5, Notes: Delete Note 1/ in its entirety.

4.4.2.5, Notes, Note 3/: Delete "Part II" and substitute "Part I."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

PAGE 15

4.4.3.1: Delete "9277371" and substitute "9381562."

4.4.3.1: Delete first sentence in its entirety.

4.4.3.2: Delete first sentence in its entirety.

PAGE 19

4.5.3: Delete in its entirety.

4.5.4: Delete in its entirety.

PAGE 21

* 4.5.7: Delete in its entirety.

PAGE 22

4.5.10 Fin-boom simulation test. Add new paragraph as follows:

"4.5.10 Fin-boom simulation test. The container assemblies shall be tested for flexiblity needed during field use. The container assemblies shall be visually examined for any homogeneity defects prior to the test. The defect-free container assemblies shall be positioned on and removed two times from a solid bar of the maximum allowable outside diameter of the fin boom. The "snap" on and off of the boom shall be performed with the container assembly oriented perpendicular to the bar. After removal, the container assemblies shall be visually inspected for cracks, tears, open seams, crushed ends, and fold/creases in the container wall. The Government shall establish visual standards prior to production with assistance of the contractor."

PAGE 23

6.4, last sentence: Delete "ARRADCOM" and substitute "ARDEC."

6.7: Delete "QAT-A" and substitute "QAT-B."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

6.9: Delete "QAT-A" and substitute "QAT-B."

6.9: Delete references to paragraphs 4.5.3.1 and 4.5.4 in their entirety.

NOTE: The margins of this amendment are marked with an asterisk or vertical line to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1310-A445)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.