INCH-POUND

MIL-T-83822
9 JULY 1991

MILITARY SPECIFICATION

TOWER AB-1368/F, 10 FOOT AND 17 FOOT SECTIONS FOR USE WITH OR WITHOUT A RIGID RADOME

This specification is approved for use within the Department of the Air Force and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the details of one type of tower, designated Tower AB-1368/F, and herein after referenced as the tower. The tower shall be composed of one 17 foot section, and from zero to six 10 foot sections, resulting in a tower height from 17 feet to 77 feet. The tower can be used with or without a rigid radome. The tower is designed for a high wind load of 150 knots.

2. APPLICABLE DOCUMENTS

2.1 Government Documents. The following government documents form a part of this specification to the extent specified. Unless otherwise specified, the issues of these documents shall be those listed in the the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: WR-ALC/LVRG, Robins AFB, GA 31098-5345 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A

FSC 5445

DISTRIBUTION STATEMENT A: Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

Federal

FF-B-575	Bolts, Hexagon and Square
RR-G-661	Grating, Metal Floor (Except for Naval Vessels)
FF-N-836	Nuts, Square, Hexagon, Cap, Slotted, Castle, Knurled, Welding and Single Ball Seat

Military

MIL-P-116	Preservation, Methods of
MIL-M-17194	Metal, Expanded, Steel

STANDARDS

Military

MIL-STD-129	Marking for Shipping and Storage
MIL-STD-130	Identification Marking of US Military Property
MIL-STD-143	Specifications and Standards, Order of Procurement for Selection of
MIL-STD-163	Steel Mill Products, Preparation for Shipment and Storage
MIL-STD-794	Parts and Equipment, Procedures for Packaging and Packing of
MIL-STD-882	Systems Safety Program for Systems, Associated Subsystems and Equipment; Requirements for
MIL-STD-889	Dissimilar Metals

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other Publications. The following documents form a part of this specification to the extent specified.

AMERICAN CONCRETE INSTITUTE

ACI 318 (Revised 1986) Building Code Requirements for Reinforced Concrete

(Application for copies should be addressed to the American Concrete Institute, P.O. Box 19150, Redford Station, Detroit MI 48219.)

AMERICAN INSTITUTE OF STEEL CONSTRUCTION

AISC Specification for the Design, Fabrication and Erection of Structural Steel for Buildings

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.

(Application for copies should be addressed to the American Institute of Steel Construction, 400 North Michigan Avenue, Chicago IL 60611.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS

A-36/A36M	Standard Specification for Structural Steel
A-53	Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless
A-123	Zinc, (Hot Dip) Coating on Products Fabricated from Rolled, Pressed, and Forged Steel Shapes, Plates, Bars, and Strips
A-153	Zinc Coating (Hot Dip) on Iron and Steel Hardware
A-325	Specification for High Strength Carbon Steel Bolts, Including Suitable Nuts, and Plain Hardened Washers
A-490	Specification for Quenched and Tempered Alloy Steel Bolts for Structural Steel Joints
B-633	Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia PA 19103.)

AMERICAN WELDING SOCIETY

Welding Code D1.1

(Applications for copies should be addressed to the American Welding Society Inc (AWS), 2501 NW 7th Street, Miami FL 33125.)

ELECTRONIC INDUSTRIES ASSOCIATION

EIA-222 Structural Standards for Steel Antenna Towers and Antenna Supporting Structures

(Applications for copies should be addressed to Electronic Industries Association, 2001 Eye Street, N.W., Washington D.C. 20006.)

UNIFORM CLASSIFICATION COMMITTEE (UCC)

Uniform Freight Classification Rules

(Applications for copies should be addressed to the Uniform Classification Committee, 202 Union Station, 516 W Jackson Blvd, Chicago IL 60606.)

DEPARTMENT OF LABOR OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION

Occupational Safety and Health Act (OSHA) Standard 1910-23(c)(1)

(Applications for copies should be addressed to the Superintendent of Documents, US Government Printing Office, Washington DC 20402.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.

NATIONAL MOTOR FREIGHT CLASSIFICATION RULES

(Applications for copies should be addressed to the American Trucking Association Inc (ATA), Traffic Department, 1616 P Street NW, Washington DC 20036.)

3. REQUIREMENTS

3.1 Tower Drawings. Design, fabrication and erection of Tower AB-1368/F is shown in Air Force Drawings 9029961 thru 9030027. A complete drawing list is furnished in section 6.2, Ordering Data.

3.2 Preproduction Assembly and Inspection. This specification makes provision for preproduction assembly and postassembly inspection.

3.3 General Description. The tower is composed of one 17-foot section, and from zero to six 10-foot sections, resulting in a tower height from 17 feet to 77 feet. The tower can be used with or without a rigid radome. The tower is designed for a high wind load of 150 knots. A radar mount is provided at the main floor level for the installation of a GPN or ASR radar antenna pedestal.

3.4 Materials, Parts, and Processes. Materials, parts, and processes shall be as specified herein. Materials and parts not covered by applicable specifications shall be of the best commercial quality, entirely suited for the purpose, and readily available.

3.4.1 Selection of Specifications and Standards. Specifications and standards for necessary commodities and services not specified herein shall be selected in accordance with MIL-STD-143.

3.5 Dissimilar Metals. Dissimilar metals, as defined by MIL-STD-889, shall not be used in intimate contact without suitable protection against electrolytic corrosion.

3.6 Materials of Construction.

3.6.1 Structural Steel. Steel for structural and framing members is in accordance with ASTM A-36 for structural shapes and A-53 (Grade B) for structural tubing. All structural steel shall be finished as specified in paragraph 3.10.1.

3.6.2 Fasteners. Bolts for joining main structural members are high strength bolts conforming to ASTM A-325 and A-490, and shall be furnished with suitable nuts, palnuts or lockwashers, and plain hardened washers. All other bolts are in accordance with FF-B-575 and nuts shall be in accordance with FF-N-836. All bolts, nuts, washers, and other hardware shall be finished as specified in paragraph 3.10.2.

3.6.3 Excess Fasteners. The contractor shall furnish a five percent excess of the required number of specified bolts, nuts, washers, palnuts and other fasteners required to field assemble each tower 10 FT section and each tower 17 FT section.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.

3.6.4 Grating.

3.6.4.1 Bar Type. Bar type grating is in accordance with RR-G-661.

3.6.4.2 Expanded Metal Type. Expanded metal type grating is in accordance with MIL-M-17194.

3.7 Stairways and Handrails.

3.7.1 Stairway. Steel stairway(s) are furnished with each tower section and equipped with toe boards, in accordance with OSHA Standard 1910- 23(c) (1). Safety handrails are also furnished with each tower section.

3.7.2 Handrails. Handrails have the provision to support the weight of a man lurching against it should this occur by accident. All handrail is designed to support the weight a 200 pound man with a safety factor of three. Additionally, all handrails meet OSHA Standards and are provided with middle rail and kick plate. All necessary hardware is provided to facilitate attachment of handrail to the structure in accordance with the drawings.

3.8 Welding. All welding shall be done in accordance with the American Welding Society Structural Welding Code D1.1, and all welders shall be certified in accordance with this code. There shall be no welding, riveting, or other special procedures required for field erection.

3.9. Service Conditions (Design) The tower is structurally designed and fabricated in accordance with the American Institute of Steel Construction Specification for the Design, Fabrication and Erection of Structural Steel for Buildings. The tower is also structurally designed to withstand any probable combination of the following service conditions without any mechanical or electrical damage, or any degradation in the performance specified.

STRUCTURAL DESIGN

a.	Wind and Ice	1. 150 knots with radome and operating radar antenna. 2. 100 knots plus 2 inches radial ice (density 56 lb/cu ft) with radome and operating radar antenna. 3. 150 knots without radome and operating radar antenna. 4. 100 knots plus 2 inches radial ice (density 56 lb/cu ft) without radome and operating antenna.
b.	Wind Direction Analysis	1. Horizontal & normal to face of tower. 2. 45 degrees upward to face of tower. 3. Horizontal & diagonal to tower. 4. 45 degrees upward & diagonal to tower
c.	Seismic Load	Zone 4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.

d.	Ambient Temperature	Minus 65F (-54C) to 160F (+70C).
e.	Relative Humidity	Up to 100 percent including condensation due to temperature changes
f.	Barometric Pressure	From 30 to 5.54 inches of mercury (from sea level to 40,000 feet).
g.	Salt Atmosphere	As encountered in coastal regions and during ocean transportation.
h.	Sand and Dust	As encountered in arid regions (particles as small as 0.0017 inch).
i.	Insects and Fungi	As encountered in the tropics.

3.9.1 Service Conditions (Mechanical). The tower is fabricated such that no fixed part will become loose, no moveable part or permanently set adjustment will be shifted in setting or position, and no degradation be caused in the performance specified.

3.9.2 Service Life. The equipment is designed and fabricated for a service life of 10 years after a storage period of 2 years.

3.10 Structure and Fastener Finish.

3.10.1 Structure. All structural members, framing members and all miscellaneous parts are galvanized by the hot dip method in accordance with ASTM A-123 after 100 percent fabrication.

3.10.2 Fasteners. Fasteners including type ASTM A-325, nuts, palnuts and washers are hot dipped galvanized per ASTM A-153. High strength fasteners type ASTM A-490, bolts and nuts, are zinc electroplated in accordance with ASTM B-663, service condition requirement, SC-4, Very Severe, minimum thickness, 25 micrometres.

3.11 Interchangeability. Individual parts, subassemblies, assemblies, ten foot sections and seventeen foot sections are designed and fabricated to be physically and functionally interchangeable without modification of any kind. Reliance shall not be placed on any unspecified dimension, rating or other unknown factor.

3.12 Identification Markings.

3.12.1 Identification of Parts. All equipment, assemblies and parts shall be marked for identification in accordance with MIL-STD-130. Structural steel shall be depth stamped for permanent identification. The identification marks shall be stamped into the steel before galvanizing and shall be legible after galvanizing to the naked eye at a distance of six feet.

3.12.2 Erection and Assembly Drawings. Erection and assembly drawings identify the location and orientation of all equipment, assemblies and parts required for tower assembly and erection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.

3.13 Workmanship. All fabricated structural steel and other parts of the tower shall be in accordance with this specification. All shearing, punching, back and end cuts shall be accurately and carefully performed. Holes shall be true and square with the plane of the material, and all exposed raw edges, including edges exposed in the dismantled stage, shall be ground, machined, or otherwise smoothed to prevent accidental cutting or scratching of both handlers and users of the tower.

3.14 Tolerances. The contractor is responsible for providing fabrication tolerances in accordance with the drawings and any other industrial standards to ensure proper fit and assembly.

3.15 Safety (Category I and II Hazards). All equipment furnished under this specifications shall be analyzed for Category I and II hazards as defined by MIL-STD-882. Any hazard so identified shall be brought to the attention of the procuring activity with recommended action for satisfying safety requirements. Action order of precedence shall be as specified in MIL-STD-882 paragraph 5.6.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements specified. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for Compliance. All items must meet all requirements of this specification. The inspections set forth shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.2 Classification of Inspections. The inspection requirements are classified in the following categories.

a. Preassembly Inspection
b. Preproduction Assembly and Postassembly Inspection
c. Acceptance Inspection

4.2.1 Tower Sections Used for Inspections. Tower sections, 17 FT and 10 FT, representative of production quantities, shall be subjected to the inspections specified. The tower sections shall be identified with their government assigned federal stock class number (NSN).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.

4.2.2 Preassembly Inspection. All parts of the tower shall be given a thorough inspection to ensure that the quality of the finished product is in compliance with the requirements of this specification. Particular attention shall be given to the following items.

Category	Major Items
101	Certification of specified fabrication material
102	Certification of fasteners in meeting specifications and that no fasteners are counterfeit quality.
103	Nameplates and identification markings.
104	Certification of galvanized finish and thickness
105	Welds of welded assemblies
106	Number of parts identical with Bill of Material.
107	Certification of zinc plating on A-490 bolts & nuts.
108	Certification of galvanized hardware
109	Grounding lugs on tower legs
110	Parts and tower dimensions same as drawings.
111	Workmanship (see 3.12)
	Minor Items
112	Blimishes and other visual defects.

4.2.3 Preproduction Assembly. Contractor shall assemble tower sections based on the following criteria.

a. Assemble a 17 Ft section with a 10 Ft section when both 17 FT and 10 FT sections are being acquired on the contract.

b. Assemble only a 17 FT section when only a 17 FT section(s) is being acquired on the contract.

c. Assemble only a 10 FT sections when only a 10 FT section(s) is being acquired on the contract.

4.2.4 Required Assembly. The required listed assemblies shall be fitted together while lying on a flat surface. Finger tight bolts and nuts will be used for structural parts. Grating and deck plate fasteners can be omitted.

a. Assemble one side of tower with legs, channels and K bracing.
b. 10 FT section horizontal layout (DWG 9029974), excluding parts H1, 2 each L2 and stairway, but including grating and handrail.
c. 10 FT section stairway with two threads and handrail on one side.
d. 17 FT section mezz horizontal layout (DWG 9029983), excluding parts M1, 2 each L2 and stairway, but including grating and handrail.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:47Z
Check the source to verify that this is the current version before use.

e. 17 FT section main level horizontal layout (DWG 9029984), excluding parts 4 each L2 and radar mount, but including grating parts one each of G13,14,15,16,17,17A,18,19 and 20, deck plating parts one each of S1 and S3, six each of S2, handrail two sides of octagon and handrail at both stairways.
f. 17 FT section inner and outer stairways with two threads and handrail on one side.
g. Radar mount and plate (DWG 9030023).

4.2.5 Postassembly Inspection. The required tower section assemblies shall be subjected to a careful mechanical inspection. All parts shall fit easily without the use of force and without bending. Particular attention shall be given to the following items.

Category	Major Items
101	Fitup of parts in their required positions.
102	Correct bolts size and length.
103	Bent, twisted or damaged parts.
104	Part dimensions identical to drawings.
105	Tower dimensions identical to drawings.
106	Name plate complete
107	Workmanship (see 3.12).
	Minor Items
108	Blimishes and other visual effects

4.2.6 Acceptance Inspection. The acceptance inspection shall be identical to paragraph 4.2.2.

5. PACKAGING

5.1 Preparation for Delivery Inspection. The preservation, packaging, packing, and marking of the tower shall be inspected to verify conformance to the requirements of this specification.

5.2 Preservation and Packaging. The preservation and packaging shall be Level A or Level C as specified in paragraph 6.2.

5.2.1 Level A. Methods of preservation and packaging for tower components and accessories shall be determined and accomplished in accordance with MIL-P-116 and MIL-STD-794. The contents of each package shall contain items and quantities, which will facilitate efficient and expeditious placement at the erection site, for timely unpacking and erection in established steps of succession called for in the erection manual. Bolts, nuts, washers, clips, screws and similar items of like description shall be preserved in accordance with MIL-P-116, Method IC-2, except where small quantities (2 pounds or less) are involved, then Method IC-3 may be used.

5.2.2 Level C. The complete tower shall be preserved and packaged in accordance with the supplier's standard practice.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.

5.3 Packing. The packing shall be Level A or Level C as specified in paragraph 6.2.

5.3.1 Level A. Packing and exterior shipping containers shall conform to the requirements of MIL-STD-794, except that large bar (framing) sheet, plate, and structural shape components shall be packed in accordance with MIL-STD-163. The final arrangement of shipping containers shall be in accordance with MIL-STD-794 and lifts conforming to MIL-STD-163 shall be entirely suitable for identification, documentation, and accountability of the packages belonging to one tower, when multiple quantities of like towers are being processed or handled simultaneously through shipping and receiving ports.

5.3.2 Level C. The complete tower shall be packed in a manner to insure arrival at destination in satisfactory condition and which will be acceptable to carriers at lowest rates. Packing shall comply with UCC Uniform Freight Classification Rules or National Motor Freight Classification Rules, according to the mode of transportation.

5.4 Marking. Interior packages, bundles, and shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended Use. Tower AB-1368/F is a sectionalized multiheight structure used for the installation of various types of electronic equipment.

6.2 Ordering Data. Procurement documents must specify the following:

a. Title, number, and date of this specification.
b. Air Force Drawings
Engineering and Reference Drawings.

Drawing Number	Title
9029961	Drawing Index
9029962	77 FT Elevation
9029963	67 FT Elevation
9029964	57 FT Elevation
9029965	47 FT Elevation
9029966	37 FT Elevation
9029967	27 FT Elevation
9029968	17 FT Elevation
9029969	Foundation Plans and Details
9029970	Loading Diagrams
9029971	Loading Diagrams
9029972	Loading Diagrams
9029973	Loading Diagrams
9030025	Information Only, Typical Grounding Details
9030026	Information Only, Typical Grounding Details
9030027	Information Only, Typical Obstruction Lighting

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:47Z
Check the source to verify that this is the current version before use.

10 Foot Section (Intermediate or Bottom Section)

9029974	Erection Drawing
9029975	Stairway Erection Detail
9029976	Bill of Material
9029977	Fabrication Drawing, Interior Members
9029978	Fabrication Drawing, Exterior Members
9029979	Fabrication Drawing, Handrail and Post
9029980	Fabrication Drawing, Handrail, Post and Toe Board
9029981	Fabrication Drawing, Handrail and Post
9029982	Fabrication Drawing, Stair and Grating Detail

17 Foot Section (Top Section)

9029983	Erection Drawing, Mezz Level
9029984	Erection Drawing, Main Level
9029985	Erection Drawing, Bolt Placement, Main Level
9029986	Erection Drawing, Work Level
9029987	Stairway Erection Detail (Mezz Level)
9029988	Stairway Erection Detail (Work Level)
9029989	Stairway Erection Detail (Inner Stairway)
9029990	Outer Stairway and Handrail Erection Detail
9029991	Bill of Material
9029992	Bill of Material
9029993	Fabrication Drawing, Tower Leg Detail
9029994	Fabrication Drawing, Mezz Exterior Members
9029995	Fabrication Drawing, Mezz Exterior Members
9029996	Fabrication Drawing, Mezz Brackets and Plates
9029997	Fabrication Drawing, Mezz Interior Members
9029998	Grating and Tread Detail, Mezz & Work Level
9029999	Fabrication Drawing, Main Level Exterior Members
9030000	Fabrication Drawing, Brackets and Plates
9030001	Fabrication Drawing, Main Level Interior Members
9030002	Fabrication Drawing, Main Level Interior Members
9030003	Fabrication Drawing, Main Level Interior Members
9030004	Fabrication Drawing, Main Level Deck Plate
9030005	Fabrication Drawing, Work Level Interior Members
9030006	Fabrication Drawing, Work Level Interior Members
9030007	Fabrication Drawing, Exterior Members
9030008	Fabrication Drawing, Interior Overhang
9030009	Fabrication Drawing, Overhang Grating
9030010	Fabrication Drawing, Stairway Stringers
9030011	Fabrication Drawing, Stairway Stringers
9030012	Handrail Detail Transition from 10 FT to 17 FT Section
9030013	Fabrication Drawing, Handrail for Overhang
9030014	Fabrication Drawing, Handrail Work Level
9030015	Fabrication Drawing, Inner Stairways
9030016	Fabrication Drawing, Outer Stairway Main Level
9030017	Fabrication Drawing, Handrail and Post
9030018	Fabrication Drawing, Handrail Overhang
9030019	Fabrication Drawing, Handrail Mezz Level

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.

9030020	Fabrication Drawing, Handrail Work Level
9030021	Fabrication Drawing, Handrail Mezz Level
9030022	Fabrication Drawing, Handrail Mezz Level
9030023	Fabrication Drawing, Radar Mount and Plate
9030024	Fabrication Drawing, Stairway Gate

c. Number of 17 FT tower sections.
d. Number of 10 FT tower sections.
e. Level of preservation and packaging (see 5.2).
f. Level of packing (see 5.3).

6.3 Drawing Changes. Contractor will notify the contracting officer with recommendations for drawing changes or corrections should the need for such items arise. All such items will be reviewed, approved or disapproved by the procuring activity. Any permanent drawing revisions shall be directed by WR-ALC/LVRG, Robins AFB, GA 31098-5345.

6.4 Subject Term (Key Word) Listing.

Tower
Radar Tower
Steel Structure
Prefabricated
Multiple Height Tower
Tower with Radome
High Wind Load Structure

Custodian:
Air Force - 99

Preparing Activity:
Air Force - 84

Project Number:
5445-0026

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-T-83822	2. DOCUMENT DATE (YYMMDD) 9 Jul 91

3. DOCUMENT TITLE: TOWER AB-1368/F, 10 FOOT AND 17 FOOT SECTIONS FOR USE WITH OR WITHOUT A RIGID RADOME

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME WR-ALC/LVRG ATTN: Ed McCall	b. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON DSN 468-6171
c. ADDRESS (Include Zip Code) Robins AFB GA 31098-5345	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2022-07-28T12:12Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:47Z
Check the source to verify that this is the current version before use.