INCH-POUND

MIL-F-11522F
AMENDMENT 1
26 July 1989

MILITARY SPECIFICATION

FUZE, SMOKE POT, M208 AND FUZE, HAND GRENADE, M226

This amendment forms a part of MIL-F-11522F, dated 12 December 1973, and is approved for use by all Departments and Agencies of the Department of Defense.

PAGE 3

3.3, lines 1 and 2: Delete "after being subjected to transportation vibration in accordance with 4.4.4.2".

3.8, line 2: Delete "4.4.4.2" and substitute "4.3.4.4".

3.9, end of paragraph: Add "The pyrotechnic loading methods and processes, including the order of materials loading, number of consolidations, consolidation load, and dwell time, that are used to produce an acceptable preproduction fuze lot shall serve as minimum standards during regular production."

PAGE 4

Add the following new paragraph:

"**3.11 Consolidation of first fire and delay composition.** The loading equipment shall include, as a minimum, independently actuated consolidating punches that shall reach the required consolidation pressure before stopping. A pressure gage shall be incorporated as an integral part of each consolidation station to measure directly the pressure of each consolidating punch. The overall height of the complete column shall be gaged automatically by the loading machine. In the event any punch does not reach the required consolidating pressure or the overall height of the complete column does not meet the

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T18:18Z
Check the source to verify that this is the current version before use.

requirement specified, the loading machine shall automatically reject the fuze or fuzes in question."

PAGE 5

Add the following new paragraph:

"**4.3.2.2 For in-process inspection.** A sample of 25 consecutive fuzes at the start of every shift and immediately upon restarting any loading machine after a shutdown period for repair or adjustment and a sample of 10 consecutive fuzes during each 2 hours of production shall be observed and the order of material loading, number of consolidations, consolidation load, dwell time, and column height recorded."

4.3.3.2(a), line 2: After "with" add "4.3.4.4,".

Add the following new paragraph:

"**4.3.3.3 For in-process inspection.** Record the order of material loading, number of consolidations, consolidation load, dwell time, and column height. In the event the observed consolidation characteristics are not consistent with the preceding production or the column height exceeds the drawing requirement, the portion of production since the last check was made shall be rejected, and the loading machine shall be repaired or adjusted and shall be requalified prior to use."

Add the following new paragraph:

"**4.3.4.4 Vibration.** The fuze shall be vibrated in accordance with test 104 of MIL-STD-331."

PAGE 6

Add the following new paragraph:

"**4.4.2.3 For in-process inspection.** A sample of 25 consecutive fuzes at the start of every shift and immediately upon restarting any loading machine after a shutdown period for repair or adjustment and a sample of 10 consecutive fuzes during each 2 hours of production shall be observed and the order of material loading, number of consolidations, consolidation load, dwell time, and column height recorded."

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T18:18Z
Check the source to verify that this is the current version before use.

PAGE 7

4.4.3.4(a): Add the following new defect:

"108 Excessive wax or shellac at center of B13-10-11 or on A36-7-19".

Add the following new subparagraph to paragraph 4.4.3.4:

"(c) **Ignition mixture III (W/B) (Dwg C143-8-2)**

Categories	**Defects**
Critical:	None defined
Major:	AQL 1.0 percent defective
101	Granulation incorrect"

Add the following new paragraph:

"**4.4.3.5 For in-process inspection.** Record the order of material loading, number of consolidations, consolidation load, dwell time, and column height. In the event the observed consolidation characteristics fail to comply with those used for the acceptable preproduction lot or the column height exceeds the drawing requirements, the portion of production since the last control check was made shall be rejected and not used in further assembly unless they are screened or reworked, and the loading machine shall be repaired or adjusted and shall be requalified prior to use in production."

4.4.4.1: Delete subparagraph (a) in its entirety.

4.4.4.2: Delete paragraph in its entirety.

Custodians:

Army - EA
Navy - OS

Preparing activity:

Army - EA

Project No. 1365-0245

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T18:18Z
Check the source to verify that this is the current version before use.