MIL-B-52075F
9 December 1977
SUPERSEDING
MIL-B-52075E
24 April 1974

MILITARY SPECIFICATION

BATH UNIT, PORTABLE, 8-SHOWER HEAD, M-1958

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a self-contained bath unit for use in the field, using a gasoline operated engine generator and water heater. The unit is designed to pump water from a stream and furnish 16 gallons (61 liters) of normal bath temperature water per minute to the shower heads.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids, or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

V-T-276	-	Thread, Cotton
W-R-550	-	Rod, Ground (With Attachments)
TT-P-636	-	Primer Coating, Alkyd Wood and Ferrous Metal
VV-F-800	-	Fuel Oil, Diesel
PPP-T-60	-	Tape: Packaging, Waterproof

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Natick Research and Development Command, Natick, MA 01760, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 4510

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-C-104	-	Crates, Wood, Lumber and Plywood Sheathed, Nailed and Bolted
MIL-P-116	-	Preservation-Packaging, Methods Of
MIL-B-121	-	Barrier Material, Greaseproofed, Waterproofed, Flexible
MIL-C-496	-	Clips, End, Strap
MIL-W-530	-	Webbing, Textile, Cotton, General Purpose, Natural or in Colors
MIL-B-543	-	Buckle, Tongueless and Web Strap
MIL-T-3530	-	Thread and Twine; Mildew Resistant or Water Repellent Treated
MIL-S-7916	-	Sealing Compound, Thread and Gasket, Fuel, Oil, and Water Resistant
MIL-C-10578	-	Corrosion Removing Metal Conditioning Compound (Phosphoric Acid Base)
MIL-P-10603	-	Pumps and Pumping Units, Centrifugal, Power-Driven, for Water, Packaging of
MIL-W-13518	-	Wood Preservative, Tetrachlorophenol and Pentochlorophenol, Surface Sealing Compound
MIL-V-13811	-	Varnish, Waterproofing, Electrical, Ignition
MIL-L-21260	-	Lubricating Oil, Internal Combustion Engine, Preservative and Break-In
MIL-E-52798	-	Enamel, Alkyd, Camouflage

STANDARDS

FEDERAL

FED-STD-751	-	Stitches, Seams, and Stitchings

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	-	Marking for Shipment and Storage
MIL-STD-130	-	Identification Marking of US Military Property
MIL-STD-461	-	Electromagnetic Interference Characteristics, Requirement for Equipment
MIL-STD-462	-	Electromagnetic Interference Characteristics, Measurement of

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

DRAWINGS

US ARMY NATICK RESEARCH AND DEVELOPMENT COMMAND

6-1-733	-	Bath Unit, 8-Shower Head M-1958; Water Heater Assembly
6-1-1984	-	Bath Unit, 8-Shower Head M-1958; Ignition Cable Assembly

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply:

AMERICAN WELDING SOCIETY

Standard Qualification Procedure of the American Welding Society

(Application for copies should be addressed to American Welding Society, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Welding Qualifications of the American Society of Mechanical Engineers

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

UNIFORM CLASSIFICATION COMMITTEE, AGENT

Uniform Freight Classification

(Application for copies should be addressed to the Uniform Classification Committee, Room 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION, INC., AGENT

National Motor Freight Classification

(Application for copies should be addressed to the American Trucking Associations, Inc., Traffic Department, 1616 P Street, N.W., Washington, DC 20036.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA No. 70 - National Electrical Code

(Application for copies should be addressed to the National Fire Protection Association, 60 Battery March Street, Boston, MA 02110.)

HYDRAULIC INSTITUTE STANDARDS

(Application for copies should be addressed to the Standard Hydraulic Institute, 122 East 42nd Street, New York, NY 10017.)

3. REQUIREMENTS

3.1 Alternate components. Components offered as equivalent to components specified herein and on the referenced drawings as a specific manufacturer's part number or equal shall be functionally equal, of equal or better quality with the manufacturer's part number identified. The incorporation and inclusion of such a component in the design of the specified end product shall not require modification or change to any other specified component, and shall not reduce ease of maintenance to it or any other components, unless such modification or change is specifically approved by the contracting officer. Prior to manufacture of the first article, or if none is required, prior to commencing production, the contractor shall submit for the contracting officer's approval, a list identifying each alternate component, together with proof that each listed component complies with requirements specified herein. The contracting officer, at his option, may require a physical sample of the proposed substitution. Approval of the submitted listing, together with necessary supporting data does not relieve the contractor of the responsibility that these components perform in accordance with specified requirements when incorporated into the end product.

3.2 First article. When specified (see 6.2), the contractor shall furnish a sample for first article inspection and approval (see 4.3 and 6.3).

3.3 Materials and components. The materials and components shall be as specified herein and on the applicable drawings. Materials and components not definitely specified shall be of the quality normally used by the manufacturer provided the completed item complies with all the provisions of this specification (see 6.5).

3.3.1 Buckle. The 1-inch (25 mm) buckle shall conform to type III, class 1 of MIL-B-543.

3.3.2 End clip. The 1 inch (25 mm) end clip shall be brass and conform to type I, class 1 of MIL-C-496.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

3.3.3 Thread, cotton, machine. The thread used for all machine stitching shall be ticket number 12, 4 ply and conform to type I A3 or 1 B3 of V-T-276. The thread shall match olive drab shade S-1 (CA 66022) and shall be treated for mildew resistance in accordance with type I, class 1 of MIL-T-3530.

3.3.4 Primer. Primer for steel and aluminum surfaces shall conform to TT-P-636.

3.3.5 Enamel. Enamel shall conform to MIL-E-52798. The color shall be lusterless forest green.

3.3.6 Sealer. Sealer for plywood shall conform to type II of MIL-W-13518. Sealer compound for thread joints and gaskets shall conform to MIL-S-7916.

3.4 Design and construction. The design and construction of the bath units shall be as specified herein, and as shown on Drawing 6-1-733 and drawings referenced thereon. The electric power shall be 3 phase, 60 hertz, 4 wire, 120 volts line to neutral on 208 volts line to line 120/208 volts. All wiring shall be in accordance with the provisions of NFPA No. 70. The ground rod with attachments shall conform to type III, class B of W-R-550. The bath unit shall have seven web straps each having a buckle on one end and an end clip on the other. The buckles shall be fastened by a cross stitch 3/4 x 1 inch (19 x 25 mm), double stitched at both ends. Ends of webbing where buckles are attached shall be overedge stitched or turned under before stitching to prevent raveling. The webbing shall be inserted to the full depth of the clip. The clip shall be securely attached without cutting the webbing and shall lie flat at the point of entrance. Two straps, 3 foot (914 mm) long each, shall hold the shower heads in place and be secured to the plywood floor. Three straps, 18 inch (457 mm) long each, shall hold the coiled fire hose. One strap, 18 inch (457 mm) long, shall hold the coiled suction hose and another strap, 18 inch (457 mm) long shall hold all the electric cables together. Machine stitching shall be 5 to 7 stitches per inch (2 to 3 stitches per cm). Box stitching shall conform to type 301 of FED-STD-751. Stitching shall conform to type 304 or 503 of FED-STD-751.

3.5 Performance.

3.5.1 Pump, water. One sample water pump at a speed of 3450 revolutions per minute shall have a performance curve of total head versus capacity that lies within the curves shown on Drawing 6-1-1984, when tested as specified in 4.4.2.2.1.

3.5.2 Firebox and outside vessel assembly. Each firebox and outside vessel assembly shall have no visible evidence of leakage when individually tested as specified in 4.4.2.2.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

3.5.3 Heater, water. Each water heater shall have no visible evidence of leakage, fractures or breakage of parts when tested as specified in 4.4.2.2.3.

3.5.4 Shower head and riser assembly. Each shower head and riser assembly shall be tested for leaks when tested as specified in 4.4.2.2.4.

3.5.5 Heater, water assembly. All components of the water heater shall be completely assembled and tested as specified in 4.5.1 for the following:

(a) A minimum rate of 16 gallons per minute (61 liters per minute) of water with a minimum temperature rise of 70°F (21°C).

(b) The fuel pump shall supply fuel at 100 psi (690 kPa) gauge with the bypass valve closed.

(c) The combination temperature and pressure control shall stop the supply of fuel when the temperature reaches 120°F (49°C) and also shall allow the fuel to flow when the water pressure is 15 psi (103 kPa) gage or above.

(d) No leakage of the assembly.

3.5.6 Switch, overload and reset. The overload and reset switch of the burner blower shall be capable of stopping the motor when an overload condition occurs, and of being reset to resume motor operation after the overload condition has been eliminated (see 4.5.2).

3.5.7 Electromagnetic compatability. When specified (see 6.2) the bath unit shall be designed and equipped for electromagnetic compatability in accordance with class II B of MIL-STD-461 (see 4.5.3).

3.6 Contract data requirements. The contract data requirements shall be as specified (see 6.2 and 6.2.1).

3.7 Finish.

3.7.1 Surface preparation. After fabrication and completion of tests specified in 4.4.2.2.1 through 4.4.2.2.4 and 4.5.1, each component to be coated shall have all rough, and sharp edges and scale removed prior to finishing. All metal surfaces shall be thoroughly cleaned and prepared for painting using compound conforming to type I or II of MIL-C-10578. Surfaces shall be dried prior to application of paint. All plywood surfaces shall be given a coat of sealer specified in 3.3.6. Plywood edges shall be sealed prior to assembly of the shower units using a sealer conforming to MIL-W-13518, type II, class 2.

3.7.2 Priming. Metal and wood surfaces, except shower head nozzles, shall be coated with primer conforming to TT-P-636.

3.7.3 Enameling. After primer is dry, all metal primed surfaces shall be coated with enamel conforming to MIL-E-52798. Government-furnished painted parts which have become exposed due to alterations shall be touched up.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

3.7.4 Handles and plugs. All control handles and drain plugs shall be painted red after cleaning.

3.8 Marking. Marking for identification shall be in accordance with MIL-STD-130.

3.9 Government-furnished property. Unless otherwise specified (see 6.2), the Government shall furnish 18 feet (5.5 m) of cotton, webbing, 1 inch (25 mm) type II a, class 4, Olive Drab, No. 7 conforming to MIL-W-530.

3.10 Workmanship. The bath unit shall be free from defects such as fractures, splits, punctures, tears, dents, creases, deteriorations, or malformations. There shall be no sharp edges, burrs, or slivers. The finish shall be free of blisters, peel, chipped areas or areas of no film. The finish shall be free from smudges, poor touch up, scale, scratches, stain, overspray sag, imprint or embedded foreign matter. All bolts, studs, nuts and screws shall be drawn tight. Rivets shall be driven to completely fill the holes, with full size heads neatly finished and in full contact with the surface of the riveted members.

3.10.1 Welders. Unless otherwise specified (see 6.2), before assigning any welder to work covered by this specification, the contractor shall provide the Government inspection service with the names of the welders to be employed in the work, together with certification that each of the welders has passed a qualification test as prescribed by either of the following listed codes for the type of welding operation to be performed, and that such qualification is effective as defined by that particular code as follows:

(a) Standard Qualification Procedure of the American Welding Society.
(b) Welding Qualification of the American Society of Mechanical Engineers.

3.10.2 Welding. The surface of parts to be welded shall be free from oxide, scale, paint, grease, and other foreign matter. Welds shall be sound, continuous, smooth, and free from porosity, cracks, incomplete fusion, and deformation of material. All scale and flux deposits (when flux is used) shall be removed from the finished welds.

3.10.3 Electrical wiring. Wiring shall not be cut, abraded, or have excessive insulation stripped, and shall be properly and tightly joined at terminals. Wiring shall have adequate slack to provide strain relief.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspection. The inspection requirements specified herein are classified as follows:

1. First article inspection (see 4.3).
2. Quality conformance inspection (see 4.4).

4.3 First article inspection. When a first article is required (see 3.2), the bath unit shall be examined as specified in 4.4.3.1 and 4.4.3.2 and tested as specified in 4.5.1 and 4.5.3. The presence of any defects or failure to pass any test shall be cause for rejection of the first article.

4.4 Quality conformance inspection. Except as otherwise specified herein, sampling for inspection shall be performed in accordance with the provisions set forth in MIL-STD-105.

4.4.1 Component and material inspection. The contractor shall insure that all components and materials used are manufactured, examined, and tested in accordance with referenced specifications, drawings, and standards unless excluded, amended, modified, or qualified in this specification or applicable purchase document.

4.4.2 In-process inspection.

4.4.2.1 Visual examination of operations. In-process examination shall be made of surface preparation prior to the application of the finished coat to determine compliance with 3.7.1. Also examination of surface preparation prior to welding shall be made to determine compliance with 3.10.2. Whenever nonconformance is noted, correction shall be made to the applicable process and all items processed.

4.4.2.2 In-process testing.

4.4.2.2.1 Pump, water test. One sample water pump shall be tested in accordance with the applicable section of the centrifugal pump test code of the Hydraulic Institute for conformance to the pump speed and the performance curves as specified in 3.5.1. Failure to pass the test shall be cause for rejection. For certification of the remainder of the pumps, see 4.4.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

4.4.2.2.2 Firebox and outside vessel assembly test. Prior to painting, each firebox and outside vessel assembly shall be tested separately and under a hydrostatic pressure of 75 psi (517 kPa) gauge for leaks with the water-connections capped for a period of 5 minutes. Any nonconformance with the requirements of 3.5.2 shall constitute failure of this test.

4.4.2.2.3 Heater, water test. Prior to painting, and assembly to the bath unit, each water heater shall be tested under a hydrostatic pressure of 75 psi (517 kPa) gauge for leakage, fractures or breakage of parts. Any nonconformance with the requirements of 3.5.3 shall constitute failure of this test.

4.4.2.2.4 Shower head and riser assembly test. Prior to painting, each shower head and riser assembly shall be capped and completely submerged in water with an internal pressure of 10 to 15 psi (69 to 103 kPa) gauge. Any nonconformance with the leakage requirements of 3.5.4 shall constitute failure of this test.

4.4.3 End item inspection. The lot shall be all the bath units offered for inspection at one time. The sample unit for this examination shall be one assembled bath unit.

4.4.3.1 Visual examination. Examination shall be made of the end item for defects in table I. The inspection level shall be II with acceptable quality level (AQLs) of 2.5 for major defects and 6.5 for total defects, expressed in terms of defects per hundred units.

TABLE I. Classification of defects

Examine	Defect	Classification	
		Major	Minor
Finish	Color not as specified		X
	Blistered, peeled, chipped or area of no film		X
	Poor touch-up, orange peel, color separation, smudge, scale, scratched, stained, overspray, sag, imprint or foreign matter imbedded		X
Design, construction and workmanship, general (applicable to all components and assemblies)	Any component or part missing or not specified type or size	X	
	Fractured, split, punctured, torn, dented, creased, deteriorated or malformed	X	
	Component misplaced, or not in proper alignment		X

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

TABLE I. Classification of defects (cont'd)

Examine	Defect	Classification Major	Minor
Design, construction and workmanship, general (applicable to all components and assemblies) (cont'd)	Component loose		X
	Sharp burr or edge or sliver		X
	Any operation omitted or not properly performed	X	
	Any functioning component that is inoperative or will not operate as intended	X	
	Any functioning component that requires abnormal force to operate or not interchangeable		X
	Any adjustable assembly that cannot be adjusted		X
	Any assembly not properly adjusted		X
	Any component not readily accessible for servicing where required		X
Welding	Missing, incomplete, burn holes, cracked, fractured, not fused	X	
	Undercut, not smooth and uniform or scale or flux deposits not removed		X
Soldering (when applicable)	Missing, not adherent or incomplete		X
	Not clean (flux residue not removed, pinholes in solder)		X
Bolts, nuts, screws, studs and other types of threaded fasteners	Broken, stripped, fractured or not tight		X
Rivets (when required)	Broken, not peened or insufficiently peened or loose		X
Electrical assembly	Wiring cut, abraded, or not properly installed or joined	X	
	Adequate slack not provided for wiring to relieve strain		X

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

TABLE I. Classification of defects (cont'd)

Examine	Defect	Classification Major	Minor
Gauges, instruments, controls, thermometer, etc.	Not properly mounted or not specified type or capacity		X
	Not free of foreign matter		X
Marking	Missing, incomplete, not legible, not specified type or size, not in proper location		X

4.4.3.2 Dimensional examination. Examination shall be made of the bath unit for compliance with dimensions specified. Any dimension that is not within the specified tolerance shall be classified as a defect. The inspection level shall be S-2 with an AQL of 6.5, expressed in terms of defects per hundred units.

4.4.3.3 Testing of the end item. When electromagnetic compatability is required, and the applicable test was not accomplished under 4.3, the first produced end item shall be tested as specified in 4.5.3. In addition, each end item shall be tested as specified in 4.5.1. One item selected at random from the first lot offered for inspection shall be tested as specified in 4.5.2. Failure to pass either test shall be cause to reject the effected end item.

4.4.4 Packaging inspection. Packaging inspection shall be made to determine that preservation-packaging, packing and marking comply with section 5 of this specification. Defects shall be scored as set forth in table II. The sample unit shall be one shipping container fully packed except that it need not be closed. The lot shall be the number of shipping containers offered for inspection at one time. The inspection level shall be S-1 with an AQL of 4.0, expressed in terms of defects per hundred units.

TABLE II. Packaging inspection

Examine	Defect
Markings	Omitted; incorrect; illegible; of improper size; location, sequence, or method of application
Preservation	Improperly applied or missing
Materials	Components missing, damaged
Workmanship	Inadequate application of components such as incomplete closure of barrier materials, not taped as specified System not completely drained and dried

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

4.4.4.1 Inspection of shipping container. When shipping containers are required to comply with MIL-C-104, examination for defects in the closure and strapping shall be in accordance with the applicable requirements of MIL-C-104.

4.4.5 Code and standard compliance. Certification that the pump total head-capacity characteristic curve complies with the performance curve specified in 3.5.1 shall be furnished and acceptable to the Government representative.

4.5 Tests.

4.5.1 Performance heater, water test. The complete water heater shall be connected to a source of water that shall supply a minimum rate of 16 gpm (61 lpm), through the boiler outlet. Thermometers shall be located in the inlet and outlet water connections of the heater. The heater shall be operated for 15 minutes with the burner fuel pressure maintained at 100 psi (690 kPa) gauge. At the completion of this test, the complete heater assembly shall be examined for water leaks including the removal of the front cover and burner assembly to allow for examination of the firebox. Any nonconformance with the requirements of 3.5.5 for heater temperature rise, fuel pump pressure, combination pressure and temperature control, and leakage shall constitute failure of this test.

4.5.2 Overload and reset switch test. One burner, blower motor, overload and reset switch when assembled with the complete water heater shall be tested to determine compliance with 3.5.6, as follows:

(a) The blower wheel shall be restrained from turning, until the overload switch opens the electrical circuit.

(b) After a suitable period to allow for the thermal element of the switch to cool, the switch shall be reset manually to determine resumption of motor operation. Any nonconformance with the overload and reset switch requirements of 3.5.6 shall constitute failure of this test.

4.5.3 Electromagnetic compatibility test. When electromagnetic compatibility is required the first article or initial production unit, as applicable, shall be tested by the contractor in accordance with test method CE03 and RE02 of MIL-STD-462. The Government reserves the right to witness tests performed by the contractor or an independent agency. The contractor shall furnish the contracting officer written certification that the Interference Control Plan, the EMI/EMC Test Plan, the Electromagnetic Test Report and the requirements meet MIL-STD-461 (see 3.5.7).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 Preservation-packaging. Preservation-packaging shall be level A or C, as specified (see 6.2).

5.1.1 Level A. All preservation-packaging shall be in accordance with the method and material requirements of MIL-P-116 or as hereinafter specified. Varnish specified hereinafter shall conform to MIL-V-13811. Tape hereinafter specified shall conform to type IV, class 1 of PPP-T-60. All exposed surfaces of the tape shall be coated with varnish. The color of the tape shall be of a contrasting color to the surface to which applied. The tape shall not be applied directly to plastic gauge faces and dials. Such surfaces shall be protected with kraft paper or cushioning material prior to application of the tape.

5.1.1.1 Drainage of water system. The entire water system of the unit, including the water heater, water pump, line strainer, shower stands, hoses, etc., shall be thoroughly drained, blown out and dried with compressed air. All valves and petcocks shall be left open. A red tag shall be wired in a conspicuous place indicating that the entire water system has been completely drained.

5.1.1.2 Drainage of fuel system. The fuel lines, including the burner fuel lines, fuel pump, fuel filter and all connections, shall be completely drained and thoroughly dried and replaced. The exterior surfaces of all flexible fuel lines shall be coated with varnish. The fuel hoses with the barrel plug assembly shall be coiled and secured with tape. The fuel pump shall be filled with diesel oil fuel conforming to VV-F-800 and the inlet pump fitting capped.

5.1.1.3 Cleaning. All uncoated and unpainted ferrous metal surfaces of the bath unit and components shall be cleaned in accordance with the process C-1 of MIL-P-116, and thoroughly dried prior to application of preservative.

5.1.1.4 Repainting and recoating. Painted and permanently coated surfaces from which the paint or permanent coating has been removed or which are defective shall be repainted or recoated with material identical with the original.

5.1.1.5 Preservation.

5.1.1.5.1 Water pump. The water pump, drained as specified in 5.1.1.1, shall be cleaned and preserved in accordance with applicable requirements of MIL-P-10603.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

5.1.1.5.2 Water heater. The combustion chamber, exhaust tubes, exhaust pipe, and burner nozzles, cleaned as specified in 5.1.1.3, shall be fogged with type I or II preservative of MIL-L-21260. The shutter assembly shall be coated with preservative specified herein. The blower assembly and exhaust port shall be sealed with a combination of barrier-material conforming to type I or II, grade A of MIL-B-121 and tape. The fuel pressure and temperature gauge glasses, all inlets and outlets, sight glasses, and electrical receptable covers shall be sealed with tape.

5.1.1.5.3 Shower stand and hose assembly. The drained and dried shower stand assemblies shall be disassembled by removing legs and hoses. Each shower nozzle shall be sealed with tape. All open ends of the shower heads, legs and hoses shall be sealed with tape.

5.1.1.5.4 Electric cords. The receptacle ends of the electric cords shall be sealed with tape.

5.1.1.6 Securing of components. The water heater and pump shall be secured to the plywood base with the holddowns provided. The shower stands shall be secured to the base with straps provided. The firehoses and suction hoses shall be coiled and secured with straps provided. The electric cords shall be coiled and secured with straps provided. The ground rod sections shall be disassembled and the three sections, together with the ground wire, secured together with tape, cord or twine. The water strainer, shower stand legs, and ground rod shall be placed within the burner exhaust duct and the ends of the duct sealed with tape.

5.1.2 Level C. The bath unit shall be preserved-packaged to afford adequate protection against corrosion, deterioration and damage during shipment from the supply source to the first receiving activity. The contractor may use his standard practice when it meets these requirements.

5.2 Packing. Packing shall be level A or C, as specified (see 6.2).

5.2.1 Level A. Each bath unit, preserved-packaged as specified in 5.1, shall be packed in a crate constructed, closed and bolted to conform to type II, class 1 or 2, style a of MIL-C-104, except that floorboards or load bearing members shall not be required. The plywood base shall be utilized as the floor of the crates. The plywood base shall abut the headers and be bolted directly to the skids with not less than four 3/8-inch (10 mm) diameter carriage bolts. The bolts shall set in not less than 6 inches (152 mm) from each end of the plywood base and shall be centered in the skids. The firehoses, suction hose, and electric cords, coiled and secured as specified in 5.1.1.6, shall be stacked on the plywood base of the bath unit and secured. The burner exhaust duct, packaged as specified in 5.1.1.6, shall be anchored in an unused portion of the crate in accordance with the applicable requirements of the appendix of MIL-C-104.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

5.2.2 Level C. Bath units, preserved-packaged as specified in 5.1, shall be packed in a manner to insure carrier acceptance and safe delivery at destination at the lowest transportation rate for such supplies. Containers shall comply with Uniform Freight Classification or National Motor Freight Classification, as applicable.

5.3 Marking. In addition to any special marking required by the contract or order, interior packages and shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. The portable bath unit covered by this specification is a self contained unit for use in the field. The unit is designed to take water from streams, rivers, lakes and the like by means of a pump and to heat it sufficiently to furnish normal bath temperature water to the shower heads.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) When a first article is required (see 3.2, 4.3 and 6.3).
(c) When electromagnetic compatibility is required (see 3.5.7).
(d) Contract data requirements (see 3.6).
(e) Source and delivery of GFP when furnished (see 3.9).
(f) When certification of qualification test for welders is not required (see 3.10.1).
(g) Selection of applicable levels of preservation-packaging, and packing (see 5.1 and 5.2).

6.2.1 Contract data requirements. Any data item to be delivered under any contract for items covered by this specification should be specifically called for in the contract in accordance with the applicable regulation of the procuring activity (see 3.6 and 6.2).

6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of the Armed Services Procurement Regulation (ASPR) 7-104.55. The first article should be a preproduction sample, initial production item or other specific item described under the definition of a first article in the ASPR. The contracting officer should specify the appropriate type of first article and the number of units to be furnished. The contracting officer should include specific instructions in all procurement instruments regarding arrangements for inspection and approval of the first article.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

6.4 Government-furnished property. The contracting officer should arrange to furnish the property listed in 3.9.

6.5 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of this specification (see 3.3).

6.6 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness of the changes.

Custodians:

Army - GL
Air Force - 99

Review activities:

Army - MD, ME
DLA - CS

Preparing activity:

Army - GL

Project No. 4510-0152

☆U.S. GOVERNMENT PRINTING OFFICE: 1977 — 703-122/335

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.
NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER *(Number)* AND TITLE

MIL-B-52075F - Bath Unit, Portable, 8-Shower Head, M-1958

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1 OCT 76 1426 EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:06Z
Check the source to verify that this is the current version before use.