INCH-POUND

MIL-C-43343C
13 September 1989
SUPERSEDING
MIL-C-43343B
31 March 1986

MILITARY SPECIFICATION

CONTROL, FUEL FLOW, OIL BURNER

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers one type of constant level fuel flow control with multifuel capabilities for use with gravity feed oil burning equipment (see 6.1).

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: U.S. Army Natick Research, Development, and Engineering Center, Natick, MA 01760-5014, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 4530

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

VV-F-800 - Fuel Oil Diesel
VV-G-1690 - Gasoline, Automotive, Leaded or Unleaded
PPP-B-601 - Boxes, Wood, Cleated-Plywood
PPP-B-636 - Boxes, Shipping, Fiberboard

MILITARY

MIL-C-5501 - Cap and Plug, Protective, Rust and Moisture Seal
MIL-P-116 - Preservation, Methods Of
MIL-T-5624 - Turbine Fuel Aviation, Grades JP-4 and JP-5
MIL-A-8625 - Anodic Coatings, for Aluminum and Aluminum Alloys
MIL-T-83133 - Turbine Fuel, Aviation, Kerosene Type, Grade JP-8

STANDARDS

FEDERAL

FED-STD-595 - Colors

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129 - Marking for Shipment and Storage
MIL-STD-147 - Palletized Unit Loads
MIL-STD-731 - Quality of Wood Members for Containers and Pallets
MIL-STD-970 - Standards and Specifications, Order of Preference for Selection of

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

DRAWINGS

U.S. ARMY NATICK RESEARCH, DEVELOPMENT, AND ENGINEERING CENTER

5-13-5130 - Control, Fuel Flow, Oil Burner, Assembly

(Copies of drawings are available from the U.S. Army Natick Research, Development, and Engineering Center, Natick, MA 01760-5014.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

B 633 - Electrodeposited Coating of Zinc on Iron and Steel

D 3951 - Standard Practice for Commercial Packaging

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.2 Materials and components. The materials and components shall be as specified herein and on the applicable drawing. Materials and components not specified shall be selected by the contractor in accordance with MIL-STD-970. Materials and components specified in accordance with MIL-STD-970 shall not degrade the operation suitability of effectiveness of the burner. It is encouraged that recycled material be used when practical as long as it meets the requirements of this document.

3.3 Design. The fuel control shall be designed to maintain a constant head and deliver a constant fuel flow rate to a burner by means of a float actuated valve. The fuel flow control shall include a manual adjustment for fuel rate of flow and a shutoff assembly for "ON" and "OFF" operation. The fuel control shall have eight settings that provide an increase in fuel flow rate for each successive setting over the entire fuel flow range when tested as specified in 4.5.3. The fuel control shall compensate for the differences in viscosity of gasoline (unleaded VV-G-1690), DF-2 (VV-F-800) and JP-4 (MIL-T-5624) by being calibrated to produce the flow rates in cubic centimeters per minute (cc/min)

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

specified in table I for the No. 1 and No. 8 settings of the metering knob, when tested as specified in 4.5.1. Obtaining the flow rates in table I when using the test fluid JP-8 will ensure an equivalent fuel flow range for the three fuels being used in operation.

TABLE I. Flow rates

Test fuel	Valve position	Metering knobs Setting No.	Flow rates (cc/min) ± 3cc/min
JP-8	Gas	1-8	9-22
JP-8	JP-4	1-8	10-23
JP-8	DF-2	1-8	16-58

3.4 Construction. The fuel flow control shall be constructed as specified on the drawing 5-13-5130 and herein. The fuel flow control shall consist of a housing assembly, an attached cover assembly, and an exterior guard.

3.4.1 Housing assembly. The housing assembly shall consist essentially of a body with an inlet, two outlets, and overflow fittings and assemblies of float, strainer and shutoff valve. The float assembly in the housing assembly shall:

a. Maintain an operating fuel level of 1.000 to 1.064 inches measured from fuel surface to the center of the side outlet opening of the body, when tested as specified in 4.5.4.a.

b. Completely shut off the supply of fuel to the housing assembly at a fuel level of not more than 1.125 inches measured as in (a) above, when tested as specified in 4.5.4.b.

3.4.1.1 Body. The body shall have a drain screw which is accesible through the protective cover, and an overflow, inlet opening, two outlet openings, and one outlet plug. The body with attached components shall not leak when tested as specified in 4.5.5.

3.4.1.2 Strainer assembly. The strainer assembly shall have a screen for filtering fuel. The screen shall be constructed of 50 by 60 mesh monel wire cloth. The strainer assembly shall be attached to the body without the use of special tools and a sealer. The strainer assembly shall not leak around the threads when tested as specified in 4.5.5.

3.4.2 Cover assembly. The cover assembly shall consist of a gasket, plate, nameplate, metering knob assembly, and shutoff assembly. The shutoff assembly handle when in the "OFF" position shall completely stop the flow of fuel when tested as specified in 4.5.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

3.4.2.1 Metering knob. The metering knob shall indicate the fuel flow setting and shall have holes with screws to allow calibration of the fuel flow control without disassembly. The knob shall operate without binding. The metering knob, when turned from setting 1 thru 8 shall provide an increase in fuel flow rate for each successive setting when tested as specified in 4.5.3.

3.5 Marking.

3.5.1 Nameplate. The nameplate shall be marked as specified on Drawing 5-13-5130. The paint coat shall not peel or become capable of being rubbed off the nameplate surface when tested as specified in 4.5.6.

3.5.2 Body. The body specified in 3.4.1.1 shall be marked as specified on Drawing 5-13-5130.

3.6 Finish. The finish of the body and knob shall conform to either type I or II of MIL-A-8625. The plak shall be finished by a zinc coating in accordance with type III, class SC-2 thickness of ASTM B 633. The color of the body shall conform to X24087 of FED-STD-595. The nameplate shall be smooth and free from scratches, imbedded foreign matter, and areas of no paint.

3.7 Workmanship. The end items shall conform to the quality of product established by this specification.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

4.1.2 Responsibility for dimensional requirements. Unless otherwise specified in the contract or purchase order, the contractor is responsible for ensuring that all specified dimensions have been met. When dimensions cannot be examined on the end item, inspection shall be made at any point, or at all points in the manufacturing process necessary to assure compliance with all dimensional requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).

4.3 First article inspection. When a first article is required (see 3.1 and 6.2), it shall be examined for the defects specified in 4.4.3 and 4.4.4 and tested as specified in 4.5.1, 4.5.2, 4.5.3, 4.5.4, 4.5.5, and 4.5.6.

4.4 Quality conformance inspection. Unless otherwise specified, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.4.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents unless otherwise excluded, amended, modified, or qualified in this specification or applicable purchase document.

4.4.1.1 Component testing. Prior to assembly of the fuel flow control, each housing assembly shall be tested for fuel level, and each body shall be tested for leaks in accordance with test sequence 1 and 2 in the first column of table II, as applicable. Failure to pass any test shall be cause for rejection of the affected item. The sample nameplate shall be tested in accordance with test sequence 3. Failure to pass any test shall be considered a defect. The inspection level shall be S-2 (see 6.4).

TABLE II. Component test schedule

Testing sequence	Test paragraph	Requirement paragraph
1	4.5.4	3.4.1
2	4.5.5	3.4.1.1 and 3.4.1.2
3	4.5.6	3.5.1

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

4.4.2 In-process inspection. Inspection of subassemblies shall be made to ascertain that construction details which cannot be examined in the finished product are in accordance with specified requirements. The Government reserves the right to exclude from consideration for acceptance, any material or service for which in-process inspection has indicated nonconformance.

4.4.3 End item visual examination. The end items shall be examined for the defects in table III. The lot size shall be expressed in units of fuel flow controls. The sample unit shall be one fuel flow control. The inspection level shall be S-2 (see 6.4).

TABLE III. End item visual defects

Examine	Defect	Classification Major	Minor
Finish	Not anodized where required	101	
	Nameplate coat not smooth and free from scratches, imbedded foreign matter and areas of no paint		201
Construction and workmanship	Not connected or joined as specified	102	
	Fuel flow control not assembled as specified		202
	Component missing	103	
	Not clean and free from burrs, slivers, and sharp edges		203
	Not free from dents, blowholes, and fractures	104	
Knob	Sticky operation	105	
Body	Drain screw missing		204
	Overflow outlet missing	106	
Thread fasteners	Missing	107	
	Loose or broken		205
Guard	No hole for access to drain screw	108	
Marking:			
Nameplate	Missing, incomplete, improper, lettering and numerals not size specified		206
Body marking	Missing, incomplete, improper, lettering not size specified	109	

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

4.4.4 End item dimensional examination. The end items shall be examined for conformance to the dimensions specified on Drawing 5-13-5130. Only those dimensions that can be evaluated without damaging or disassembling the end items shall be examined. Any dimension not within the specified tolerance shall be classified as a defect. The lot size shall be expressed in units of fuel flow controls. The sample unit shall be one fuel flow control. The inspection level shall be S-2 (see 6.4).

4.4.5 End item testing. All end items shall be subjected to the test specified in 4.5.1 and 4.5.2. Failure to pass any test shall be cause for rejection of the inspection lot.

4.4.5.1 End item linear flow progression test. One out of 100 end items shall be subjected to the test specified in 4.5.3. Failure of this test shall be cause for rejection of the lot.

4.4.6 Packaging examination. The fully packaged end items shall be examined for the defects in table IV. The lot size shall be expressed in units of shipping containers. The sample unit shall be one shipping container fully packaged. The inspection level shall be S-2 (see 6.4).

TABLE IV. Packaging defects

Examine	Defect
Marking (exterior and interior)	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application
Materials	Any component missing, damaged, or not as specified
Workmanship	Inadequate application of components, such as: incomplete sealing or closure of flap, improper taping, loose strapping, or inadequate stapling Bulged or distorted container
Content	Number per container is more or less than required

4.4.7 Palletization examination. The fully packaged and palletized end items shall be examined for the defects listed in table V. The lot size shall be expressed in units of palletized unit loads. The sample unit shall be one palletized unit load, fully packaged. The inspection level shall be S-1 (see 6.4).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

TABLE V. Palletizatio examination

Examine	Defect
Finished dimensions	Length, width, or height exceeds specified maximum requirement
Palletization	Pallet pattern not as specified Load not bonded as specified
Weight	Exceeds maximum load limits
Marking	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application

4.5 Methods of testing. The fuel flow control and housing assembly for tests specified in 4.5.1 through 4.5.4 shall be leveled and operated with JP-8 (MIL-T-83133) fuel at a temperature between 50°F and 70°F, and the fuel shall be allowed to flow until all air is removed prior to conducting the test. The inlet liquid head for tests in 4.5.2 and 4.5.4 shall be no less than 96 inches measured from the center of the discharge opening of the test liquid supply source and inlet opening of the fuel flow control body.

4.5.1 Flow rate test. With an inlet test liquid head of between 18 and 24 inches, the fuel flow control shall be operated with the metering knob set at the Nos. 1 and 8 positions, respectively. After the test liquid has been flowing for a minimum of 1 minute while the metering knob is set at position 1, the test liquid flow measurements in volume and time shall be taken to determine compliance with the requirements specified in 3.3. The same procedure shall be followed while the metering knob is set at position 8. Any nonconformance shall constitute failure to pass this test.

4.5.2 Fuel shutoff test. The fuel flow control shall be operated at the specified test liquid inlet head (see 4.5) and at a fuel flow setting of No. 8 for 1 minute. Then the shutoff assembly handle shall be turned to the "OFF" position to determine compliance with the requirements specified in 3.4.2. Any nonconformance shall constitute failure to pass this test.

4.5.3 Linear flow progression test. With an inlet test liquid head of between 18 and 24 inches, the fuel flow control shall be operated with the metering knob set from the positions 1 thru 8, respectively. After the test liquid has been flowing for a minimum of 1 minute while the metering knob is set at position 1, the test liquid flow measurements in volume and time shall be taken to determine compliance with the requirements specified in 3.4.2.1. The same procedure shall be followed while the metering knob is set at the remaining positions 2 thru 8. Any nonconformance shall constitute failure to pass this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

4.5.4 Housing assembly test. The housing assembly as specified in 3.4.1 shall be operated as follows:

a. The housing assembly shall be set at a discharge fluid flow rate of 40 ± 4 cubic centimeters per minute. With this flow setting and at an inlet head as specified (see 4.5), the housing assembly shall be operated with the test liquid for 1 minute, and the liquid level in the housing assembly shall then be checked to determine compliance with the fuel level requirements of 3.4.1.a. Any nonconformance shall constitute failure to pass this test.

b. The discharge flow of test liquid in the above test shall be stopped, and the level and supply flow of the liquid in the housing assembly shall then be checked to determine compliance with fuel level and float assembly shutoff requirements of 3.4.1.b. Any nonconformance shall constitute failure to pass this test.

4.5.5 Body leak test. The strainer assembly, inlet, outlet, and overflow fittings, metering stem bushing, and shutoff valve seat shall be installed. The drain hole, open portion of the body, inlet, outlet, and overflow openings shall be sealed externally. The fuel flow control body shall then be pressurized with air at 10 pounds per square inch pressure through an opening in the seal over the open portion and submerged in a clear liquid to determine compliance with the no leak requirements specified in 3.4.1.1 and 3.4.1.2. Any nonconformance shall constitute failure to pass this test.

4.5.6 Nameplate paint test. The nameplate paint coat shall be exposed to an atmosphere of 100 percent relative humidity with a temperature between 50°F and 100°F for 72 hours, immersed in kerosene at a temperature between 110°F and 120°F for 10 days. The nameplate shall be removed and examined for peeling, and then rubbed 15 times with 2 fingers in a dry cloth, pressing moderately with a force of 3 to 5 lbs, to determine compliance with the paint requirements specified in 3.5.1. Any nonconformance shall constitute failure to pass this test.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or Commercial, as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Preservation application. The interior of each fuel control shall be cleaned by process C-1, thoroughly dried, and then fogged through one of the openings in the control with a preservative conforming to type P-10, grade 1 of MIL-P-116. The interior surfaces shall be completely covered with the preservative, and there shall be no collection of excess oil in the control.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

All openings into the control shall be protected with plastic plugs and cap thread protectors conforming to MIL-C-5501. The control, in an upright position, shall have its connecting nipple placed vertically on the flat portion of the right side and secured with minimum 0.0230-inch diameter annealed wire passing through the nipple and around the neck portion of the control.

5.1.1.2 Unit packing. Each fuel flow control shall be unit packed upright in a fiberboard box conforming to Grade V3c or B3S, of PPP-B-636. The inside box dimensions shall be 4 inches in length, 3 3/8 inches in width, and 4 3/4 inches in depth. Each box shall be closed in accordance with method V of PPP-B-636.

5.1.2 Commercial. The fuel flow controls shall be preserved in accordance with ASTM D 3951.

5.2 Packing. Packing shall be level A, B, or Commercial, as specified (see 6.2).

5.2.1 Level A packing. Forty fuel flow controls, preserved as specified in 5.1, shall be packed in a wood shipping container conforming to overseas type, style 1 of PPP-B-601. The inside container dimensions shall be 18 1/2 inches in length, 17 1/4 inches in width, and 10 1/2 inches in depth. Each shipping container shall be closed and strapped in accordance with the appendix of PPP-B-601.

5.2.2 Level B packing. Forty fuel flow controls, preserved as specified in 5.1, shall be packed in a fiberboard shipping container conforming to style RSC, type CF, class domestic, grade 275 of PPP-B-636. The inside container dimensions shall be 18 1/2 inches in length, 17 1/4 inches in width, and 10-1/2 inches in depth. Each shipping container shall be closed in accordance with method II of the appendix of PPP-B-636.

5.2.2.1 Weather-resistant fiberboard container. When specified (see 6.2), the shipping container shall be a grade V3c, V3s, or V4s fiberboard box fabricated in accordance with PPP-B-636 and closed in accordance with method III in the appendix of PPP-B-636.

5.2.3 Commercial packing. Fuel flow controls, preserved and packaged as specified in 5.1, shall be packed in accordance with ASTM D 3951.

5.3 Palletization. When specified (see 6.2), fuel flow control containers, packed as specified in 5.2, shall be palletized on a 4-way entry pallet in accordance with load type I or Ia of MIL-STD-147. Pallet type shall be type I (4-way entry), type II, type IV, or type V in accordance with MIL-STD-147. Pallets shall be fabricated from wood groups I, II, III, and IV of MIL-STD-731. Each prepared load shall be bonded with straps by means C and D or film bonding means F or G. Pallet pattern shall be Number 95 in accordance with the appendix of MIL-STD-147.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

5.4 Marking. In addition to any special marking required by the contract or purchase order, unit packs, shipping containers, and palletized unit loads shall be marked in accordance with MIL-STD-129 or ASTM D 3951, as applicable.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The control is intended to be used with the Burner Assembly Space Heater covered by MIL-B-2029 and Heaters, Space, Radiant Type, Portable, 45,000 BTU/Hr covered by MIL-H-13514.

6.2 Acquisition requirements. Acquisition documents must specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required. the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. When a first article is required (see 3.1, 4.3, and 6.3).
d. Levels of preservation and packing (see 5.1 and 5.2).
e. When weather-resistant fiberboard containers are required (see 5.2.2.1).
f. When palletization is required (see 5.3).
g. Acceptance criteria required (see 6.4).

6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of FAR 52.209. The first article should be a preproduction sample. The contracting officer should specify the appropriate type of first article and the number of units to be furnished. The contracting officer should also include specific instructions in all acquisition documents regarding arrangements for selection, inspection, and approval of the first article.

6.4 Acceptance criteria. The acceptance criteria below is recommended for use. The acceptance criteria as specified in the contract or purchase order shall be binding. Unless otherwise specified, the following acceptance criteria are in accordance with MIL-STD-105.

6.4.1 For component testing. An acceptable quality level (AQL), expressed in terms of defects per hundred units, of 4.0 is recommended.

6.4.2 For end item visual examination. An AQL, expressed in terms of defects per hundred units, of 2.5 for major defects and 6.5 for total (major and minor combined) defects is recommended.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

6.4.3 For end item dimensional examination. An AQL, expressed in terms of defects per hundred units, of 4.0 is recommended.

6.4.4 For packaging examination. An AQL, expressed in terms of defects per hundred units, of 2.5 is recommended.

6.4.5 For palletization examination. An AQL, expressed in terms of defects per hundred units, of 6.5 is recommended.

6.5 Subject term (key word) listing.

Stove, valve, fuel
Metering valve, control valve, fuel valve

6.6 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodians:
Army - GL
Navy - YD
Air Force - 99

Preparing activity:
Army - GL

(Project 4530-0045)

Review activities:
Air Force - 84
DLA - CS

User activity:
Navy - MC

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-C-43343C	CONTROL, FUEL, FLOW, OIL BURNER

3. NAME OF SUBMITTING ORGANIZATION

4. TYPE OF ORGANIZATION *(Mark one)*

- ☐ VENDOR
- ☐ USER
- ☐ MANUFACTURER
- ☐ OTHER *(Specify)*: _____

5. ADDRESS *(Street, City, State, ZIP Code)*

6. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

7. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY

U.S. ARMY NATICK RESEARCH, DEVELOPMENT
and ENGINEERING CENTER
ATTN: STRNC-ES
Natick, MA 01760-5014

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
U.S. Army Natick Research, Development
and Engineering Center
ATTN: STRNC-ES
Natick, MA 01760-5014

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:13Z
Check the source to verify that this is the current version before use.