INCH-POUND

MIL-P-53125/3(ME)
14 April 1992
SUPERSEDING
MIL-P-53045A(ME)
27 JUNE 1985

# MILITARY SPECIFICATION SHEET

## POWER PLANT, ELECTRIC,

## 10 KW, 400 HERTZ, AN/MJQ-25

The requirements for acquiring the product described herein shall consist of this specification sheet and the issue of the following specification listed in that issue of the Department of Defense Index of Specifications and Standards (DODISS) specified in the solicitation: MIL-P-53125.

1. APPLICABLE DOCUMENTS

1.1 Government drawings. The following Government drawings form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

DRAWINGS

ME

TA13226E5860 - Power Plant, Electric, AN/MJQ-25.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-FG, Fort Belvoir, VA 22060-5606.)

AMSC N/A FSC 6115

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:09Z
Check the source to verify that this is the current version before use.

## 2. REQUIREMENTS

2.1 Description. The power plant, AN/MJQ-25, shall be in accordance with TA13226E5860 and as specified herein and MIL-P-53125.

2.2 Government-furnished property. The following property in the quantities indicated will be furnished by the Government:

| Item No. | Description | Identification | Quantity for each AN/MJQ-25 |
|---|---|---|---|
| 1 | Chassis, trailer, 1-1/2 ton, 2 wheel, Model M103A3 | NSN 2330-00-141-8052 | 1 |
| 2 | Generator set, diesel-engine-driven, 10 kw, 400 hertz, DoD Model MEP-112A | NSN 6115-00-465-1027 | 2 |

3. QUALITY ASSURANCE PROVISIONS

3.1 Test conditions. The following preparation shall be made prior to testing the switch box assembly:

a. Cables running between the switch box assembly and the generator sets shall be installed to the switch box assembly rotary switch.
b. The free ends of the cables shall be attached to each generator set as follows:

(1) Cable wire marked L1 shall be attached to Phase A.
(2) Cable wire marked L2 shall be attached to Phase B.
(3) Cable wire marked L3 shall be attached to Phase C.
(4) Cable wire marked L0 shall be attached to neutral.

c. A 3-phase, 4-wire, 10 kw resistive load shall be connected to the output of the switch box.
d. Provide ground to ground terminal of switch box.

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 6115-A582



Source: https://assist.dla.mil -- Downloaded: 202610-22T22:09Z
Check the source to verify that this is the current version before use.