MIL-C-50814 (MU)
13 NOVEMBER 1970
SUPERSEDING
PA-PD-3065
6 February 1968

MILITARY SPECIFICATION

CDU - MISCELLANEOUS CANISTER PARTS

1. SCOPE

1.1 This specification covers the miscellaneous parts for one type of Loaded Canister designated as CDU.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-R-11470	-	Radiographic Inspection: Qualification of Equipment Operators and Procedures
MIL-I-45607	-	Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 202640-22T20:39Z
Check the source to verify that this is the current version before use.

MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

9228056 - Base Plate
9228058 - Spacer Internal, Forward
9228060 - Clip Assembly
9228063 - Opener Plate
9228082 - Pad, Saddle Plate
9228085 - Clip Assembly
9228087 - Pad, Retention Ring
9228091 - Tube Assembly
9228093 - Sleeve, Protective
9228095 - Spacer Monitor, Cable Bracket
9229424 - Spacer Internal, Rear
9234030 - Filler
9234031 - Plug
9235219 - Indicator Eye Assembly
9238870 - Opener Plate (Modified)

PUBLICATIONS

ARMY

ET-9230674 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

3.2 Parts.-The parts shall comply with all requirements specified on applicable drawings, all associated drawings, and with all requirements specified in applicable specifications.

3.3 Workmanship.-All parts and assemblies shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products, and other foreign matter. The cleaning method used shall not be injurious to any parts, nor shall the parts be contaminated by the cleaning agents.

3.4 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

3.5 Cavitation of plug for tube assembly (see dwg. 9231671) .-The plug for the tube assembly shall be free of internal voids in excess of .040 inch in width or diameter in the area running vertically between the two (2) .125 diameter holes, and horizontally between the bottom of the aforementioned holes and the .127 diameter hole and the .056 wide slot. In the event a plug contains more than one (1) void in the area previously described the plug shall be rejected if the voids are in a straight line with one another and the total sum of those voids exceeds .040."

3.6 Functioning Test.-When the indicator eye is submerged in freon up to the threads, the indicator glass shall be black; when the indicator is removed from freon, the glass shall be clear.

3.7 Pressure test.-The indicator eye assembly shall not leak (as evidenced by bubbles) when 60 psig air pressure is applied for 5 minutes to the indicator screen end, while the indicator eye end is submerged in freon.

3.8 Submersion (Filler and Plug Assembled, Dwgs. 9234030 and 9234031).-The filler and plug assembly shall submerge to the extent that not more than 1/4 inch of the assembly remains exposed to the atmosphere 60 seconds after being placed in a container of desensitizer (TCTFE). Test shall be performed as specified in 4.4.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 in order to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified within this specification.
b. Number of units of product inspected.
c. Results obtained, by code number, for all inspections performed.
d. Drawing, specification number and date, together with and identification and date of changes.
e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.
f. Number of items in the lot.
g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2 (see 6.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

The first article sample shall consist of ten (10) each of the applicable part. All parts and completed assemblies submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed.-Assemblies and components will be subjected by the Government to any or all the examinations or tests specified in this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection.-If any assembly or component fails to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Base Plate (see dwg. 9228056)

Categories	Defects	Method of Inspection	Defect Code
Critical: None defined			

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

Major:	AQL 1.00 Percent		
101.	Location of large hole	Gage	01001
102.	Pitch diameter of tapped hole(s)	Gage	01002
103.	Minor diameter of tapped hole(s)	Gage	01003
104.	Location of tapped holes	Gage	01004
105.	Location of countersunk holes	Gage	01005
106.	Locating lines missing	Visual	01006
Minor:	AQL 2.50 Percent		
201.	Diameter of large hole	Gage	01007
202.	Daimeter of countersunk hole(s)	Gage	01008
203.	Diameter of plate	Gage	01009
204.	Protective finish missing or damaged	Visual	01010
205.	Evidence of poor workmanship (see 3.3)	Visual	01011

4.3.2.2 Spacer Internal, Forward (see dwg. 9228058)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.50 Percent		
201.	Length	Gage	02001
202.	Width	Gage	02002
203.	Thickness	Gage	02003
204.	Evidence of poor workmanship (see 3.3)	Visual	02004

4.3.2.3 Spacer Internal, Rear (see dwg. 9229424)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

Minor:		AQL 2.50 Percent	
201.	Length	Gage	12001
202.	Width	Gage	12002
203.	Thickness	Gage	12003
204.	Diameter of hole	Gage	12004
205.	Chamfer(s) missing	Visual	12005
206.	Evidence of poor workmanship (see 3.3)	Visual	12006

4.3.2.4 Clip Assembly (see dwg. 9228060).

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Rivet(s) missing or loose	Visual/Manual	04001
Minor:	AQL 2.50 Percent		
201.	Location of countersunk holes	Gage	04002
202.	Diameter of countersunk holes	Gage	04003
203.	Width at narrow end	Gage	04004
204.	Protective finish missing or damaged	Visual	04005
205.	Evidence of poor workmanship (see 3.3)	Visual	04006

4.3.2.5 Opener Plate (see dwg. 9228063)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 1.00 Percent		
101.	Location of small holes	Gage	05001
102.	Location of countersunk hole	Gage	05002
103.	Diameter of countersunk hole	Gage	05003
104.	Countersunk missing	Visual	05004
105.	Length of cutout(s)	Gage	05005
106.	Location to cutout(s)	Gage	05006

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

Minor:	AQL 2.50 Percent		
201.	Diameter of small holes	Gage	05007
202.	Diameter of large hole (min.)	Gage	05008
203.	Location of large hole	Gage	05009
204.	Length	Gage	05010
205.	Thickness	Gage	05011
206.	Protective finish missing or damaged	Visual	05012
207.	Evidence of poor workmanship (see 3.3)	Visual	05013

4.3.2.6 Pad, Saddle Plate (see dwg. 9228082)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.00 Percent		
201.	Profile of pad	Gage	06001
202.	Evidence of poor workmanship (see 3.3)	Visual	06002

4.3.2.7 Clip Assembly, (See dwg. 9228085)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Rivets loose or missing	Visual/Manual	07001
Minor:	AQL 1.00 Percent		
201.	Diameter of large hole	Gage	07002
202.	Evidence of poor workmanship (see 3.3)	Visual	07003

4.3.2.8 Pad, Retention Ring (see dwg. 9228087)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

Major: None defined

Minor:		AQL 1.00 Percent	
201.	Profile of pad	Gage	08001
202.	Evidence of poor workmanship (see 3.3)	Visual	08002

4.3.2.9 Tube Assembly (see dwg. 9228091)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 1.00 Percent		
101.	Pitch diameter of thread	Gage	09001
102.	Major diameter of thread	Gage	09002
103.	Depth of spanner wrench holes (max.)	Gage	09003
104.	Length to slot from thread end (min.)	Gage	09004
105.	Length of plug	Gage	09005
106.	Total length	Gage	09006
107.	Red marking missing from slotted hole	Visual	09012
Minor:	AQL 1.00 Percent		
201.	Adhesive missing	Visual	09010
202.	Evidence of poor workmanship (see 3.3)	Visual	09011

4.3.2.10 Sleeve, Protective (see dwg. 9228093)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Outside diameter	Gage	10001
102.	Inside diameter	Gage	10002
103.	Total length	Gage	10003
104.	Pliability of material	Manual	10004
Minor:	AQL 0.65 Percent		
201.	Evidence of poor workmanship (see 3.3)	Visual	10005

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

4.3.2.11 Spacer, Monitor, Cable Bracket (see dwg. 9228095)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	None defined		
Minor:	AQL 4.00 Percent		
201.	Length	Gage	11001
202.	Width	Gage	11002
203.	Location of holes	Gage	11003
204.	Distance between holes	Gage	11004
205.	Diameter of holes	Gage	11005
206.	Chamfer missing	Visual	11006
207.	Protective finish missing or damaged	Visual	11007
208.	Evidence of poor workmanship (see 3.3)	Visual	11008

4.3.2.12 Indicatory Eye Assembly (see dwg. 9235219)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 1.00 Percent		
101.	Thickness of flange	Gage	14001
102.	Pitch diameter of thread	Gage	14002
103.	Indicator glass broken or damaged	Visual	14003
104.	Indicator screen missing or damaged	Visual	14004
105.	Length of hole, min.	Gage	14005
106.	Width of hole, min.	Gage	14006
Minor:	None defined		

4.3.2.13 Filler (see dwg. 9234030)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

Major:	AQL 1.00 Percent		
101.	Length, min.	Gage	16001
102.	Width, min.	Gage	16002
103.	Diameter of hole, max.	Gage	16003
104.	Overall thickness	Gage	16004
105.	Location of hole	Gage	16005
106.	Length of shoulder, max.	Gage	16006
107.	Depth of shoulder	Gage	16007
108.	Small holes missing	Visual	16008
Minor:	AQL 0.65 Percent		
201.	Evidence of poor workmanship (see para. 3.3)	Visual	16009

4.3.2.14 Plug (see dwg. 9234031)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Outside diameter, min.	Gage	17001
102.	Thickness, min.	Gage	17002
103.	Inside diameter, max.	Gage	17003
104.	Location of hole	Gage	17004
Minor:	AQL 0.65 Percent		
201.	Evidence of poor workmanship (see para. 3.3)	Visual	17005

4.3.2.15 Opener Plate (Modified) (See dwg. 9238870)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 1.00 Percent		
101.	Location of small holes	Gage	18001
102.	Location of countersunk hole	Gage	18002
103.	Diameter of countersunk hole	Gage	18003
104.	Length of cutout(s)	Gage	18004
105.	Location to cutout(s)	Gage	18005

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.50 Percent		
201.	Diameter of small holes	Gage	18006
202.	Diameter of large hole (min)	Gage	18007
203.	Location of large hole	Gage	18008
204.	Length	Gage	18009
205.	Thickness	Gage	18010
206.	Protective finish missing or damaged	Visual	18011
207.	Evidence of poor workmanship (see 3.3)	Visual	18012

4.3.3 Testing

4.3.3.1 Dimensional control of stamped parts.-In place of the normal sampling associated with the Classification of Defects, and the the approval of the Contracting Officer, a sample of at least ten (10) parts maybe dimensionally inspected to quality the tool used in the stamping process for use in production. In addition, a random sample of five (5) parts shall be selected from the last portion of each hour's production for dimensional inspection as a control of the tool during production.

If any defective parts are found during qualification of the tool, the tool producing the defective part shall not be used in production.

If any defective parts are found when inspection is sperformed for control of the tool, the tool producing the defective part shall be removed from production. Further, that portion of production since the last tool control check shall be returned to the contractor for corrective action.

All tools removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the contracting officer to substantiate the request.

4.3.3.2 Dimensional control of molded parts.-In place of the normal sampling associated with the Classification of Defects, and with the approval of the Contracting Officer, and after a curing time for the parts has been approved (see Note 1), a sample of three (3) parts (as molded) from each cavity may be dimensionally inspected to qualify a new or reworked cavity for use in production or as a control of each cavity during production.

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:39Z
Check the source to verify that this is the currentversion before use.

The inspection of the parts shall be performed only when the curing time for the parts has been reached. The inspection for control of each cavity during production shall be performed on the above quantities from each cavity after production of each 500 parts or at the end of each shift, providing the number of parts produced during that shift is less than 500 parts. Of the three (3) samples, one (1) sample shall be the last part produced. Parts that fail to comply with dimensional requirements after dimensional stability has been attained shall be classed defective.

If any defective parts are found during qualification of the cavity, the cavity producing the defective part will not be used in production. If any defective parts are found when inspection is performed for control of the cavity, the cavity producing the defective part shall be removed from production. Further, that portion of production since the last control check shall be returned to the contractor for corrective action.

All cavities formerly removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test as above. The contractor may request a change of inspection frequency providing he presents objective evidence to substantiate the request to the Contracting Officer.

(NOTE 1) - In establishing a curing time, dimensionally check ten (10) parts from each cavity at fifteen (15)-minute intervals until dimensional stability is attained. The curing time will be from the time the parts comes out of the mold until dimensional stability is attained. The inspection data used in determining the curing time shall be sent to Picatinny Arsenal, SMUPA-ND8. If any new change in material, cycle time, a reworked cavity, or new cavity is used, a new curing time shall be submitted for approval.

4.3.3.3 X-ray of Plug (see 3.5), Critical Defect, Code No. 13001.-Each plug shall be x-rayed for compliance with the specified requirement. Any plug which fails to comply with the applicable requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.1.

4.3.3.4 Functioning Test, Major Defect, Defect Code 15001.- This test shall be performed 100% using the equipment as specified in 4.3.4. Any item not meeting the requirements of 3.6 shall be classified defective and removed from the lot.

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:39Z
Check the source to verify that this is the currentversion before use.

4.3.3.5 Pressure Test, Major Defect, Defect Code 15002.-One hundred twenty five (125) items from each lot shall be subjected to this test. If one, or more items fail to meet the requirements as specified in 3.7 the lot shall be rejected. The test shall be performed as specified in 4.4.2.

4.3.3.6 Submersion, Major Defect, Defect Code 19001 (see 3.8).-This test shall be performed 100 percent. Any filler and plug assembly which fails the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.3, using equipment in accordance with 4.3.4.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 9230674 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures

4.4.1 X-ray of Plug.-The plug shall be positioned on a fixture as specified on the equipment list. Each plug shall be identified as to its position on the radiograph and the exposure made. Examinations of the radiographs shall be made for compliance with the applicable requirement. Radiographic equipment, operators and procedures shall be qualified in accordance with MIL-R-11470. This is a non-destructive test; plugs so tested may be returned to the lot, if acceptable.

4.4.2 Pressure Test.-The indicator eye assembly shall be assembled to a fixture as shown on the Equipment List and tested for compliance with 3.7. Parts so tested shall not be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

4.4.3 Submersion.-The assembly shall be placed upright in a container filled with at least 4 inches of desensitizer (TCTFE), and at the specified time the height of exposure shall be measured. Any assembly which fails to comply with the requirement specified in 3.8 shall be classed defective. This is a non-destructive test.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level C.-The applicable parts shall be preserved and packaged in accordance with MIL-STD-1169.

5.2 Packing

5.2.1 Level C.-The applicable parts, preserved and packaged as specified in 5.1.1, shall be packed for shipment in accordance with MIL-STD-1169.

5.3 Marking.-Marking of the carton shall comply with MIL-STD-1169.

5.4 Shipping.-When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of First Article Samples.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the number of drawings for Federal Stock numbers of exisiting equipment deisgns, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army Designs, the contractor shall comply with and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor-prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes, and operating and calibration instructions be properly depicted in

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor deisgns may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit one copy of final designs as a rolled set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor designs.-All submitted designs shall contain a reference to the applicable five-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects clssified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND8. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1345-A-312

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:39Z
Check the source to verify that this is the current version before use.