MILITARY SPECIFICATION

PROBE ASSEMBLY, BATTERY TEMPERATURE

1. SCOPE

1.1 Scope. This specification covers the requirements for a battery temperature probe assembly consisting of a bushing and a sensor assembly which houses a thermistor-type sensor and a pressure valve.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of the specification to the extent specified herein.

SPECIFICATIONS

Military

MIL-C-13486	-	Cable, Special Purpose, Electrical.
MIL-B-11188	-	Batteries, Storage: Lead Acid.

STANDARDS

Military

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-202	-	Test Methods for Electronic and Electrical Component Parts.
MS-35000-1	-	Batteries, Storage, Lead-acid (dry charged).
MS-35000-2	-	Batteries, Storage, Lead-acid (wet batteries).

FSC-6685

Source: https://assist.dla.mil -- Downloaded: 202640-23T01:26Z
Check the source to verify that this is the current version before use.

DRAWINGS

Army Part No.
12250318 - Probe Assembly, Battery.
12250318-1 - Sensor Assembly.
12250318-2 - Bushing.

(Copies of specifications, standards, drawings, and publications required by supppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

NATIONAL BUREAU OF STANDARDS
Handbook H28 - Screw-Thread Standards for Federal Services.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, D. C. 20402.)

3. REQUIREMENTS

3.1 First article. A first article shall be produced and furnished for testing prior to the manufacture of probe assemblies in production quantities. The First Article(s) shall pass testing specified herein (see 4.2). All items furnished to the Government under this specification shall be representative of those which have passed First Article Testing and inspection. Approval of the first article samples shall not relieve the contractor of his responsibility to provide probe assemblies in production quantities that are fully representative of the first article samples. Changes or deviations of the production units from the first article sample shall be subject to approval of the contracting officer.

3.2 Materials. Material shall be as specified herein, applicable specifications, and on applicable drawings. Materials not specifically designated shall be sutiable for use in units operating over an ambient temperature range from minus 65° to plus 250°F without any change in physical or dimensional properties that would result in operation of the units falling outside of the limits specified herein. All materials shall be capable of being immersed into a fully charged battery (electrolyte) without physical damage, deformation and/or property breakdown.

3.3 Design and Construction.

3.3.1 Use of dissimilar metals. Except where necessary to complete an electrical circuit, contact between dissimilar metals, which would encourage galvanic action, shall be avoided. Where such contact is not necessary to complete an electrical circuit, but is otherwise unavoidable, parts shall be insulated.

Source: https://assist.dla.mil -- Downloaded: 202610-23T01:26Z
Check the source to verify that this is the current version before use.

3.3.2 Interchangeability. All units shall be mechanically and electrically interchangeable with all other such units of the same Part Number.

3.3.3 Threaded parts. All screw threads shall conform to Handbook H28 (see 2.2). The form, number per inch, and class of threads shall be as specified on applicable standards or drawings.

3.3.4 Cable. Unless otherwise specified, all external cable shall conform to Specification MIL-C-13486, Type I, Class A.

3.3.5 Probe assembly. The probe assembly shall consist of a bushing conforming to Army drawing No. 12250318-2, capable of fitting into the fill port of batteries MS 35000-1 (Type 2HN) and MS 35000-3 (Type 6TN); and a sensor assembly conforming to Army drawing No. 12250318-1, which contains a resistance-type thermistor (negative temperature coefficient). The thermistor shall be capable of functioning within the resistance limits specified in Table I at each of the ambient temperature levels listed.

Table I. Zero Power Resistance (see 6.3)

Temperature °F	(°C)	Maximum Ohms (Ω)	Minimum Ohms (Ω)
40	(4.4)	1202.4	1117.3
77	(25)	510.0	490.0
104	(40)	296.6	278.0
140	(60)	154.2	130.0

3.3.5.1 Locking. The sensor assembly shall be capable of locking in a fixed position into the bushing with not more than a 180° turn.

3.3.5.2 Check valve. The sensor assembly shall incorporate a vent with a check valve to permit the escape of gases from the battery. The check valves shall not leak more than two drops of water in ten seconds when under a four foot head of water and shall be designed to open before internal pressure reaches 0.5 pounds per square inch (psi) in excess of the external pressure.

3.3.5.3 Measurement accuracy. The sensor assembly design shall be such as to make measurement accuracy independent of immersion depth (0.25 to 0.60 inches). Resistance measurements recorded shall not differ by more than 5 ohms when tested in accordance with 4.5.2.5.

3.3.5.4 Gaskets. The probe assembly shall incorporate two water sealant gaskets. One gasket shall be used between the Bushing and the top of the battery. The second gasket shall be used between the Sensor Assembly and the Bushing. (See Ordnance Drawing No. 12250318). All gaskets and/or sealants shall be in accordance with the battery cap requirements of MIL-B-11188. As an option to separate gaskets, an equivalent sealant feature may be incorporated into the design of the Bushing and Sensor Assembly.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.4 Performance.

3.4.1 Electrical characteristics.

3.4.1.1 Resistance-temperature characteristics. The sensor assembly shall exhibit the temperature vs. resistance characteristics required in Table I when tested in accordance with 4.5.2.1.

3.4.1.2 Dissipation factor. The probe dissipation factor shall not be less than 0.016 watts per degree Fahrenheit when tested in accordance with 4.5.2.2. The probe assembly shall subsequently meet the requirements of 3.4.1.1.

3.4.1.3 Electrical leakage. The probe assembly shall meet the requirements of 3.4.1.1 after having been tested in accordance with 4.5.2.3.

3.4.1.4 Temperature-resistance stabilization. The time required for the resistance to stabilize shall not exceed two minutes from the moment the probe is immersed in a temperature bath when tested in accordance with 4.5.2.4.

3.4.2 Environmental Characteristics.

3.4.2.1 Thermal resistance. The probe shall be capable of withstanding ambient air temperatures from minus 65°F to plus 250°F for a sustained period without evidence of damage such as cracking or melting (see 4.5.3.1).

3.4.2.2 Vibration. The probe shall remain intact in the battery fill port as installed and shall not sustain damage when subjected to a vibration test (see 4.5.3.2).

3.4.2.3 Shock. The probe shall remain intact in battery fill port and shall not sustain damage when subjected to the shock test as specified in 4.5.3.3.

3.4.2.4 Endurance. When installed in the battery fill port and connected in circuit under loading conditions and duration as specified in 4.5.3.4 the probe shall show no signs of damage, deformation or deterioration.

3.4.2.5 Check valve leakage. The check valve shall be tested for leakage in accordance with 4.5.3.6 in order to meet the requirements of 3.3.5.2.

3.4.3 Mechanical.

3.4.3.1 Bushing-Sensor Assembly Locking Torque. The average torque required to remove the sensor assembly from the bushing shall not be less than 6 in-lbs nor more than 8 in-lbs.

3.5 Marking. The cap of each sensor assembly shall be marked with the following data:

PROBE ASSEMBLY
MANUFACTURER'S IDENTIFICATION
ARMY PART NUMBER
NATIONAL STOCK NUMBER (NSN)

Source: https://assist.dla.mil -- Downloaded: 202640-23T01:26Z
Check the source to verify that this is the current version before use.

3.6 Workmanship. Workmanship shall be of a quality which will assure a product free of burrs, rust, scratches, chips, sharp edges, loose or defective connectors, cracked insulation, faulty soldering or other defects which affect serviceability or appearance.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First Article Testing. The First Article sample consisting of four (4) of the units proposed to be furnished shall be submitted for testing in order to conform to 3.1. First Article testing shall be conducted by the contractor under government surveillance and shall consist of examination and classification of defects specified in 4.3.2.2 and testing specified in Table II in the order listed therein.

4.2.1 Failure. Failure of a First Article sample to pass any of the tests specified herein may be cause for the Government to refuse to witness additional testing until the faults revealed by the tests have been corrected.

Table II. Order of First Article Testing

Sample	Paragraph	Test
All 4	4.5.2.1	Temperature-Resistance Characteristics (77°F only)
All 4	4.5.2.2	Dissapation Factor
1 and 2	4.5.2.3	Electrical Leakage
1 and 2	4.5.2.4	Temperature-Resistance Stabilization
3	4.5.2.5	Immersion Depth
1 and 2	4.5.3.1	Thermal Resistance Test
3	4.5.3.2	Vibration
3	4.5.3.3	Shock
4	4.5.3.4	Endurance
3	4.5.3.5	Check Valve Leakage
1 and 2	4.5.4.1	Bushing-Sensor Assembly Locking Torque
All 4	4.5.2.1	Temperature-Resistance Characteristics

4.3 Acceptance Inspection.

4.3.1 Zero power resistance. Each probe assembly shall be checked for conformance to zero power resistance requirements in accordance with 4.5.2.1 (77°F only).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

4.3.2 Sampling for units.

4.3.2.1 Lot formation. Unless otherwise specified (see 6.2), a lot shall consist of all units of one part number, from an identifiable production period, from one manufacturer, submitted at one time for acceptance.

4.3.2.2 Sampling for acceptance examination. Samples for acceptance examination shall be selected in accordance with Standard MIL-STD-105.

4.3.2.3 Sampling for acceptance testing. Samples for acceptance testing shall be selected in accordance with inspection level S-3 of Standard MIL-STD-105.

4.3.3 Examination inspection for units.

4.3.3.1 Acceptable quality levels. Each sample selected in accordance with 4.3.2.2 shall be examined for conformance to the following acceptable quality levels (AQL) on the basis of percent defective:

Classification	AQL
Major	1.0
Minor	2.5

4.3.3.2 Classification of defects. For examination purposes defects shall be classified as follows:

Categories	Defects	Inspection Method
Critical:	None Defined	
Major:		
101	Length of Probe	Dimensional
102	Dimensions not affecting interchangeability	Dimensional/ Functional
103	Battery Fillport Fitting	Functional
Minor:		
201	Dimensions not affecting interchangeability	Dimensional
202	Improper of Illegible Marking	Visual
203	Faulty Workmanship	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

4.3.4 Testing Inspection for units. Samples selected in accordance with 4.3.2.3 shall be subjected to the tests specified in Table III using an AQL of 2.5 on the basis of percent defective.

Table III. Acceptance Tests

Paragraph	Test
4.5.2.1	Temperature-Resistance Characteristics (77°F only)
4.5.4.1	Bushing-Sensor Assembly Locking Torque

4.4 Control tests.

4.4.1 Sampling for control tests. Control test samples shall be selected at the rate of 3 of every 1000 units produced except that not less than 3 nor more than 6 units shall be selected in any 30-day period.

4.4.2 Unit control testing. Units selected in accordance with 4.4.1 shall be examined for the defects specified in 4.3.3.2, and subsequently tested as specified in table IV.

4.4.3 Failure. Failure of a control test sample to pass any specified test may be cause for the Government to refuse to accept subsequent lots until it has been proved to the satisfaction of the Government that the faults revealed by the test have been corrected.

Table IV. Control tests

Sample	Paragraph	Test
All	4.5.2.1	Temperature-Resistance Characteristics
All	4.5.2.2	Dissipation Factor
1	4.5.3.5	Check Valve Leakage
2	4.5.2.4	Temperature-Resistance Stabilization
2	4.5.2.5	Immersion Depth
3	4.5.2.3	Electrical Leakage

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

4.5 Test procedures.

4.5.1 Inspection standards.

4.5.1.1 Temperature standard. The contractor shall provide a standard of temperature measurement in the form of a precision resistance thermometer or equal for standardizing the calibration and inspection equipment used in the manufacture of the temperature elements. The standard shall cover the full operating range of the element and shall provide an accuracy in temperature to within ± 0.05°C. Copies of certificates of accuracy for the standard used, issued by a competent authority within one year prior to each time it is used on the contract, shall be furnished the contracting officer.

4.5.1.2 Temperature measurements. The accuracy of all temperature measuring equipment used for the calibration and inspection of the temperature elements shall be maintained at all times to within ± 0.05°C of the standard. The measuring equipment shall be calibrated against the standard specified in paragraph 4.5.1.1 above, before the beginning of the inspection, and at regular monthly intervals thereafter.

4.5.1.3 Temperature baths. Temperature baths shall be of a neutral liquid that will not affect the calibration of the temperature elements tested. The baths shall be thoroughly stirred so that any temperature gradients between the temperature measuring equipment and the elements under test do not exceed 0.05°C. The drift of the temperature of the baths shall not exceed 0.1°C per minute. The bath shall be provided for temperature covering the range from 140°C to -60°C. The resistance of the temperature bath, measured between two electrodes spaced a distance equal to the length of the body of the temperature element, shall be maintained at a value of at least 500 times of the resistance of the element at the testing temperature, under all testing conditions.

4.5.1.4 Temperature chambers. If an air testing chamber is to be used, the air in the chamber shall be thoroughly mixed and circulated over the element being tested. Temperature gradients within the measuring space in the chamber shall not exceed 0.5°F per minute. The chamber shall be suitable for operating at any point in the temperature range from -65°F to 200°F.

4.5.1.5 Resistance measurements. Resistance measuring equipment shall be available in the form of a precision Wheatstone Bridge, electronic bridge, precision potentiometer, or by equivalent means of measuring the resistance of the element to any accuracy with ± 0.1 percent of the resistance measured.

4.5.1.6 Electrical measurements. Voltage or current measuring instruments shall be available in the form of direct current voltmeters and ammeters capable of determining the quantities measured to an accuracy of ± 0.5 percent of the quantity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

4.5.2 Electrical tests.

4.5.2.1 Temperature-resistance characteristics. To determine conformance to 3.4.1.1, the end of the probe shall be immersed to a depth of 0.5 ± 0.1 inches into a stabilized temperature bath as provided by 4.5.1.3. Zero power resistance shall be recorded at each of the following temperatures:

140°F	(60°C)
104°F	(40°C)
77°F	(25°C)
40°F	(4.4°C)

4.5.2.2 Dissipation factor. To determine conformance to 3.4.1.2 the following shall be performed: Measure and record the sensor zero power resistance (Rt_1, below). The probe shall then be connected into a circuit as shown in Figure 1. The end of the probe shall then be immersed to a depth of 0.6 ± 0.1 inches into a temperature bath as provided by 4.5.1.3 which is stabilized at 77°F. Adjust milliammeter (I) to 0.0350 ± .0005 amperes. When readings stabilize, record I and voltage (V). Then calculate the Dissipation Constant (DC) as follows:

(1) Plot a zero resistance-temperature curve for the specimen under test at the following temperatures, using the temperature bath provided in 4.5.1.3: 40°F, 60°F, 77°F, 90°F, 104°F and 140°F. Use values along curve for (Rt_x, below).

(2) Determine Thermistor Resistance (Rt_2):

$$Rt_2 = \frac{V}{I - \frac{V}{R_1}}$$

(3) Determine Sensor Dissipation (Pt):

$$Pt = \frac{V^2}{Rt_2}$$

(4) Determine Sensor Element Temperature Rise (Δt):

By interpolation of the resistance-temperature curve described above, determine the temperature of the thermistor, T_2.

Rt_1	T_1
Rt_2	T_2
Rt_x	T_x

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

Where:

T_1 = Temperature of bath ($77^{\circ}F$)

Rt_1 = Zero power resistance of the Thermistor at $77^{\circ}F$

T_2 = Temperature of the Thermistor at Rt_2

Rt_2 = Resistance of Thermistor under power load

T_x = Temperature taken from resistance-temperature curve, where $T_x - T_1$ is not greater than $10^{\circ}F$.

Rt_x = Resistance of thermistor at temperature T_x

R_1 = External parallel resistor (See Figure 1)

Then Δt (change in temperature) by calculation:

$$\Delta t = T_2 - T_1$$

OR

$$\Delta T = \frac{Rt_1 - Rt_2}{Rt_1 - Rt_x} \quad (T_x - T_1)$$

(Use one equation to check the other)

(5) Dissipation Constant:

$$D.C. = \frac{Pt}{\Delta t}$$

4.5.2.3 Electrical leakage. To determine conformance to 3.4.1.3, immerse the probe assembly into a 5 percent solution of slat water for four hours avoiding wetting of conductor wires. Apply 500 Volts Direct Current between each probe conductor and the grounded salt solution for 15 seconds. The probe shall subsequently meet the requirements of 3.4.1.1.

4.5.2.4 Temperature-resistance stabilization. To determine conformance to 3.4.1.4 the temperature bath (see 4.5.1.3) shall be adjusted until its temperature is stabilized $20^{\circ} \pm 2^{\circ}F$ above air ambient. The end of the probe shall then be immersed 0.5 ± 0.1 inches and the time of immersion recorded. The resistance of the sensor shall be monitored from the time of immersion until the time of resistance stabilization ($\pm$ 2 ohms). Total time to resistance stabilization shall be calculated and recorded.

Source: https://assist.dla.mil -- Downloaded: 202610-23T01:26Z
Check the source to verify that this is the current version before use.

4.5.2.5 Measurement accuracy. To determine conformance to 3.3.5.3, the temperature bath (see 4.5.1.3) shall be stabilized at 120° ± 2°F. The end of the probe shall then be immersed to a depth of 0.25 inches for five minutes. At the end of the five minute period the zero power resistance shall be recorded. The process shall then be repeated with the probe immersed to a depth of 0.6 inches. The two resistance recordings shall be compared and their differences recorded in ohms.

4.5.3 Environmental tests.

4.5.3.1 Thermal resistance test. To determine conformance to 3.4.2.1 the probe assembly shall be placed in an ambient air temperature of minus 65° ± 2°F for 2 hours. At the end of the cooling period, the probe assembly shall be removed and immediately placed in an oven at an ambient air temperature of plus 250° ± 5°F for 90 minutes. The plugs shall then be removed and inspected for evidence of damage such as cracking or melting. The probe assembly shall subsequently meet the requirements of 3.4.1.1.

4.5.3.2 Vibration. To determine conformance to 3.4.2.2, the probe assembly shall be securely mounted into a battery fillport (MS-35000-1 or MS-35000-2) and shall be subjected to the test specified in Method 201 of MIL-STD-202. The probe assembly shall subsequently meet the requirements of 3.4.1.1.

4.5.3.3 Shock. To determine conformance to 3.4.2.3 the probe assembly shall be securely mounted in a manner indicative of its intended use, in a shock machine and subjected to the test specified in Method 213, Test Condition A, of MIL-STD-202. The probe assembly shall subsequently meet the requirements of 3.4.1.1 and 3.4.3.1.

4.5.3.4 Endurance. To determine conformance to 3.4.2.4, the probe assembly shall be mounted into the fillport of a fully charged battery at an ambient temperature of plus 65°F to 75°F and a specific gravity of 1.290 (Battery per MS-35000-1 or MS-35000-2). The battery with probe assembly shall be connected in circuit as shown in Figure 2. The voltage shall be adjusted until (I) reads 0.035 ± 0.0005 amperes. The battery and probe assembly shall remain under this loading condition for 720 hours. The specific gravity shall be measured every 72 hours and the battery shall be recharged when the specific gravity falls to or below 1.270. The sensor assembly shall be loosened from and securely tightened to the bushing once every 24 hours. The probe assembly shall subsequently meet the requirements of 3.4.1.1 and 3.4.3.1.

4.5.3.5 Check valve leakage. To determine conformance to 3.4.2.5 the probe assembly shall be placed in an ambient air temperature of minus 65° ± 5°F for 2 hours. At the end of the 2 hour period it shall be removed and immediately placed in an oven at an ambient temperature of 185° ± 5°F for 90 minutes. The probe assembly shall then be removed from the oven and inspected for evidence

Source: https://assist.dla.mil -- Downloaded: 202640-23T01:26Z
Check the source to verify that this is the current version before use.

of damage such as melting or cracking. After a cooling period of one hour, the probe assembly shall be inserted in a fixture arranged so that water pressure can be applied on the upper side and an air pressure on the lower side. The upper side of the probe assembly shall be subjected to water pressure which exceeds the air pressure on the lower side by 1.75 psi (water head of four feet with air pressure at 1 atmosphere). The number of drops of water that leak through the probe assembly and the time required therefore shall be recorded. The water pressure shall then be released and the air pressure on the lower side increased to 0.5 psi above the pressure existing on the upper side. The probe assembly shall subsequently meet the requirements of 3.4.1.1 and 3.4.3.1.

4.5.4 Mechanical.

4.5.4.1 Bushing-sensor assembly locking torque. To determine conformance to 3.4.3.1, the probe assembly shall be securely mounted into a battery fillport. A torque shall be gradually applied to the sensor assembly until it is unlocked from the bushing. The torque required shall be recorded. This procedure shall be repeated ten times. The sum of the ten readings shall be divided by ten. The resulting average torque shall fall within the 6 to 8 in. - lb. range.

4.6 Inspection of preparation for delivery.

4.6.1 Materials and processes. The Government inspector shall, at unscheduled intervals, inspect all materials and processes involved in the preparation for delivery, to determine conformance to the requirements of section 5. Any evidence of deviation from specified requirements shall be cause, at the option of the Government, for refusal to conduct further inspection until objective evidence has been provided by the contractor that corrective action has been taken.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packaging, packing, and marking. Preservation, packaging, packing, and marking for the desired level of protection shall be in accordance with the applicable packaging standard or packaging data sheet specified by the procuring activity (see 6.2).

6. NOTES

6.1 Intended use. The battery temperature probe assembly is used to control the charging voltage in the vehicle generating system. The sensor will serve as a variable input resistance to the solid state voltage regulator. As the temperature of the battery electrolyte increases, the charging voltage of the generating system will decrease. The charging voltage will increase as the electrolyte temperature decreases. The probe assembly will fit into either wet or dry-charged battery fillports.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

6.2 Ordering data. Procurement documents should specify the following as a minimum:

a. Title
b. Military Part Number (Army)
c. National Stock Number (NSN)
d. Applicable drawing
e. First Article Testing (see 4.2)
f. Special lot sizes for inspection (4.3.2.1)
g. Selection of applicable packaging standard or packaging data sheet (see 5.1)

6.3 Definitions.

Zero Power Resistance - Resistance measured with zero watts dissipation.

Custodian:
Army - AT

Preparing Activity:
Army - AT

Preparing No. 6685-A548

Source: https://assist.dla.mil -- Downloaded: 202640-23T01:26Z
Check the source to verify that this is the currentversion before use.

DISSAPATION CONSTANT
TEST CIRCUIT




FIGURE 1

Source: https://assist.dla.mil -- Downloaded: 202640-23T01:26Z
Check the source to verify that this is the current version before use.

ENDURANCE
TEST CIRCUIT




FIGURE 2

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

MIL-P-62224(AT)

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.