MIL-C-29153A(YD)
14 February 1983
SUPERSEDING
MIL-C-29153(YD)
19 August 1975

MILITARY SPECIFICATION

COMPACTOR, SANITARY LANDFILL, SELF-PROPELLED, COMMERCIAL

This specification is approved for use by the Naval Facilities Engineering Command, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers commercial, self-propelled, sanitary landfill compactors specifically designed to crush, compact, move, and cover refuse and other solid wastes.

1.2 Classification. Compactors shall be of the following types, as specified (see 6.2.1).

Type I - 36,000 pounds minimum without ballast.
Type II - 55,000 pounds minimum without ballast.

2. APPLICABLE DOCUMENTS

2.1 Government documents

2.1.1 Specifications, standards and handbooks. Unless otherwise specified (see 6.2.1), the following specifications, standards, and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATION

MILITARY

MIL-R-3075 - Rollers, Motorized, Road, Diesel- or Gasoline-Engine-Driven, Packaging of.

Beneficial comments (recommendations, additions, deletions) and any pertinent data that may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 3895

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:45Z
Check the source to verify that this is the current version before use.

STANDARD

FEDERAL

FED-STD-595 - Color.

(Copies of specifications, standards, handbooks, drawings, and publications required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents form a part of this specification to the extent specified herein.

DEPARTMENT OF LABOR (DoL)
OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA)

Occupational Safety and Health Standards.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

2.2 Other publications. The following document forms a part of this specification to the extent specified herein. The issues of the documents that are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 Description. The landfill compactor, herein referred to as the compactor, shall consist essentially of a steel articulated frame, two axles, steel compacting drums, diesel engine, power train, enclosed all-weather operator's cab, and a hydraulically actuated leveling blade.

3.2 First article. When specified (see 6.2.1), the contractor shall furnish one compactor for first article inspection and approval (see 4.2.1 and 6.3).

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:45Z
Check the source to verify that this is the current version before use.

3.3 Materials. Materials used shall be free from defects that would adversely affect the performance or maintainability of individual components or of the overall assembly. Materials not specified herein shall be of the same quality used for the intended purpose in commercial practice. Unless otherwise specified herein, all equipment, material, and articles incorporated in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. The term "recovered materials" means materials that have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. None of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification unless otherwise specified.

3.4 Standard commercial product. The compactor shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer's standard commercial product. Additional or better features that are not specifically prohibited by this specification, but are a part of the manufacturer's standard commercial product, shall be included in the compactor being furnished. A standard commercial product is a product that has been sold or is being currently offered for sale on the commercial market through advertisements or manufacturer's catalogs, or brochures and represents the latest production model.

3.5 Interchangeability. All compactors of the same classification furnished with similar options under a specific contract shall be identical to the extent necessary to ensure interchangeability of component parts, assemblies, accessories, and spare parts.

3.6 Safety. All rotating or reciprocating parts and all parts subject to high operating temperatures, which are of such a nature or are so located as to be or become a hazard to operating and/or maintenance personnel, shall be adequately guarded or insulated to the extent necessary to eliminate the hazard. All platforms and steps shall have antiskid surfaces. Ladders, steps, and handholds shall be provided for easy access to the operator's cab. Except for the first step from ground level, ladders and steps shall have a rise of not more than 12 inches. Guardrails shall be provided on the outer extremities of the control station, except where access is required or visibility is hindered. All safety systems shall be in accordance with DoL, OSHA standards. A backup alarm device, which meets SAE J994, shall be furnished.

3.7 Performance. The compactor shall be capable of compacting solid wastes from housing areas and construction projects, as well as the covering material, used in landfill operations. The compactor shall develop sufficient pressures to crush and compact refuse. The leveling blade shall be capable of light bulldozing and spreading of both refuse and cover material. The compactor shall be capable of all normal operations when utilized on terrain that is sloped up to 15° from the horizontal in a direction at a right angle to the path of forward motion.

3.8 Maintainability. Provision shall be made to permit the contents of the radiator, crankcase, hydraulic oil reservoir, transmission, and other gearcases for fluid reservoirs to completely drain by gravity into a suitable catch basin adjacent to or under the compactor.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:45Z
Check the source to verify that this is the current version before use.

3.9 Construction. The equipment shall be designed and constructed to facilitate field maintenance. All adjustment locations and replaceable accessories shall be readily accessible. Construction features that can be hazardous to personnel engaged in normal operational use or maintenance of the equipment, or deleterious to equipment itself, shall not be permitted.

3.10 Frame. The frame shall be fabricated from steel plate or rolled sections. The frame shall be constructed to allow the compaction drums to oscillate along the longitudinal axis.

3.11 Power train. Engine power shall be transmitted through a full hydrostatic drive with infinite forward and reverse gears, or through a torque converter with full power shifting in a minimum of three forward and two reverse gears. In high gear, the compactor shall be able to attain a speed of at least 9 miles per hour on level ground.

3.12 Steering. Full power hydraulic steering shall be provided. Articulated frame locks shall be provided in accordance with SAE J276.

3.13 Operator's cab. The cab shall be of the full enclosed, all-weather type that provides maximum visibility. The cab shall be provided with two doors or one door and one exit type window, tinted safety glass, windshield washers and wipers front and rear in accordance with SAE J942 and J198, rearview mirrors, and an adjustable, suspended operator's seat. Seat belts shall be furnished. Windshield defrosters, front and rear, shall be provided in accordance with SAE J381. All controls and instruments necessary to operate the compactor shall be located in the cab. When seated in the normal operating position, the controls shall be visible. All controls and instruments shall be clearly identified for their intended operation and function with permanently affixed label plates of noncorrosive material. Controls that are obvious in function do not need to be marked. Decals shall not be used.

3.13.1 Heating-cooling. The cab shall be equipped with heating and air-conditioning systems. The heater shall be of the hot water type with fresh air intakes. Discharge outlets shall be provided to direct heated air to floor and defroster louvers. Heater shall be complete with blower and mounted controls convenient to the driver. Heating, ventilation, and air conditioning shall be in accordance with SAE J1129.

3.13.2 Noise. Noise generated by the operation of the compactor, at all speeds and operating conditions, shall not exceed the permissible sound level in the interior of the operator's cab as defined by DoL, OSHA standards. Noise generated shall not exceed levels specified in SAE J98 for external sound.

3.13.3 Roll-over protective structure. Each compactor shall be equipped with a roll-over protective structure conforming to the requirements of SAE J1040.

3.14 Brakes. Service brakes and parking brakes shall be independently located and actuated. Service brakes shall be air or hydraulically actuated. Compactors equipped with air brakes shall be provided with an air pressure indicator and warning device located at the control station. Parking brakes shall be provided with a warning device located at the control station. Service brakes and parking brakes shall meet the performance criteria of SAE J1136.

Source: https://assist.dla.mil -- Downloaded: 202610-20T21:45Z
Check the source to verify that this is the current version before use.

3.15 Compaction drums. Drum diameter, measured to the outside extremities of the compaction surfaces, shall be not less than 54 inches for type I or 65 inches for type II. The compaction surfaces on the drum shall be replaceable by normal cutting and welding operations. Compaction surfaces shall be designed to chop and crush refuse and shall be the self-cleaning type. Sheep-foot type compaction surfaces are not permitted.

3.16 Guards. Steel plate guarding shall be provided to protect all components of the braking system, engine compartment, drive train, fuel tanks, hydraulic tank, and steering cylinders.

3.17 Leveling blade. The leveling blade shall be hydraulically operated and shall have a replaceable cutting edge. The blade width shall exceed the compaction width and be not less than 8 feet 0 inches for type I nor less than 12 feet 0 inches for type II. The blade shall be of sufficient height to prevent refuse from entering the engine compartment, but not less than 4 feet 6 inches for type I nor less than 5 feet 0 inches for type II. The upper portion of the blade shall be constructed of heavy steel grating with suitable spacing to provide sufficient visibility for the operator. Hydraulic controls shall include lift, lower, float, and hold. The lift shall be not less than 33 inches for either type I or type II compactors.

3.18 Lighting system. A complete 12 volt (V) or 24V lighting system shall be provided. The lighting system shall include at least two forward and two rearward directed sealed beam lights. Controls shall be provided for forward directed lights and rearward directed lights. Controls shall be clearly identified. Sealed beam lights shall conform to SAE J598 and shall be provided with lamp housings. Sealed beam lights shall be used to floodlight the work area and to permit safe travel at night. Panel lamps shall be provided on the instrument panel for night illumination of all instruments. The circuit for panel lamps shall be actuated by the controls of the sealed beam lights. Electrical wiring shall conform to SAE J1292 as applicable.

3.18.1 Warning light. When specified (see 6.2.1), a standard commercial, revolving, yellow warning light shall be provided and installed over the operator's cab and shall be in accordance with SAE J845.

3.19 Diesel engine. The diesel engine shall be the manufacturer's standard or optional engine that meets or exceeds the requirements of this specification. Horsepower (hp) shall be not less than 175 net flywheel hp for type I compactors and not less than 300 net flywheel hp for type II compactors. The diesel engine shall achieve self-sustained combustion at the manufacturer's rated idle speed in not more than 5 minutes at ambient temperatures from -20° Fahrenheit (F) to +125°F. The engine shall be ready for full-load operation in not more than 15 minutes. Starting aids may be either electric glow plug or ether primer. When an ether priming system is required, it shall be of the measured shot type with storage capacity of not less that 12 fluid ounces. As a minimum, the engine shall be furnished complete with the following:

a. The manufacturer's standard 12V or 24V electrical cranking system.
b. A battery charging alternator with a rating of not less than 50 amperes.
c. A two-stage, dry-type, intake air cleaner with service indicator.
d. Safety control devices of the visual or audible type for high coolant temperature and low lubricating oil pressure.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:45Z
Check the source to verify that this is the current version before use.

e. Hour meter - An engine hour meter having a totalizing mechanism of not less than 9,999 hours shall be furnished to register accurately the number of hours of engine operating time. Meter shall be of strong rugged construction to ensure continuous trouble-free performance under the most extreme equipment operating conditions indicated in this specification.
f. Lubricating oil pressure indicator.
g. Cooling liquid temperature indicator.
h. Start-stop control.
i. Battery-alternator indicator.
j. Muffler.
k. Liquid quantity fuel indicator or dipstick.

All engine instruments and controls, with the exception of the hour meter and dipstick, shall be located at the operator's cab and shall be visible to the operator as specified in 3.13. The hour meter may be located on the engine in an accessible location to facilitate reading during servicing. Radiator grilles shall be provided to protect the core from puncture, lint, and debris.

3.19.1 Fuel tank. The fuel tank shall be of sufficient capacity for not less than 8 hours of normal operation.

3.19.2 Housing. A housing shall be provided to protect the engine from adverse weather and from the entry of refuse into the engine compartment. Housing shall be designed to incorporate pusher fan radiator cooling features. Housing doors or covers shall be provided to allow accessibility to any engine components requiring routine maintenance and repair. Latches shall be provided to hold all doors or covers in the closed position. Doors or covers, if hinged, shall be designed to permit their being restrained in the open position. The housing shall be removable or otherwise designed to permit engine removal and replacement.

3.19.3 Exhaust stacks. Exhaust stacks shall be designed or guarded to not present a fire or burn hazard.

3.20 Vandalism protection. Unless otherwise specified (see 6.2.1), vandalism protection shall be provided that will, as a minimum, include locking caps for the fuel oil, hydraulic oil, radiator, and engine oil fill openings.

3.21 Accessories. The compactor shall be shipped with all required accessories, repair parts, and tools unless written deviation is received from the contracting officer. All accessories, repair parts, and tools shall be made available by the contractor through international sales offices.

3.22 Lubrication. Lubrication means shall be provided for all moving parts requiring lubrication. Hydraulic lubrication fittings shall be in accordance with SAE J534. Pressure lubrication fittings shall not be used where normal lubricating pressure may damage grease seals or other parts. The unit shall be lubricated as specified in section 5 with lubricants designated for use in the 0°F to 32°F temperature range. The unit shall be conspicuously tagged to identify the lubricants and their temperature range.

3.23 Instruction plates. The compactor shall be equipped with instruction plates suitably located, describing any special or important procedures to be followed in operating and servicing the equipment. Plates shall be of a

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:45Z
Check the source to verify that this is the current version before use.

material that will last and remain legible for the life of the equipment, and shall be securely affixed thereto with nonferrous screws or bolts of not less than 1/8-inch diameter.

3.24 Name plate. A name plate will be furnished by the contracting officer for each compactor. The contractor shall stamp all necessary data in the blank spaces of the plate provided for that purpose and securely affix the plate to each compactor in a conspicuous place with brass screws or bolts not less that 1/8-inch diameter. The applicable nomenclature contained in the contract item description shall be placed in the top blank.

3.25 Technical publications. When specified (see 6.2.1), the contractor shall provide commonly available commercial instructions for installation, maintenance, and operation of the compactor. Instructions should also include an available replacement parts list indicating the manufacturer's name and part number.

3.26 Cleaning, treatment, and painting. Surfaces normally painted in good commercial practice shall be cleaned, treated, and painted as specified herein. Surfaces to be painted shall be cleaned and dried to ensure that they are free from contaminants such as oil, grease, welding slag and spatter, loose mill scale, water, dirt, corrosion products, or any other interfering substances. As soon as practicable, after cleaning, and before any corrosion product or other coating interfering material can result, the surface shall be prepared or treated to insure the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat. The primer shall be applied to a clean, dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current processes and the total dry film thickness shall be not less than 2.5 mils over the entire surface. The paint shall be free from runs, sags, orange peel, or other defects. Color of the finish coat shall conform to FED-STD-595 as specified (see 6.2.1).

3.27 Workmanship

3.27.1 Steel fabrication. The steel used in fabrication shall be free from kinks, sharp bends, and other conditions that would be deleterious to the finished product. Manufacturing processes shall not reduce the strength of the steel to a value less than intended by the design. Manufacturing processes shall be done neatly and accurately. All bends shall be made by controlled means to ensure uniformity of size and shape.

3.27.2 Bolted connections. Bolt holes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commercial practice, and all bolts, nuts, and screws shall be tight.

3.27.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

3.27.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:45Z
Check the source to verify that this is the current version before use.

be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.27.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect that reduces the castings ability to perform its intended function.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2. Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

4.2.1 First article inspection. First article inspection shall be performed on one compactor when a first article inspection is required (see 3.2). This inspection shall include the examination of 4.3; the tests of 4.4; and, when specified (see 6.2.1), the preproduction pack inspection of 4.6. The first article may be a standard production item from the supplier's current inventory provided the compactor meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining compactors to be furnished under the contract.

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, test of 4.5, and packaging inspection of 4.6.

4.3 Examination. Each compactor shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirement or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.4 First article tests. The first article compactor shall be subjected to the tests specified in 4.4.1 through 4.4.2. Failure to pass one or more tests shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 202640-20T21:45Z
Check the source to verify that this is the current version before use.

4.4.1 Performance tests. The designated test site shall be appropriate for demonstrating a landfill situation or arrangements shall be made to utilize an existing landfill operation that will adequately demonstrate the equipment capability. The compactor shall be operated for 24 hours in three 8-hour shifts, compacting solid waste, refuse, and cover material in forward and reverse operation modes. The compactor shall utilize the normal working forward and reverse transmission ranges during the refuse compaction phase of the test. After the refuse is compacted, a 4- to 6-inch lift of cover material shall be placed over the refuse, using the leveling blade. The compactor shall then compact the cover material. The compactor will then continue to repeat the process until 24 hours of operating has elapsed. After each 8-hour shift, the compactor shall be refueled, lubricant and coolant levels checked, and lubricated in accordance with the manufacturer's lubrication instructions. Operation shall include, but not necessarily be limited to the following:

a. At the start of each shift, while the brake shoes and drums are cold, the compactor shall be driven at maximum speed in reverse gear and the brakes shall be applied in a panic stop. The compactor shall then be driven at maximum forward speed and the brakes shall be applied in a panic stop.
b. Twenty-five percent of each shift shall consist of figure-8 turns at the minimum turning radius and at the maximum safe operating speed. Compactors shall be observed to determine conformance to:

(1) The performance requirements of 3.7 and 3.10 while operating in a normal, functional manner.
(2) The accessibility and maintainability requirements of 3.8, 3.9, and 3.19.
(3) The speed and steering system requirements of 3.11 and 3.12.
(4) The heating-cooling requirements of 3.13.1 within the available ambient temperature range.
(5) The noise level requirements of 3.13.2.

4.4.2 Brake test. The compactor shall be completely stopped five times with the service brakes from maximum speed on dry, level ground. The distance from the point of application to the actual stop shall be measured on the fifth pass to determine conformance to 3.14. The test shall be conducted in both forward and reverse. Parking brake test shall be conducted with the compactor headed up and down slope to determine conformance to 3.14.

4.5 Quality conformance test. Each compactor shall be completely assembled, properly adjusted, and otherwise serviced for operation. Each compactor shall be operated for not less than 1 hour. All controls shall be operated as many times as necessary, but not less than 30 times, to determine ease of operation, effectiveness, and responsiveness; and that the mechanism actuated by the controls operate promptly, fully, and without restriction, malfunction, or excessive vibration. Gearcases, bearings, and other moving parts shall be examined for excessive heating or abnormal operation insofar as is practicable and possible. The entire compactor shall be examined for evidence of failure, slippage, or deformation. Failure to pass any phase of this test shall be cause for rejection.

4.6 Packaging inspection. The inspection of the preservation, packing, and marking shall be in accordance with the requirements of section 4 of

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:45Z
Check the source to verify that this is the current version before use.

MIL-R-3075. The inspection shall consist of the quality conformance inspection and, when specified (see 6.2.1), a preproduction pack shall be furnished for examination and test within the time frame required (see 6.2.1).

5. PACKAGING

5.1 Preservation, packing, and marking. Preservation, packing, and marking shall be in accordance with the requirements of MIL-R-3075 with the level of preservation and the level of packing as specified (see 6.2.1).

6. NOTES

6.1 Intended use. Landfill compactors covered by this specification will be used for sanitary landfill operations where it is necessary to compact trash, garbage, all other forms of solid refuse, and cover material for future land use purposes.

6.2 Ordering data

6.2.1 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Type of compactor (see 1.2).
c. When issue of specification, standard, or handbook shall be other than that listed in the solicitation's DODISS (see 2.1.1).
d. When a first article is required for inspection and approval (see 3.2, 4.2.1, and 6.3).
e. When a revolving warning light is required (see 3.18.1).
f. When vandalism protection is not required (see 3.20).
g. When technical publications are required (see 3.25 and 6.2.2).
h. Color of finish coat (see 3.26).
i. When specified, a preproduction pack is required and the time frame required for submission (see 4.6).
j. Level of preservation and level of packing required (see 5.1).

6.2.2 Data requirements. When this specification is used in an acquisition that incorporates a DD Form 1423, Contract Data Requirements List (CDRL), the data requirements identified below shall be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved CDRL incorporated into the contract. When the provisions of DAR 7-104.9 (n) are invoked and the DD Form 1423 is not used, the data specified below shall be delivered by the contractor in accordance with the contract or purchase order requirements. Deliverable data required by this specification is cited in the following paragraphs:

PARAGRAPH	DATA REQUIREMENTS	APPLICABLE DD-1664
3.25	Technical publications	DI-M-24042
4.4	Tests	DI-T-2072

(Data item descriptions related to this specification, and identified in section 6 will be approved and listed as such in DoD 5000.19L, Vol. II, AMSDL. Copies of data item descriptions required by the contractors in connection with specific acquisition functions should be obtained from the Naval Publications and Forms Center or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 20260-20T21:45Z
Check the source to verify that this is the current version before use.

6.3 First article. When a first article inspection is required, the item will be tested and should be a first article sample or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The first article should consist of one unit. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test, and approval of the first article.

6.4 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:

Navy - YD

Preparing activity:

Navy - YD

Project No. 3895-N206

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:45Z
Check the source to verify that this is the current version before use.