MIL-R-82200A
25 July 1980
SUPERSEDING
MIL-R-82200
25 March 1976

MILITARY SPECIFICATION

RAMP, LOADING VEHICLE (GENERAL PURPOSE TYPE)

This specification is approved for use by the Departments of the Navy and the Air Force and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers lightweight portable loading ramps, for loading and unloading with forklift trucks between ground level and the floors of railcars, highway trucks, trailers and container vans. The ramps shall have a manually operated hydraulic system for vertical positioning.

1.2 Classification. Portable, loading vehicle, ramps shall be of the following types and sizes as specified (see 6.2):

Type I - Aluminum with aluminum grating.

Type II - Aluminum with steel grating.

Size 2 - 16,00 pounds (7257.4 kg) capacity.

Size 4 - 24,000 pounds (10886.2 kg) capacity.

Style 1 - 70 inches (177.8 cm) wide.

Style 2 - 84 inches (213.3 cm) wide.

Style 3 - 96 inches (243.8 cm) wide.

FSC 3990

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

2. APPLICABLE DOCUMENTS

2.1 Issues of Documents. The following documents, of the issue in effect on date of invitation for bids or requestes for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

QQ-C-320	- Chromium Plating (Electrodeposited).
QQ-S-781	- Strapping, Steel, and Seals.
RR-C-271	- Chains and Attachments, Welded and Weldless.
PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-T-75	- Tape, Preservation and Sealing.

MILITARY

MIL-P-116	- Preservation-Packaging, Methods of.
MIL-B-121	- Barrier Material, Greaseproofed, Waterproofed, Flexible.
MIL-G-3859	- Grease Guns, Hand Operated, Lever, Push and Screw Type.
MIL-P-15328	- Primer (Wash), Pretreatment, (Formula No. 117 For Metals).

STANDARDS

FEDERAL

FED-STD-H28	- Screw Thread Standards for Federal Services
FED-STD-595	- Colors

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

MIL-STD-130	- Identification Marking of U. S. Military Property.
MIL-STD-209	- Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.
MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.

(Copies of specifications and standards and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

2.2 Other publications. The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

SOCIETY OF AUTOMOTIVE ENGINEERS (SAE)
SAE Standard J534
(Application for copies should be addressed to the Society of Automotive Engineers, 400 Commonwealth Drive, Warrendale, PA 15096).

3. REQUIREMENTS

3.1 First article (preproduction model). Unless otherwise specified the supplier shall furnish one ramp for examination and testing within the time frame specified (see 6.2) to prove prior to starting production that his production methods and choice of design detail will produce ramps that comply with the requirements of this specification. Examination and tests shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government.

3.2 Standard product. The portable loading vehicle ramps covered by this specification shall be the manufacturer's current standard commercial product, except for any modifications required to comply with these specifications.

3.3 Material. Material shall be new and of a composition and quality suitable to meet the requirements specified herein. Recycled material may be used it fully meets the requirements of this specification.

3.4 Design and construction. The ramps shall be designed and constructed with aluminum structural members. Type I ramps shall have aluminum grating. Type II ramps shall have steel grating. Each ramp shall be designed to perform in accordance with the requirements of 3.8 for carrier floor heights from 38 inches (96.5 cm) to 62 inches (157.4 cm) above ground level. The overall length of the ramp shall be 36 feet (10.97 m) including a level-off section of at least 6 feet (1.83 m) at the top end. The upper end of the ramp shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

have a solid lip of not less than 14 inches (35.6 cm) to support the ramp on the carrier floor. The ramp shall be equipped with handholds for positioning by four people manually to other locations over semi-improved surfaces. The ramp shall be equipped with two safety chains 8 feet (2.44 m) to 12 feet (3.66 m) in length with grabhooks to secure the ramp to the carrier or dock. The ramp shall be equipped with side mounted reflectors at each end. The ramp design shall provide for safety curbs to prevent run-off of operating equipment while on the ramp. The safety curbs shall have a minimum height of 4 inches (10 cm). The ramp shall have a capacity as specified in 1.2 and be capable of withstanding 200 percent of the rated capacity. The wheels for moving the ramp shall be located (approximately) at the center of balance underneath the ramp and shall be connected to the hydraulic actuating system so that the ramp can be utilized through the full height range without the wheels acting as load supports.

3.4.1 Surface. The surface of the grating shall be an 'all weather' self-cleaning and draining type with top surface fully serrated to provide traction for fork truck wheels under all weather conditions. When the Type II ramp is specified, the steel grating shall be galvanized by the hot dipped process or shall have two coats of a baked-on epoxy base synthetic finish. The design shall provide safety side curbing to prevent equipment run-off without imparting tire or wheel damage. The approach at both ends of the deck shall consist of an integral safety tread plate. The approach edges of the tread plates shall be beveled. All other deck surfaces shall consist of open type grating. The grating holddown fasteners shall not project above top surface of the grating.

3.4.2 Hydraulic system. Vertical positioning of the ramp through a range from 38 inches (96.5 cm) to 62 inches (157.4 cm) above ground level shall be accomplished by a manually operated hydraulic system. The system shall be capable of elevating the ramp through this range within 120 seconds. The hydraulic system shall incorporate an overload relief valve to protect the hydraulic system from damage due to overload. The pump level shall be recessed and positioned for ease of access and operation. The force at the grip end of the pump lever to operate the pump against relief pressure shall not exceed 50 pounds.

3.4.2.1 Cylinder and piston rods. Hydraulic system cylinders shall have an exclusion device to prevent foreign material and fluids from entering around the piston rod. Piston rods for the hydraulic system shall be plated with an electrodeposited hard chrome finish of uniform thickness not less than 0.0005 iches (.00127 mm) in accordance with QQ-C-320. Rod surface roughness shall not exceed 32 microinches (.0000813 mm).

3.4.3 Wheels. Wheels shall be industrial or automotive type and shall be mounted on tapered roller bearings. Hub design shall provide a means to retain lubrication.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

3.4.4 Tires. Each wheel shall be provided with a pneumatic tire. Tire loading shall not exceed the tire manufacturer's rating for the application.

3.4.4.1 Spring suspension system. A coil spring suspension system with hydraulic shock absorbers shall be provided to permit towing of the ramp at speeds up to and including 25 miles per hour (40.23 km/hr). Springs shall be pin connected to permit securing of undercarriage in the proper position for towing and for operation by one man without the use of tools. Means shall be provided to retain the springs clear of the ground in the operating position.

3.4.5 Safety chains. Safety chains shall be provided on each side at the high end of the ramp to secure the carrier. Each chain shall be not less than 8 feet (243.8 cm) in length and be equipped with a grabhood on one end and a shackle on the opposite end. Chain, shackle, and hook shall conform to RR-C-271, Type I, Grade C, Class 4, minimum 1/4 inch (.635 cm) nominal size; Type IV; and Type V, Class 1 and 2 respectively.

3.4.6 Tow bar. The loading ramp shall be equipped with a detachable tow bar for towing. The tow bar shall be equipped with a quicklock device for attachment to the ramp. The towing eye of the bar shall have a 3 inch minimum inside diameter and the center of the towing eye shall extend a minimum distance of 48 inches (121.9 cm) from the edge of the ramp. With the towing eye at a height of 28 inches (71.12 cm) the ramp shall be approximately level. The tow bar shall be stowed in brackets on the side of or beneath the ramp where it shall be easily accessible. There shall be no evidence of permanent deformation of the tow bar or ramp or any loosening of connection between the tow bar and the ramp when the ramp is tested as specified in 4.5.2.5.

3.4.7 Grease fittings. Grease fittings shall be provided where required for lubrication or corrosion resistance, except where prelubricated sealed bearings are used. All fittings shall be of SAE Standard (J534) configuration and located in a protected yet easily accessible position for lubrication with a hand operated grease gun conforming to MIL-G-3859.

3.4.8 Finish. The safety curb and outside of ramp side beams shall be primed and painted. Primer shall be a wash primer in accordance with MIL-P-15328. The finish paint shall be a high visibility yellow color 13538 in accordance with FED-STD-595. Primer and finish coats shall be applied in accordance with normal commercial practices to assure complete coverage and durability of the finish. The finish coat, when dry, shall be a smooth even surface, free from runs, sags, peels, chips, blisters, areas of thin film or no film. Paint shall be kept off working surfaces when interference with the working parts will result.

3.4.9 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease and other foreign matter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

3.4.10 Fastening devices. All nuts, bolts, pins, and similar parts shall be installed with adequate means for preventing them from loosening or becoming out of adjustment. All fastening devices subject to removal or adjustment shall not be swaged, peened, staked, or otherwise permanently deformed. Threads shall conform to the applicable requirements of FED-STD-H28.

3.4.11 Brazing and soldering. Brazing and soldering shall be employed only where those operations are included in the original design. These operations shall not be employed as repair measures for defective parts.

3.4.12 Interchangeability. All parts from the same manufacturer shall be manufactured to such standards that will permit replacement or adjustment without modification of parts or total equipment.

3.4.13 Slinging provisions. Permanently affixed slinging provisions that enable the ramp to be lifted in its normal travel position shall be provided and shall conform to MIL-STD-209. Slinging provisions may also be used as tiedwons when such provisions conform to MIL-STD-209.

3.4.14 Tiedown provisions. Permanently affixed tiedown provisions that permit fastening the ramp to the floor or deck of a transportation medium shall be provided and shall conform to MIL-STD-209. Tiedown provisions may also be used as slinging provisions when such provisions conform to MIL-STD-209.

3.5 Equipment manual. One copy of an equipment manual shall be furnished with each ramp. The equipment manual shall contain complete instructions for operation and maintenance. An illustrated repair parts list shall be furnished with a repair parts section that includes actual manufacturer's name and part number and quantity of each part required. The repair parts illustration may be a drawing or picture. Repair parts for the same or different model ramps shall not have the same part number unless the parts are interchangeable.

3.6 Identification plate. Each ramp shall be provided with an identification plate in accordance with MIL-STD-130. The identification plate shall include manufacturer's name, type, model or serial number, contract number, date of manufacture and load capacity of the unit.

3.7 Workmanship. The ramps shall perform loading operations without permanent deformation, breakage of connections, malfunction, or component interference caused by incorrect workmanship. All parts of the ramp shall be clean and free from sand, rust, dirt, films, pits, sprues, scale, flux, and other harmful extraneous materials. Edges and surfaces exposed to operating and maintenance personnel shall be smooth and rounded to the extent that a hazardous surface does not exist.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

3.7.1 Rivet Connections. Rivet holes shall be accurately punched or drilled, and shall have burrs removed. Rivets shall be driven with power tools. Rivet heads shall be full, neatly made, concentric with rivet holes and in full contact with the surface of the member. Excessive upsetting of rivets to fill holes will not be acceptable.

3.7.2 Bolted connections. Bolt holes shall be accurately formed and shall have burrs removed. Washers or lockwashers or a combination of the two shall be provided on all bolts, studs, and cap screws having straight thread. Self-locking nuts are acceptable in lieu of standard nuts and lockwashers. All fasteners shall be correctly tightened and nuts shall have full thread engagement.

3.7.3 Welds. Welded joints shall be sound, smooth, free from pits, holes, fissures, rough projecting edges, and slag; and shall be thoroughly fused to the base metal.

3.7.4 Machine work. All parts shall bemanufactured to insure accuracy of assembly through the use of correct jigs, fixtures or tape controlled machines or any combination thereof. Like parts shall be interchangeable.

3.8 Performance.

3.8.1 Structure. The ramp shall be capable of withstanding momentary stresses up to 200% of rated capacity without permanent deformation or indications of material or workmanship defects when tested as specified in 4.5.2.1.

3.8.2 Hydraulic system. The hydraulic system shall show no evidence of leakage, malfunction, downward drift of more than 1/2 inch (1.27 cm), or permanent deformantion when tested as specified in 4.5.2.2.

3.8.3 Towing operation. The ramp deck shall be capable of being towed with a vehicle having a pintle height of 28 inches (71.12 cm) with no evidence of permanent deformation or failure when tested as specified in 4.5.2.4.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspection. Inspection shall be classified as follows:

(a) Preproduction inspection (see 4.3).

(b) Quality conformance inspection (see 4.4).

(c) Inspection of packaging (see 4.6).

4.3 Preproduction inspection.

4.3.1 Examination. The ramp shall be inspected as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. The ramp shall be tested as specified in 4.5.2.1 through 4.5.2.6. Failure of any test shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for inspection, as specified in 4.5.1, shall be in accordance with MIL-STD-105. Sampling for tests shall be in accordance with MIL-STD-105, Level S-4.

4.4.2 Examination.

4.4.2.1 In-process examination. During fabrication, exterior surfaces of parts shall be examined for mil scale, oil, grease, dirt, and rust. Presence of any of these defects shall be cause for rejection.

4.4.2.2 Samples. Samples selected in accordance with 4.4.1 shall be examined in accordance with 4.5.1. AQL shall be 2.5 for major defects and 6.5 total defects, expressed in terms of defects per hundred units.

4.4.2.3 Dimensional examination. Sampling for dimensional examination shall be in accordance with MIL-STD-105, Level S-2. Samples selected shall be examined for the dimensional requirements specified in section 3. Each nonconformance to a specified dimensional requirement shall constitute a defect. AQL shall be 4.0 defects, expressed in terms of defects per hundred units.

4.4.3 Tests.

4.4.3.1 First production ramp. When a preproduction model is not required, the first production ramp shall be tested as specified 4.5.2.1 through 4.5.2.6. Failure of any test shall be cause for rejection.

4.4.3.2 Samples. Samples selected in accordance with 4.4.1 shall be tested as specified in 4.5.2.2, 4.5.2.3, and 4.5.2.5. The inspection level shall be S-4 with an AQL of 2.5 expressed in terms of defects per hundred units.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

4.5 Inspection procedure.

4.5.1 Visual examination. Examination shall be in accordance with Table I.

TABLE I - CLASSIFICATION OF DEFECTS

Examine	Defects	Classification Major	Minor
1. Finish	A. Surface preparation, treatment and primer not as specified.	x	
	B. Finish not color specified.		x
	C. Finish surface contains runs, sags, peels, chips, blisters, areas of thin film or no film.		x
2. Design	A. Material not as specified.	x	
	B. Dimensions not as specified.	x	
	C. Wheels act as load supports within range of 38 inches to 62 inches.	x	
	D. Approach edges of tread plates not beveled.	x	
	E. Grating is not all-weather, self-cleaning, and draining type.	x	
	F. Grating holddown fasteners project above top surface.		x
	G. Pump not recessed in protected position.	x	
	H. Pump lever socket not accessible	x	
	I. Cylinders not as specified.	x	
	J. Tire loading exceeds tire manufacturer's recommendations.		x
	K. Suspension not as specified.	x	
	L. Means not provided to retain springs clear of the ground in operating position.	x	
	M. No provision for slinging and tiedown.	x	
	N. Safety chains not as specified.		x
	O. Quick-lock device not separable from tow bar without the use of handtools.	x	
	P. Tow bar storage not as specified.	x	
	Q. Grease fittings not as specified (SAE J534).		x
	R. Grease fittings not accessible.	x	
	S. Screw threads not in accordance with FED-STD-H28.	x	

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

TABLE I- CLASSIFICATION OF DEFECTS (Con'td.)

Examine	Defects	Classification Major	Minor
	T. Fastening devices not as specified	x	
	U. Assemblies not accessible for maintenance.	x	
	V. No provision for handholds for positioning ramp.	x	
3. Construction and Workmanship			
	A. Hydraulic system leaks		x
	B. Sharp edges and burrs not removed.	x	
	C. Rivet connections not as specified.		x
	D. Bolted conncections not as specified.		x
	E. Welding not as specified.	x	
	F. Component missing or damaged.	x	
4. Instructions	A. Identification plate missing, incomplete, or illegible.		x
	B. Equipment manual not furnished or incomplete.		x
5. Identification Marking			
	A. Missing, incomplete, not legible.		x

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

4.5.2 Performance tests. Prior to test, the ramp shall be lubricated with oils and greases as recommended by the supplier. Tests shall be conducted in the order listed. The contractor shall provide the contracting officer with a certificate of conformance that all prescribed tests have been met.

4.5.2.1 Overload test. The assembled ramp shall be subjected to a static load of 200 percent of the rated load. The load shall be applied through an area extending no more than 9 inches (22.86 cm) on each side of the lateral centerline of the ramp. The ramp wheels shall not act as load supports during the test. The ramp shall be left under this load for a period of 1 hour, after which the load shall be removed and the ramp then inspected to determine compliance with 3.8.1 and Table I. Nonconformance to 3.8.1 or Table I shall constitute failure of this test.

4.5.2.2 Hydraulic test. After successful completion of the above tests, the ramp shall then be lowered to its lowest position. Then operate the hydraulic system manually to raise the level platform of the ramp to its highest position within 120 seconds. Then the ramp shall be lowered to its lowest position which completes one cycle. The above cycle shall be performed for a total of 10 times at the fully raised position. After completion of the 10 cycles, all moving parts shall be examined for evidence of excessive wear to the operating mechanism. At the fully raised position, the ramp shall be held for a minimum two hour period. There shall be no leakage and the ramp shall not drift downward more than 1/2 inch (1.27 cm) during this period. Nonconformance to 3.8.2 or Table I shall constitute failure of the test.

4.5.2.3 Leakage test. At the completion of the above 10 cycles, the hydraulic components and lines shall be examined for leakage and damage. Nonconformance to 3.8.2 or Table I shall constitute failure of this test.

4.5.2.4 Towing test. The ramp shall be coupled to a towing vehicle and be towed over a semi-improved road, including rough railroad crossings, at an average speed of not less than 15 mph (24.1 km/hr) for 14 hours with maximum speed of not less than 25 mph (40.2 km/hr) maintained for a distance of not less than 1 mile (1.609 km) each hour. In addition the ramp shall be towed cross-country for a distance of not less than 50 miles (80.4 km) at speeds up to 5 mph (8.04 km/hr). Nonconformance to 3.8.3 or Table I shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

4.5.2.5 Tow bar test. With the ramp raised to towing height and tow bar in place, the ramp shall be permitted to fall free to the ground. Nonconformance to 3.4.6 shall constitute failure.

4.5.2.6 Endurance. The ramp shall be elevated to maximum height and attached to a container or dock. A forklift truck compatible with the ramp shall be used for the test. Each cycle shall consist of the fully loaded truck (not less than 12,000 pounds (5443.6 kg)) total weight for size 2 and 18,000 pounds (8164.8 kg) for size 4 ramps) ascending the ramp, depositing the load on the container or dock, descending the ramp, ascending the ramp, pick up the load, descend the ramp. A total of 3,000 cycles shall be performed. Nonconformance to 3.8.4 shall constitute failure of this test.

4.6 Inspection of packaging.

4.6.1 Quality conformance inspection of pack.

4.6.1.1 Unit of product. For the purpose of inspection a completed pack prepared for shipment shall be considered a unit of product.

4.6.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.1.3 Examination. Samples selected in accordance with 4.6.1.2 shall be examined for the following defects:

101. Materials, methods, and containers not as specified for Level A. Each incorrect material, method, or container shall be considered one defect.

102. Bearings not lubricated as specified for Level A.

103. Hydraulic system not preserved as specified for Level A.

104. Consolidation not as specified for Level A.

105. Packing not as specified for Level A.

106. Marking missing, illegible, incorrect, or incomplete for Level A or Commercial.

5. PACKAGING

5.1 Preservation. Preservation shall be Level A or Commercial as specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

5.1.1 Level A.

5.1.1.1 Preservatives. Preservatives specified herein shall conform to the applicable specifications listed in and shall be applied in accordance with MIL-P-116.

5.1.1.2 Unfinished surfaces. Exterior metal surfaces of components requiring the application of a contact preservative shall be coated with Type P-1 preservative.

5.1.1.3 Bearings. Bearings shall be lubricated to capacity with the manufacturer's recommended lubricant containing a rust inhibitor.

5.1.1.4 Hydraulic system. The hydraulic fluid supply tank shall be filled to the operating level with the hydraulic fluid required for operation. The piston shall be retracted as far as practicable into the cylinder. When the piston cannot be fully retracted into the cylinder the exposed portion of the piston shall be coated with Typed P-6 or P-11 preservative and the coated surface wrapped or convered with barrier material conforming to MIL-B-121, Type II, Grade A, Class 2, extending the wrap approximately 2 inches on the ram cylinder. The barrier material shall be secured in place with tape conforming to PPP-T-75, Type II. The pump lever shall be secured in a manner to prevent movement.

5.1.1.5 Equipment manual. The equipment manual shall be preserved in accordance with MIL-P-116, Method IC-1 or IC-3.

5.1.1.6 Consolidation. The equipment manual and any accessories or installation hardware shall be consolidated together in a close-fitting box conforming to PPP-B-601, Overseas Type, Grade B, style optional. The contents shall be blocked, braced, or cushioned as applicable within the box to prevent movement or damage.

5.1.2 Commercial. Each complete ramp shall be preserved in accordance with MIL-STD-1188.

5.2 Packing. Packing shall be Level A or Commercial as specified (see 6.2).

5.2.1 Level A. The ramp shall be prepared for unboxed (mobile) shipment. The consolidation box shall be secured to the ramp in a protected location that will not interfere with the lifting or its mobility.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

The securing shall be accomplished by the use of steel strapping conforming to QQ-S-781, Type I or IV, Finish B, size as applicable. The tow bar shall be stowed in brackets provided and if needed to prevent loss, secured in place with strapping herein.

5.2.2 Commercial. Each complete ramp shall be packed in accordance with MIL-STD-1188.

5.3 Marking.

5.3.1 Military. Marking for military levels of protection shall be accordance with MIL-STD-129.

5.3.2 Commercial. Marking for commercial packaging shall be in accordance with MIL-STD-1188.

6. NOTES

6.1 Intended use. The Style 1 portable loading ramp covered by this specification is normally used for loading and unloading with forklift trucks between ground level and the floors of railcars, highway trucks, or trailer equipment. The Style 2 ramp and the Style 3 ramp are normally used for container loading and unloading operations.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number and date of this specification.

(b) Type, size, and style required (see 1.2).

(c) When preproduction sample is not required (see 3.1).

(d) Schedule for submission of preproduction model, when required, (see 3.1).

(e) Degree of preservation and packing required (see 5.1 and 5.2).

6.3 Preproduction model. Any changes or deviations of production ramps from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the supplier of his obligation to furnish ramps conforming to this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

Custodians:
Navy - SA
Air Force

Review activity:
Navy - OS
DSA - GS

User activities:
Navy - SH, MC
Air Force - 99

Preparing activity:
Navy - SA

Project 3990-0166

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE NAVY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12503 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE NAVY

Naval Supply Systems Command
SUP 0322, CM#3 Room #602
Washington, DC 20376

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

(TO DETACH THIS FORM, CUT ALONG THIS LINE.)

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:56Z
Check the source to verify that this is the current version before use.