INCH-POUND

MIL-S-70941A(AR)
14 June 1991

SUPERSEDING
MIL-S-70941(AR)
30 July 1990

MILITARY SPECIFICATION

SYSTEM TEST UNIT: 12922091

This specification is approved for use by the U.S. Army Armament, Munitions and Chemical Command and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification establishes the requirements for manufacture and acceptance of the System Test Unit used in the M90 Radar Chronograph. (See 6.1).

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards and handbooks. The following specifications, standards and handbooks form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

SPECIFICATIONS

MILITARY

MIL-F-13926 - Fire Control Materiel, Manufacture and Inspection, General Specification for

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document, should be addressed to: Commander, U.S. Army ARDEC, ATTN: SMCAR-BAC-S, Picatinny Arsenal, New Jersey 07806-5000 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 1290

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

MIL-P-14232 - Parts, Equipment and Tools for Army Materiel, Packaging of
MIL-I-45607 - Inspection Equipment, Acquisition, Maintenance and Disposition of

STANDARDS

MILITARY

MIL-STD-454 - Standard General Requirements for Electronic Equipment
MIL-STD-2164 - Environmental Stress Screening Process for Electronic Equipment

(Unless otherwise indicated, copies of federal and military specifications, standards and handbooks are available from: Standardization Documents Order Desk, Bldg. 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings and publications The following other Government documents, drawings and publications form a part of this specification to the extent specified herein. Unless otherwise specified, the issues shall be those in effect on the date of the solicitation.

DRAWINGS (See 6.4)

U.S. ARMY ARMAMENT RESEARCH, DEVELOPMENT AND ENGINEERING CENTER (ARDEC)

12922089 - System Test Unit, Schematic Diagram
12922091 - System Test Unit Assembly
12922225 - Environmental Test Methods

SPECIAL PACKAGING INSTRUCTIONS

P12922091 - Special Packaging Instructions for the System Test Unit

(Copies of drawings, publications, and other Government documents required by the contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

2.2 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

Source: https://assist.dla.mil -- Downloaded: 202640-23T04:15Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 General description. The System Test Unit is an electronic device used to test the M90 Radar Chronograph and to simulate the effects of a projectile in flight.

3.2 Materials. The Materials shall be in accordance with the applicable drawings and specifications.

3.3 Components and assemblies. The components and assemblies shall comply with all requirements specified on Drawing 12922091, all associated drawings, and with all requirements specified in applicable specifications and standards. Where applicable, the System Test Unit shall meet the requirements of MIL-F-13926 and MIL-STD-454 as follows :

a. Dimensions and tolerances
b. Inorganic protective surface finishings
c. Part identification and marking
d. Workmanship
e. Soldering electrical connections

3.4 Performance

3.4.1 General. The Antenna Unit transmits a low power continuous microwave (X-band) signal. The transmitted signal strikes the outgoing projectile in flight and the reflected RF energy is received by the antenna. The frequency reflected signal differs from the transmitted signal, due to the Doppler Effect. The antenna unit detects the difference between the transmitted and received frequencies which is directly proportional to the projectile velocity. In order to achieve the simulation of an outgoing projectile, the reflected signal shall be modulated so that the received frequency matches the velocity measuring range of the M90 Chronograph. This is attained by modulating a pin switch in the System Test Unit at the appropriate frequency. Because of the square wave modulation, the reflected signal contains many spectral components. The primary spectral component is used to the simulated Doppler frequency.

3.4.2 System test. Performance of the System Test Unit shall be verified by conducting an M90 Radar Chronograph system test.

3.4.3 Diode modulation. The system test unit shall use a diode to reflect the antenna radiated energy. The diode shall be modulated on and off by a square wave in the frequency of

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

23,346 ± 4 Hz. Duty Cycle shall be 1.4 ± 0.2 second ON and 2.8 ± 0.2 second OFF.

3.4.4 Operating switch. The System Test Unit is operated by an ON/OFF pushbutton switch that is turned on whenever the System Test Unit is mounted on the Antenna unit. The switch disengages when the System Test unit is removed from the Antenna unit.

3.4.5 Power. The System Test Unit shall be operated by a standard 9V battery.

3.5 Environmental requirements.

3.5.1 High temperature. The System Test Unit shall meet the requirements of 3.3 and 3.4 when thermally stabilized at +125 degrees F. The CCA when subjected to storage temperature of +150 degrees F shall meet the requirements of 3.3 and 3.4 when returned and thermally stabilized at ambient temperature.

3.5.2 Low temperature. The System Test Unit shall meet the requirements of 3.3 and 3.4 when thermally stabilized at -50 degrees F and when returned and thermally stabilized at ambient temperature.

3.5.3 Humidity. The System Test Unit shall meet the requirements of 3.3 and 3.4 after being subjected to 240 hours at a relative humidity of 94 ±-5 percent from +68 degrees F to +125 degrees F.

3.5.4 Vibration. The System Test Unit shall meet the requirements of 3.3 and 3.4 after being subjected to vibration, having a double amplitude of 1.0 inch, from 5 to 6.5 HZ and acceleration level of 2 G's over the 6.5 to 200 Hz frequency range for a 15-minute duration in each of its three mutually perpendicular axes.

3.5.5 Rain. The System Test Unit shall meet the requirements of 3.3 and 3.4 after being subjected to a 2.0 in per hour, 20 mile per hour wind driven rain.

3.6 Environmental stress screening (ESS). The System Test Unit shall be subjected to a 40-hour run-in period (excluding downtime) which includes vibration and operation at temperature extremes. The time required to conduct the vibration test shall not be included as part of-the-run-in period. The System Test Unit shall meet the requirements in 3.3 and 3.4 of this specification for the 40-hour run-in period.

Source: https://assist.dla.mil -- Downloaded: 202610-23T04:15Z
Check the source to verify that this is the currentversion before use.

3.6.1 Environmental stress screening (ESS) temperature. The System Test Unit shall meet the performance in 3.3 and 3.4 after being subjected to 40 hours of temperature cycling between 0 degrees F and +125 degrees F in accordance with 5.1.2.1 of MIL-STD-2164.

3.6.2 Environmental stress screening (ESS) vibration. The System Test Unit shall meet the performance requirements in 3.3 and 3.4, after being subjected to random motion in the range of 20 to 2000 Hz for 5 minutes at an axis perpendicular to the largest surfaces of the System Test Unit. Acceleration spectral density is 6.06 g. RMS in accordance with 5.1.1 of MIL-STD-2164.

3.7 Fabrication. The System Test Unit shall be manufactured in accordance with Drawings 12922088 and 12922091.

3.8 First article inspection. When specified in the contract or purchase order, three samples shall be subjected to first article inspection in accordance with the technical provisions herein (see 4.3).

3.9 Workmanship. The workmanship requirements of MIL-F-13926 and MIL-STD-454 shall apply.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

indicated or actual, nor does it commit the Government to accept defective material.

4.1.2 General provisions. The component and subassembly inspection requirements of MIL-F-13926 and MIL-STD-454 forms a part of the Quality Assurance Provisions of this specification.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Special sampling (see 4.5).

4.2.1 Inspection conditions. Unless otherwise specified, all examinations and tests shall be conducted at the following standard ambient conditions:

a.	Temperature	+60 degrees to +90 degrees F.
b.	Relative humidity	90% RH maximum.
c.	Pressure	28 to 32 inches of Hg.

4.3 First article inspection.

4.3.1 First article submission. The contractor shall submit a first article sample as designated by the contracting officer consisting of three System Test Units for inspection in accordance with 4.3.2.

4.3.2 Inspections to be performed. First article assemblies, components and test specimens may be subjected by the Government to any or all of the examinations and tests specified in TABLE I and TABLE II herein, and to any or all requirements of the applicable drawings.

4.3.3 Rejection. If any assembly, component or test specimen fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of any System Test Unit to comply with any of the stated requirements.

4.4 Quality conformance inspection.

4.4.1 Inspection lot formation. The term "inspection lot" is defined as a homogeneous collection of units of product from which a representative sample is drawn or which is inspected 100 percent to determine conformance with applicable requirements. Units of product selected for inspection shall represent only the

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

inspection lot from which they are drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, using the same materials and methods, in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein, regardless of the type of inspection procedure which is being applied to determine conformance with requirements.

4.4.2 Examinations and tests.

4.4.2.1 Components, assemblies and subassemblies. All components, assemblies and subassemblies shall be inspected in accordance with the inspection provisions contained in this specification and Quality Assurance Provisions (QAP) listed in the Technical Data Package (TDP). In the absence of QAPs, the applicable quality assurance provisions of MIL-F-13926 shall apply.

4.4.2.2 Final acceptance inspection. Subsequent to first article approval, examination and tests related to Section 3 herein shall be performed in accordance with the sampling plans specified in 4.4.2.3 herein. Examination and test for packaging and marking shall be in accordance with MIL-P-14232 and Section 5 herein. The tabulated classification of defects in 4.4.2.3 shall constitute the minimum inspection to be performed by the supplier after first article approval and prior to Government acceptance or rejection by item or lot.

4.4.2.3 Functional tests. The tests in TABLE I shall be performed as noted under the characteristics.

TABLE I. Functional tests
(100% Inspection)

No.	Characteristics	Requirement	Test Procedure
Critical:	None	None	N/A
Major:			
101	System Test	3.4.2	4.8.1
102	Diode Modulation	3.4.3	4.8.2
103	Operating Switch	3.4.4	Visual
104	Power	3.4.5	Visual
105	ESS Temperature	3.6.1	4.7.1.1

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

106	ESS Vibration	3.6.2	4.7.1.2
Minor:			
201	Fabrication	3.7	Applicable Drawing/ Visual
202	Materials	3.2	Applicable Drawing/ Visual
203	Workmanship	3.9	Applicable Drawing/ Visual

4.5 Special sampling. Three System Test Units shall be selected at random as a special sample from each lot or each 150 produced whichever occurs first. The sample shall meet the requirements and tests of TABLE II.

TABLE II. Environmental sampling tests.

No.	Characteristics	Requirement	Test Procedure
Critical:	None	None	N/A
Major:			
301	High temperature	3.5.1	4.7.2.1
302	Low temperature	3.5.2	4.7.2.2
303	Humidity	3.5.3	4.7.2.3
304	Vibration	3.5.4	4.7.2.4
305	Rain	3.5.5	4.7.2.5
No.	Characteristics	Requirement	Test Procedure
Minor:	None	None	N/A

4.6 Inspection equipment.

4.6.1 Government-furnished inspection equipment. Where the contract provides for Government-furnished test equipment, supply and maintenance of test equipment shall be in accordance with the applicable requirements of MIL-I-45607.

4.6.2 Contractor-furnished inspection equipment.

4.6.2.1 Government design. Unless otherwise specified in the contract, all inspection equipment identified by drawing number in specifications or QAPs forming a part of the contract shall be supplied by the contractor in accordance with the design specified. The contractor may, however, propose alternatives to Government designs for approval in accordance with 6.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

4.6.2.2 Contractor design. The contractor shall design and supply inspection equipment compatible with the "Methods of Inspection" specified in 4.7 of this specification and with the component inspection procedures specified in "Examination" and "Test Facilities" requirements of MIL-F-13926 whenever Government designs are not specified (see 4.6.2.1). Since tolerance of test equipment is normally considered to be within 10 percent of the product tolerance for which it is intended, this inherent error in the test equipment design must be considered as part of the prescribed product tolerance limit. Thus, concept, construction, materials, dimensions, and tolerances used in the design of test equipment will reliably indicate acceptability of a product which does not exceed 90 percent of the prescribed tolerance limit and permit positive rejection when non-conforming. Construction shall be such as to facilitate routine calibration of test equipment. Contractor inspection equipment designs shall be submitted for approval in accordance with 6.4.

4.6.2.3 Inspection equipment design requirements.

4.6.2.3.1 Temperature testing. The volume of the test chamber shall conform to the test facilities requirements of MIL-F-13926. The air temperature at the control sensor shall be in accordance with the specified requirements within plus or minus 2.5 degrees F (1.4 degrees C). The temperature gradient across the cross-sectional area occupied by the test item shall not exceed 0.5 degrees F per foot in any direction. The heat source of the test chamber shall be located so that radiant heat, if used, will not fall directly on the test item. Thermocouples or equivalent temperature sensors utilized to determine or control the specified chamber temperature shall be centrally located within the test chamber within the supply airstream, or in the return airstream, whichever provides the specified test condition at the item under test and shall be baffled or otherwise protected against radiation effects.

4.6.2.3.2 Fabrication, setup and calibration. Design and fabrication of test equipment shall be such that it incorporates the features of rigidity, stability, and ease of maintenance. Setup and calibration equipment necessary for certification of the testing equipment accuracy shall be furnished and will become a part of the testing equipment. Operating and calibration instructions shall be prepared and submitted to the procuring activity.

4.7 Methods of inspection. Unless otherwise specified in the contract, the following procedures shall be utilized to conduct specified tests. If the contractor chooses to use alternate test procedures, a detailed description of the set-up

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

and procedure shall be submitted to the government procuring agency for approval prior to use.

4.7.1 Environmental stress screening. Prior to conducting acceptance testing of this specification, the System Test Unit shall be subjected to 40 hours of run-in time. The run-in shall exclude any downtime necessary to repairs. It shall include vibration, followed by temperature cycling.

4.7.1.1 ESS temperature. Testing equipment utilized in this test shall conform to the requirements of 4.6.2.3.1. The System Test Unit shall be placed in the chamber and subjected to a 40-hour run-in period which includes vibration and operation at temperature extremes. The temperature shall be raised gradually at a rate not to exceed 2 degrees F per minute until thermally stabilized at +125 degrees F for 4 hours duration. Then the temperature of the chamber shall be decreased to 0 degrees F at the same rate for another 4 hours. Subsequent to the above temperature extremes (+125 degrees F and 0 degrees F), the System Test Unit shall not have been damaged or adversely affected and shall meet the requirements in 3.3 and 3.4 of this specification for the entire 40-hour run-in period.

4.7.1.2 ESS vibration. The System Test Unit in an operating mode shall be exposed to a 5 minute burst of random vibration. Failures occurring during this five minute test shall be accrued(if possible) and corrected at the conclusion of the 5 minute period in accordance with the requirements of 3.3 and 3.4. The random vibration spectrum shall be:

20 - 80	Hz	at 3 dB/octave rise
80 - 350	Hz	at 0.04 g sq/Hz
350-2000	Hz	at 3 dB/octave rolloff

The motion shall be applied perpendicular to the largest surfaces of the System Test Unit.

4.7.2 Environmental methods of inspection.

4.7.2.1 High temperature. This test shall be conducted in accordance with Drawing 12922225. Subsequent to the exposure, the System Test Unit shall not be damaged or adversely affected and shall meet the performance requirements in 3.5.1 of this specification.

4.7.2.2 Low temperature. This test shall be conducted in accordance with Drawing 12922225. Subsequent to the exposure, the System Test Unit shall not be damaged or adversely affected and shall meet the performance requirements of 3.5.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

4.7.2.3 Humidity. The System Test Unit shall be subjected to the humidity test as outlined in Drawing 12922225. Performance test to be conducted during the exposure shall be conducted during the first, third and fifth cycles; subsequently, the System Test Unit shall not be damaged or adversely affected and shall meet the performance requirements of 3.5.3.

4.7.2.4 Vibration. The System Test Unit shall be subjected to the vibration as specified in Drawing 12922225. The displacement and frequency shall be as follows:

GRAVITY	FREQUENCY (Hz)
1.0 inch Double Amplitude	5 - 6.5
2 G Acceleration	6.5 - 200

Subsequent to the vibration test, the System Test Unit shall not have been damaged or adversely affected and shall meet the performance requirements of 3.5.4. Duration shall be one sweep of 15 minutes in each plane.

4.7.2.5 Rain. The System Test Unit shall be subjected to rain test as specified in Drawing 12922225. Subsequent to the exposure, the System Test Unit shall not be damaged or adversely affected and shall meet the performance requirements of 3.5.5.

4.8 System test. System test will be conducted by the Government. Test samples shall be arranged and shipped to the Government (see 6.5).

a. Install the System Test Unit in its proper place on the Antenna Unit and press the PRESS BEFORE FIRE pushbutton on the M90 Data Unit.

b. The M90 Data Unit shall display the simulated projectile velocity of 333.8 ± 0.2 m/sec.

c. Procedure in a. and b. shall be repeated four times.

4.8.2 Diode modulation. The diode modulation shall be demonstrated using a contractor designed, Government approved, test fixture simulating operating conditions. The Diode modulation shall be measured in accordance with 3.4.3.

5. PACKAGING

5.1 Packaging, packing, and marking. Packaging, packing and marking shall be in accordance with MIL-P-14232 and Special

Source: https://assist.dla.mil -- Downloaded: 202610-23T04:15Z
Check the source to verify that this is the current version before use.

Packaging Instruction P12922091. The level of protection shall be specified in the procurement document.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful but is not mandatory.)

6.1 Intended use. The System Test Unit is intended for use in the M90 Radar Chronograph.

6.2 Acquisition requirements. Procurement data should specify the following :

a. Title, number and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1).
c. Applicable stock number.
d. First Article Sample requirements (see 3.8).
e. Level of preservation and packing (see 5.1).
f. Serialization requirements, if applicable.
g. Certificate of conformance for each lot or shipment of product.

6.3 Drawings. Drawings listed in Section 2 of this specification under the heading U.S Army Armament Research, Development and Engineering Center (ARDEC), may also include drawings prepared by, and identified as, U.S. Army Armament, Research and Development Command (ARRADCOM), Frankford Arsenal, Rock Island Arsenal or Picatinny Arsenal drawings. Technical data originally prepared by these activities is now under cognizance of ARDEC.

6.4 Submission of contractor inspection equipment designs for approval. Submit two copies of designs as required: Commander, U.S. Army AMCCOM, ATTN: AMSMC-QAF-I(D), Picatinny Arsenal, NJ 07806-5000. This address will be specified on the Contract Data Requirements List, DD Form 1423 for the appropriate data item as specified in the contract.

6.5 Submission of system test. Test samples for the system test requirement (see 3.4.2 and 4.8) shall be shipped to: U.S. Army Armament, Munitions and Chemical Command, Attn: AMSMC-QAL-A, Rock Island, IL 61299-6000.

6.6 Definitions.

Source: https://assist.dla.mil -- Downloaded: 202610-23T04:15Z
Check the source to verify that this is the currentversion before use.

6.6.1 Contractor. Unless otherwise specified, the word Contractor used throughout this specification shall mean any supplier or producer of items or material to the Government. This shall include commercial contractors, sub-contractors, Government Owned-Contractor Operated (GOCO), and Government Owned-Government Operated (GOGO) plants.

6.6.2 Technical data package. A technical description of an item adequate for use in procurement. The description defines the required design configuration and assures adequacy of item performance. It consists of all applicable lists, specifications, standards, models, performance requirements, quality assurance provisions and packaging data.

6.7 Subject term (key word) listing.

M90 Radar Chronograph (M90)

6.8 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1290-A466)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-S-70941A (AR)	2. DOCUMENT DATE (YYMMDD) 14 June 1991

3. DOCUMENT TITLE
SYSTEM TEST UNIT: 12922091

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets if needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME Commander US Army ARDEC	b. TELEPHONE (Include Area Code) (1) Commercial: (201) 724-6674 (2) AUTOVON: 880-6674
c. ADDRESS (Include Zip Code) ATTN: SMCAR-BAC-S Picatinny Arsenal, NJ 07806-5000	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 202640-23T04:15Z
Check the source to verify that this is the current version before use.