MIL-S-43674B
23 April 1985
SUPERSEDING
MIL-S-43674A
31 March 1978

MILITARY SPECIFICATION

SHOWER PAIL, COLLAPSIBLE, COTTON DUCK, 5-GALLON CAPACITY

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This document covers a collapsible shower pail.

2. APPLICABLE DOCUMENTS

2.1 Government documents. Unless otherwise specified, the following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this document to the extent specified herein.

SPECIFICATIONS

FEDERAL

DDD-L-20	-	Label: for Clothing, Equipage, and Tentage (General Use)
PPP-B-601	-	Boxes, Wood, Cleated-Plywood
PPP-B-636	-	Boxes, Shipping, Fiberboard

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: U.S. Army Natick Research and Development Center, Natick, MA 01760-5014, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 8465

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

STANDARDS

FEDERAL

FED-STD-751 - Stitches, Seams, and Stitchings

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129 - Marking for Shipment and Storage
MIL-STD-147 - Palletized Unit Loads

DRAWINGS

US ARMY NATICK RESEARCH AND DEVELOPMENT CENTER

5-4-984 - Shower Pail, Collapsible, Cotton Duck, 5-Gallon Capacity; Assembly and Details
5-4-985 - Shower Pail, Collapsible, Cotton Duck, 5-Gallon Capacity; Sections
5-4-986 - Shower Pail, Collapsible, Cotton Duck, 5-Gallon Capacity; Showerhead Assembly and Details
5-4-1243 - Shower Pail, Collapsible, Cotton Duck, 5-Gallon Capacity; Alternate Showerhead Assembly and Details

(Copies of documents required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

* 2.2 Other publications. Unless otherwise specified, the following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this document to the extent specified herein.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 3951 - Standard Practice for Commercial Packaging

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

(Technical society and technical association documents are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

* 2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document shall take precedence.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 First article. When specified, a sample shall be subjected to first article inspection (see 4.3, 6.2 and 6.3).

3.2 Materials and components. Materials and components shall conform to the requirements specified herein and on applicable drawings (see 6.4).

3.3 Construction. The shower pail shall conform to the drawings listed in section 2 and as specified herein.

3.3.1 Stitching, machine. All stitching shall conform to type 301, 6 to 8 stitches per inch of FED-STD-751.

3.3.1.1 Thread breaks. Thread breaks shall be overstitched not less than 1 inch at each break.

3.3.1.2 Stitching ends. Stitching ends shall be overstitched not less than 1 inch on stitch type 301, except where ends are turned under in a hem or held down by other stitching. Where stitching is performed automatically on stitch patterns such as box, box with cross-stitch, "W" stitching, or straight line tacking; three or more tying, overlapping, or backstitches shall be used to secure the ends.

3.3.1.3 Skipped stitches. Skipped stitches shall be overstitched not less than 1 inch where two or more consecutively skipped stitches occur.

3.3.2 Showerhead assembly. The showerhead assembly shall be attached to the bottom of the pail as shown on Drawing 5-4-984. The water shower valve shall turn "on" or "off" without binding.

3.3.2.1 Metal showerhead. The flange nut shall be tightly secured to prevent rotation of the flange when rotating the showerhead. The pail with showerhead assembly attached shall not leak when tested as specified in 4.4.5.1.

* 3.3.2.2 Plastic showerhead (alternate). The pail with showerhead attached shall not leak after cold soaking and dropping. The showerhead shall be capable of withstanding cold and hot soaking and dropping without showing signs of fracture, breakage, deformation of the showerhead contours in excess of 1/2 inch, or loosening of cemented parts when tested as specified in 4.4.5.2. The showerhead shall be tightened without the alignment pin showing signs of breaking or deforming and without the pin cutting or deforming the wall of the alignment slot.

3.3.3 Attachment to bottom. The showerhead assembly shall be attached to the bottom of the pail as shown on Drawing 5-4-984. The flange nut shall be tightly secured to prevent rotation of flange when regulating showerhead.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

3.3.4 Bottom reinforcement. The bottom reinforcement webbing shall be stretched taut when stitching to bottom.

3.3.5 Soldering. All soldering shall be as specified on Drawing 5-4-986. Soldering shall be adherent and the soldered joint shall be free from splatter or excess solder.

3.3.6 Welds. Welds shall be smooth and free from porosity, cracks, incomplete fusion, and deformation of material.

3.4 Marking. All markings shall conform to DDD-L-20. The identification marking shall be applied in the location shown on the Drawing 5-4-984 and shall conform to type IV, class 5. The letters "U.S." and the warning marking "NOT TO BE USED FOR THE STORAGE OF DRINKING WATER" shall be applied in the size characters and in the location indicated on the drawing and shall conform to type IV, class 9. Fastness of the class 9 marking shall be as specified for class 5 marking.

3.5 Workmanship. Cloth components shall be clean and free of holes, cuts, tears, or cloth defects such as multiple floats or broken or missing yarns. Webbing shall contain no frayed or scalloped edges. Thread tension shall be maintained so that there shall be no loose or tight stitching. Seam allowances shall be maintained with seams secured so that no runoffs or twisted, pleated, or open seams shall result. Care shall be exercised in sewing to see that no needle chews occur. All thread ends shall be trimmed to 1/2 inch or less in length. Metal components shall be smooth; shall be free of burrs, porosity, cracks, sharp edges, and corroded area; and shall not be broken or malformed. Plastic components of the plastic showerhead, when applicable, shall be smooth and free from visible variable thickness and warpage.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the document where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspection. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).

* 4.3 First article inspection. When a first article is required (see 6.2), it shall be examined for the defects listed in table I and 4.4.4 and tested as

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

specified in 4.4.5. The presence of any defect or failure of any test shall be cause for rejection of the first article.

4.4 Quality conformance inspection. Unless otherwise specified herein, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.4.1 Components and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents, unless otherwise excluded, amended, modified, or qualified in this document or applicable purchase documents.

4.4.2 In-process inspection. Inspection shall be made to determine that soldering is in compliance with 3.3.5 and the welding of metal showerhead is in compliance with 3.3.6. Whenever nonconformance is noted, correction shall be made to the items affected and the process.

★ 4.4.3 End item visual examination. The end item shall be examined for the defects listed in table I. The lot size shall be expressed in units of pails. The sample unit shall be one shower pail. The inspection level shall be II and the acceptable quality level (AQL), expressed in terms of defects per hundred units, shall be 4.0 for major defects, 10.0 for major and minor A combined defects, and 25.0 for total (major, minor A and minor B combined) defects.

TABLE I. End item visual defects

Examine	Defects	Classification Major	Minor A	Minor B
Cloth	Hole, cut, or tear	X		
	Broken or missing yarns, multiple floats clearly visible at normal inspection distance (approximately 3 feet)		X	
Webbing	Edge frayed or scalloped		X	
	Webbing not taut stitched to bottom			X
Seams and stitching	Open seam on stitch type 301:			
	- more than 1 inch	X		
	- more than 1/4 inch but not more than 1 inch		X	
	- 1/4 inch or less			X

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defects	Classification Major	Minor A	Minor B
Seams and stitching (cont'd)				
	NOTE: A seam shall be classified as open when one or more stitches joining a seam are broken or when one or more skipped stitches or runoffs occur. On double stitched seams, a seam shall be classified as open when either one or both sides of a seam are open.			
	Raw edges caught in stitching (where turnunder is required):			
	- more than 3/4 inch but not more than 1-1/2 inches			X
	- more than 1-1/2 inches		X	
	Thread breaks:			
	- overstitched less than 1 inch			X
	NOTE: Thread breaks not overstitched shall be classified as open seams.			
	Needle chews resulting in hole, cut, or tear.	X		
	Skipped stitches overstitched less than 1 inch on stitch type 301 (where two or more stitches are skipped consecutively)			X
	NOTE: Skipped stitches not overstitched shall be classified as open seams.			
	One or more required rows of stitching omitted (except on boxstitching)	X		
Boxstitching	Incomplete:			
	- one row of stitching omitted			X
	- two or more rows of stitching omitted		X	
	Any boxstitching less than specified length by more than 1/8 inch			X

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defects	Classification Major	Minor A	Minor B
Seam and stitch type	Wrong seam or stitch type	X		
Stitch tension	Loose, resulting in loosely exposed top or bottom (bobbin or looper) thread for more than 6 inches		X	
Stitches per inch	One stitch less than minimum specified			X
	Two or more stitches less than minimum specified		X	
	One or more stitches in excess of maximum specified			X
	NOTE: Variation in the number of stitches per inch, caused by the operator speeding the machine and pulling the fabric in order to sew over heavy places or in turning corners shall be classified as follows: a. Within the minor A defect classification - minor B defect b. Within the minor B defect classification - no defect			
Stitching gage	Not as specified		X	
Stitching margin	Larger than specified by more than 3/16 inch			
	- for more than 2 inches but not more than 4 inches in length			X
	- for more than 4 inches in length		X	
	- less than specified			X
Stitching ends	Overstitched less than 1 inch (except where ends are held down by other stitching or turned under in a hem or where stitching is performed automatically)		X	
	Secured with less than three tying, overlapping, or backstitches when automatic stitching is performed		X	

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects (cont'd)

Examine	Defects	Classification Major	Minor A	Minor B
Components and assembly	Any component broken or fractured, or required operation omitted (unless otherwise classified)	X		
Showerheads (with post and cotter pin)	Any component broken or fractured	X		
	Water valve does not turn "on" or "off" without binding	X		
Metal showerhead	Not smooth and not free from burrs and sharp edges	X		
	Not free from cracks, porosity, or corroded area	X		
Plastic showerhead (alternate)	Not smooth and not free of variable thickness or surface warpage	X		
	Loosening of cemented parts	X		
	Cracked, broken, or deformed	X		
Handle	Not constructed as specified on applicable drawing; not set to body of pail as specified on drawing	X		
Markings	Omitted, incorrect, illegible, misplaced, or not type specified			X
Cleanness	Grease or oil stains; thread ends not trimmed to 1/2 inch or less			X

* 4.4.4 End item dimensional examination. The end item shall be examined for conformance to the dimension specified on the drawings. Any dimension not within the specified tolerance shall be classified as a defect. The lot size shall be expressed in units of pails. The sample unit shall be one shower pail. The inspection level shall be S-3 and the AQL, expressed in terms of defects per hundred units, shall be 10.0.

4.4.5 Testing of the end item. Testing shall be performed in accordance with 4.4.5.1 or 4.4.5.2 as applicable.

4.4.5.1 Testing of shower pails with metal showerheads. The shower pail shall meet the leakage requirement in 3.3.2.1 when tested as specified in 4.5.1. The

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

lot size shall be expressed in units of pails. The sample unit shall be one shower pail. The inspection level shall be S-3 and the AQL, expressed in terms of defects per hundred units, shall be 0.65.

4.4.5.2 Testing of shower pails with plastic showerheads. The shower pail shall be tested for the characteristics as indicated in table II. The lot size shall be expressed in units of pails. The sample unit shall be two shower pails. The inspection level shall be S-1 and the AQL, expressed in terms of defects per hundred units, shall be 2.5.

TABLE II. End item tests (plastic showerhead)

Characteristic	Requirement paragraph	Test method	No. of determs	Results reported as
Cold soak	3.3.2.2	4.5.2	1	Pass or fail
Leakage	3.3.2.2	4.5.1	1	Pass or fail
Heat soak	3.3.2.2	4.5.3	1	Pass or fail

* 4.4.6 Packaging inspection. An examination shall be made to determine that the preservation packing, and marking comply with the section 5 requirements. Defects shall be scored in accordance with table III. The sample unit shall be one shipping container fully packaged. The lot size shall be the number of shipping containers in the inspection lot. The inspection level shall be S-2 and the AQL, expressed in terms of defects per hundred units, shall be 2.5.

TABLE III. Packaging defects

Examine	Defect
Marking	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application.
Materials	Any component missing or not as specified.
Workmanship	Cotter pin or hexagonal nut, as applicable, not covered by means specified.
Content	Number per container not as required.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

4.4.7 Palletization inspection. An examination shall be made to determine that the palletization complies with the section 5 requirements. Defects shall be scored in accordance with table IV. The sample unit shall be one palletized unit load fully packaged. The lot size shall be the number of palletized unit loads in the inspection lot. The inspection level shall be S-1 and the AQL, expressed in terms of defects per hundred units, shall be 6.5.

TABLE IV. Palletization defects

Examine	Defect
Finished dimensions	Length, width, or height exceeds specified maximum requirement.
Palletization	Not as specified. Pallet pattern not as specified. Interlocking of loads not as specified. Load not bonded with required straps specified.
Weight	Exceeds maximum load limit.
Marking	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application.

4.5 Methods of inspection.

* 4.5.1 Leak test. At 65°F ambient conditions, the shower pail shall be filled with water and suspended. The showerhead shall be turned to the "on" position to check for starting of water shower and leaks at the connection between the canvas pail and the showerhead. The showerhead shall then be turned to the "off" position and checked again for leaks at the connection of the canvas pail and showerhead. For the plastic showerhead, the leak test shall be conducted after the cold soak test of 4.5.2. Any noncompliance with the applicable requirements of 3.3.2.1 and 3.3.2.2 shall constitute failure of this test.

4.5.2 Cold soak test. A shower pail with the plastic showerhead shall be cold soaked at -35°F temperature for 24 hours and in this cold soaked condition with the showerhead spray plate facing down and at a height of 42 inches, the pail shall be dropped in free fall on a concrete floor. The showerhead shall then be examined to determine compliance with the fracture, breakage, contour deformation, or loosening of cemented parts requirements of 3.3.2.2. Any noncompliance shall constitute a failure.

4.5.3 Heat soak test. A shower pail with the plastic showerhead shall be heat soaked at 125°F temperature for 24 hours and in this heat soaked condition shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

be drop tested as specified in 4.5.2 to determine compliance with the fracture, breakage, contour deformation, or the loosening of cemented parts requirement of 3.3.2.2. Any nonconformance shall constitute a failure.

5. PACKAGING

* 5.1 Preservation. Preservation shall be level A or Commercial as specified (see 6.2).

5.1.1 Level A. Each shower pail shall be collapsed, compactly arranged, the cotter pin of the metal showerhead or the hexagonal nut of the plastic showerhead , covered with wadding or tape to prevent puncturing of fabric, and then unit packed in a snug-fitting fiberboard box conforming to style OPF, grade W6c or W6s of PPP-B-636. Inside dimensions of the box shall approximate 12 inches in length, 12 inches in width, and 3 inches in depth. Approximate dimensions are furnished as a guide only. Each box shall be closed in accordance with the appendix of PPP-B-636.

* 5.1.2 Commercial. Pails shall be preserved in accordance with ASTM D-3951.

* 5.2 Packing. Packing shall be level A, B, or Commercial as specified (see 6.2).

* 5.2.1 Level A packing. Twenty-four shower pails, preserved as specified in 5.1, shall be packed in a wood cleated-plywood shipping container conforming to overseas type, style RSC, grade V3c of PPP-B-636. The shower pails shall be packed on edge, twelve in length, one in width, and two in depth within the shipping container. Inside dimensions of the shipping container shall approximate 44 inches in length, 13 inches in width, and 25 inches in depth. Approximate dimensions are furnished as a guide only.

* 5.2.2 Level B packing. Twenty-four shower pails, preserved as specified in 5.1, shall be packed in wood cleated-plywood shipping container conforming to domestic type, style A of PPP-B-601. The shower pails shall be packed on edge, twelve in length, one in width, and two in depth within the shipping container. Inside dimension of the shipping container shall approximate 44 inches in length, 13 inches in width, and 25 inches in depth. The shipping container shall be assembled, closed, waterproofed, and reinforced in accordance with the appendix of PPP-B-636. Approximate dimensions are furnished as a guide only.

* 5.2.3 Commercial packing. Each shower pail preserved as specified in 5.1 shall be packed in accordance with ASTM D 3951.

* 5.3 Palletization. When specified (see 6.2), shower pails packed as specified shall be palletized on a 4 way entry pallet, in accordance with load type I or Ia of MIL-STD-147. Each prepared load shall be bonded with primary and secondary straps in accordance with bonding means K and L or film bonding mean O or P. The pallet pattern No. 85 shall be used in accordance with the appendix of MIL-STD-147.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

* 5.4 Marking. In addition to any special marking required by the contract or purchase order; unit packs, shipping containers, and palletized unit loads shall be marked in accordance with MIL-STD-129, or ASTM D-3951, as applicable.

6. NOTES

6.1 Intended use. The shower pail is intended for use in tropical combat zones.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this document.
b. When first article sample is required (see 3.1, 4.3, and 6.2).
c. Selection of applicable levels of preservation and packing (see 5.1 and 5.2).
d. When palletization is required (see 5.3).

6.3 First article. When a first article sample is required, it shall be inspected and approved under the appropriate provisions of FAR 52.209. The first article should be a preproduction sample consisting of one finished shower pail. The contracting officer should include specific instructions in all acquisition instruments regarding arrangements for inspection and approval of the first article.

6.4 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of the document (see 3.2).

6.5 Changes from previous issue. The margins of this document are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

Custodians:

Army - GL
Navy - NU

Review activities:

Army - MD
Navy - CG
DLA - CT

User activity:

Navy - MS

Preparing activity:

Army - GL

Project No. 8465-0906

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY
US Army Natick Research and Development Center
Natick, Massachusetts 01760

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300
STRNC-ES

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Natick Research and Development Center
ATTN: STRNC-ES
Natick, MA 01760

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-S-43674B	Military Specification Shower Pail, Collapsible, Cotton Duck, 5-Gallon Capacity

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION (Mark one)
	☐ VENDOR ☐ USER ☐ MANUFACTURER ☐ OTHER (Specify): _____
b. ADDRESS (Street, City, State, ZIP Code)	

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER (Last, First, MI) – Optional	b. WORK TELEPHONE NUMBER (Include Area Code) – Optional
c. MAILING ADDRESS (Street, City, State, ZIP Code) – Optional	8. DATE OF SUBMISSION (YYMMDD)

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

NATICK OP. 1 ACT 84

Source: https://assist.dla.mil – Downloaded: 2026-10-21T22:00Z
Check the source to verify that this is the current version before use.