INCH-POUND

MIL-P-11859H
26 June 1991
SUPERSEDING
MIL-P-11859G
12 February 1985

MILITARY SPECIFICATION

PONTON BOATS, ALUMINUM, FOR

FLOATING FOOTBRIDGE

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers aluminum ponton boats used to support floating aluminum footbridges and light vehicular bridges.

1.2 Classification. The ponton boats shall be the following types, as specified (see 6.2):

Type I - For supporting floating aluminum footbridges.
Type II - For supporting floating aluminum footbridges and light vehicular bridges.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2)

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 20261O-17T22:04Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-T-704	-	Treatment and Painting of Materiel.
MIL-C-3774	-	Crates, Wood, Open, 12,000- and 16,000- Pound Capacity.
MIL-C-46168	-	Coating, Aliphatic Polyurethane, Chemical Agent Resistant.
MIL-C-53039	-	Coating, Aliphatic, Polyurethane, Single Component, Chemical Agent Resistant (CARC), Lead and Chromate Free.
MIL-F-83671	-	Foam-In-Place Packaging Materials, General Specification for.

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	-	Marking for Shipment and Storage.
MIL-STD-130	-	Identification Marking of US Military Property.
MIL-STD-209	-	Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.
MIL-STD-889	-	Dissimilar Metals.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Government drawings. The following Government drawings form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those in effect on the date of the solicitation.

DRAWINGS

ME

TA13211E8580	-	Ponton Boat, Welded Aluminum, for Floating Footbridge.
TA13211E8570	-	Ponton Boat, Welded Aluminum for Floating Footbridge (with Light Vehicular Capabilities).
D13207E1366-1	-	Packing for: Ponton Boat, Aluminum for Floating Footbridge.
D13207E1366-2	-	Packing for Floating Footbridge: Ponton Crate Details, Level A.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-JBS, Fort Belvoir, VA 22060-5606.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:04Z
Check the source to verify that this is the current version before use.

2.2 Non-Government publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN WELDING SOCIETY (AWS)

A5.10 - Bare Aluminum and Aluminum Alloy Welding Electrodes and Rods.
D1.2 - Structural Welding Code - Aluminum.

(Application for copies should be addressed to the American Welding Society, 550 N.W. LeJeune Road, P. O. Box 351040, Miami, FL 33135.)

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION (NMFTA)

National Motor Freight Classification Rules.

(Application for copies should be addressed to the American Trucking Association, ATTN: Traffic Order Section, 2200 Mill Road, Alexandria, VA 22314.)

UNIFORM CLASSIFICATION COMMITTEE (UCC)

Uniform Freight Classification Rules.

(Application for copies should be addressed to the Uniform Classification Committee, ATTN: Tariff Publishing Officer, Room 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

(Non-Government standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein (except for related associated detail specifications, specification sheets or MS standards), the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:04Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Description. The ponton boats shall be in accordance with top assemblies TA13211E8580 for type I and TA13211E8570 for type II, and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the ponton. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or the designated representative. Dimensions shown on the drawings shall be verified using parts at 68 degrees Fahrenheit (F) to 70 °F.

3.2 First article. Unless otherwise specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Material. Material shall be as specified herein and on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification.

3.3.1 Material deterioration prevention and control. The ponton boats shall be fabricated from compatible materials, inherently corrosion and deterioration resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable storage and operating environments to which the ponton boats may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with components and subcomponents, and shall make information available, upon request, to the contracting officer or designated representative.

3.3.2 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the ponton boats may be newly fabricated from recovered materials to the maximum extent practicable, provided the ponton boats produced meet all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the ponton boats.

3.3.3 Polyurethane foam. The space between the floor sheet and the skin shall be filled utilizing a polyurethane froth foam-in-place process. The

Source: https://assist.dla.mil -- Downloaded: 2026l0-17T22:04Z
Check the source to verify that this is the currentversion before use.

floor sheet, skins, and structural members in the cavity shall be cleaned in accordance with MIL-T-704 prior to filling. The material as foamed and in place shall conform to MIL-F-83671, class 1, category 1.

3.3.3.1 Sample for first article inspection. A sample of the cured foam shall be prepared for testing as specified in MIL-F-83671.

3.3.3.2 Foaming procedure. The material shall be dispensed as a froth into the ponton boat through an opening in the stern sheet. The ponton boat shall be restrained to prevent shape distortion from the force of the expanding material. When installed, the plastic material shall show sufficient expansion to seal off all openings leading to the flotation compartment. Excess material shall be trimmed flush to the adjacent metal prior to painting the ponton boat.

3.3.3.3 Foaming process. Prior to the foaming of any ponton boat, the contractor shall prepare and submit to the contracting officer for approval, a written foaming procedure defining process and control. This procedure shall include, but not be limited to, the factors listed below. Process changes affecting any of the factors shall be approved by the contracting officer or designated representative prior to adoption of the change. No change in material suppliers will be made without approval of the contracting officer or designated representative.

a. Method of restraining the ponton boat.
b. Temperature range of the ponton boats prior to foaming.
c. Temperature range of foam components.
d. Method of placing material in ponton boat.
e. Total foam dispensing time.
f. Calibration of equipment.
g. Ponton boat cure time in restraining fixture.

3.4 Identification markings. The ponton boat shall be identified in accordance with MIL-STD-130. The identification plates shall be as shown on the drawing and shall be attached in accordance with the drawing.

3.5 Treatment and painting. The portions of the ponton boat normally painted, internally and external, shall be cleaned, treated, and painted in accordance with MIL-T-704, type B. Unless otherwise specified (see 6.2), the top coat color shall be camouflage green 383 conforming to MIL-C-46168 or MIL-C-53039.

3.6 Workmanship.

3.6.1 Metal fabrication. The surfaces of all complete members used in fabrication shall be free from buckling, kinks, wrinkles, washboarding, burrs, scribe lines, and scratches. Corners shall be square and true. All bends shall be made with controlled means to insure uniformity of size and shape. Moving parts shall operate without binding.

3.6.2 Welders and welding operators. Before assigning any welder or welding operator to welding work covered by this specification, the contractor shall obtain certification that the welder or welding operator has passed

Source: https://assist.dla.mil -- Downloaded: 20260-17T22:04Z
Check the source to verify that this is the current version before use.

qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

ASME Boiler and Pressure Vessel Code, Section IX
AWS D1.2, Structural Welding Code - Aluminum

Contractors who make only horizontal welds need not qualify welders for all position welding. The certification shall be made available for review by the contracting officer or the contracting officer's representative. In the event of evidence of poor welds, the Government reserves the right to require recertification of any welder or welding operator. The test results shall be made available for review by the contracting officer or the contracting officer's representative.

3.6.3 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, mill scale and all other foreign matter, which shall be removed by a stainless steel wire brush. Parent materials, weld filler metals, and fabrication techniques shall be as required to enable the ponton boat to conform to the examination and test requirements specified in section 4. Parts to be joined by fillet welds shall be brought into as close contact as possible and in no event shall be separated by more than 3/16 inch. Welding procedures shall be qualified in accordance with applicable ASME or AWS code, and all welding and welds shall be in accordance with ASME or AWS code.

3.6.3.1 Aluminum welding. Aluminum welding shall be done by the metal-inert-gas method or the tungsten-arc method. Filler metal shall conform to AWS A5.10, classification ER4043. Complete and uniform penetration and fusion of the metals shall be obtained on all welds. Aluminum welds may be ground, filed, wire brushed with a stainless steel wire brush or chipped but shall not be hammered. Preheating for welding is permissible providing the temperature does not exceed 400 °F for a total time of 30 minutes. No process requiring the use of welding flux shall be used. Completed welds shall be free from discontinuities such as base metal cracks adjacent to or behind welds, cracks in weld metal, undercutting of base metal, lack of fusion between weld and parent metal or between passes, incomplete penetration, lack of prescribed fit, or splatter.

3.7 Transportability.

3.7.1 Tiedown provisions. The tiedown provisions shall conform to MIL-STD-209, class 2 or 3, type IV equipment. The tiedown provisions shall satisfactorily complete the pull testing as specified without weld failure, permanent deformation, cracking, loosening, or breaking of the provision or its connecting structural components.

3.7.2 Slinging provisions. The slinging provisions shall conform to MIL-STD-209, class 1 or 3, type III. The provisions shall enable the complete ponton boats to be lifted in the normal operating position. The provisions shall be located so that not less than one inch clearance is maintained between slings and all exterior parts and shall be fastened to members which will withstand stresses in the amount and direction of pull specified for the

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:04Z
Check the source to verify that this is the current version before use.

provisions without weld failure, permanent deformation, cracking, loosening, or breaking of the provision or its connecting structural components. Slinging provisions may also be used as tiedown provisions when such provisions meet the requirements specified in 3.7.1. All slinging/tiedown provisions shall be labeled "LIFT", "TIEDOWN" or "LIFT TIEDOWN", as appropriate, in 1-inch (2.54 cm) high letters.

4 QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the quality assurance provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.4 and 6.5).

4.2 Classification of inspections. Inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The first article ponton boats shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. The first article ponton boats shall be tested as specified in 4.5.2.2 and 4.5.2.3. Failure of these tests shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:04Z
Check the source to verify that this is the current version before use.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa.

4.4.2 Examination. Samples selected in accordance with 4.4.1 shall be examined as specified in 4.5.1. The presence of one or more defects shall be cause for rejection.

4.4.3 Tests. Each ponton boat shall be tested as specified in 4.5.2.2. Failure of this test shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. The ponton boats shall be examined as specified herein for the following defects:

Major

101. Any part or components not in accordance with the QAP requirements as shown on the drawings (see 3.1).
102. Components missing, damaged, or not as specified (see 3.1).
103. Welds missing (see 3.1).
104. Materials not as specified (see 3.3).
105. Materials not resistant to corrosion and deterioration, or treated to be resistant to corrosion and deterioration for the applicable storage and operating environments (see 3.3.1).
106. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other (see 3.3.1.1).
107. Contractor does not have documentation available for identification of material, material finishes or treatment (see 3.3.1.2).
108. Used, rebuilt or remanufactured components, pieces, or parts incorporated in the ponton boat (see 3.3.2).
109. Foaming process not in accordance with approved process (see 3.3.3.3).
110. Workmanship not as specified (see 3.6).
111. Moving parts binding (see 3.6.1).
112. Distortion of the floor sheet (washboarding) (see 3.6.1).
113. Welders and welding operators not certified as specified (see 3.6.2).
114. Welding and welds not as specified (see 3.6.3).
115. Welding not in accordance with approved process (see 3.6.3.1).
116. Tiedown and slinging provisions not as specified (see 3.7.1 and 3.7.2).

Minor

201. Any dimensions, other than those identified on the QAP requirements shown on the drawings, not as specified (see 3.1).
202. Polyurethane filler material not filling the space between the inner floor and outer skin (see 3.3.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:04Z
Check the source to verify that this is the current version before use.

203. Identification marking not as specified (see 3.4).
204. Cleaning, treating, and painting not as specified (see 3.5).
205. Presence of buckling, kinks, or scribe lines on complete members (see 3.6.1).
206. Sharp edges, slivers, burrs, or projections on finished surfaces (see 3.6.1).
* 207. Weld defects such as base-metal cracks adjacent to or behind welds, crater cracks, or cracks in weld metal, spatter, undercutting of base metal (see 3.6.3.1).

* Examination for these items shall be made prior to painting.

4.5.2 Tests.

4.5.2.1 Precautions. Since toxic isocyanate fumes may be evolved during the foaming operation, adequate ventilation shall be provided to reduce the isocyanate concentration in the air below 0.1 parts per million, or gas masks equipped with the appropriate gas filter shall be worn. Additional personnel protection shall consist of face shields, gloves and protective clothing.

4.5.2.2 Foaming process. The unfinished ponton shall be weighed, placed in the restraining fixture and foamed in accordance with the approved foaming procedure (see 3.3.3.3). After the specified waiting period the ponton shall be removed from the fixture and reweighed to determine the amount of foam added. The increased weight of the ponton after foaming of more than 25 pounds or less than 15 pounds shall constitute failure of this test.

4.5.2.3 Foam sample. The cured foam sample (see 3.3.3.1) shall be tested for homogeneity, flame resistance, and oil resistance in accordance with MIL-F-83671. Nonconformance to MIL-F-83671 shall constitute failure of these tests.

4.5.2.4 Transportability.

4.5.2.4.1 Tiedown provisions test. The tiedown provisions shall be tested in accordance with MIL-STD-209 to prove conformance to 3.7.1. Inability to meet the requirements of 3.7.1 shall constitute failure of this test.

4.5.2.4.2 Slinging provisions test. The slinging provisions shall be tested in accordance with MIL-STD-209 to prove conformance to 3.7.2. Inability to meet the requirements of 3.7.2 shall constitute failure of this test.

4.6 Inspection of packaging.

4.6.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be a unit of product.

4.6.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:04Z
Check the source to verify that this is the current version before use.

4.6.3 Examination. Samples selected in accordance with 4.6.2 shall be examined for the defects listed below. Presence of one or more defects shall be cause for rejection.

117. Packing not as specified for level A and C (see 5.1.1 and 5.1.2).
118. Marking illegible, incorrect, or incomplete (see 5.2).

5. PACKAGING

5.1 Packing. Packing shall be level A or C, as specified (see 6.2).

5.1.1 Level A. Ponton boats shall be assembled in groups of 21 each and secured to the MIL-C-3774, type I modified crate base as shown on drawings D13207E1366-1 and -2. After the boats are secured to the crate base, the sides, ends, and top of the crate shall be positioned and secured.

5.1.2 Level C. Ponton boats shall be packed to assure carrier acceptance and safe delivery to destination at lowest ratings in compliance with Uniform Freight Classification Rules or National Motor Freight Classification Rules.

5.2 Marking.

5.2.1 Military marking. Ponton boats and shipping containers shall be marked in accordance with MIL-STD-129. The marking on each ponton boat shall include the National Stock Number, nomenclature, and contract number and shall be stenciled on the port side of the stern and on the starboard side forward, prior to the bow rise, approximately 3 inches below the gunwale.

6. NOTES

(This section contains information of a general or explanatory nature which is helpful, but is not mandatory).

6.1 Intended use.

6.1.1 Type I ponton boat. The type I ponton boat is intended for U.S. Army use in supporting floating footbridges.

6.1.2 Type II ponton boat. The type II ponton boat is intended for U.S. Marine Corps use in supporting floating footbridges and light vehicular bridges.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. Type of ponton boat required (see 1.2).
d. When a first article is required for inspection and approval, and the number of units required (see 3.2).
e. Color required when other than specified (see 3.5).
f. Level of packing required (see 5.1).

Source: https://assist.dla.mil -- Downloaded: 2026l0-17T22:04Z
Check the source to verify that this is the current version before use.

6.3 First article. When a first article inspection is required, the ponton boat should be an initial production item. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, approval of the first article test results and disposition of the first article(s). Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product with has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 Quality assurance provisions (QAP) record. The contracting officer should require the contractor to maintain records of all QAP inspections. A suggested paragraph is as follows:

"The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include, as a minimum, lot size, sample size, drawing requirements, actual measurements, number and type of deficiencies found, quantity approved, quantity rejected, and corrective action taken when applicable."

6.5 Definitions.

6.5.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of the specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.6 International standardization. Certain provisions of this specification are the subject of international standardization agreement ABCA-QSTAG-88. When amendment, revision, or cancellation of this specification is proposed which will modify the international agreement concerned, the preparing activity will take appropriate action through international standardization channels, including departmental standardization offices, to change the agreement or make other appropriate accommodations.

6.7 Subject term (key word) listing.

Boat
Ponton boat
Ponton boat, aluminum

6.8 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:04Z
Check the source to verify that this is the current version before use.

Custodians:
Army - ME

User activity:
Navy - CG

Preparing activity:
Army - ME

Project 5420-0166

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:04Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-P-11859H	2. DOCUMENT DATE (YYMMDD) 910626

3. DOCUMENT TITLE
Ponton Boats, Aluminum, for Floating Footbridge

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION
c. MAILING ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)
	e. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON
	(703) 664-5717 354-5717
c. ADDRESS (Include Zip Code) US Army Belvoir RDE Center ATTN: STRBE-TSE Ft. Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:04Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 202610-17T22:04Z
Check the source to verify that this is the current version before use.