MIL-D-45411B (MU)
3 March 1969
SUPERSEDING
MIL-D-45411A (MU)
15 June 1965

MILITARY SPECIFICATION

DEMOLITION KIT, PROJECTED CHARGE, M1E1 LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of demolition kit designated as Demolition Kit, Projected Charge, M1E1, complete with Rocket Motor Unit, M4.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-D-409 - Detonators, Delay, M1 and M2
MIL-A-2550 - Ammunition and Special Weapons; General Specification for

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

FSC: 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

DRAWINGS

U. S. ARMY MUNITIONS COMMAND

8796266 - Demolition Kit, Projected Charge, M1E1 Complete with Rocket Motor Unit, M4 Assembly
8796269 - Container Assembly
8797610 - Box, Packing, Ammunition, for Kit, Demolition, Projected Charge, w/Rocket Motor Unit, M4
9210948 - Box, Fiber, Ammunition, for Kit, Demolition, Projected Charge, M1E1, w/Rocket Motor, M4

PUBLICATIONS

U. S. ARMY MUNITIONS COMMAND

ET - 8796266 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material.- Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Demolition kit.- The demolition kit shall comply with all requirements specified on Drawing (dwg.) 8796266 and with all requirements specified in applicable specifications.

3.3 Static pull.- The detonating cable with the cable grip assembled shall withstand a static load of 800 pounds, minimum (min.) for twenty seconds, minimum, when tested as specified in 4.3.1.

3.4 Functioning of booster assembly.- The booster assembly shall function satisfactorily when the delay detonator is attached and functioned as specified in 4.3.2. Satisfactory functioning is defined as observing that the detonating cable is initiated.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

3.5 Functioning.- The demolition kit shall function between 0 and 120 degrees Fahrenheit (F.) and shall comply with the following requirements when tested as specified in 4.3.4.

a. Range.- The functioned line charge shall extend not less than 160 feet (ft).

b. Accuracy.- The direction of the projected charge shall be not more than 15 degrees on either side of the aiming point.

c. Detonation of line charge.- The line charge shall detonate along the entire length when initiated by the M1A2 Delay Detonator.

3.6 Workmanship.- All parts and assemblies shall be fabricated and loaded in a thorough workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, rust and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.- At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.

b. Drawing and specification number and date, together with identification and date of changes thereto.

c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.

d. Number of items in the lot.

e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 Inspection provisions

4.2.1 Lot formation.- The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot of loaded projected charge demolition kits shall contain:

a. Parts and parts assemblies from not more than one lot interfix number from one manufacturer.

b. Rocket motor units from not more than one lot interfix number from one manufacturer.

c. Blasting time fuze igniters from not more than one lot interfix number from one manufacturer.

d. PETN from not more than one lot interfix number from one manufacturer.

e. Detonating cord from not more than one lot interfix number from one manufacturer.

f. Pentolite from not more than one lot interfix number from one manufacturer.

g. Detonators from not more than one lot from one manufacturer.

4.2.2 Examination.- The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.2.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.2.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.2.2.1 Booster assembly (see dwg. 8796277 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Depth of charge	Gage	01001
102.	Foreign matter in detonator well	Visual	01002
103.	Tube cracked or split	Visual	01003
Minor:	AQL 1.50 percent		
201.	Total length, maximum (max.)	Gage	01004
202.	Deep cuts in tube	Visual	01005
203.	Assembly dented, wrinkled or deformed	Visual	01006

4.2.2.2 Cone and detonating cable assembly (see dwg. 8796267 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Swivel assembly improperly assembled or not free	Visual-Manual	02001
102.	Nozzle plugs on rocket motor loose or missing	Visual-Manual	02002
103.	Cable damaged (cuts, breaks)	Visual	02003
104.	Either grip assembly kinked or broken	Visual	02004

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

105.	Rocket motor unit damaged (dents, deformed parts).....	Visual	02005
106.	Evidence of poor workmanship (see 3.6).....	Visual	02006

Minor: None defined

4.2.2.3 Assembly, less covers (see dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Fuse lighter, detonator, stake, booster, or cable grip loose or insecure in clips.....	Manual	03001
102.	Cotter pin improperly assembled in clevis bolt.....	Visual	03002
103.	Component missing or improperly assembled.....	Visual	03003
Minor:	AQL 1.50 percent		
201.	Screws securing container to plate loose or missing.....	Visual-Manual	03004
202.	Cable assembly not taped to cable grips.....	Visual	03005
203.	Instruction sheet illegible or misleading.....	Visual	03006

4.2.2.4 Assembly (see dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.40 percent		
101.	Fittings or handles missing, damaged or loose.....	Visual-Manual	04001
102.	Assembly damaged (dented, deformed, punctured.....	Visual	04002
Minor:	AQL 1.50 percent		
201.	Marking misleading or unidentifiable.....	Visual	04003
202.	Protective coating damaged (other than slight scratches)...	Visual	04004
203.	Incorrect lid assembly at top or bottom.....	Visual	04005
204.	Evidence of poor workmanship (see 3.6).....	Visual	04006

4.2.2.5 Sealed fiber box, prior to insertion into bag (see dwg. 9210948).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Assembly damaged so that contents are exposed or liable to become exposed.....	Visual	05001
102.	Sealing strip incomplete, badly wrinkled, or not in contact with surface of container for at least 1/2 inch around entire circumference (when applicable)	Visual	05002
Minor:	AQL 1.00 percent		
201.	Contents move when box is tilted.....	Manual	05003
202.	Marking misleading or unidentifiable.....	Visual	05004

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.2.2.6 Sealed barrier bag, prior to insertion into box (see dwg. 9210948).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Waterproofness destroyed by separation of heat seal or rip, tear or puncture.....	Visual	06001
Minor:	None defined		

4.2.2.7 Sealed wooden packing box (see dwg. 8797610).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Hardware missing, broken or loose.....	Visual-Manual	07001
102.	Strapping missing, broken or loose.....	Visual-Manual	07002
103.	Contents exposed.....	Visual	07003
104.	Board broken or split.....	Visual	07004
105.	DOD symbol misleading or unidentifiable.....	Visual	07005
Minor:	AQL 2.50 percent		
201.	Hardware improperly engaged.....	Visual-Manual	07006
202.	Handle missing or insecure.....	Visual-Manual	07007
203.	Contents loose when box is tilted.....	Manual	07008

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

204.	Marking misleading or unidentifiable.....	Visual	07009
205.	Strapping improperly assembled..	Visual	07010
206.	Car seal missing, unsealed or improperly positioned.....	Visual	07011

4.2.3 Testing

4.2.3.1 Static pull (see 3.3) - Major defect - Code No. 08001.- A two foot length of detonating cord shall be cut from each eight (8) hours of production for the static pull test. The test shall be performed as specified in 4.3.1 using equipment in accordance with 4.2.4. If the assembly fails to comply with the requirements specified, action shall be taken as indicated in the following provisions:

a. If the cable grips are the cause of failure; i.e., if the grips pull off without breaking the cable, a second sample of three (3) assemblies shall be produced and tested. If one of the six (6) cable grips fails during the second sampling, the entire lot of demolition kits assembled with that lot of cable grips shall be rejected subject to replacement with acceptable grips by the contractor.

b. If the detonating cable alone fails, then all cable produced since the last satisfactory test shall be rejected.

4.2.3.2 Functioning of booster assembly (see 3.4) - Major defect - Code No. 09001

4.2.3.2.1 Beginning with the first lot produced and continuing until three (3) consecutive lots have passed the acceptance criteria specified, a sample of 32 booster assemblies and 32 samples of the detonating cord, which was subjected to the static pull test specified in 4.2.3.1, each approximately 6 inches long shall be selected from each lot. The test shall be performed as specified in 4.3.2. If one assembly fails to comply with the applicable requirement, a second sample of 64 booster assemblies and 64 samples of detonating cord shall be tested. If the total number of defectives in the first sample is two (2) or more, or if the combined number of defectives in the first and second samples is two (2) or more, the lot shall be rejected.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.2.3.2.2 After three (3) consecutive lots have met the criteria of 4.2.3.2.1, the sampling plan for this test shall be in accordance with MIL-STD-105 using Code Letter G and an AQL of 1.50 percent (double sampling plan). Any assembly which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.3.2.

4.2.3.3 Pull of container assembly hook clasp (see dwg. 8796269) - Major defect - Code No. 11001.-The sampling plan for this test shall be in accordance with MIL-STD-105 using Code Letter G and an AQL of 0.40 percent. Any clasp assembly which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.3.3 using equipment in accordance with 4.2.4.

4.2.3.4 Functioning (see 3.5) - Major defect - Code No. 10001

4.2.3.4.1 Beginning with the first lot produced and continuing until three (3) consecutive lots have complied with the acceptance criteria specified, a sample of 20 complete demolition kits shall be selected from each lot. Ten (10) of these kits shall be conditioned at 0 degrees Fahrenheit (F.) plus or minus 2 degrees Fahrenheit (F.) and the other ten (10) shall be conditioned at 120 degrees Fahrenheit (F.) plus or minus 2 degrees Fahrenheit(F.). The test shall be performed as specified in 4.3.4. If one kit fails to meet the applicable requirements, a second sample of 40 kits shall be selected and 20 kits tested at each temperature. If the total number of defectives in the first sample is two (2) or more, or if the combined number of defectives in the first and second samples is two (2) or more, the lot shall be rejected.

4.2.3.4.2 After three (3) consecutive lots have met the acceptance criteria specified, the sampling plan for this test shall be in accordance with MIL-STD-105 using Code Letter F and an AQL of 2.50 percent (double sampling plan). An approximately equal number of kits shall be conditioned at each temperature specified in 4.2.3.4.1. Any kit which fails to comply with the applicable requirements shall be classed defective. The test shall be performed as specified in 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.2.3.5 Check test of detonators (see MIL-D-409) - Major defect - Code No. 12001.- If the total time between original acceptance of any detonator lot and the assembly of that lot into the cone and detonating cable assembly of the demolition kit exceeds 2 years, or if the detonators have been subjected to adverse conditions, however brief, at any time since previous tests, the detonator lot shall be subjected to and must satisfactorily pass the check test specified in the applicable detonator loading specification immediately before the detonator lot is assembled into the cone and detonating cable assembly. This test shall be performed by the contractor on detonators selected by the Government inspector at the facility assembling the detonators into the cone and detonating cable assembly (see 6.4).

4.2.4 Inspection equipment.- Equipment Tabulation Number ET - 8796266 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.2.4.1 Government rights to documentation.- Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3 Test methods and procedures

4.3.1 Static pull.- The cable grips shall be attached to each end of the two-foot length of detonating cord and the required load applied for the time specified. Observation shall be made to determine compliance with the applicable requirement. Test equipment shall be in accordance with 4.2.4.

4.3.2 Functioning of booster assembly.- The six inch sample of the detonating cord shall be crimped to the booster assembly using the same production equipment utilized to assemble booster assemblies to detonating cable in the production of the complete

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

kit. A standard M1 delay detonator shall be assembled to the booster assembly and initiated. Observation shall be made to determine compliance with the applicable requirements.

4.3.3 Pull of container assembly hook clasp.-This test shall be performed on the final assembly by applying the force at the surface of the link end of the pivoted lever in a direction perpendicular to the axis of the assembly. Observation shall be made to determine compliance with the applicable requirement. Test equipment shall be in accordance with 4.2.4.

4.3.4 Functioning.-This test shall be performed at a Government proving ground. The kit shall be conditioned at the specified temperature for a minimum of 18 hours and the rocket motor functioned within 10 minutes after removal from the conditioning chamber and the line charge functioned within 20 minutes after removal from the conditioning chamber. The kit shall be set-up for functioning in accordance with the applicable operational manual. The launcher shall be aimed at a stake placed in the ground 170 feet from the coiled line charge and the rocket motor functioned. Observation shall consist of measuring the angle between the line of sight and a line drawn from the point where the rocket motor first contacts the earth and the launcher, and the distance measured from the line charge stake to the point where the rocket motor comes to rest. The line charge shall then be functioned and observation made for complete functioning.

5. PREPARATION FOR DELIVERY

5.1 Packaging

5.1.1 Level A.-Demolition kits with rocket motor shall be packaged in accordance with dwg. 9210948.

5.2 Packing

5.2.1 Level A.- Packing shall be in accordance with dwg. 8797610.

5.3 Marking.-Unit and exterior containers shall be marked in accordance with dwgs. 8797610 and 9210948.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Ordering data.- Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards.- Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers.- The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. In addition, they should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.5).

6.3 Inspection equipment.- The contractor shall design inspection equipment as required by the inspection Equipment Lists (EL) referenced on the applicable ET in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Inspection equipment lists (EL).- Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Inspection equipment list codes.- The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

6.3.3 Army designs.- Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.- Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to MIL-D-1000, Category A, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor designs.- All submitted designs shall contain a reference to the applicable five digit Code Number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND15. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

6.4 Cost of check test.- The contracting officer will arrange for the contractor to be reimbursed for the expense incurred in the performance of the check test for deterioration of the detonators. The test shall be conducted at Government expense without cost to the contractor who loaded the detonators or to the contractor assembling the detonators into the cone and detonating cable assembly of the demolition kit, and shall not constitute a basis for rejection against either contractor except where deterioration has occurred as a direct result of carelessness in handling, storage, etc., permitted while the detonator lot was under the jurisdiction of either contractor.

6.5 Submission of test data and ammunition data cards.- In addition to the normal distribution of records, for loaded items procured by the Department of the Army, one copy of all ballistic test data and ammunition data cards shall be forwarded to the following:

Commanding Officer
Picatinny Arsenal
Dover, New Jersey 07801
ATTN: SMUPA-ND5.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1375-A-036

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.