MIL-D-45412B (MU)
3 March 1969
SUPERSEDING
MIL-D-45412A (MU)
15 June 1965

MILITARY SPECIFICATION

DEMOLITION KIT, M1E1, CONTAINER AND ACCESSORIES

1. SCOPE

1.1 This specification covers the container and accessory parts for one type of demolition kit designated as Demolition Kit, M1E1, Container and Accessories.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

FSC: 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

DRAWINGS

U. S. ARMY MUNITIONS COMMAND

8796266 - Demolition Kit, Projected Charge, M1E1, Complete with Rocket Motor Unit, M4, Assembly
8796269 - Container Assembly
8797610 - Box, Packing, Ammunition for Kit, Demolition, Projected Charge, M1E1, w/Rocket Motor Unit, M4, Assembly

PUBLICATIONS

U. S. ARMY MUNITIONS COMMAND

ET - 8796269 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material.- Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Container and accessories.- The containers and accessories, less load components, shall comply with all requirements specified on drawing (dwg.) 8796266, and with all requirements specified in applicable specifications.

3.3 Spot welds.- Each spot weld shall withstand a separation force of 200 pounds without evidence of failure. The test shall be performed as specified in 4.4.1.

3.4 Static load.- The tow cable assembly, cable grip assembly, and the anchor grip assembly shall withstand a static load of 800 pounds (lbs.) minimum (min.), for a minimum of 20 seconds. The test shall be performed as specified in 4.4.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

3.5 Workmanship.- All parts shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, chips, scale, dirt, grease, rust and other foreign material. The cleaning agent shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

3.6 First article inspection.- This specification makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.- At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.

b. Drawing and specification number and date, together with identification and date of changes thereto.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.

d. Number of items in the lot.

e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.- Prior to the start of regular production, the contractor shall submit a first article sample to a Government approved facility as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2. The first article sample shall consist of ten (10) complete sets of containers and accessories, less loaded components, and ten (10) each of every sub-assembly, individual component, and weld coupons (from each welding machine) which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance for materials. A first article sample, or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.2.2 Inspections to be performed.- Components will be subjected by the Government to any or all of the examinations or tests specified in this specification, and any or all requirements of the applicable drawings.

4.2.3 Rejection.- If any component fails to comply with any or all of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of any component in the sample to comply with any or all of the stated requirements. In the event of rejection the Government reserves the right to require the contractor to take corrective action and submit a new first article sample or portion thereof. Until a first article sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the contracting officer.

4.3 Inspection provisions

4.3.1 Lot formation.- The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot of demolition kits shall contain:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

a. Containers from not more than one lot interfix number from one manufacturer.

b. Accessories from not more than one lot interfix number from one manufacturer.

4.3.2 Examination.- The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Launcher assembly (see dwg. 8796316 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Width between rocket motor guide	Gage	01001
102.	Angle between fully open members	Gage	01002
103.	Weld missing or incomplete	Visual	01003
104.	Assembly binds in opening or closing	Manual	01004

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.00 percent		
201.	Protective coating missing or incomplete	Visual	01005
202.	Evidence of poor workmanship (see 3.5)	Visual	01006

4.3.2.2 Plate, bottom (see dwg. 8796302 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor:	AQL 2.50 percent		
201.	Outside diameter, maximum (max.)	Gage	02001
202.	Hole crimping inadequate	Visual	02002
203.	Reinforcing boss missing	Visual	02003
204.	Hole missing	Visual	02004
205.	Evidence of poor workmanship (see 3.5)	Visual	02005

4.3.2.3 Bottom plate assembly (see dwg. 8796298 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Component missing	Visual	03001
Minor:	AQL 1.00 percent		
201.	Protective coating missing or incomplete	Visual	03002
202.	Evidence of poor workmanship (see 3.5)	Visual	03003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.3.2.4 Top plate (see dwg. 8796301 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major: None defined			
Minor:	AQL 1.50 percent		
201.	Outside diameter, max.....	Gage	04001
202.	Reinforcing boss missing.....	Visual	04002
203.	Operation missing.....	Visual	04003
204.	Evidence of poor workmanship (see 3.5).....	Visual	04004

4.3.2.5 Cone (see dwg. 8796300 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.40 percent		
101.	Puncture, cut or tear.....	Visual	05001
Minor:	AQL 1.00 percent		
201.	Length, max.....	Gage	05002
202.	Evidence of poor workmanship (see 3.5).....	Visual	05003

4.3.2.6 Cone assembly (see dwg. 8796297 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.65 percent		
101.	Wood screw heads above flush....	Visual	06001
102.	Strap insecurely riveted.....	Visual-Manual	06002
103.	Strap stitching inadequate.....	Visual	06003
104.	Damaged components.....	Visual	06004
Minor:	AQL 1.00 percent		
201.	Component or operation missing..	Visual	06005
202.	Evidence of poor workmanship (see 3.5).....	Visual	06006

4.3.2.7 Stake (see dwg. 8796327 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Total length, min.....	Gage	07001
102.	Diameter, min.....	Gage	07002
103.	Wood defects - cross grain, knots, splits, etc.....	Visual	07003
Minor:	AQL 1.00 percent		
201.	Taper length, min.....	Gage	07004
202.	Protective coating incomplete or inadequate.....	Visual	07005

4.3.2.8 Cable grip assembly (see dwg. 8796330 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Cable grip frayed or damaged to the extent that function may be impaired.....	Visual	08001

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.50 percent		
201.	Length of small cable diameter, min.....	Gage	08002
202.	Protective coating incomplete or inadequate.....	Visual	08003
203.	Evidence of poor workmanship (see 3.5).....	Visual	08004
204.	Assembly incorrect.....	Visual	08005

4.3.2.9 Tow cable assembly (see dwg. 8796282 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major: None defined			
Minor:	AQL 1.50 percent		
201.	Length of flexible cable.....	Gage	09001
202.	Protective coating incomplete or inadequate.....	Visual	09002
203.	Evidence of poor workmanship (see 3.5).....	Visual	09003
204.	Assembly incorrect.....	Visual	09004

4.3.2.10 Anchor grip assembly (see dwg. 8796283 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major: None defined			
Minor:	AQL 1.00 percent		
201.	Protective coating incomplete or inadequate.....	Visual	10001
202.	Evidence of poor workmanship (see 3.5).....	Visual	10002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.3.2.11 Swivel bushing (see dwg. 8796287 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Outside diameter of body, max...	Gage	11001
102.	Inside diameter, min.....	Gage	11002
103.	Length to flange, min.....	Gage	11003
Minor:	AQL 1.50 percent		
201.	Outside diameter of body, min...	Gage	11004
202.	Outside diameter of flange, min.	Gage	11005
203.	Total length, min.....	Gage	11006
204.	Evidence of poor workmanship (see 3.5).....	Visual	11007

4.3.2.12 Swivel bolt (see dwg. 8796286 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Pitch diameter of thread.....	Gage	12001
102.	Major diameter of thread, min...	Gage	12002
103.	Diameter of hole, min.....	Gage	12003
Minor:	AQL 1.50 percent		
201.	Length of thread, min.....	Gage	12004
202.	Length from threaded end to flange, min.....	Gage	12005
203.	Protective finish missing or damaged.....	Visual	12006
204.	Evidence of poor workmanship (see 3.5).....	Visual	12007

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.3.2.13 Lid (see dwg. 8796272 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.40 percent		
101.	Puncture, cut or tear.....	Visual	13001
Minor:	AQL 1.50 percent		
201.	Length from top to bottom.....	Gage	13002
202.	Thickness, min.....	Gage	13003
203.	Depth from top to bottom of handle recess, min.....	Gage	13004

4.3.2.14 Tail retainer (see dwg. 8796291 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major: None defined			
Minor:	AQL 2.50 percent		
201.	Outside diameter, max.....	Gage	14001
202.	Thickness, min.....	Gage	14002
203.	Width of launcher slot, min.....	Gage	14003
204.	Profile of rocket motor cut-out.	Gage	14004
205.	Warping or separated plies.....	Visual	14005

4.3.2.15 Nose retainer block (see dwg. 8796292 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

Major: None defined

Minor:	AQL 1.50 percent		
201.	Diameter of small end, max.....	Gage	15001
202.	Length, max.....	Gage	15002
203.	Depth from center to launcher shelf.....	Gage	15003
204.	Profile of rocket motor cut-out.	Gage	15004

4.3.2.16 Lid assembly prior to painting (see dwgs. 8796270 and 8796272 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Embossing missing (when applicable).....	Visual	16001
102.	Handle missing.....	Visual	16002
Minor:	AQL 1.50 percent		
201.	Rivet missing or loose.....	Visual	16003
202.	Protective coating incomplete or inadequate.....	Visual	16004
203.	Evidence of poor workmanship (see 3.5).....	Visual	16005

4.3.2.17 Container (see dwg. 8796271 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Thickness, min.....	Gage	17001
102.	Total length, min.....	Gage	17002
103.	Puncture, cut or tear.....	Visual	17003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.00 percent		
201.	Length to lid stop.....	Gage	17004
202.	Weld incomplete.....	Visual	17005

4.3.2.18 Container assembly prior to packing accessories (see dwg. 8796269 covering a detail of dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.50 percent		
201.	Fitting missing or loose.....	Visual-Manual	18001
202.	Lid assembly tight on container.	Manual	18002
203.	Fitting action improper.....	Manual	18003
204.	Evidence of poor workmanship (see 3.5).....	Visual	18004

4.3.2.19 Container assembly with accessories, prior to assembling lid (see dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.00 percent		
201.	Accessory missing or damaged to an extent that function is impaired.....	Visual	19001
202.	Evidence of poor workmanship (see 3.5).....	Visual	19002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.3.2.20 Container assembly with accessories (see dwg. 8796266).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Assembly damaged	Visual	20001
Minor:	AQL 1.50 percent		
201.	Lid assembly incorrect	Visual	20002
202.	Protective coating incomplete or inadequate	Visual	20003
203.	Contents loose	Manual	20004
204.	Marking misleading or unidentifiable	Visual	20005

4.3.2.21 Sealed wood packing box (see dwg. 8797610).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Hardware missing, broken or loose	Visual-Manual	21001
102.	Strap missing, broken or loose	Visual-Manual	21002
103.	Board broken or loose	Visual	21003
Minor:	AQL 1.50 percent		
201.	Hardware improperly engaged	Visual-Manual	21004
202.	Handle missing or insecure	Visual-Manual	21005
203.	Label missing or illegible	Visual	21006

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.3.3 Testing

4.3.3.1 Spot welds (see 3.3) - Major defect - Code No. 22001.- One coupon shall be prepared in accordance with 4.4.1 during each four (4) hours of production from each spot welding machine and after any machine adjustment or repair. If the coupon fails to meet the applicable requirements, production by the machine producing the defective coupon shall be stopped until corrective action has been taken and two acceptable consecutive test coupons are produced. All material produced by that machine during that four (4) hours of production shall be rejected. The test shall be performed as specified in 4.4.1.

4.3.3.2 Static load (see 3.4) - Major defect - Code No. 23001.- The sampling plan for testing each type of assembly shall be in accordance with MIL-STD-105 using Code Letter G and an AQL of 0.40 percent. Any assembly which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.3.3.3 Clasp operation (see dwg. 8796269) - Major defect - Code No. 24001.- The sampling plan for this test shall be in accordance with MIL-STD-105 using Code Letter G and an AQL of 0.40 percent. Any clasp assembly which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.3 using equipment in accordance with 4.3.4.

4.3.4 Inspection equipment.- Equipment Tabulation Number ET - 8796269 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.3.4.1 Government rights to documentation.- Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

4.4 Test methods and procedures

4.4.1 Spot weld pull test.- The coupon shall be prepared from two pieces of metal of the same type and thickness as that used in the fabrication of the launcher. These pieces shall measure one inch in width and four inches in length. The ends of the pieces shall be overlapped approximately one inch (leaving a single thickness of one inch by three inches on each end) and one spot weld applied to the approximate center of the double thickness. The welded coupon shall be tested in a tensile testing machine utilizing the required load. The coupon shall be classed defective if the weld separates completely.

4.4.2 Static load.- The tow cable assembly, cable grip assembly, and anchor grip assembly, shall be attached to a testing device in a manner simulating the fastening in the item. The required load shall be applied for the time specified and observation made to determine compliance with the applicable requirement. Test equipment shall be in accordance with 4.3.4.

4.4.3 Clasp operation.- The clasps on both ends of the container shall be fully seated in the lock-down position at the start of the test. The specified force shall be applied in the unlocking direction and observation made for compliance with the applicable requirement. Test equipment shall be in accordance with 4.3.4.

5. PREPARATION FOR DELIVERY

5.1 Packaging

5.1.1 Level C.- Component parts shall be packaged in accordance with the requirements of MIL-STD-1169.

5.2 Packing

5.2.1 Level C.- Packing shall be in accordance with the requirements of MIL-STD-1169.

5.3 Marking.- Marking shall be as prescribed in MIL-STD-1169.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Ordering data.- Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards.- Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

c. Provisions for submission of first article samples.

6.2 Inspection code numbers.- The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. In addition, they should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.5).

6.3 Inspection equipment.- The contractor shall design inspection equipment as required by the inspection Equipment Lists (EL) referenced on the applicable ET in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Inspection equipment lists (EL).- Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Inspection equipment list codes.- The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.- Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.- Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to MIL-D-1000, Category A, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.

6.3.5 Submission of contractor designs.- All submitted designs shall contain a reference to the applicable five digit Code Number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND15. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1375-A-034

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:55Z
Check the source to verify that this is the current version before use.