MIL-C-8052C(USAF)
16 August 1967
Superseding
MIL-C-8052B(USAF)
22 September 1955

MILITARY SPECIFICATION

CONTROL, PRESSURIZING SET C-1173/ASQ

1. SCOPE

1.1 This specification covers one type of electronic equipment pressurizing system control, designated C-1173/ASQ.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bid, or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

Military

MIL-E-5272	Environmental Testing, Aeronautical and Associated Equipment, General Specification for
MIL-E-17555	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of

STANDARDS

Military

MIL-STD-130	Identification Marking of U.S. Military Property
MIL-STD-831	Test Reports Preparation of

Air Force-Navy Aeronautical

AN565	Setscrew - Hexagon and Fluted Socket, Headless

DRAWING

Air Force

53D13247	Control-Pressurizing Set C-1173-ASQ

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Preproduction. This specification makes provisions for preproduction testing.

3.2 Design and construction. The design and construction of the control shall conform to Drawing 53D13247. Where the requirements of the drawing and this specification conflict, the requirements of this specification shall govern.

3.2.1 Setscrews (control knob). Setscrews in the control knobs shall have No. 8-32 UNC-3A threads in accordance with AN565.

3.2.2 Tubing connections. The tubing connections in the control shall be tight to preclude leakage of the pressurized air.

3.2.3 Electrical circuitry. The electrical circuitry of the control shall conform to Drawing 53B13250.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T09:51Z
Check the source to verify that this is the current version before use.

3.3 Performance. The control shall be capable of satisfactory continuous operation under the following conditions:

a. A relative humidity as encountered in tropical and semitropical climates

b. Exposure to atmosphere containing salt-laden moisture

c. Vibration incident to use in aircraft.

3.3.1 Leakage. The leakage shall not be more than 0.5 inch Hg in 1 minute when tested in accordance with 4.5.2.

3.4 Identification of product. Equipment, assemblies, and parts shall be marked for identification in accordance with MIL-STD-130.

3.5 Workmanship

3.5.1 General. The control, including all parts and accessories, shall be fabricated and finished in a thoroughly workmanlike manner. Particular attention shall be given to freedom from blemishes, defects, burrs, and sharp edges; accuracy of dimensions, radii of fillets and marking of parts and assemblies; thoroughness of soldering, brazing, and riveting; alignment of parts and tightness of assembly screws and bolts; et cetera.

3.5.2 Riveting. Riveting operations shall be carefully performed to insure tightness and satisfactory heading of rivets.

3.5.3 Cleaning. The control shall be thoroughly cleaned. Loose, spattered, or excess solder, metal chips, and other foreign material shall be removed during and after final assembly.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of tests. The inspection and testing of controls shall be classified as follows:

a. Preproduction tests

b. Acceptance tests

4.3 Preproduction testing

4.3.1 Test sample. The contractor shall subject three controls to the preproduction tests specified in 4.3.2.

4.3.2 Preproduction tests. The three controls shall be subjected to the acceptance tests and the following tests as described under 4.5:

a. First control to be subjected to the humidity test specified in 4.5.4.1

b. Second control to be subjected to the salt spray test specified in 4.5.4.2

c. Third control to be subjected to both the vibration test specified in 4.5.4.3 and to the leakage test specified in 4.5.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T09:51Z
Check the source to verify that this is the current version before use.

4.4 Acceptance tests. Acceptance tests shall consist of the individual tests.

4.4.1 Individual tests. Each control shall be subjected to the following tests as described under 4.5:

a. Examination of product

b. Leakage test

c. Circuit continuity

4.5 Test methods

4.5.1 Examination of product. The control shall be inspected to determine compliance with the requirements specified herein with respect to materials, workmanship, and marking.

4.5.2 Leakage. The control shall be connected to an air pressure source. A pressure sufficient to produce an indication of 42 to 45 inches Hg on the control pressure gage shall be applied. The connecting tubing shall then be pinched off or otherwise completely sealed at a point within 2 inches of the control pressure connection. During the first minute after the connecting tubing has been completely sealed, the gage pointer shall not change its position by more than 0.5 inch Hg.

4.5.3 Circuit continuity. The electrical circuitry in the control shall be given a continuity check to determine that the circuit meets the requirements specified on Drawing 53B13250.

4.5.4 Environmental tests. The control shall be subjected to the following environmental tests in accordance with MIL-E-5272.

4.5.4.1 Humidity. The control shall be subjected to humidity in accordance with procedure I of MIL-E-5272. Corrosion of components, except for the following components, shall be cause for rejection of the control:

a. Purge valve

b. Air pressure indicating gage

c. Switch and guard assembly

d. Light panel plastic plate lighting

e. Light assembly press-to-test indicator.

4.5.4.2 Salt spray. The control shall be subjected to salt spray in accordance with procedure II specified in MIL-E-5272. Cause for rejection shall be as specified in 4.5.4.1.

4.5.4.3 Vibration. The control shall be subjected to the vibration test specified in procedure I of MIL-E-5272. Upon conclusion of this test, the control shall be subjected to the tests specified in 4.5.4.3.1 and 4.5.3. Structural failure or failure of the control, except for the air pressure indicating gage, panel light assemblies, and press-to-test light indicator shall be cause for rejection. Failure of any of the three components specified shall be indicated.

4.5.4.3.1 Post vibration leakage test. A gage, of the same type as the gage in the control unit, shall be connected externally through a tee to the control pressure connection in such manner that the internal volume will be minimum. The control shall be connected to an air-pressure source and a pressure applied sufficient to produce an indication of 42 to 45 inches on the external pressure gage. The connecting tube shall be pinched off, or otherwise completely sealed, at a point

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T09:51Z
Check the source to verify that this is the current version before use.

upstream of the gage and within 3 inches of the control pressure connection. During the first minute after the connecting tube has been completely sealed, the external gage pointer shall not change position more than 0.5 inch Hg.

5. PREPARATION FOR DELIVERY

5.1 The control shall be prepared for delivery in accordance with MIL-P-17555.

6. NOTES

6.1 Intended use. The C-1173/ASQ control covered by this specification is intended for use as a controlling componet of a direct-current or an alternating-current pressurizing set used to maintain a relatively fixed pressure in various airborne electronic equipment under all altitude conditions.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, date, and number of this specification

b. Number of preproduction samples required

c. Levels of preservation and packaging, and packing required.

6.2.1 Data to accompany the preproduction test sample. The contractor shall furnish the following to the procuring activity:

a. Three copies of a test report in accordance with MIL-STD-831

b. The samples that were tested and met the test requirements.

6.2.2 Lighting-plate test report. A certified test report indicating that the plastic lighting plate meets the requirements of MIL-P-7788 will be submitted to the procuring activity.

6.3 Detail drawings. The following drawings are pertinent to AF Drawing 53D13247:

50A14020-3	Spacer - Control Panel
52A13614	Disc, Control Panel
52B13611	Shield, Dial, Control
52B13612	Coupling Assembly, Gauge, Control Panel
52B13613	Gauge, Control Panel
52C13607	Plate, Lighting Plastic Control Panel
52C13608	Plate, Mounting Control Panel
53C13809	Plate Mounting, Pressurizing Set, Control, Rear
53C13810	Cover Pressurizing Set Control
53B13250	Wiring Diagram, C1173/ASQ Pressurizing Set Control Schematic
MIL-G-8190	Gage, Absolute Pressure, Dial Indicating, AIR, 15 to 45 Inch Mercury Range, Type MA-1.

Custodian:
Air Force - 11

Preparing activity:
Air Force - 11
Project No. 1650-F009

Review Activity:
Air Force - 71

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T09:51Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

SPECIFICATION

ORGANIZATION *(Of submitter)* | CITY AND STATE

CONTRACT NO. | QUANTITY OF ITEMS PROCURED | DOLLAR AMOUNT $

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)* | DATE

DD FORM 1 APR 63 1426 REPLACES NAVSHIPS FORM 4863, WHICH IS OBSOLETE C-8378

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T09:51Z
Check the source to verify that this is the current version before use.

FOLD

SEG (SEPS)
WRIGHT-PATTERSON AFB, OHIO

POSTAGE AND FEES PAID

UNITED STATES AIR FORCE
OFFICIAL BUSINESS

Commander
Systems Engineering Group
ATTN: SEPS
Wright-Patterson AFB, Ohio

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T09:51Z
Check the source to verify that this is the current version before use.