MILITARY SPECIFICATION

MINE, APERS, NM, M14E1 WITH INTEGRAL FUZE LOADING, ASSEMBLING AND PACKING

This amendment forms a part of Military Specification MIL-M-13693A (Ord) dated 18 July 1962.

Delete "MIL-M-13693A (Ord)" wherever it appears in this specification and substitute "MIL-M-13693A (MU)".

Page 1, Paragraph 2.1, line 2: Insert after bids", or request for proposals,".

Page 2, Paragraph 2.1, under STANDARDS, MILITARY, after MIL-STD-109: Delete "Inspection" and substitute "Quality Assurance".

Paragraph 2.1, under STANDARDS, MILITARY: Add

"MIL-STD-1235 — Single and Multi-level Continuous Sampling Procedures and Tables for Inspection by Attributes".

Paragraph 2.1, under PUBLICATIONS, ORDNANCE CORPS: Delete:

"ORD-M608-11 — Procedures and Tables for Continuous Sampling by Attributes".

Paragraph 2.1, parenthetical source paragraph, line 2: Delete: "contractors" and substitute "suppliers".

Page 3, Paragraph 3.7: Delete this paragraph and substitute:

"**3.7 Workmanship.** All parts and assemblies shall be fabricated and loaded in a thorough workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, rust and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

Page 4, Paragraph 4.1.2, part e, line 1: Delete "procured" and substitute "purchased".

Page 5, Paragraph 4.1.3, line 4: Delete "shall" and substitute "will".

Paragraph 4.2.1, line 2: Delete "fifty" and substitute "seventy-four".

Paragraph 4.2.2, line 3: Delete this paragraph and substitute:

"**4.4.2** *Inspections to be performed.* Each mine assembly shall be inspected by the Government for all the inspections specified in 4.3.2.4 and 4.4.2 of this specification. Following this twenty-four of the assemblies shall be subjected to the jolt and jumble tests (see 4.4.1) and the remaining fifty assemblies shall be sunbjected to the functioning test (see 4.4.3)".

Page 6, paragraph 4.3.2, line 5: Delete "Handbook ORD-M608-11" and substitute "Standard MIL-STD-1235".

Page 12, paragraph 4.3.3.3, line 6: Delete "code letter N" and substitute "inspection level III".

FSC 1345

701044—63—(540)

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:10Z
Check the source to verify that this is the current version before use.

Page 12, paragraph 4.3.3.3.1, lines 4 and 5: Delete "code letter L and an AQL of 0.25 percent" and substitute "inspection level II and an AQL of 0.40 percent".

Page 13, paragraph 4.3.3.4, line 6: Delete "code letter J and an AQL of 1.50 percent" and substitute "inspection level II and an AQL of 0.10 percent".

Page 13, paragraph 4.3.3.4.1, lines 4 and 5: Delete "code letter H and an AQL of 1.50 percent" and substitute "inspection level I and an AQL of 0.25 percent".

Page 13, paragraph 4.3.4: Delete this paragraph and substitute:

"**4.3.4** *Inspection equipment.* Index of Inspection Equipment Number IEL–7155570 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL–I–45607.

4.3.4.3 *Government use of contractor's inspection and test equipment.* The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government".

Page 14, paragraph 4.4.1, line 10: Delete "parellel" and substitute "parallel".

Page 16, delete paragraphs 6.3, 6.3.1, 6.3.2, 6.3.3, 6.3.4, 6.3.5, 6.3.6 and 6.3.7 and substitute the following:

"**6.3 Inspection equipment.** The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "contractor design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5, and 6.3.6 will be designated in the inspection equipment list by the following codes:

CDOF — Contractor's design responsibility on Ordnance format: ORDM–608–12.
CDCF — Contractor's design responsibility on contractor format.
OD — Ordnance design.
ODMU — Ordnance design, mandatory for use.
CE — Commercial equipment.
SCD — Specification Control Drawing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:10Z
Check the source to verify that this is the current version before use.

6.3.3 *Ordnance designs.* Ordnance designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Ordnance design is listed for an item of inspection equipment. Ordnance designs fall into two basic classifications; mandatory and nonmandatory. ings. When an inspection equipment list references mandatory Ordnance designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with nonmandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawings.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic, or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial inspection equipment but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDOF shall comply with the format and requirements of ORDM 608–12, and, in addition, contain the detail and information specified above.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs."

Custodian:

Army—MU

Preparing activity:

Army—MU

Project No. 1345–A117

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:10Z
Check the source to verify that this is the current version before use.