MIL-M-52287C(ME)
27 February 1984
SUPERSEDING
MIL-M-52287B(ME)
12 October 1973

MILITARY SPECIFICATION

MAST, TELESCOPIC, FLOODLIGHT

This specification is approved for use by the USA Belvoir Research and Development Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a telescoping mast for mounting floodlights.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified (see 6.2), the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner.

MILITARY

MIL-P-116	- Preservation, Methods of.
MIL-T-704	- Treatment and Painting of Materiel.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research and Development Center, ATTN: STRBE-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 6230

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:13Z
Check the source to verify that this is the current version before use.

MIL-T-22085	- Tape, Adhesive, Preservation and Sealing.
MIL-G-20241	- Gasket Material, Wool Felt, Impregnated Adhesive, Pressure-Sensitive.
MIL-C-46168	- Coating, Aliphatic Polyurethane, Chemical Agent Resistant.
MIL-S-81733	- Sealing and Coating Compound, Corrosion Inhibitive.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-889	- Dissimilar Metals.
MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein.

DRAWINGS

ME

TA13208E4120	- Mast, Telescopic, Floodlight.

(Copies of specifications, standards, and drawings required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.2 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 Description. The floodlight telescopic mast (hereinafter called "mast") shall be in accordance with top assembly TA13208E4120 and as specified herein. The mast shall be hand crank operated, and shall be approximately 20 feet tall when fully extended.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:13Z
Check the source to verify that this is the current version before use.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly and operation of the mast. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 Material. Material shall be as specified herein and on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification.

3.2.1 Material deterioration and control. The flood light telescopic mast shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable storage and operating environments to which the telescopic mast may be exposed.

3.2.1.1 Dissimilar metals. Dissimilar metals, as defined in MIL-STD-889, shall be electrically insulated from one another to minimize or prevent galvanic corrosion. Insulation may be provided by an insulating barrier such as a corrosion inhibiting sealant conforming to MIL-S-81733, or chromate tape conforming to MIL-G-20241. Protection against galvanic corrosion could also be obtained by exclusion of the electrolyte if feasible.

3.2.1.2 Identification of materials and finishes. The contractor shall identify the specific material, finish or treatment for use with components and sub-components, and shall make information available, upon request, to the contracting officer or his/her designated representative.

3.3 Identification marking. Each mast assembly shall be identified in accordance with MIL-STD-130.

3.4 Treatment and painting. The portions of the mast and its components and parts normally painted shall be cleaned, treated, and painted in accordance with MIL-T-704, type A, with the top coat conforming to MIL-C-46168, color camouflage forest green.

3.5 Workmanship. All parts, components, and assemblies of the mast including castings, molded parts, machined surfaces, and welded parts shall be clean and free from sand, dirt, fins, pits, sprues, scale, flux, and other harmful extraneous material.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:13Z
Check the source to verify that this is the current version before use.

inspection requirements specified herein. Except as otherwise specified in the contract or order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Acceptability criteria. Masts which conform to all requirements in sections 3 and 5 of this specification and pass all applicable examinations in section 4 of this specification will be considered acceptable by the Government.

4.1.2 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the quality assurance provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.3 and 6.4.1).

4.2 Classification of inspections. Inspections shall be classified as follows:

a. Quality conformance inspection (see 4.3).
b. Inspection of packaging (see 4.5).

4.3 Quality conformance inspection.

4.3.1 Sampling for examination. Sampling for examination shall be in accordance with MIL-STD-105, inspection level II. Samples selected shall be examined for the major and minor defects specified in 4.4.1. AQL shall be 2.5 percent defective for major defects and 4.0 percent defective for minor defects.

4.3.2 Individual test. Each mast shall be subjected to the operating test specified in 4.4.2. Failure of the test shall be cause for rejection.

4.4 Inspection procedure.

4.4.1 Examination. The mast shall be examined for the following defects:

Major

101. Any part or component not in accordance with the QAP requirements as shown in the drawings.
102. Any dimension not as specified.
103. Absence of any part or component.
104. Misalinement of parts or component.
105. Materials or components not as specified.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:13Z
Check the source to verify that this is the current version before use.

106. Materials are not corrosion resistant or treated to be made resistant for applicable storage and operating environments.
107. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other.
108. Contractor does not have documentation available for identification of material, finish or treatment.
109. Treatment and painting not as specified.

Minor

201. Identification or special marking missing or illegible.
202. Workmanship not as specified.

4.4.2 Operating test. The mast shall be erected to its normal operating position and collapsed five times. Failure of the mast to extend or collapse or damage (see 6.4.2) to any component shall constitute failure of this test.

4.5 Inspection of packaging.

4.5.1 Quality conformance inspection of pack.

4.5.1.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.5.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.5.1.3 Examination. Samples selected in accordance with 4.5.1.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

110. Materials or containers not as specified for level A or level B. Each incorrect container or material shall constitute one defect.
111. Preservation not applied as specified for level A.
112. Mast sections not fully collapsed as specified for level A and commercial.
113. Preservation and packing not in accordance with the referenced document as specified for commercial.
114. Marking illegible, incomplete, incorrect or missing for level A, level B, or commercial.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or commercial as specified (see 6.2).

5.1.1 Level A. Working surfaces of the telescopic mast shall be coated with type P-7 preservative conforming to the applicable specification listed in MIL-P-116 and shall be applied in accordance with MIL-P-116. The mast sections shall be retracted to the fully collapsed position. The crank shall be secured to the mast with tape conforming to MIL-T-22085, type II.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:13Z
Check the source to verify that this is the current version before use.

5.1.2 Commercial. The mast, in fully collapsed position, shall be preserved in accordance with MIL-STD-1188.

5.2 Packing. Packing shall be level A, level B, or commercial as specified (see 6.2).

5.2.1 Level A. Each telescopic mast, preserved as specified in 5.1, shall be packed in a close-fitting box conforming to either PPP-B-601, overseas type, style optional or PPP-B-621, class 2, style optional. Blocking as required to prevent movement or damage shall be required. Box closure and strapping shall be in accordance with the Appendix to the applicable box specification.

5.2.2 Level B. Packing shall be as specified in 5.2.1, except boxes shall be domestic type or class as applicable.

5.2.3 Commercial. Masts, preserved as specified in 5.1, shall be packed in accordance with MIL-STD-1188.

5.3 Marking.

5.3.1 Military. Marking for military levels of protection (level A or B) shall be in accordance with MIL-STD-129.

5.3.2 Commercial. Commercial marking shall be in accordance with MIL-STD-1188.

6. NOTES

6.1 Intended use. The mast is intended for use to support floodlights.

6.2 Ordering data. Procurement documents should specifiy the following:

a. Title, number, and date of this specification.
b. Date of issue of DoDISS applicable and exceptions thereto (see 2.1.1).
c. Degree of preservation and of packing required (see 5.1 and 5.2).

6.3 Quality assurance provisions (QAP) information. The contracting officer should require the contractor to maintain records of all QAP inspections. A suggested paragraph is as follows:

> "The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, and corrective action taken when applicable."

6.4 Definitions. The following definitions shall apply throughout this specification.

Source: https://assist.dla.mil -- Downloaded: 20261O-22T21:13Z
Check the source to verify that this is the currentversion before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY
US Army Belvoir R & D Center
ATTN: STRBE-DS
Fort Belvoir, VA 22060

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
USA Belvoir R & D Center
STRBE-DS
Fort Belvoir, VA 22060

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:13Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-M-52287C(ME)	Mast, Telescopic, Floodlight

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426

PREVIOUS EDITION IS OBSOLETE.

(TO DETACH THIS FORM, CUT ALONG THIS LINE.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:13Z
Check the source to verify that this is the current version before use.